Second Edition — iOS 15 · Xcode 13 · Swift 5.5




UIKit Apprentice

Beginning iOS Development with Swift

By the raywenderlich Tutorial Team

Fahim **Farook** & Matthijs **Hollemans**



UIKit Apprentice, Second Edition

Fahim Farook & Matthijs Hollemans

Copyright ©2021 Razeware LLC.

Notice of Rights

All rights reserved. No part of this book or corresponding materials (such as text, images, or source code) may be reproduced or distributed by any means without prior written permission of the copyright owner.

Notice of Liability

This book and all corresponding materials (such as source code) are provided on an "as is" basis, without warranty of any kind, express or implied, including but not limited to the warranties of merchantability, fitness for a particular purpose, and non-infringement. In no event shall the authors or copyright holders be liable for any claim, damages or other liability, whether in action of contract, tort or otherwise, arising from, out of or in connection with the software or the use of other dealing in the software.

Trademarks

All trademarks and registered trademarks appearing in this book are the property of their own respective owners.

Table of Contents: Overview

Book License 15

Before You Begin 16

What You Need 17

Book Source Code & Forums 18

Acknowledgments 21

Section 1: Getting Started 22

Chapter 1: Introduction 23

Chapter 2: The One-Button App 35

Chapter 3: Slider & Labels 64

Chapter 4: Outlets 87

Chapter 5: Rounds & Score 107

Chapter 6: Polish 123

Chapter 7: The New Look 139

Chapter 8: The Final App 173

Section 2: Checklists 204

Chapter 9: Table Views 205

Chapter 10: The Data Model 241

Chapter 11: Navigation Controllers 269

Chapter 12: Add Item Screen 294

Chapter 13: Delegates & Protocols 319

Chapter 14: Edit Items 336

Chapter 15: Saving & Loading 359
Chapter 16: Lists 378
Chapter 17: Improved Data Model 409
Chapter 18: User Defaults 433
Chapter 19: UI Improvements 452
Chapter 20: Local Notifications 484

Section 3: My Locations 508

Chapter 21: Swift Review 509
Chapter 22: Get Location Data 536
Chapter 23: Use Location Data 559
Chapter 24: Objects vs. Classes 589
Chapter 25: The Tag Location Screen 604
Chapter 26: Adding Polish 633
Chapter 27: Saving Locations 657
Chapter 28: The Locations Tab 690
Chapter 29: Maps 719
Chapter 30: Image Picker 741
Chapter 31: Polishing the App 774

Section 4: Store Search 806

Chapter 32: Search Bar 807
Chapter 33: Custom Table Cells 834
Chapter 34: Networking 864
Chapter 35: Asynchronous Networking 899

Chapter 36: URLSession 918
Chapter 37: The Detail Pop-up 951
Chapter 38: Polish the Pop-up 977
Chapter 39: Landscape 994
Chapter 40: Refactoring 1032
Chapter 41: Internationalization 1062
Chapter 42: The iPad 1089
Chapter 43: Distributing the App 1125
Conclusion 1151

Table of Contents: Extended

Book License 15

Before You Begin 16

What You Need 17

Book Source Code & Forums 18

About the Authors 20

Acknowledgments 21

Content Development 21

Section 1: Getting Started 22

Chapter 1: Introduction 23

About this book 24

Who this book is for 26

iOS 15 and later only 27

What you need 28

Xcode 29

What's ahead: an overview 30

Chapter 2: The One-Button App 35

The Bull's Eye game 36

The one-button app 38

UIKit 61

Chapter 3: Slider & Labels 64

Portrait vs. landscape 65

Understanding objects, data and methods 69

Adding the other controls 73

Chapter 4: Outlets 87

Improve the slider 88

Generate the random number 94
Adding rounds to the game 97
Displaying the target value 102

Chapter 5: Rounds & Score 107
Getting the difference 108
Simplifying the algorithm 113
What's the score? 117
Showing the total score 117
Displaying the score 119
One more round... 121

Chapter 6: Polish 123
Tweaks 124
The alert 132
Start over 135

Chapter 7: The New Look 139
Landscape orientation revisited 140
Spice up the graphics 142
The About screen 158

Chapter 8: The Final App 173
Support different screen sizes 174
Crossfade 189
The icon 191
Display name 192
Run on device 194
The end... or the beginning? 203

Section 2: Checklists 204

Chapter 9: Table Views 205
Table views and navigation controllers 206
The Checklists app design 208

Add a table view 209
The table view delegates 222

Chapter 10: The Data Model 241
Model-View-Controller 242
The data model 244
Clean up the code 266

Chapter 11: Navigation Controllers 269
Navigation controller 270
Delete rows 281
The Add Item screen 283

Chapter 12: Add Item Screen 294
Static table cells 295
Read from the text field 302
Polish it up 307

Chapter 13: Delegates & Protocols 319
Add new ChecklistItems 320

Chapter 14: Edit Items 336
Edit items 337
Refactor the code 352
One more thing 354

Chapter 15: Saving & Loading 359
The need for data persistence 360
The documents folder 361
Save checklist items 365
Load the file 372
What next? 377

Chapter 16: Lists 378
The All Lists view controller 379
The All Lists UI 386

View the checklists 392
Manage checklists 397
Are you still with me? 408

Chapter 17: Improved Data Model 409
The new data model 410
Fake it 'til you make it 413
Do saves differently 420
Improve the data model 427

Chapter 18: User Defaults 433
Remember the last open list 434
Defensive programming 441
The first-run experience 446

Chapter 19: UI Improvements 452
Show counts 453
Sort the lists 462
Add icons 465
Make the app look good 479

Chapter 20: Local Notifications 484
Try it out 485
Set a due date 490
Due date UI 495
Schedule local notifications 499
That's a wrap! 506

Section 3: My Locations 508

Chapter 21: Swift Review 509
Variables, constants and types 510
Methods and functions 518
Making decisions 523
Loops 528

Objects 531
Protocols 534

Chapter 22: Get Location Data 536
Get GPS coordinates 538
Core Location 545
Display coordinates 555

Chapter 23: Use Location Data 559
Handle GPS errors 560
Improve GPS results 566
Reverse geocoding 571
Testing on device 580

Chapter 24: Objects vs. Classes 589
Classes 590
Inheritance 592
Overriding methods 596
Casts 600

Chapter 25: The Tag Location Screen 604
The screen 605
The new view controller 606
Make the cells 609
Display location info 616
The category picker 624

Chapter 26: Adding Polish 633
Improve the user experience 634
The HUD 639
Handle the navigation 652

Chapter 27: Saving Locations 657
Core Data overview 658
Using Core Data 658

The data store 666
Pass the context 669
Browse the data 673
Save the locations 679
Handle Core Data errors 682

Chapter 28: The Locations Tab 690
The Locations tab. 691
Create a custom table view cell subclass 699
Edit locations 701
Use NSFetchedResultsController 707
Delete locations 714
Table view sections 716

Chapter 29: Maps 719
Add a map view. 720
Make your own pins 731

Chapter 30: Image Picker 741
Add an image picker 742
Show the image. 750
UI improvements 755
Save the image. 760
Edit the image 766
Thumbnails 768

Chapter 31: Polishing the App. 774
Convert placemarks to strings 775
Back to black 779
The map screen. 785
UI updates to screens 786
Polish the main screen. 791
Make some noise 799
The icon and launch images 802

The end 804

Section 4: Store Search 806

Chapter 32: Search Bar 807
Create the project 809
Create the UI 814
Do fake searches 819
UI Improvements 824
Create the data model 827
No results found 829

Chapter 33: Custom Table Cells 834
Custom table cells and nibs 835
Change the look of the app 850
Tag commits 854
The debugger 855

Chapter 34: Networking 864
Query the iTunes web service 865
Send an HTTP(S) request 870
Parse JSON 875
Work with the JSON results 885
Sort the search results 895

Chapter 35: Asynchronous Networking 899
Extreme synchronous networking 900
The activity indicator 905
Make it asynchronous 912

Chapter 36: URLSession 918
Branch it 919
Put URLSession into action 921
Cancel operations 931
Search different categories 934

Download the artwork 940
Merge the branch 948

Chapter 37: The Detail Pop-up 951
The new view controller 952
Add the rest of the controls 960
Show data in the pop-up 971

Chapter 38: Polish the Pop-up 977
Dynamic Type 978
Gradients in the background 984
Animation! 989

Chapter 39: Landscape 994
The landscape view controller 995
Fix issues 1006
Add a scroll view 1010
Add result buttons 1016
Paging 1024
Download the artwork 1027

Chapter 40: Refactoring 1032
Refactor the search 1033
Improve the categories 1040
Enums with associated values 1044
Spin me right round 1050
Nothing found 1053
The Detail pop-up 1055

Chapter 41: Internationalization 1062
Add a new language 1063
Localize on-screen text 1073
InfoPlist.strings 1084
Regional settings 1085

Chapter 42: The iPad 1089
Deployment platforms 1090
The split view controller 1092
Improve the secondary pane 1097
Fix the Detail pop-up for iPhone 1104
Size classes in the storyboard 1107
Your own popover 1113
Send e-mail from the app 1116
Landscape on bigger iPhones 1120
Chapter 43: Distributing the App 1125
Join the Apple Developer program 1126
Beta testing 1127
Submit for review 1146
The end 1149
Conclusion 1151

Book License

By purchasing *UIKit Apprentice*, you have the following license:

- You are allowed to use and/or modify the source code in *UIKit Apprentice* in as many apps as you want, with no attribution required.
- You are allowed to use and/or modify all art, images and designs that are included in *UIKit Apprentice* in as many apps as you want, but must include this attribution line somewhere inside your app: "Artwork/images/designs: from *UIKit Apprentice*, available at www.raywenderlich.com".
- The source code included in *UIKit Apprentice* is for your personal use only. You are NOT allowed to distribute or sell the source code in *UIKit Apprentice* without prior authorization.
- This book is for your personal use only. You are NOT allowed to sell this book without prior authorization, or distribute it to friends, coworkers or students; they would need to purchase their own copies.

All materials provided with this book are provided on an "as is" basis, without warranty of any kind, express or implied, including but not limited to the warranties of merchantability, fitness for a particular purpose and non-infringement. In no event shall the authors or copyright holders be liable for any claim, damages or other liability, whether in an action of contract, tort or otherwise, arising from, out of or in connection with the software or the use or other dealings in the software.

All trademarks and registered trademarks appearing in this guide are the properties of their respective owners.

Before You Begin

This section tells you a few things you need to know before you get started, such as what you'll need for hardware and software, where to find the project files for this book and more.

What You Need

To follow along with this book, you'll need the following:

- A **Mac computer with an Intel/ARM processor**. Any Mac that you've bought in the last few years will do, even a Mac mini or MacBook Air.
- **Xcode 13 and Swift 5.5**: Xcode is the main development tool for writing code in Swift. You'll need Xcode 13 at a minimum, since that version includes Swift 5.5. You can download the latest version of Xcode for free from the Mac App Store.
- Optionally, an **iPhone, iPad, or iPod touch** running iOS 15.

Book Source Code & Forums

Book source code

The materials for this book are all available in the GitHub repository here:

- https://github.com/raywenderlich/ia-materials/tree/editions/10.0

You can download the entire set of materials for the book from that page.

Forum

We've also set up an official forum for the book at https://forums.raywenderlich.com/c/books/uikit-apprentice/. This is a great place to ask questions about the book or to submit any errors you may find.

"For my parents and my wife."

— Fahim Farook

"To Floortje, my familiar. Thanks for all the cuddles!"

— Matthijs Hollemans

About the Authors



Fahim Farook is the author of this book. He is a developer with over 30 years of experience in developing in over a dozen different languages. Fahim's current focus is on mobile development with over 100+ iOS apps, 10+ macOS apps, a few Android apps, and several Flutter apps under his belt. He has lived in Sri Lanka, USA, Saudi Arabia, New Zealand, Singapore, Malaysia, France, the UAE, Spain, and Canada, and enjoys science fiction and fantasy novels, TV shows, and movies. You can follow Fahim on Twitter at @FahimFarook (https://twitter.com/FahimFarook).

Acknowledgments

Content Development

We would like to thank **Matthijs Hollemans** as one of the original authors of this book.
He is a mystic who lives at the top of a mountain where he spends all of his days and nights coding up awesome apps. Actually he lives below sea level in the Netherlands and is pretty down-to-earth but he does spend too much time in Xcode. Check out his website at www.matthijshollemans.com.

Section 1: Getting Started

This section introduces you to the first of the four apps you'll build over the course of this book — *Bull's Eye*.

As you progress through building the Bull's Eye app, the section will teach you how to think like a programmer and how to plan your programming tasks. In addition, you'll also learn how to use Xcode, Interface Builder, and even the basics of coding for iOS.


While some of the concepts in this section might seem a bit basic, please do not skip this section if you are new to iOS development – you will learn some fundamentals which act as the building blocks for what you learn later.

Chapter 1: Introduction

By Fahim Farook

Hi, welcome to *The UIKit Apprentice: Beginning iOS Development with Swift, Second Edition*, the swiftest way — if you'll pardon the pun — to iOS development mastery!

In this book, you'll learn how to make your own iPhone and iPad apps using Apple's Swift programming language (and Xcode 13) and the iOS UIKit framework, by building four interesting iOS apps.



The apps you'll be making in The UIKit Apprentice

Everybody likes games, right? So, you'll start by building a simple but fun iPhone game named *Bull's Eye*. It will teach you the basics of iPhone programming, and the other apps will build on what you learn there.

Taken together, the four apps that you'll build cover everything you need to know to make your own apps. By the end of the book, you'll be experienced enough to turn your ideas into real apps that you can put on the App Store!

Even if you've never programmed before, or if you're new to iOS, you should be able to follow along with the step-by-step instructions and understand how these apps are made. Each chapter has a ton of illustrations to prevent you from getting lost. Not everything might make sense right away, but hang in there and all will become clear in time.

Writing your own iOS apps is a lot of fun, but it's also hard work. If you have the imagination and perseverance, there is no limit to what you can make your apps do. It is my sincere belief that this book can turn you from a complete newbie into an accomplished iOS developer, but you do have to put in the time and effort. By writing this book, I've done my part. The rest is up to you…

About this book

The UIKit Apprentice will help you focus on developing applications for iOS using Apple's UIKit framework. There are other ways to develop iOS user interfaces (UI) too — such as using SwiftUI. If you are interested in that approach, you can take a look at our other book, *SwiftUI Apprentice*.

This book will help you become an excellent iOS developer, but only if you let it. Here are some tips that will help you get the most out of this book.

Learn through repetition

You're going to make several apps in this book. Even though the apps will start out quite simple, you may find the instructions hard to follow at first — especially if you've never done any computer programming before — because I will introduce a lot of new concepts.

It's OK if you don't understand everything right away, as long as you get the general idea. As you proceed through the book, you'll go over many of these concepts again and again until they solidify in your mind.

Follow the instructions yourself

It is important that you not just read the instructions but also actually **follow them**. Open Xcode, type in the source code fragments, and run the app in the simulator as instructed. This helps you to see how the app gets built step by step.

Even better, play around with the code and with the Xcode settings. Feel free to modify any part of the app and see what the results are — make a small change to the code and see how it affects the entire app. Experiment and learn! Don't worry about breaking stuff — that's half the fun. You can always find your way back to the beginning. But better still, you might even learn something from simply breaking the code and learning how to fix it.

If you try everything but are still stuck, the forums for this book are at https://forums.raywenderlich.com/c/books/uikit-apprentice/, so drop by. I'm around most of the time and will be happy to answer any questions related to the book and any issues you might have run into.

Don't panic — bugs happen!

You will run into problems, guaranteed. Your programs will have strange bugs that will leave you stumped. Trust me, I've been programming for 30 years and that still happens to me, too. We're only humans and our brains have a limited capacity to deal with complex programming problems. In this book, I will give you tools for your mental toolbox that will allow you to find your way out of any hole you have dug for yourself.

Understanding beats copy-pasting

Too many people attempt to write iOS apps by blindly copy-pasting code that they find on blogs and other websites, without really knowing what that code does, or how it should fit into their programs.

There is nothing wrong with looking on the web for solutions — I do it all the time — but I want to give you the tools and knowledge to understand what you're doing and why. That way, you'll learn quicker and write better programs.

This is hands-on practical advice, not a bunch of dry theory — although we can't avoid *some* theory. You are going to build real apps right from the start, and I'll explain how everything works along the way, with lots of images that illustrate what is going on.

I will do my best to make it clear how everything fits together, why we do things a certain way and what the alternatives are.

Do the exercises

I will also ask you to do some thinking of your own — yes, there are exercises! It's in your best interest to actually do these exercises. There is a big difference between knowing the path and walking the path... And the only way to learn programming is to do it.

I encourage you to not just do the exercises but also to play with the code you'll be writing. Experiment, make changes, try to add new features. Software is a complex piece of machinery, and to find out how it works, you sometimes have to put some spokes in the wheels and take the whole thing apart. That's how you learn!

Have fun!

Last but not least, remember to have fun! Step by step, you will build up your understanding of programming while making fun apps. By the end of this book, you'll have learned the essentials of Swift and the iOS Software Development Kit (SDK). More importantly, you should have a pretty good idea of how everything goes together and how to think like a programmer.

It's my aim that, by the time you reach the end of the book, you will have learned enough to stand on your own two feet as a developer. I am confident that, eventually, you'll be able to write any iOS app that you want as long as you get those basics down. You still may have a lot to learn but, when you're through with *The UIKit Apprentice*, you can do it without the training wheels.

Who this book is for

This book is great whether you are completely new to programming or if you come from a different programming background and are looking to learn iOS development.

If you're a complete beginner, don't worry — this book doesn't assume you know anything about programming or making apps. Of course, if you do have programming experience, that helps. Swift is a new programming language but, in many ways, it's similar to other popular languages such as PHP, C#, or JavaScript.

If you've tried iOS development before with the old language, Objective-C, then its low-level nature and strange syntax may have put you off. Well, there's good news: Now that we have a modern language in Swift, iOS development has become a lot easier to pick up.

It is not my aim, with this book, to teach you all the ins and outs of iOS development. The iOS SDK is huge and there is no way we can cover everything. Fortunately, we don't need to. You just need to master the essential building blocks of Swift and the iOS SDK. Once you understand these fundamentals, you can easily figure out how the other parts of the SDK work and learn the rest on your own terms.

The most important thing I'll teach you is how to think like a programmer. That will help you approach any programming task, whether it's a game, a utility, a mobile app that uses web service or anything else you can imagine.

As a programmer, you'll often have to think your way through difficult computational problems and find creative solutions. By methodically analyzing these problems, you will be able to solve them, no matter how complex. Once you possess this valuable skill, you can program anything!

iOS 15 and later only

The code in this book is aimed exclusively at iOS version 15 and later. Each new release of iOS is such a big departure from the previous one that it just doesn't make sense anymore to keep developing for older devices and iOS versions. Things move fast in the world of mobile computing!

The majority of iPhone, iPod touch and iPad users are pretty quick to upgrade to the latest version of iOS anyway, so you don't need to be too worried that you're leaving potential users behind.

Owners of older devices may be stuck with older iOS versions, but this is only a tiny portion of the market. The cost of supporting these older iOS versions for your apps is usually greater than the handful of extra customers it brings you.

It's ultimately up to you to decide whether it's worth making your app available to users with older devices, but my recommendation is that you focus your efforts where they matter most. Apple, as a company, relentlessly looks towards the future — if you want to play in Apple's backyard, it's wise to follow its lead. So back to the future it is!

What you need

It's a lot of fun to develop for the iPhone and iPad but, like most hobbies (or businesses!), it will cost some money. Of course, once you get good at it and build an awesome app, you'll have the potential to make that money back many times.

You will have to invest in the following:

iPhone, iPad or iPod touch. I'm assuming that you have at least one of these. iOS 15 runs on the following devices:

- iPhone 6s and 6s Plus or newer
- iPhone SE 1st and 2nd generation
- iPad 5th generation or newer
- iPad Air 2 or newer
- iPad mini 4 or newer
- iPad Pro (any generation)
- iPod touch 7th generation or newer

If you have an older device, then this is a good time to think about getting an upgrade. But don't worry if you don't have a suitable device: You can do most of your testing on iOS Simulator.

> **Note:** Even though I mostly write about developing for the iPhone in this book, everything I write applies equally to the iPad and iPod touch. Aside from small hardware differences, they all use iOS (or iPadOS on the iPad) and you program them in exactly the same way. You should also be able to run the apps from this book on your iPad or iPod touch without problems.

Mac computer with an Intel processor: Any Mac that you've bought in the last few years will do, even a Mac mini or MacBook Air. It needs to have at least macOS Big Sur 11.3. Xcode, the development environment for iOS apps, is a memory-hungry tool. So having at least 16 GB of RAM in your Mac would be preferable. You can get by with less, but do yourself a favor and upgrade your Mac. The more RAM, the better. A smart developer invests in good tools!

With some workarounds, it's possible to develop iOS apps on Windows or a Linux machine, or a regular PC that has macOS installed (a "Hackintosh"), but you'll save yourself a lot of hassle by just getting a Mac.

If you can't afford to buy the latest model, then consider getting a second-hand Mac from eBay or some other resale vendor. Just make sure it meets the minimum requirements — Intel CPU, preferably 8 GB RAM or more. Should you happen to buy a machine that has an older version of macOS (earlir than Big Sur 11.3 or earlier), you can upgrade to the latest version of macOS from the online Mac App Store for free.

Apple Developer Program account: You can download all the development tools for free, and you can try out your apps on your own iPhone, iPad or iPod touch while you're developing, so you don't have to join the Apple Developer Program just yet. But to submit finished apps to the App Store, you will have to enroll in the paid Developer Program. This will cost you $99 per year.

See developer.apple.com/programs/ for more info.

Xcode

The first order of business is to download and install Xcode and the iOS SDK.



Xcode is the development tool for iOS apps. It has a text editor where you'll type in your source code, and it has a visual editor for designing your app's user interface.

Xcode transforms the source code that you write into an executable app and launches it in the iOS Simulator or on your iPhone/iPad. Because no app is bug-free, Xcode also has a debugger that helps you find defects in your code. Unfortunately, it won't automatically fix them for you; that's still something you have to do yourself.

You can download Xcode for free from the Mac App Store (apple.co/2wzi1L9). This requires an up-to-date version of macOS Big Sur 11.3 or later. So, if you're still running an older version of macOS, you'll first have to upgrade to the latest version of macOS — also available for free from the Mac App Store. Get ready for a big download, as the full Xcode package is over 11 GB!

Important: You may already have a version of Xcode on your system that came pre-installed with your version of macOS. That version could be hopelessly outdated, so don't use it. Apple puts out new releases of Xcode on a regular basis and you are encouraged to always develop with the latest Xcode and the latest available SDK on the latest version of macOS.

This revision of the book was written using **Xcode version 13** and the **iOS 15** SDK on **macOS Big Sur (11.4)**. By the time you're reading this, the version numbers might have gone up again. We will do our best to keep the PDF versions of the book up-to-date with new releases of the development tools and iOS versions, but don't panic if the screenshots don't correspond 100% to what you see on your screen. In most cases, the differences will be minor.

Many older books and blog posts (anything before 2014) talk about iOS development in Xcode 5 or earlier. Ignore them; they're from an earlier era of iOS development and use a completely different programming language. If you're look at an article or book that predates Swift, it's seriously out of date.

More recent materials may mention Xcode versions 6 all the way to 12, which, at first glance, are similar to Xcode 13, but may differ in some of the details.


So if you're reading an article and you see a picture of Xcode that looks different from yours, the author might be writing about an older version. You may still be able to get something out of those articles, as the programming examples are still valid. It's just Xcode that is slightly different.

What's ahead: an overview

The UIKit Apprentice is spread across four apps, moving from beginning to intermediate topics. For each app, you will build it from start to finish, from scratch! Let's take a look at what's ahead.


App 1: Bull's Eye

You'll start by building a game called *Bull's Eye*. You'll learn how to use Xcode, Interface Builder, and Swift in an easy-to-understand manner.




App 2: Checklists

For your next app, you'll create your own to-do list app. You'll learn about the fundamental design patterns that all iOS apps use, and about table views, navigation controllers and delegates. Now you're making apps for real!




App 3: MyLocations

For your third app, you'll develop a location-aware app that lets you keep a list of spots that you find interesting. In the process, you'll learn about Core Location, Core Data, Map Kit, and much more!



App 4: StoreSearch

Mobile apps often need to talk to web services and that's what you'll do in your final app. You'll make a stylish app that lets you search for products on the iTunes store using HTTP requests and JSON.



Let's get started and turn you into a full-fledged iOS developer!

★ ★ ★

The language of the computer

The iPhone may pretend that it's a phone, but it's really a pretty advanced computer that also happens to have the ability to make phone calls.

Like any computer, the iPhone works with ones and zeros. When you write software to run on iPhone, you somehow have to translate the ideas in your head into those ones and zeros that the computer can understand.

Fortunately, you don't have to write any ones and zeros yourself. That would be a bit too much to ask of the human brain. On the other hand, everyday English is not precise enough to use for programming computers.

So you will use an intermediary language, Swift, that is a little bit like English, so it's reasonably straightforward for us humans to understand; at the same time, it can be easily translated into something the computer can understand as well.

This is an approximation of the language that the computer speaks:

```
Ltmp96:
    .cfi_def_cfa_register %ebp
    pushl   %esi
    subl    $36, %esp
Ltmp97:
    .cfi_offset %esi, -12
    calll   L7$pb
L7$pb:
    popl    %eax
    movl    16(%ebp), %ecx
    movl    12(%ebp), %edx
    movl    8(%ebp), %esi
    movl    %esi, -8(%ebp)
    movl    %edx, -12(%ebp)
    movl    %ecx, (%esp)
    movl    %eax, -24(%ebp)
    calll   _objc_retain
    movl    %eax, -16(%ebp)
    .loc    1 161 2 prologue_end
```

Actually, what the computer sees is this:

```
00011001010011111010010001100111111001010
00101000100111101011011100111010110100 1
01010001110011111101011101100001110001 10
10010000011100010100110100111100110011 1
```

The `movl` and `calll` instructions are just there to make things more readable for humans. I don't know about you, but for me it's still hard to make much sense out of it.

It certainly is possible to write programs in that arcane language — that is what people used to do in the old days when computers cost a few million bucks apiece and took up a whole room — but I'd rather write programs that look like this:

```
func handleMusicEvent(command: Int, noteNumber: Int, velocity:
Int) {

  if command == NoteOn && velocity != 0 {
    playNote(noteNumber + transpose, velocityCurve[velocity] /
127)

  } else if command == NoteOff ||
          (command == NoteOn && velocity == 0) {
    stopNote(noteNumber + transpose, velocityCurve[velocity] /
127)

  } else if command == ControlChange {
    if noteNumber == 64 {
      damperPedal(velocity)
    }
  }
}
```

This code snippet is from a sound synthesizer program. It looks like something that almost makes sense. Even if you've never programmed before, you can sort of figure out what's going on. It's almost English.

Swift is a hot new language that combines traditional object-oriented programming with aspects of functional programming. Fortunately, Swift has many things in common with other popular programming languages, so if you're already familiar with C#, Python, Ruby or JavaScript, you'll feel right at home with Swift.

Swift is not the only option for making apps. Until just a few years ago, iOS apps were programmed in Objective-C, which is an object-oriented extension of the tried-and-true C language. Because of its heritage, Objective-C has some rough edges and is not really up to the demands of modern developers. That's why Apple created a new language.

Objective-C will still be around for a while, but it's obvious that the future of iOS development is Swift. All the cool kids are using it already.

C++ is another language that adds object-oriented programming to C. It is very powerful, but as a beginning programmer, you probably want to stay away from it. I only mention it because C++ can also be used to write iOS apps, and there is an unholy marriage of C++ and Objective-C named Objective-C++ that you may come across from time to time.



I could have started *The UIKit Apprentice* with an in-depth exploration of the features of Swift, but you'd probably fall asleep halfway. So, instead, I will explain the language as we go along — very briefly at first, but more in-depth later.

In the beginning, the general concepts — what is a variable, what is an object, how do you call a method, and so on — are more important than the details. Slowly but surely, all the arcane secrets of the Swift language will be revealed to you!

Are you ready to begin writing your first iOS app?

Chapter 2: The One-Button App

By Fahim Farook


There's an old Chinese proverb that says, "A journey of a thousand miles begins with a single step." You are about to take that first step on your journey to iOS developer mastery. And you will take that first step by creating the *Bull's Eye* game.

This chapter covers the following:

- **The Bull's Eye game:** An introduction to the first app you'll make.
- **The one-button app:** Creating a simple one-button app in which the button can take an action based on a tap on the button.
- **The anatomy of an app:** A brief explanation as to the inner-workings of an app.

The Bull's Eye game


This is what the *Bull's Eye* game will look like when you're finished:



The finished Bull's Eye game

The objective of the game is to put the bull's eye, which is on a slider that goes from 1 to 100, as close to a randomly chosen target value as you can. In the screenshot above, the aim is to put the bull's eye at 84. Because you can't see the current value of the slider, you'll have to "eyeball" it.

When you're confident of your estimate, you press the "Hit Me!" button and a pop-up, also known as an alert, will tell you what your score is:



An alert pop-up shows the score

The closer to the target value you are, the more points you score. After you dismiss the alert pop-up by pressing the OK button, a new round begins with a new random target. The game repeats until the player presses the "Start Over" button (the curly arrow in the bottom-left corner), which resets the score to 0.

This game probably won't make you an instant millionaire on the App Store, but even future millionaires have to start somewhere!

Making a programming to-do list

> **Exercise:** Now that you've seen what the game will look like and what the gameplay rules are, make a list of all the things that you think you'll need to do in order to build this game. It's OK if you draw a blank, but give it a shot anyway.

I'll give you an example:

The app needs to put the "Hit Me!" button on the screen and show an alert pop-up when the user presses it.

Try to think of other things the app needs to do — it doesn't matter if you don't actually know how to accomplish these tasks. The first step is to figure out *what* you need to do; *how* to do these things is not important yet.

Once you know what you want, you can also figure out how to do it, even if you have to ask someone or look it up. But the "what" comes first. You'd be surprised at how many people start writing code without a clear idea of what they're actually trying to achieve. No wonder they get stuck!

Whenever I start working on a new app, I first make a list of all the different pieces of functionality I think the app will need. This becomes my programming to-do list. Having a list that breaks up a design into several smaller steps is a great way to deal with the complexity of a project.

You may have a cool idea for an app, but when you sit down to write the program it can seem overwhelming. There is so much to do… and where to begin? By cutting up the workload into small steps you make the project less daunting – you can always find a step that is simple and small enough to make a good starting point and take it from there.

It's no big deal if this exercise gives you some difficulty. You're new to all of this! As your understanding grows of how software and the development process works, it will become easier to identify the different parts that make up a design and to split it into manageable pieces.

This is what I came up with. I simply took the gameplay description and split it into very small chunks:


- Put a button on the screen and label it "Hit Me!"
- When the player presses the Hit Me! button, the app has to show an alert pop-up to inform the player how well he or she did. Somehow, you have to calculate the score and put that into this alert.
- Put text on the screen, such as the "Score:" and "Round:" labels. Some of this text changes over time; for example, the score, which increases when the player scores points.
- Put a slider on the screen with a range between the values 1 and 100.
- Read the value of the slider after the user presses the Hit Me! button.
- Generate a random number at the start of each round and display it on the screen. This is the target value.
- Compare the value of the slider to that random number and calculate a score based on how far off the player is. You show this score in the alert pop-up.
- Put the Start Over button on the screen. Make it reset the score and put the player back to the first round.
- Put the app in landscape orientation.
- Make it look pretty. :]

I might have missed a thing or two, but this looks like a decent list to start with. Even for a game as basic as this, there are quite a few things you need to do. Making apps is fun, but it's definitely a lot of work, too!

The one-button app

Let's start at the top of the list and make an extremely simple first version of the game that just displays a single button. When you press the button, the app pops up an alert message. That's all you are going to do for now. Once you have this working, you can build the rest of the game on this foundation.

The app will look like this:



The app contains a single button (left) that shows an alert when pressed (right)

Time to start coding! I'm assuming you have downloaded and installed the latest version of Xcode at this point.


In this book, you'll work with **Xcode 13.0** or better. Newer versions of Xcode may also work, but anything older than version 13.0 probably would be a no-go.

Because Swift is a new-ish language, it tends to change between versions of Xcode. If your Xcode is too old — or too new! — then not all of the code in this book may work properly. For this same reason, you're advised not to use beta versions of Xcode, only the official one from the Mac App Store.

Creating a new project


➤ Launch Xcode. If you have trouble locating the Xcode application, you can find it in the **/Applications** folder or in your Launchpad. Because I use Xcode all of the time, I've placed it in my dock for easy access.

Xcode shows the "Welcome to Xcode" window when it starts:



Xcode bids you welcome

➤ Choose **Create a new Xcode project**. The main Xcode window appears with an assistant that lets you choose a template:




Choosing the template for the new project

Xcode has bundled templates for a variety of app styles. Xcode will make a pre-configured project for you based on the template you choose. The new project will already include some of the source files you need. These templates are handy because they can save you a lot of typing. They are ready-made starting points.

➤ Select **App** and press **Next**.

This opens a dialog where you can enter options for the new app.



Configuring the new project


➤ Fill out these options as follows:

- Product Name: **BullsEye**. If you want to use proper English, you can name the project Bull's Eye instead of BullsEye, but it's best to avoid spaces and other special characters in project names.
- Team: If you're already a member of the Apple Developer Program, this will show your team name. For now, it's best to leave this setting alone; we'll get back to this later on.
- Organization Identifier: Mine says "com.razeware". That is the identifier I use for my apps. As is customary, it is my domain name written in reverse. You should use your own identifier here. Pick something that is unique to you, either the domain name of your website (but backwards) or simply your own name. You can always change this later.

- Interface: Set this to (or leave as) **Storyboard**. The other option for this dropdown is SwiftUI. That lets you develop applications using SwiftUI, which we won't be covering in this book since our focus is on developing using UIKit.
- Language: **Swift**. This is basically the programming language you'll be using. The other option is Objective-C, but our focus will be on Swift.

Make sure the two options at the bottom — Use Core Data and Include Tests — are *not* selected. You won't use those in this project.

➤ Press **Next**. Now, Xcode will ask where to save your project:



Choosing where to save the project

➤ Choose a location for the project files; for example, the Desktop or your Documents folder.


Xcode will automatically make a new folder for the project using the Product Name that you entered in the previous step (in your case, BullsEye), so you don't need to make a new folder yourself.

At the bottom of the File Save dialog, there is a checkbox that says, "Create Git repository on My Mac." You can ignore this for now. You'll learn about the Git version control system later on.

➤ Press **Create** to finish.

Xcode will now create a new project named BullsEye, based on the template you selected, in the folder you specified.

When it is done, the screen should look something like this:




The main Xcode window at the start of your project

There may be small differences with what you're seeing on your own computer if you're using a version of Xcode newer than my version. Rest assured, any differences will only be superficial.

> **Note:** If you don't see a file named ViewController.swift in the list on the left but instead have ViewController.h and ViewController.m, then you picked the wrong language (Objective-C) when you created the project. Start over and be sure to choose **Swift** as the programming language.

Running your project


➤ Press the **Run** button in the top-left corner.



Press Run to launch the app

> **Note:** If this is the first time you're using Xcode, it may ask you to enable developer mode. Click **Enable** and enter your password to allow Xcode to make these changes.
>
> Also, make sure that you do not have your iPhone or iPad plugged in at this point to your computer — for example, for charging. If you do, it might switch to the actual device instead of the simulator for running the app and, since you are not yet set up for running on a device, this could result in errors that might leave you scratching your head.

Xcode will labor for a bit and then launch your brand new app in an iOS Simulator. The app may not look like much yet — and there is not anything you can do with it either — but this is an important first milestone in your journey!



What an app based on the Single View Application template looks like

If Xcode says "Build Failed" or "Xcode cannot run using the selected device" when you press the Run button, then make sure the picker at the top of the window says **BullsEye > iPod touch** (or any other device model) and not **Generic iOS Device**:



Making Xcode run the app on the Simulator

If your iPhone is currently connected to your Mac via USB cable, Xcode may have attempted to run the app on your iPhone, and that may not work without some additional setting up. I'll show you how to get the app to run on your iPhone so that you can show it off to your friends soon, but for now just stick with the iOS Simulator.

➤ To the left of the Run button is the **Stop** button (the square thingy). Press that to exit the app.

On your phone (or even the simulator), you'd use the Home button to exit an app (on the simulator, you could also use the **Device ▸ Home** item from the menu bar or use the handy ⇧+⌘+**H** shortcut), but that won't actually terminate the app. The app will disappear from the simulator's screen, but it stays suspended in the simulator's memory, just as it would on a real iPhone.

Until you press Stop, Xcode's Activity viewer at the top says, "Running BullsEye on iPod touch":



The Xcode activity viewer

It's not really necessary to stop the app, as you can go back to Xcode and make changes to the source code while the app is still running. However, these changes will not become active until you press Run again. That will terminate any running version of the app, build a new version, and launch it in the simulator.

What happens when you press Run?

Xcode will first *compile* your source code — that is, translate it – from Swift into machine code that the iPhone (or iOS Simulator) can understand. Even though the programming language for writing iOS apps is Swift or Objective-C, the iPhone itself doesn't speak those languages. A translation step is necessary.

The compiler is the part of Xcode that converts your Swift source code into executable binary code. It also gathers all the different components that make up the app — source files, images, storyboard files and so on — and puts them into the "application bundle."

This entire process is also known as *building* the app. If there are any errors (such as spelling mistakes in your code), the build will fail. If everything goes according to plan, Xcode copies the application bundle to the simulator or the iPhone and launches the app. All that from a single press of the Run button.


Adding a button

I'm sure you're as unimpressed as I am with an app that just displays a dull white screen! So let's make it a bit more interesting by adding a button to it.

The left pane of the Xcode window is named the **Navigator area**. The row of icons along the top lets you select a specific navigator. The default navigator is the **Project navigator**, which shows the files in your project.

The organization of these files corresponds to the project folder on your hard disk, but that isn't necessarily always so. You can move files around and put them into new groups and organize away to your heart's content. We'll talk more about the different files in your project later.


➤ In the **Project navigator**, find the item named **Main.storyboard** and click it once to select it:



The Project navigator lists the files in the project


Like a superhero changing his or her clothes in a phone booth, the main editing pane now transforms into the **Interface Builder**. This tool lets you drag-and-drop user interface components such as buttons to create the UI of your app. (OK, maybe a bad analogy, but Interface Builder is a super tool, in my opinion.)

➤ If there is no sidebar on the right side of the Xcode window, click the **Hide or show the inspectors** button in the right-hand side of Xcode's toolbar.



Click this button to show the Utilities pane

This toolbar button opens the **Inspectors pane** on the right side of the Xcode window. Your Xcode window should now look something like this:



Editing Main.storyboard in Interface Builder

This is the *storyboard* for your app. The storyboard contains the designs for all of your app's screens and shows the navigation flow in your app from one screen to another.

Currently, the storyboard contains just a single screen or *scene*, represented by the big white device frame in the middle of the Interface Builder canvas.

The grey frame enclosing the smaller white frame on the top right, in case you're wondering, is the minimap. It shows a preview of the whole canvas so that you can navigate around quickly — you'll see how it works as you add more screens to your app.

Given that there are many devices of differing screen sizes, the scene could be set to any of the available iPhone sizes. To keep things simple, you will first design the app for the iPhone SE, which has one of the smallest available screen sizes. Later, you'll also make the app fit on the larger iPhone models.

➤ At the bottom of the Interface Builder window, click the tiny screen icon to the left of the text saying **iPhone 11** — depending on your Xcode, it might say something other than "iPhone 11" — to open up the following pop-up:



Choosing the device type


Select **iPhone SE (2nd Generation)** from the list of devices. This will change (and resize) the preview UI you see in Interface Builder to that of an iPhone SE.

➤ In the Xcode toolbar, make sure it says **BullsEye > iPhone SE (2nd Generation)** in the central area, like this:



Switching the Simulator to iPhone SE

➤ If it doesn't, then click the Choose Device dropdown and pick **iPhone SE** from the list:




Switching the Simulator to iPhone SE

Now, when you run the app, it will run on the iPhone SE (2nd Generation) Simulator (try it out!).

Back to the storyboard:


➤ The plus (+) button on the top toolbar shows the **Library** panel when you click it:



The Object Library

Select **Button** from the Object Library list (or scroll till you see it). Alternatively, you can type the word "button" in to the search/filter box at the top.

➤ Click on **Button** and drag it onto the working area, on top of the scene's rectangle.



Dragging the button on top of the scene

That's how easy it is to add most new UI (user interface) items — just drag and drop. You'll do a lot of this, so take some time to get familiar with the process.

Drag and drop a few other controls, such as labels, sliders, and switches, just to get the hang of it. Once you are done, delete everything except for the first button you added.

This should give you some idea of the UI controls that are available in iOS. Notice that the Interface Builder helps you to lay out your controls by snapping them to the edges of the view and to other objects. It's a very handy tool!

➤ Double-click the button to edit its title. Call it Hit Me!



The button with the new title

It's possible that your button might have a border around it:



The button with a bounds rectangle


This border is not part of the button, it's just there to show you how large the button is. You can turn these borders on or off using the **Editor ▸ Canvas ▸ Bounds Rectangles** menu option. When you're done playing with Interface Builder, press the Run button from Xcode's toolbar. The app should now appear in the simulator, complete with your "Hit Me!" button. However, when you tap the button, it doesn't do anything yet. For that, you'll have to write some Swift code!

Using the source code editor

A button that doesn't do anything when tapped is of no use to anyone. So let's make it show an alert pop-up. In the finished game, the alert will display the player's score. For now, you will limit yourself to a simple text message (the traditional "Hello, World!").

➤ In the **Project navigator**, click on **ViewController.swift**.

A new tab will be added to the Xcode interface alongside the Interface Builder tab and the editor area in the new tab will contain a bunch of colored text. This is the Swift source code for the main view of your app:



The source code editor

> **Note:** If your Xcode editor window does not show the line numbers as in the screenshot above, and you'd actually like to see the line numbers, from the menu bar choose **Xcode ▸ Preferences... ▸ Text Editing** and go to the **Display** tab. There, you should see a **Line numbers** checkbox under **Show** — check it.

➤ Add the following lines directly **above** the very last } bracket in the file:

```
@IBAction func showAlert() {
}
```

The source code for **ViewController.swift** should now look like this:

```
import UIKit

class ViewController: UIViewController {
  override func viewDidLoad() {
    super.viewDidLoad()
    // Do any additional setup after loading the view.
  }

  @IBAction func showAlert() {
  }
}
```

Yes, that code leaves out the bunch of grey text above the code with a copyright notice. And that's totally fine since that text is just a comment block, or notes for developers, and not a necessary part of the code.

Before I can tell you what the code means, I have to introduce the concept of a view controller.

Xcode will autosave

You don't have to save your files after you make changes to them because Xcode will automatically save any modified files when you press the Run button.

Nevertheless, Xcode isn't the most stable piece of software out there and, occasionally, it may crash on you before it has had a chance to save your changes.

Therefore, do remember to press **⌘+S** on a regular basis to save any changes that you've made.

★ ★ ★


View controllers

You've edited the **Main.storyboard** file to build the user interface of the app. It's only a button on a white background, but a user interface nonetheless. You also added source code to **ViewController.swift**.

These two files — the storyboard and the Swift file — together form the design and implementation of a *view controller*. A lot of the work in building iOS apps is making view controllers. The job of a view controller, generally, is to manage a single screen in your app.

Take a simple cookbook app, for example. When you launch the cookbook app, its main screen lists the available recipes. Tapping a recipe opens a new screen that shows the recipe in detail with an appetizing photo and cooking instructions.

Each of these screens is managed by a view controller.



The view controllers in a simple cookbook app

What these two screens do is very different. One is a list of several items; the other presents a detail view of a single item.

That's why you need two view controllers: One that knows how to deal with lists and another that can handle images and cooking instructions. One of the design principles of iOS is that each screen in your app gets its own view controller.

★ ★ ★

Currently, *Bull's Eye* has only one screen (the white one with the button) and thus only needs one view controller. That view controller is simply named "ViewController," and the storyboard and Swift file work together to implement it. (If you are curious, you can check the connection between the screen and the code for it by switching to the Identity inspector on the right sidebar of Xcode in the storyboard view. The Class value shows the current class associated with the storyboard scene.)


Simply put, the Main.storyboard file contains the design of the view controller's user interface, while ViewController.swift contains its functionality — the logic that makes the user interface work, written in the Swift language.

Because you used the App template, Xcode automatically created the view controller for you. Later, you will add a second screen to the game and you will create your own view controller for that.

Making connections


The two lines of source code you just added to ViewController.swift lets Interface Builder know that the controller has a "showAlert" action, which presumably will show an alert pop-up. You will now connect the button on the storyboard to that action in your source code.

➤ Click the **Main.storyboard** tab to go back into Interface Builder.



Select the storyboard tab

➤ In Interface Builder, there should be a second pane on the left, next to the navigator area, called the **Document Outline**, that lists all the items in your storyboard. If you do not see that pane, click the small toggle button on the very left of the Interface Builder toolbar to reveal it.




The button that shows the Document Outline pane

➤ Click the **Hit Me! button** once to select it.

With the Hit Me! button selected, hold down the **Control** key, click on the button and drag up to the **View Controller** item in the Document Outline. You should see a blue line going from the button up to View Controller.


Instead of holding down Control, you can also right-click and drag, but don't let go of the mouse button before you start dragging.



Ctrl-drag from the button to View Controller

Once you're on View Controller, let go of the mouse button and a small menu will appear. It contains several sections: "Action Segue," "Sent Events," and "Non-Adaptive Action Segue," with one or more options below each. You're interested in the **showAlert** option under Sent Events.

The Sent Events section shows all possible actions in your source code that can be hooked up to your storyboard — **showAlert** is the name of the action that you added earlier in the source code of **ViewController.swift**.



The pop-up menu with the showAlert action

➤ Click on **showAlert** to select it. This instructs Interface Builder to make a connection between the button and the line `@IBAction func showAlert()`.

From now on, whenever the button is tapped the `showAlert` action will be performed. That is how you make buttons and other controls do things: You define an action in the view controller's Swift file and then you make the connection in Interface Builder.

You can see that the connection was made by going to the **Connections inspector** in the Utilities pane on the right side of the Xcode window. You should have the button selected when you do this.

➤ Click the last icon at the top of the pane to switch to the Connections inspector:



The inspector shows the connections from the button to any other objects

In the Sent Events section, the "Touch Up Inside" event is now connected to the showAlert action. You should also see the connection in the Swift file.

➤ Select the **ViewController.swift** tab to edit it.

Notice how, to the left of the line with `@IBAction func showAlert()`, there is a solid circle? Click on that circle to reveal what this action is connected to.



A solid circle means the action is connected to something

Acting on the button

You now have a screen with a button. The button is hooked up to an action named `showAlert` that will be performed when the user taps the button. Currently, however, the action is empty and nothing will happen (try it out by running the app again, if you like). You need to give the app more instructions.

➤ In **ViewController.swift**, modify `showAlert` to look like the following:

```
@IBAction func showAlert() {
  let alert = UIAlertController(
    title: "Hello, World",
    message: "This is my first app!",
    preferredStyle: .alert)


  let action = UIAlertAction(
    title: "Awesome",
    style: .default,
    handler: nil)

  alert.addAction(action)
  present(alert, animated: true, completion: nil)
}
```

The new lines of code implement the actual alert display functionality. The commands between the { } brackets of the action tell the iPhone what to do, and they are performed from top to bottom. The code in `showAlert` creates an alert — an iOS component which shows a message — with a title "Hello, World," a message that states, "This is my first app!" and a single button labeled "Awesome."

If you're not sure about the distinction between the title and the message: Both show text, but the title is slightly bigger and in a bold typeface.

➤ Click the **Run** button on Xcode's toolbar. If you didn't make any typos, your app should launch in the iOS Simulator and you should see the alert box when you tap the button.



The alert pop-up in action

Congratulations, you've just written your first iOS app! What you just did may have seemed like gibberish to you, but that shouldn't matter. We'll take it one small step at a time.

You can strike off the first two items from the to-do list already: Putting a button on the screen and showing an alert when the user taps the button.

Take a little break, let it all sink in and come back when you're ready for more! You're only just getting started…

> **Note:** Just in case you get stuck, I have provided the complete Xcode projects, which are snapshots of the project as at the beginning and end of each chapter. That way, you can compare your version of the app to mine, or — if you really make a mess of things — continue from a version that is known to work.

You can find the project files for each chapter in the corresponding folder.

Problems?

If Xcode gives you a "Build Failed" error message after you press Run, then make sure you typed in everything correctly. Even the smallest mistake could potentially confuse Xcode. It can be quite overwhelming at first to make sense of the error messages that Xcode spits out.

A small typo at the top of a source file can produce several errors elsewhere in that file.

One common mistake is differences in capitalization. The Swift programming language is case-sensitive, which means it sees `Alert` and `alert` as two different names. Xcode complains about this with a "Cannot find <something> in scope" error.

When Xcode says things like "Expected <something>" then you probably forgot a curly bracket } or parenthesis) somewhere. Not matching up opening and closing brackets is a common error.


Tip: In Xcode, there are multiple ways to find matching brackets to see if they line up. If you move the editing cursor past a closing bracket, Xcode will highlight the corresponding opening bracket, or vice versa. You could also hold down the ⌘ key and move your mouse cursor over a line with a curly bracket and Xcode will highlight the full block from the opening curly bracket to the closing curly bracket (or vice versa) — nifty!



Xcode shows you the complete block for curly brackets

Tiny details are very important when you're programming. Even one single misplaced character can prevent the Swift compiler from building your app.


Fortunately, such mistakes are easy to find.



Xcode makes sure you can't miss errors

When Xcode detects an error, it switches the pane on the left from the Project navigator, to the **Issue navigator**, which shows all the errors and warnings that Xcode has found. (You can go back to the project navigator using the small icons along the top of the left pane.) In the above screenshot, apparently, I forgot a comma.

Click on the error message in the Issue navigator and Xcode takes you to the line in the source code with the error. Sometimes, depending on the error, it even suggests a fix:



Fix-it suggests a solution to the problem

It could be a bit of a puzzle to figure out what exactly you did wrong when your build fails — fortunately, Xcode lends a helping hand.

Errors and warnings

Xcode makes a distinction between errors (red) and warnings (yellow). Errors are fatal. If you get one, you cannot run the app until the error is fixed. Warnings are informative. Xcode just says, "You probably didn't mean to do this, but go ahead anyway."

In the previous screenshot showing all the error locations via arrows, you'll notice that there is a warning (a yellow triangle) in the Issue navigator. We'll discuss this particular warning and how to fix it later on. Generally though, it is best to treat all warnings as if they were errors. Fix the warning before you continue and only run your app when there are zero errors and zero warnings. That doesn't guarantee the app won't have any bugs, but at least they won't be silly ones!

UIKit

As the name implies, this book deals with programming iOS applications using UIKit. But what exactly is UIKIt?

iOS offers a lot of building blocks in the form of frameworks or "kits." You've used two of these building blocks already to start creating the *Bullseye* app — buttons and alerts. UIKit also manages the view controllers and generally takes care of anything else that deals with your app's user interface. (That is what UI stands for: **U**ser **I**nterface.)

If you had to write all that stuff from scratch, you'd be busy for a long while. Instead, you can build your app on top of the system-provided frameworks and take advantage of all the work the Apple engineers have already put in.

Any object you see whose name starts with UI, such as `UIButton`, comes from UIKit. When you're writing iOS apps, UIKit is the framework you'll spend most of your time with, but there are others as well.

Examples of other frameworks are Foundation, which provides many of the basic building blocks for building apps; Core Graphics for drawing basic shapes such as lines, gradients and images on the screen; AVFoundation for playing sound and video; and many others.

The complete set of frameworks for iOS is known collectively as Cocoa Touch.

★ ★ ★

The anatomy of an app

While you're learning about the bits that help you build iOS apps, it might be good at this point to get some sense of what goes on behind the scenes of an app, too.

An app is essentially made up of **objects** that can send messages to each other. Many of the objects in your app are provided by iOS; for example, the button is a `UIButton` object and the alert pop-up is a `UIAlertController` object. Some objects you will have to program yourself, such as the view controller.

These objects communicate by passing messages to each other. For example, when the user taps the Hit Me! button in the app, that `UIButton` object sends a message to your view controller. In turn, the view controller may message more objects.

On iOS, apps are *event-driven*, which means that the objects listen for certain events to occur and then process them.


As strange as it may sound, an app spends most of its time doing... absolutely nothing. It just sits there waiting for something to happen. When the user taps the screen, the app springs to action for a few milliseconds, and then it goes back to sleep again until the next event arrives.

Your part in this scheme is that you write the source code for the actions that will be performed when your objects receive the messages for such events.

In the app, the button's Touch Up Inside event is connected to the view controller's `showAlert` action. So when the button recognizes it has been tapped, it sends the `showAlert` message to your view controller.

Inside `showAlert`, the view controller sends another message, `addAction`, to the `UIAlertController` object. And to show the alert, the view controller sends the `present` message.

Your whole app will be made up of objects that communicate in this fashion.



The general flow of events in an app

Maybe you have used PHP or Ruby scripts on your web site. This event-based model is different from how a PHP script works. The PHP script will run from top-to-bottom, executing the statements one-by-one until it reaches the end and then it exits.

Apps, on the other hand, don't exit until the user terminates them (or they crash!). They spend most of their time waiting for input events, then handle those events and go back to sleep.

Input from the user, mostly in the form of touches and taps, is the most important source of events for your app, but there are other types of events as well. For example, the operating system will notify your app when the user receives an incoming phone call, when it has to redraw the screen, when a timer has counted down, etc.

Everything your app does is triggered by some event.

★ ★ ★

You can find the project files for the app up to this point under **02-The-one-button-app** in the Source Code folder.

Chapter 3: Slider & Labels


By Fahim Farook

Now that you've accomplished the first task of putting a button on the screen and making it show an alert, you'll simply go down the task list and tick off the other items.

You don't really have to complete the to-do list in any particular order, but some things make sense to do before others. For example, you cannot read the position of the slider if you don't have a slider yet.

So let's add the rest of the controls — the slider and the text labels — and turn this app into a real game!

When you're done, the app will look like this:



The game screen with standard UIKit controls

Hey, wait a minute... that doesn't look nearly as pretty as the game I promised you! The difference is that these are the standard UIKit controls. This is what they look like straight out of the box.

You've probably seen this look before because it is perfectly suitable for regular apps. But because the default look is a little boring for a game, you'll put some special sauce on top later to spiff things up.

In this chapter, you'll cover the following:

- **Portrait vs. landscape**: Switch your app to landscape mode.
- **Objects, data and methods**: A quick primer on the basics of object-oriented programming.
- **Adding the other controls**: Add the rest of the controls necessary to complete the user interface of your app.


Portrait vs. landscape

Notice that in the previous screenshot, the dimensions of the app have changed: The iPhone is rotated to its side and the screen is wider but less tall. This is called *landscape* orientation.

You've no doubt seen landscape apps before on iPhone. It's a common display orientation for games, but many other types of apps work in landscape mode, too, usually in addition to the regular "upright" *portrait* orientation.

For instance, many people prefer to write emails with their device in landscape because the wider screen allows for a bigger keyboard and easier typing.

In portrait orientation, the iPhone SE screen consists of 375 points horizontally and 667 points vertically. For landscape, these dimensions are switched.



Screen dimensions for portrait and landscape orientation

So what is a *point*?

On older devices — up to the iPhone 3GS and corresponding iPod touch models, as well as the first iPads — one point corresponds to one pixel. As a result, these low-resolution devices don't look very sharp because of their big, chunky pixels.

I'm sure you know what a pixel is? In case you don't, it's the smallest element that a screen is made up of — that's how the word originated, a shortened form of pictures, PICS or PIX + ELement = PIXEL. The display of your iPhone is a big matrix of pixels that each can have their own color, just like a television screen. Changing the color values of these pixels produces a visible image on the display. The more pixels, the better the image looks.

On the high-resolution Retina display of the iPhone 4 and later models, one point actually corresponds to two pixels horizontally and vertically, so four pixels in total. It packs a lot of pixels in a very small space, making for a much sharper display, which accounts for the popularity of Retina devices.

On the Plus devices, it's even crazier: They have a 3x resolution with *nine* pixels for every point. Insane! You need to be eagle-eyed to make out the individual pixels on these fancy Retina HD displays. It becomes almost impossible to make out where one pixel ends and the next one begins, that's how minuscule they are!

It's not only the number of pixels that differs between the various iPhone and iPad models. Over the years, they have received different form factors, from the small 3.5-inch screen in the beginning all the way up to 12.9 inches on the iPad Pro model.

The form factor of the device determines the width and height of the screen in points:

Device	Form factor	Screen dimension in points
iPhone 4s and older	3.5"	320 x 480
iPhone 5, 5c, 5s, SE (1st gen)	4"	320 x 568
iPhone 6, 6s, 7, 8, SE (2nd gen)	4.7"	375 x 667
iPhone 6, 6s, 7, 8 Plus	5.5"	414 x 736
iPhone X, Xs, 11 Pro	5.8"	375 x 812
iPhone Xr, 11	6.1"	414 x 896
iPhone Xs Max, 11 Pro Max	6.5"	414 x 896
iPad, iPad mini	9.7" and 7.9"	768 x 1024
iPad Pro	10.5"	834 x 1112
iPad Pro	12.9"	1024 x 1366

In the early days of iOS, there was only one screen size. But those days of "one size fits all" are long gone. Now, we have a variety of screen sizes to deal with.

Remember that UIKit works with points instead of pixels, so you only have to worry about the differences between the screen sizes measured in points. The actual number of pixels is only important for graphic designers because images are still measured in pixels — developers work in points, designers work in pixels.

The difference between points and pixels can be a little confusing, but if that is the only thing you're confused about right now, then I'm doing a pretty good job. ;-)


For the time being, you'll work with just the iPhone SE (2nd generation) screen size of 375×667 points — just to keep things simple. Later on, you'll also make the game fit other iPhone screens.

Converting the app to landscape

To switch the app from portrait to landscape, you have to do two things:

1. Make the view in **Main.storyboard** landscape instead of portrait.
2. Change the **Supported Device Orientations** setting of the app.

➤ Open **Main.storyboard**. In Interface Builder, in the toolbar at the bottom, change **Orientation** to landscape:



Changing the orientation in Interface Builder

This changes the dimensions of the view controller on the canvas. It also puts the button off-center.

> **Note:** It's possible that sometimes the orientation does not change on your Xcode canvas — Xcode is ornery like that :] If this happens, simply change the orientation back to portrait and then switch to landscape again — kinda like the old switch it off and switch it on again trick.

➤ Move the button back to the center of the view because an untidy user interface just won't do in this day and age.



The view in landscape orientation

That takes care of the view layout.

➤ Run the app on iPhone SE Simulator. Note that the screen does not show up as landscape yet, and the button is no longer in the center of the screen.

➤ Choose **Device ▸ Rotate Left** or **Rotate Right** from Simulator's menu bar at the top of the screen. Or, hold ⌘ and press the left or right Arrow keys on your keyboard. This will flip the simulator around.


Now, everything will look as it should.

Notice that in landscape orientation, the app no longer shows the iPhone's status bar. This gives apps more room for their user interfaces.

To finalize the orientation switch, you should do one more thing. There is a configuration option that tells iOS what orientations your app supports. New apps that you make from a template always support both portrait and landscape orientations.

➤ Click the blue **BullsEye** project icon — known as the project root — at the top of the **Project navigator**. The editor pane of the Xcode window now reveals a bunch of settings for the project.

➤ Make sure that the **BullsEye** target and the **General** tab are selected:



The settings for the project

In the **Deployment Info** section, there is an option for **Device Orientation**.

➤ Check only the **Landscape Left** and **Landscape Right** options and leave the Portrait and Upside Down options unchecked.

Run the app again and it properly launches in the landscape orientation right from the start.

Understanding objects, data and methods

Time for some programming theory. No, you can't escape it. :]

Swift is a so-called "object-oriented" programming language, which means that most of the stuff you do involves objects of some kind. I already mentioned a few times that an app consists of objects that send messages to each other.

When you write an iOS app, you'll be using objects that are provided for you by the system, such as the `UIButton` object from UIKit, and you'll be making objects of your own, such as view controllers.

Objects

So what exactly *is* an object? Think of an object as a building block of your program.

Programmers like to group related functionality into objects. *This* object takes care of parsing a file, *that* object knows how to draw an image on the screen, and *that* object over there can perform a difficult calculation.

Each object takes care of a specific part of the program. In a full-blown app, you will have many different types of objects (tens or even hundreds).

Even your small starter app already contains several different objects. The one you have spent the most time with so far is `ViewController`. The Hit Me! button is also an object, as is the alert pop-up. And the text values that you put on the alert — "Hello, World" and "This is my first app!" — are also objects.

The project also has objects named `AppDelegate` and `SceneDelegate` — you're going to ignore them for the moment, but feel free to look at their source if you're curious. These object thingies are everywhere!

Data and methods


An object can have both *data* and *functionality*:

- An example of data is the Hit Me! button that you added to the view controller earlier. When you dragged the button into the storyboard, it actually became part of the view controller's data. Data *contains* something. In this case, the view controller contains the button.
- An example of functionality is the `showAlert` action that you added to respond to taps on the button. Functionality *does* something.

The button itself also has data and functionality. Examples of button data are the text and color of its label, its position on the screen, its width and height and so on. The button also has functionality: It can recognize that the user tapped on it and it will trigger an action in response.

The thing that provides functionality to an object is commonly called a *method*. Other programming languages may call this a "procedure" or "subroutine" or "function." You will also see the term function used in Swift; a method is simply a function that belongs to an object.

Your `showAlert` action is an example of a method. You can tell it's a method because the line says `func` (short for "function") and the name is followed by parentheses:




All method definitions start with the word func and have parentheses

If you look through the rest of **ViewController.swift**, you'll see another method, `viewDidLoad()`.

It currently doesn't do much; the Xcode template placed it there for your convenience. It's a method that's often used by view controllers, so it's likely that you will need to add some code to it at some point.

> **Note:** These additional methods added by an Xcode template are known as "boilerplate code." If you don't need to add functionality to these boilerplate methods, feel free to remove them — it'll make your code cleaner and more compact. There's a caveat though; sometimes, the boilerplate code is needed in order not to get a compiler error. You will see this later on when we start using more complex view controllers. So if you remove a bunch of boilerplate code and get a compiler error, restore the code and try removing the code selectively until you figure out what is needed and what is not.

The concept of methods may still feel a little weird, so here's an example:



Every party needs ice cream!

You (or at least an object named "You") want to throw a party, but you forgot to buy ice cream. Fortunately, you have invited the object named Steve who happens to live next door to a convenience store. It won't be much of a party without ice cream so, at some point during your party preparations, you send object Steve a message asking him to bring some ice cream.

The computer now switches to object Steve and executes the commands from his `buyIceCream()` method, one by one, from top to bottom.

When the `buyIceCream()` method is done, the computer returns to your `throwParty()` method and continues with that, so you and your friends can eat the ice cream that Steve brought back with him.

The Steve object also has data. Before he goes to the store, he has money. At the store, he exchanges this money data for other, much more important, data: ice cream! After making that transaction, he brings the ice cream data over to the party — if he eats it all along the way, your program has a bug :].

Messages

"Sending a message" sounds more involved than it really is. It's a good way to think conceptually of how objects communicate, but there really aren't any pigeons or mailmen involved. The computer simply jumps from the `throwParty()` method to the `buyIceCream()` method and back again.


Often the terms "calling a method" or "invoking a method" are used instead. That means the exact same thing as sending a message: The computer jumps to the method you're calling and returns to where it left off when that method is done.

The important thing to remember is that objects have methods (the steps involved in buying ice cream) and data (the actual ice cream and the money to buy it with).

Objects can look at each other's data (to some extent anyway, just like Steve may not approve if you peek inside his wallet) and can ask other objects to perform their methods. That's how you get your app to do things. But not all data from an object can be inspected by other objects and/or code — this is an area known as access control and you'll learn about this later.

Adding the other controls

Your app already has a button, but you still need to add the rest of the UI controls, also known as "views." Here is the screen again, this time annotated with the different types of views:




The different views in the game screen

As you can see, I put placeholder values into some of the labels (for example, "999999"). That makes it easier to see how the labels will fit on the screen when they're actually used. The score label could potentially hold a large value, so you'd better make sure the label has room for it.

➤ Try to re-create the above screen on your own by dragging the various controls from the Object Library onto your scene. You'll need a few new Buttons, Labels and a Slider. You can see in the screenshot above how big the items should (roughly) be. It's OK if you're a few points off.

> **Note:** It might seem a little annoying to use the Library panel since it goes away as soon as you drag an item from it. You then have to tap the icon on the toolbar to show the Library panel again to select another item. If you are placing multiple components, just hold down the Alt/Option key (⌥) as you drag an item from the Library panel — the Library panel will remain open, allowing you to select another item.
>
> Also, if you have a component on the canvas, for example, a label, you can duplicate it by clicking on the label, holding the Alt/Option key down and then dragging to a new position.

To tweak the settings of these views, you use the **Attributes inspector**. You can find this inspector in the right-hand pane of the Xcode window (remember that you can use the Show/Hide Inspectors button on the toolbar to show the Inspectors pane if it isn't showing.):




The Attributes inspector

The inspector area shows various aspects of the item that is currently selected. The Attributes inspector, for example, lets you change the background color of a label or the size of the text on a button.

You've already seen the Connections inspector that showed the button's actions. As you become more proficient with Interface Builder, you'll be using all of these inspector panes to configure your views.

➤ Hint: The ⓘ button is actually a regular button, but its **Type** is set to **Info Light** in the Attributes inspector:



The button type lets you change the look of the button

➤ Also use the Attributes inspector to configure the **slider**. Its minimum value should be 1, its maximum 100, and its current value 50.



The slider attributes

When you're done, you should have 12 user interface elements in your scene: one slider, three buttons and a whole bunch of labels. Excellent!

➤ Run the app and play with it for a minute. The controls don't really do much yet (except for the button that should still pop up the alert), but you can at least drag the slider around.

You can now tick a few more items off the to-do list, all without much programming! That is going to change really soon, because you will have to write Swift code to actually make the controls do anything.

The slider

The next item on your to-do list is: "Read the value of the slider after the user presses the Hit Me! button."

If, in your messing around in Interface Builder, you did not accidentally disconnect the button from the `showAlert` action, you can modify the app to show the slider's value in the alert pop-up. (If you did disconnect the button, then you should hook it up again first. You know how, right?)

Remember how you added an action to the view controller in order to recognize when the user tapped the button? You can do the same thing for the slider. This new action will be performed whenever the user drags the slider.


The steps for adding this action are largely the same as before.

➤ First, go to **ViewController.swift** and add the following at the bottom, just before the final closing curly bracket:

```
@IBAction func sliderMoved(_ slider: UISlider) {
  print("The value of the slider is now: \(slider.value)")
}
```

➤ Second, go to the storyboard and Control-drag from the slider to View Controller in the Document Outline. Let go of the mouse button and select **sliderMoved:** from the pop-up. Done!

Just to refresh your memory, the Document Outline sits on the left-hand side of the Interface Builder canvas. It shows the View hierarchy of the storyboard. Here, you can see that the View controller contains a view (succinctly named View), which, in turn, contains the sub-views you've added: the buttons and labels.



The Document Outline shows the view hierarchy of the storyboard

Remember, if the Document Outline is not visible, click the little icon on the Interface Builder toolbar to reveal it:




This button shows or hides the Document Outline

When you connect the slider, make sure to Control-drag to View controller (the yellow circle icon), not View Controller Scene at the very top. If you don't see the yellow circle icon, then click the arrow in front of View Controller Scene (called the "disclosure triangle") to expand it.

If all went well, the `sliderMoved:` action is now hooked up to the slider's Value Changed event. This means the `sliderMoved()` method will be called every time the user drags the slider to the left or right, changing its value.

You can verify that the connection was made by selecting the slider and looking at the **Connections inspector**:




The slider is now hooked up to the view controller

> **Note:** Did you notice that the `sliderMoved:` action has a colon in its name but `showAlert` does not? That's because the `sliderMoved()` method takes a single parameter, `slider`, while `showAlert()` does not have any parameters. If an action method has a parameter, Interface Builder adds a `:` to the name. You'll learn more about parameters and how to use them soon.

➤ Run the app and drag the slider.

As soon as you start dragging, the Xcode window should open a new pane at the bottom, the **Debug area**, showing a list of messages:



Printing messages in the Debug area

> **Note:** If, for some reason, the Debug area does not show up, you can always show (or hide) the Debug area by using the **View ▸ Debug Area ▸ Show Debug Area** menu option. You will notice from the above screenshot that the Debug area is split into two panes. You can control which of the panes is shown/hidden by using the two blue square icons shown in the bottom-right corner.

If you swipe the slider all the way to the left, you should see the value go down to 1. All the way to the right, the value should stop at 100.

The `print()` function is a great help to show you what is going on in the app. Its entire purpose is to write a text message to the **Console** — the right-hand pane in the Debug area. Here, you used `print()` to verify that you properly hooked up the action to the slider and that you can read the slider value as the slider is moved.

I often use `print()` to make sure my apps are doing the right thing before I add more functionality. Printing a message to the Console is quick and easy.

> **Note:** You may see a bunch of other messages in the Console, too. This is debug output from UIKit and iOS Simulator. You can safely ignore these messages.


Strings

To put text in your app, you use something called a "string." The strings you have used so far are:

```
"Hello, World"
"This is my first app!"
"Awesome"
"The value of the slider is now: \(slider.value)"
```

The first three were used to make the `UIAlertController`; the last one was used with `print()`.

Such a chunk of text is called a string because you can visualize the text as a sequence of characters, as if they were pearls in a necklace:



A string of characters

Working with strings is something you need to do all the time when you're writing apps, so over the course of this book you'll get quite experienced in using strings.

In Swift, to create a string, simply put the text in between double quotes. In other languages, you can often use single quotes as well, but in Swift they must be double quotes. And they must be plain double quotes, not typographic "smart quotes."

To summarize:

```
// This is the proper way to make a Swift string:
"I am a good string"

// These are wrong:
'I should have double quotes'
''Two single quotes do not make a double quote''
“My quotes are too fancy”
@"I am an Objective-C string"
```

Anything between the characters `\(` and `)` inside a string is special. The `print()` statement used the string, `"The value of the slider is now: \(slider.value)"`. Think of the `\( … )` as a placeholder: `"The value of the slider is now: X"`, where X will be replaced by the value of the slider.

Filling in the blanks this way is a very common way to build strings in Swift and is known as *string interpolation*.

Variables

Printing information with `print()` to the Console is very useful during the development process, but it's absolutely useless to users because they can't see the Console when the app is running on a device. Let's improve this to show the value of the slider in the alert pop-up. So how do you get the slider's value into `showAlert()`?

When you read the slider's value in `sliderMoved()`, that piece of data disappears when the action method ends. It would be handy if you could remember this value until the user taps the Hit Me! button.

Fortunately, Swift has a building block for exactly this purpose: the *variable*.

➤ Open **ViewController.swift** and add the following at the top, directly below the line that says `class ViewController`:

```
var currentValue: Int = 0
```

You have now added a variable named `currentValue` to the view controller object.

The code should look like this (I left out the method code, also known as the method implementations):

```
import UIKit

class ViewController: UIViewController {
  var currentValue: Int = 0

  override func viewDidLoad() {
    . . .
  }

  @IBAction func showAlert() {
    . . .
  }

  @IBAction func sliderMoved(_ slider: UISlider) {
    . . .
  }
}
```

It is customary to add the variables above the methods, and to indent everything with a tab, or two to four spaces — which one you use is largely a matter of personal preference. I like to use two spaces. (You can configure this in Xcode's preferences panel. From the menu bar choose **Xcode ▸ Preferences... ▸ Text Editing** and go to the **Indentation** tab.)


Remember when I said that a view controller, or any object really, could have both data and functionality? The `showAlert()` and `sliderMoved()` actions are examples of functionality, while the `currentValue` variable is part of the view controller's data.

A variable allows the app to remember things. Think of a variable as a temporary storage container for a single piece of data. Similar to how there are containers of all sorts and sizes, data comes in all kinds of shapes and sizes.

You don't just put stuff in the container and then forget about it. You will often replace its contents with a new value. When the thing that your app needs to remember changes, you take the old value out of the box and put in the new value. That's the whole point behind variables: They can *vary*. For example, you will update `currentValue` with the new position of the slider every time the slider is moved. The size of the storage container and the sort of values the variable can remember are determined by its *data type*, or just *type*.

You specified the type `Int` for the `currentValue` variable, which means this container can hold whole numbers (also known as *integers*) between at least minus two billion and plus two billion. `Int` is one of the most common data types. There are many others though, and you can even make your own.

Variables are like children's toy blocks:



Variables are containers that hold values

The idea is to put the right shape in the right container. The container is the variable and its type determines what "shape" fits. The shapes are the possible values that you can put into the variables.

You can change the contents of each box later as long as the shape fits. For example, you can take out a blue square from a square box and put in a red square — the only thing you have to make sure is that both are squares.

But you can't put a square in a round hole: The data type of the value and the data type of the variable have to match.

I said a variable is a *temporary* storage container. How long will it keep its contents? Unlike meat or vegetables, variables won't spoil if you keep them for too long — a variable will hold onto its value indefinitely, until you put a new value into that variable or until you destroy the container altogether.

Each variable has a certain lifetime (also known as its *scope*) that depends on exactly where in your program you defined that variable. In this case, `currentValue` sticks around for just as long as its owner, `ViewController`, does. Their fates are intertwined.

The view controller, and thus `currentValue`, is there for the duration of the app. They don't get destroyed until the app quits. Soon, you'll also see variables that are short-lived (also known as *local variables*).

Enough theory, let's make this variable work for us!

Creating your variable

➤ Change the contents of the `sliderMoved()` method in **ViewController.swift** to the following:

```
@IBAction func sliderMoved(_ slider: UISlider) {
  currentValue = lroundf(slider.value)
}
```

You removed the `print()` statement and replaced it with this line:

```
currentValue = lroundf(slider.value)
```

What is going on here?

You've seen `slider.value` before, which is the slider's position at a given moment. This is a value between 1 and 100, possibly with digits behind the decimal point. And `currentValue` is the name of the variable you have just created.

To put a new value into a variable, you simply do this:

```
variable = the new value
```

This is known as *assignment*. You *assign* the new value to the variable. It puts the shape into the box. Here, you put the value that represents the slider's position into the `currentValue` variable.

Functions

But what is the `lroundf` part? Recall that the slider's value can be a non-whole number. You've seen this with the `print()` output in the Console as you moved the slider.

However, this game would be really hard if you made the player guess the position of the slider with an accuracy that goes beyond whole numbers. That will be nearly impossible to get right!

To give the player a fighting chance, you use whole numbers only. That is why `currentValue` has a data type of `Int`, because it stores *integers*, a fancy term for whole numbers.

You use the function `lroundf()` to round the decimal number to the nearest whole number and then store that rounded-off number in `currentValue`.

Functions and methods

You've already seen that methods provide functionality, but *functions* are another way to put functionality into your apps — the name sort of gives it away, right?. Functions and methods are how Swift programs combine multiple lines of code into single, cohesive units.

The difference between the two is that a function doesn't belong to an object while a method does. In other words, a method is exactly like a function — that's why you use the `func` keyword to define them — except that you need to have an object to use the method. But regular functions, or *free functions* as they are sometimes called, can be used anywhere.

Swift provides your programs with a large library of useful functions. The function `lroundf()` is one of them and you'll be using quite a few others as you progress. `print()` is also a function, by the way. You can tell because the function name is always followed by parentheses that possibly contain one or more parameters.

➤ Now change the `showAlert()` method to the following:

```
@IBAction func showAlert() {
  let message = "The value of the slider is: \(currentValue)"

  let alert = UIAlertController(
    title: "Hello, World",
    message: message,    // changed
    preferredStyle: .alert)

  let action = UIAlertAction(
    title: "OK",           // changed
    style: .default,
    handler: nil)

  alert.addAction(action)

  present(alert, animated: true, completion: nil)
}
```

The line with `let message =` is new. Also note the other two small changes marked by comments.


> **Note:** Anything appearing after two slashes `//` (and up to the end of that particular line) in Swift source code is treated as a comment — a note by the developer to themselves or to other developers. The Swift compiler generally ignores comments; they are there for the convenience of humans.

As before, you create and show a `UIAlertController`, except this time its message says: "The value of the slider is: X," where X is replaced by the contents of the `currentValue` variable (a whole number between 1 and 100).

Suppose `currentValue` is 34, which means the slider is about one-third to the left. The new code above will convert the string `"The value of the slider is: \(currentValue)"` into `"The value of the slider is: 34"` and put that into a new object named `message`.

The old `print()` did something similar, except that it printed the result to the Console. Here, however, you do not wish to print the result but show it in the alert pop-up. That is why you tell the `UIAlertController` that it should now use this new string as the message to display.

➤ Run the app, drag the slider and press the button. Now, the alert should show the actual value of the slider.



The alert shows the value of the slider

Cool. You have used a variable, `currentValue`, to remember a particular piece of data, the rounded-off position of the slider, so that it can be used elsewhere in the app — in this case in the alert's message text.

If you tap the button again without moving the slider, the alert will still show the same value. The variable keeps its value until you put a new one into it.

Your first bug

There is a small problem with the app, though. Maybe you've noticed it already. Here is how to reproduce the problem:

➤ Press the Stop button in Xcode to completely terminate the app, then press Run again. Without moving the slider, immediately press the Hit Me! button.

The alert now says: "The value of the slider is: 0". But the slider is obviously at the center, so you would expect the value to be 50. You've discovered a bug!

> **Exercise:** Think of a reason why the value would be 0 in this particular situation (start the app, don't move the slider, press the button).

Answer: The clue here is that this only happens when you don't move the slider. Of course, without moving the slider the `sliderMoved()` message is never sent and you never put the slider's value into the `currentValue` variable.

The default value for the `currentValue` variable is 0, and that is what you are seeing here.

➤ To fix this bug, change the declaration of `currentValue` to:

```
var currentValue: Int = 50
```

Now the starting value of `currentValue` is 50, which should be the same value as the slider's initial position.

➤ Run the app again and verify that the bug is fixed.

You can find the project files for the app up to this point under **03-Slider-and-labels** in the Source Code folder.

Chapter 4: Outlets

By Fahim Farook

You've built the user interface for *Bull's Eye* and you know how to find the current position of the slider. That already knocks quite a few items off the to-do list. This chapter takes care of a few other items from the to-do list and covers the following items:

- **Improve the slider:** Set the initial slider value (in code) to be whatever value was set in the storyboard instead of assuming an initial value.
- **Generate the random number:** Generate the random number to be used as the target by the game.
- **Add rounds to the game:** Add the ability to start a new round of the game.
- **Display the target value:** Display the generated target number on screen.

Improve the slider

You completed storing the value of the slider into a variable and showing it via an alert. That's great, but you can still improve on it a little.

What if you decide to set the initial value of the slider in the storyboard to something other than 50 — say, 1 or 100? Then `currentValue` would be wrong again because the app always assumes it will be 50 at the start. You'd have to remember to also fix the code to give `currentValue` a new initial value.

Take it from me — that kind of thing is hard to remember, especially when the project becomes bigger and you have dozens of view controllers to worry about, or when you haven't looked at the code for weeks.

Get the initial slider value

To fix this issue once and for all, you're going to do some work inside the `viewDidLoad()` method in **ViewController.swift**. That method currently looks like this:

```
override func viewDidLoad() {
  super.viewDidLoad()
  // Do any additional setup after loading the view.
}
```

When you created this project based on Xcode's template, Xcode inserted the `viewDidLoad()` method into the source code. You will now add some code to it.

The `viewDidLoad()` message is sent by UIKit immediately after the view controller loads its user interface from the storyboard file. At this point, the view controller isn't visible yet, so this is a good place to set instance variables to their proper initial values.


➤ Change `viewDidLoad()` to the following:

```
override func viewDidLoad() {
  super.viewDidLoad()
  currentValue = lroundf(slider.value)
}
```

The idea is that you take whatever value is set on the slider in the storyboard (whether it is 50, 1, 100 or anything else) and use that as the initial value of `currentValue`.

Recall that you need to round off the number, because `currentValue` is an `Int` and integers cannot take decimal (or fractional) numbers.

Unfortunately, Xcode immediately complains about these changes even before you try to run the app.



Xcode error message about missing identifier

> **Note:** Xcode tries to be helpful and it analyzes the program for mistakes as you're typing. Sometimes, you may see temporary warnings and error messages that will go away when you complete the changes that you're making.
>
> Don't be too intimidated by these messages; they are only short-lived while the code is in a state of flux.

This error is because `viewDidLoad()` does not know of anything named `slider`.

Then why did this work earlier, in `sliderMoved()`? Let's take a look at that method again:

```
@IBAction func sliderMoved(_ slider: UISlider) {
  currentValue = lroundf(slider.value)
}
```

Here, you do the exact same thing: You round off `slider.value` and put it into `currentValue`. So why does it work here but not in `viewDidLoad()`?

The difference is that, in the code above, `slider` is a *parameter* of the `sliderMoved()` method. Parameters are the things inside the parentheses following a method's name. In this case, there's a single parameter named `slider`, which refers to the `UISlider` object that sent this action message.

Action methods can have a parameter that refers to the UI control that triggered the method. This is convenient when you wish to refer to that object in the method, just as you did here (the object in question being the `UISlider`).

When the user moves the slider, the `UISlider` object basically says, "Hey view controller! I'm a slider object and I just got moved. By the way, here's my phone number so you can get in touch with me."

The `slider` parameter contains this "phone number," but it is only valid for the duration of this particular method.

In other words, `slider` is *local*; you cannot use it anywhere else.

Locals

When I first mentioned variables, I said that each variable has a certain lifetime, known as its *scope*. The scope of a variable depends on where in your program you defined that variable.

There are three possible scope levels in Swift:

1. **Global scope**: These objects exist for the duration of the app and are accessible from anywhere.
2. **Instance scope**: This is for variables such as `currentValue`. These objects are alive for as long as the object that owns them stays alive.
3. **Local scope**: Objects with a local scope, such as the `slider` parameter of `sliderMoved()`, only exist for the duration of that method. As soon as the execution of the program leaves this method, the local objects are no longer accessible.

Let's look at the top part of `showAlert()`:

```
@IBAction func showAlert() {
  let message = "The value of the slider is: \(currentValue)"

  let alert = UIAlertController(
    title: "Hello, World",
    message: message,
    preferredStyle: .alert)

  let action = UIAlertAction(
    title: "OK",
    style: .default,
    handler: nil)
  . . .
```

Because the `message`, `alert`, and `action` objects are created inside the method, they have local scope. They only come into existence when the `showAlert()` action is performed and they cease to exist when the action is done.

As soon as the `showAlert()` method completes, i.e., when there are no more statements for it to execute, the computer destroys the `message`, `alert`, and `action` objects and their storage space is cleared out.

The `currentValue` variable, however, lives on forever... or at least for as long as the `ViewController` does, which is until the user terminates the app. This type of variable is named an *instance variable*, because its scope is the same as the scope of the object instance it belongs to.

In other words, you use instance variables if you want to keep a certain value around, from one action event to the next.

Setting up outlets

So, with this newly gained knowledge of variables and their scopes, how do you fix the error that you encountered?

The solution is to store a reference to the slider as a new instance variable, just like you did for `currentValue`. Except that this time, the data type of the variable is not `Int`, but `UISlider`. And you're not using a regular instance variable but a special one called an *outlet*.

➤ Add the following line to **ViewController.swift**:

```
@IBOutlet var slider: UISlider!
```

It doesn't really matter where this line goes, just as long as it is somewhere inside the curly brackets for `class ViewController`. I usually put outlets with the other instance variables — at the top of the class implementation.

This line tells Interface Builder that you now have a variable named `slider` that can be connected to a `UISlider` object. Just as Interface Builder likes to call methods *actions*, it calls these variables *outlets*. Interface Builder doesn't see any of your other variables, only the ones marked with `@IBOutlet`.

Don't worry about the exclamation point for now. Why that is necessary will be explained later on. For now, just remember that a variable for an outlet needs to be declared as `@IBOutlet var` and has an exclamation point at the end. (Sometimes you'll see a question mark instead; all this hocus pocus will be explained in due time.)

Once you add the `slider` variable, you'll notice that the Xcode error goes away. Does that mean that you can run your app now? Try it and see what happens.

The app crashes on start with an error similar to the following:

```
32  class ViewController: UIViewController {
    @IBOutlet var slider: UISlider!
34
35    var currentValue: Int = 50
36
37    override func viewDidLoad() {
38      super.viewDidLoad()
39      currentValue = lroundf(slider.value)   Thread 1: Fatal error: Unexpectedly found nil while implicitly unwrapping an Optional value
40    }
```

App crash when outlet is not connected

So, what happened?


Remember that an outlet has to be *connected* to something in the storyboard. You defined the variable, but you didn't actually set up the connection yet. So, when the app ran and `viewDidLoad()` was called, it tried to find the matching connection in the storyboard and could not — and crashed.

Let's set up the connection in storyboard now.

➤ Open the storyboard. Hold **Control** and click on the **slider**. Don't drag anywhere, though — a menu should pop up that shows all the connections for this slider. (Instead of Control-clicking, you can also right-click once.)

This popup menu works exactly the same as the Connections inspector. I just wanted to show you this alternative approach.

➤ Click on the open circle next to **New Referencing Outlet** and drag to **View Controller**:



Connecting the slider to the outlet

➤ In the pop-up that appears, select **slider**.

This is the outlet that you just added. You have successfully connected the slider object from the storyboard to the view controller's `slider` outlet.

Now that you have done all this set up work, you can refer to the slider object from anywhere inside the view controller using the `slider` variable.

With these changes in place, it no longer matters what you choose for the initial value of the slider in Interface Builder. When the app starts, `currentValue` will always correspond to that setting.

➤ Run the app and immediately press the Hit Me! button. It correctly says: "The value of the slider is: 50." Stop the app, go into Interface Builder and change the initial value of the slider to something else — say, 25. Run the app again and press the button. The alert should read 25, now.

> **Note:** When you change the slider value — or the value in any Interface Builder field — remember to tab out of field when you make a change. If you make the change but your cursor remains in the field, the change might not take effect. This is something which can trip you up often.

Put the slider's starting position back to 50 when you're done playing.

> **Exercise:** Give `currentValue` an initial value of 0 again. Its initial value is no longer important — it will be overwritten in `viewDidLoad()` anyway — but Swift demands that all variables always have some value and 0 is as good as any.

★ ★ ★

Comments

You've probably noticed the grey text that begins with `//` a few times now. As I explained earlier briefly, these are comments. You can write any text you want after the `//` symbol as the compiler will ignore such lines from the `//` to the end of the line completely.

```
// I am a comment! You can type anything here.
```

Anything between the `/*` and `*/` markers is considered a comment as well. The difference between `//` and `/* */` is that the former only works on a single line, while the latter can span multiple lines.

```
/*
   I am a comment as well!
   I can span multiple lines.
 */
```

The `/* */` comments are often used to temporarily disable whole sections of source code, usually when you're trying to hunt down a pesky bug, a practice known as "commenting out". You can use the **Cmd**-/ keyboard shortcut to comment/uncomment the currently selected lines, or if you have nothing selected, the current line.

The best use for comment lines is to explain how your code works. Well-written source code is self-explanatory, but sometimes additional clarification is useful. Explain to whom? To yourself, mostly.

Unless you have the memory of an elephant, you'll probably have forgotten exactly how your code works when you look at it six months later. Use comments to jog your memory.



Generate the random number

You still have quite a ways to go before the game is playable. So, let's get on with the next item on the list: generating a random number and displaying it on the screen.

Random numbers come up a lot when you're making games because games often need to have some element of unpredictability. You can't really get a computer to generate numbers that are truly random and unpredictable, but you can employ a *pseudo-random generator* to spit out numbers that at least appear to be random.

With previous versions of Swift, you had to use external methods such as `arc4random_uniform()`, but as of Swift 4.2, Swift numeric types such as `Int` have the built-in ability to generate random numbers. How handy, right? Before you generate the random value though, you need a place to store it.

➤ Add a new variable at the top of **ViewController.swift**, with the other variables:

```
var targetValue = 0
```

You might wonder why we didn't specify the type of the `targetValue` variable, similar to what we'd done earlier for `currentValue`. This is because Swift is able to *infer* the type of variables if it has enough information to work with. Here, for example, you initialize `targetValue` with 0 and, since 0 is an integer value, the compiler knows that `targetValue` will be of type `Int`.

We'll discuss Swift type inference again later on but, for the time being, the important point is that `targetValue` is initialized to 0. That 0 is never used in the game; it will always be overwritten by the random value that you'll generate at the start of the game.

I hope the reason is clear why you made `targetValue` an instance variable: You want to calculate the random number in one place – like in `viewDidLoad()` — and then remember it until the user taps the button in `showAlert()` when you have to check this value against the user selection.

Next, you need to generate the random number. A good place to do this is when the game starts.

➤ Add the following line to `viewDidLoad()` in **ViewController.swift**:

```
targetValue = Int.random(in: 1...100)
```

The complete `viewDidLoad()` should now look like this:

```
override func viewDidLoad() {
  super.viewDidLoad()
  currentValue = lroundf(slider.value)
  targetValue = Int.random(in: 1...100)
}
```

What are you doing here? You call the `random()` function built into `Int` to get an arbitrary integer (whole number) between 1 and 100. The `1...100` part is known as a *closed range* wherein you specify a starting value and an ending value to specify a range of numbers. The `...` part indicates that you want the range to include the closing value (100), but if you wanted a range without the final value, then you would specify the range as `1..<100` and would get only values from 1 to 99.

All clear? Onwards!

Displaying the random number

➤ Change `showAlert()` to the following:

```
@IBAction func showAlert() {
  let message = "The value of the slider is: \(currentValue)" +
                "\nThe target value is: \(targetValue)"


  let alert = . . .
}
```

Tip: Whenever you see `. . .` in a source code listing, I mean that as shorthand for: "This part didn't change" — don't go replacing the existing code with actual ellipsis! :]

You've simply added the random number, which is now stored in `targetValue`, to the message string. This should look familiar to you by now: The `\(targetValue)` placeholder is replaced by the actual random number.

The `\n` character sequence is new. It means that you want to insert a special "new line" character at that point, which will break up the text into two lines so the message is a little easier to read. The + is also new but is simply used here to combine two strings. We could just as easily have written it as a single long string, but it might not have looked as good to the reader. :]

➤ Run the app and try it out!



The alert shows the target value on a new line

Note: Earlier, you used the + operator to add two numbers together (just like how it works in math) but, here, you're also using + to glue different bits of text into one big string.

Swift allows the use of the same operator for different tasks, depending on the data types involved. If you have two integers, + adds them up. But with two strings, + concatenates, or combines, them into a longer string.

Programming languages often use the same symbols for different purposes, depending on the context. After all, there are only so many symbols to go around!

Adding rounds to the game

If you press the Hit Me! button a few times, you'll notice that the random number never changes. I'm afraid the game won't be much fun that way.

This happens because you generate the random number in `viewDidLoad()` and never again afterwards. The `viewDidLoad()` method is only called once when the view controller is created during app startup. The item on the to-do list actually said: "Generate a random number *at the start of each round*". Let's talk about what a round means in terms of this game.

When the game starts, the player has a score of 0 and the round number is 1. You set the slider halfway (to value 50) and calculate a random number. Then you wait for the player to press the Hit Me! button. As soon as they do, the round ends.

You calculate the points for this round and add them to the total score. Then you increment the round number and start the next round. You reset the slider to the halfway position again and calculate a new random number. Rinse, repeat.

Starting a new round

Whenever you find yourself thinking something along the lines of, "At this point in the app we have to do such and such," then it makes sense to create a new method for it. This method will nicely capture that functionality in a self-contained unit of its own.

➤ With that in mind, add the following new method to **ViewController.swift**:

```
func startNewRound() {
  targetValue = Int.random(in: 1...100)
  currentValue = 50
  slider.value = Float(currentValue)
}
```

It doesn't really matter where you put the code, as long as it is inside the `ViewController` implementation (within the class curly brackets), so that the compiler knows it belongs to the `ViewController` object.

It's not very different from what you did before, except that you moved the logic for setting up a new round into its own method, `startNewRound()`. The advantage of doing this is that you can execute this logic from more than one place in your code.

Using the new method

First, you'll call this new method from `viewDidLoad()` to set up everything for the very first round. Recall that `viewDidLoad()` happens just once when the app starts up, so this is a great place to begin the first round.

➤ Change `viewDidLoad()` to:

```
override func viewDidLoad() {
  super.viewDidLoad()
  startNewRound()  // Replace previous code with this
}
```

Note that you've removed some of the existing statements from `viewDidLoad()` and replaced them with just the call to `startNewRound()`.

You will also call `startNewRound()` after the player pressed the Hit Me! button, from within `showAlert()`.

➤ Make the following change to `showAlert()`:

```
@IBAction func showAlert() {
  . . .

  startNewRound()
}
```

The call to `startNewRound()` goes at the very end, right after `present(alert, …)`.

Until now, the methods from the view controller have been invoked for you by UIKit when something happened: `viewDidLoad()` is performed when the app loads, `showAlert()` is performed when the player taps the button, `sliderMoved()` when the player drags the slider, and so on. This is the event-driven model we talked about earlier.

It is also possible to call methods directly, which is what you're doing here. You are sending a message from one method in the object to another method in that same object.

In this case, the view controller sends the `startNewRound()` message to itself in order to set up the new round. Program execution will then switch to that method and execute its statements one-by-one. When there are no more statements in the method, it returns to the calling method and continues with that — either `viewDidLoad()`, if this is the first time, or `showAlert()` for every round after.

Calling methods in different ways

Sometimes, you may see method calls written like this:

```
self.startNewRound()
```

That does the exact same thing as `startNewRound()` without `self.` in front. Recall how I just said that the view controller sends the message to itself. Well, that's exactly what `self` means.

To call a method on an object, you'd normally write:

```
receiver.methodName(parameters)
```

The `receiver` is the object you're sending the message to. If you're sending the message to yourself, then the receiver is `self`. But because sending messages to `self` is very common, you can also leave this special keyword out for many cases.

To be fair, this isn't exactly the first time you've called methods. `addAction()` is a method on `UIAlertController` and `present()` is a method that all view controllers have, including yours.

When you write Swift programs, a lot of what you do is calling methods on objects, because that is how the objects in your app communicate.

The advantages of using methods

I hope you can see the advantage of putting the "new round" logic into its own method. If you didn't, the code for `viewDidLoad()` and `showAlert()` would look like this:

```
override func viewDidLoad() {
  super.viewDidLoad()

  targetValue = Int.random(in: 1...100)
  currentValue = 50
  slider.value = Float(currentValue)
}

@IBAction func showAlert() {
  . . .

  targetValue = Int.random(in: 1...100)
  currentValue = 50
  slider.value = Float(currentValue)
}
```

Can you see what is going on here? The same functionality is duplicated in two places. Sure, it is only three lines of code but, often, the code you duplicate could be much larger.

And what if you decide to make a change to this logic (as you will shortly)? Then you will have to make the same change in two places.

You might be able to remember to do so if you recently wrote this code and it is still fresh in memory, but, if you have to make that change a few weeks down the road, chances are that you'll only update it in one place and forget about the other.

Code duplication is a big source of bugs. So, if you need to do the same thing in two different places, consider making a new method for it instead of duplicating code.

Naming methods

The name of the method also helps to make it clear as to what it is supposed to be doing. Can you tell at a glance what the following does?

```
targetValue = Int.random(in: 1...100)
currentValue = 50
slider.value = Float(currentValue)
```

You probably have to reason your way through it: "It is calculating a new random number and then resets the position of the slider, so I guess it must be the start of a new round."

Some programmers will use a comment to document what is going on (and you can do that too), but, in my opinion, the following is much clearer than the above block of code with an explanatory comment:

```
startNewRound()
```

This line practically spells out for you what it will do. And if you want to know the specifics of what goes on in a new round, you can always look up the `startNewRound()` method implementation.

Well-written source code speaks for itself. I hope I have convinced you of the value of making new methods!

➤ Run the app and verify that it calculates a new random number between 1 and 100 after each tap on the button.

You should also have noticed that, after each round, the slider resets to the halfway position. That happens because `startNewRound()` sets `currentValue` to 50 and then tells the slider to go to that position. That is the opposite of what you did before (you used to read the slider's position and put it into `currentValue`), but I thought it would work better in the game if you start from the same position in each round.

Exercise: Just for fun, modify the code so that the slider does not reset to the halfway position at the start of a new round.

Type conversion

By the way, you may have been wondering what `Float(…)` does in this line:

```
slider.value = Float(currentValue)
```

Swift is a *strongly typed* language, meaning that it is really picky about the shapes that you can put into the boxes. For example, if a variable is an `Int`, you cannot put a `Float`, or a non-whole number, into it, and vice versa.

The value of a `UISlider` happens to be a `Float` — you've seen this when you printed out the value of the slider — but `currentValue` is an `Int`. So the following won't work:

```
slider.value = currentValue
```

The compiler considers this an error. Some programming languages are happy to convert the `Int` into a `Float` for you, but Swift wants you to be explicit about such conversions.

When you say `Float(currentValue)`, the compiler takes the integer number that's stored in `currentValue` and converts it into a new `Float` value that it can pass on to the `UISlider`.

Because Swift is stricter about this sort of thing than most other programming languages, it is often a source of confusion for newcomers to the language. Unfortunately, Swift's error messages aren't always very clear about what part of the code is wrong or why.

Just remember, if you get an error message saying, "Cannot assign value of type 'something' to type 'something else'" then you're probably trying to mix incompatible data types. The solution is to explicitly convert one type to the other — if conversion is allowed, of course — as you've done here.

Displaying the target value

Great, you figured out how to calculate the random number and how to store it in an instance variable, `targetValue`, so that you can access it later.

Now, you are going to show that target number on the screen. Without it, the player won't know what to aim for and that would make the game impossible to win.

Setting up the storyboard

When you set up the storyboard, you added a label for the target value (top-right corner). The trick is to put the value from the `targetValue` variable into this label. To do that, you need to accomplish two things:

1. Create an outlet for the label so you can send it messages.
2. Give the label new text to display.


This will be very similar to what you did with the slider. Recall that you added an `@IBOutlet` variable so you could reference the slider anywhere from within the view controller. Using this outlet variable you could ask the slider for its value, through `slider.value`. You'll do the same thing for the label.

➤ In **ViewController.swift**, add the following line below the other outlet declaration:

```
@IBOutlet var targetLabel: UILabel!
```

➤ In **Main.storyboard**, click to select the correct label — the one at the very top that says "100."

➤ Go to the **Connections inspector** and drag from **New Referencing Outlet** to the yellow circle at the top of your view controller in the central scene. You could also drag to the **View Controller** in the Document Outline — there are many ways to do the same thing in Interface Builder.



Connecting the target value label to its outlet

➤ Select **targetLabel** from the popup, and the connection is made.

Displaying the target value via code

➤ On to the good stuff! Add the following method below `startNewRound()` in **ViewController.swift**:

```
func updateLabels() {
  targetLabel.text = String(targetValue)
}
```

You're putting this logic in a separate method because it's something you might use from different places.

The name of the method makes it clear what it does: It updates the contents of the labels. Currently it's just setting the text of a single label, but later on you will add code to update the other labels as well (total score, round number).

The code inside `updateLabels()` should have no surprises for you, although you may wonder why you cannot simply do:

```
targetLabel.text = targetValue
```

The answer again is that you cannot put a value of one data type into a variable of another type — the square peg just won't go in the round hole.

The `targetLabel` outlet references a `UILabel` object. The `UILabel` object has a `text` property, which is a `String` object. So, you can only put `String` values into `text`, but `targetValue` is an `Int`. A direct assignment won't fly because an `Int` and a `String` are two very different kinds of things.

So, you have to convert the `Int` into a `String`, and that is what `String(targetValue)` does. It's similar to what you've done before with `Float(…)`.

Just in case you were wondering, you could also convert `targetValue` to a `String` by using string interpolation, like you've done before:

```
targetLabel.text = "\(targetValue)"
```

Which approach you use is a matter of taste. Either approach will work fine.

Notice that `updateLabels()` is a regular method — it is not attached to any UI controls as an action — so it won't do anything until you actually call it. You can tell because it doesn't say `@IBAction` before `func`.

Action methods vs. normal methods

So what is the difference between an action method and a regular method?

Answer: Nothing.

An action method is really just the same as any other method. The only special thing is the `@IBAction` attribute, which allows Interface Builder to see the method so you can connect it to your buttons, sliders and so on.

Other methods, such as `viewDidLoad()`, don't have the `@IBAction` specifier. This is good because all kinds of mayhem would occur if you hooked these up to your buttons.

This is the simple form of an action method:

```
@IBAction func showAlert()
```

You can also ask for a reference to the object that triggered this action, via a parameter:

```
@IBAction func sliderMoved(_ slider: UISlider)
@IBAction func buttonTapped(_ button: UIButton)
```

But the following method cannot be used as an action from Interface Builder:

```
func updateLabels()
```

That's because it is not marked as `@IBAction` and as a result, Interface Builder can't see it. To use `updateLabels()`, you will have to call it yourself.

Calling the method

The logical place to call `updateLabels()` would be after each call to `startNewRound()`, because that is where you calculate the new target value. So, you could always add a call to `updateLabels()` in `viewDidLoad()` and `showAlert()`, but there's another way, too!


What is this other way, you ask? Well, if `updateLabels()` is always (or at least in your current code) called after `startNewRound()`, why not call `updateLabels()` directly from `startNewRound()` itself? That way, instead of having two calls in two separate places, you can have a single call.

➤ Change `startNewRound()` to:

```
func startNewRound() {
    targetValue = Int.random(in: 1...100)
    currentValue = 50
    slider.value = Float(currentValue)
    updateLabels()  // Add this line
}
```

You should be able to type just the first few letters of the method name, like **upd**, and Xcode will show you a list of suggestions matching what you typed.

Press **Enter** to accept the suggestion (if you are on the right item — or scroll the list to find the right item and then press Enter):




Xcode autocomplete offers suggestions

You can also use **Tab** to make your selection, but Tab will complete items from the menu a segment (or word) at a time — try it out to see what I mean. So you might have to press Tab multiple times before your selection is complete, as opposed to Enter, which selects the current item immediately.

Also worth noting is that you don't have to start typing the method (or property) name you're looking from the beginning — Xcode uses fuzzy search and typing "dateL" or "label" should help you find "updateLabels" just as easily.

➤ Run the app and you'll actually see the random value on the screen. That should make it a little easier to aim for.



The label in the top-right corner now shows the random value

You can find the project files for the app up to this point under **04-Outlets** in the Source Code folder.

Chapter 5: Rounds & Score

By Fahim Farook

OK, so you have made quite a bit of progress on the game, and the to-do list is getting ever shorter! So what's next on the list now that you can generate a random number and display it on screen?

A quick look at the task list shows that you now have to "compare the value of the slider to that random number and calculate a score based on how far off the player is." Let's get to it!

This chapter covers the following:


- **Get the difference:** Calculate the difference between the target value and the value that the user selected.
- **Other ways to calculate the difference:** Other approaches to calculating the difference.
- **What's the score?:** Calculate the user's score based on the difference value.
- **The total score:** Calculate the player's total score over multiple rounds.
- **Display the score:** Display the player score on screen.
- **One more round...:** Implement updating the round count and displaying the current round on screen.

Getting the difference

Now that you have both the target value (the random number) and a way to read the slider's position, you can calculate how many points the player scored.

The closer the slider is to the target, the more points for the player.

To calculate the score for each round, you look at how far off the slider's value is from the target:



Calculating the difference between the slider position and the target value

A simple approach to finding the distance between the target and the slider is to subtract `currentValue` from `targetValue`.

Unfortunately, that gives a negative value if the slider is to the right of the target because now `currentValue` is greater than `targetValue`.

You need some way to turn that negative value into a positive value — or you end up subtracting points from the player's score (unfair!).

Doing the subtraction the other way around — `currentValue` minus `targetValue` — won't always solve things either because, then, the difference will be negative if the slider is to the left of the target instead of the right.

Hmm, it looks like we're in trouble here...

> **Exercise:** How would you frame the solution to this problem if I asked you to solve it in natural language? Don't worry about how to express it in computer language for now, just think it through in plain English.

I came up with something like this:

- *If the slider's value is greater than the target value, then the difference is: slider value minus the target value.*
- *However, if the target value is greater than the slider value, then the difference is: target value minus the slider value.*
- *Otherwise, both values must be equal, and the difference is zero.*

This will always lead to a difference that is a positive number, because you always subtract the smaller number from the larger one.

Do the math:

If the slider is at position 60 and the target value is 40, then the slider is to the right of the target value, and the difference is 60 - 40 = 20.

However, if the slider is at position 10 and the target is 30, then the slider is to the left of the target and has a smaller value. The difference here is 30 - 10 = also 20.

Algorithms

What you've just done is come up with an *algorithm*, which is a fancy term for a series of steps for solving a computational problem. This is only a very simple algorithm, but it is an algorithm nonetheless.

There are many famous algorithms, such as *quicksort* for sorting a list of items and *binary search* for quickly searching through such a sorted list. Other people have already invented many algorithms that you can use in your own programs — that'll save you a lot of thinking!

However, in the programs that you write, you'll probably have to come up with a few algorithms of your own at some time or other. Some are simple such as the one above; others can be pretty hard and might cause you to throw up your hands in despair. But that's part of the fun of programming. :]

The academic field of Computer Science concerns itself largely with studying algorithms and finding better ones.

You can describe any algorithm in plain English. It's just a series of steps that you perform to calculate something. Often, you can perform that calculation in your head or on paper, the way you did above. But for more complicated algorithms, doing that might take you forever so, at some point, you'll have to convert the algorithm to computer code.

The point I'm trying to make is this: If you ever get stuck and you don't know how to make your program calculate something, take a piece of paper and try to write out the steps in English. Set aside the computer for a moment and think the steps through. How would you perform this calculation by hand?

Once you know how to do that, converting the algorithm to code should be a piece of cake.

The difference algorithm

Getting back to the problem at hand, it is possible you came up with a different way to solve it. I'll show you two alternatives in a minute, but let's convert the above algorithm to computer code first:

```
var difference: Int
if currentValue > targetValue {
  difference = currentValue - targetValue
} else if targetValue > currentValue {
  difference = targetValue - currentValue
} else {
  difference = 0
}
```

The `if` construct is new. It allows your code to make decisions, and it works much like you would expect:

```
if something is true {
  then do this
} else if something else is true {
  then do that instead
} else {
  do something when neither of the above are true
}
```

Basically, you put a *logical condition* after the `if` keyword. If that condition turns out to be true, for example `currentValue` is greater than `targetValue`, then the code in the block between the `{ }` brackets is executed.

However, if the condition is not true, then the computer looks at the `else if` condition and evaluates that. There may be more than one `else if`, and code execution moves one by one from top to bottom until one condition proves to be true.

If none of the conditions are found to be valid, then the code in the final `else` block is executed.

In the implementation of this little algorithm, you first create a local variable named `difference` to hold the result. This will either be a positive whole number or zero, so an `Int` will do:

```
var difference: Int
```

Then you compare the `currentValue` against the `targetValue`. First, you determine if `currentValue` is greater than `targetValue`:

```
if currentValue > targetValue {
```

The > is the *greater-than* operator. The condition `currentValue > targetValue` is considered true if the value stored in `currentValue` is at least one higher than the value stored in `targetValue`. In that case, the following line of code is executed:

```
  difference = currentValue - targetValue
```

Here, you subtract `targetValue` (the smaller one) from `currentValue` (the larger one) and store the result in the `difference` variable.

Notice how I chose variable names that clearly describe what kind of data the variables contain. Often, you will see code such as this:

```
a = b - c
```

It is not immediately clear what this is supposed to mean, other than that some arithmetic is taking place. The variable names "a", "b" and "c" don't give any clues as to their intended purpose or what kind of data they might contain.

Back to the `if` statement. If `currentValue` is equal to or less than `targetValue`, the condition is untrue (or *false* in computer-speak) and execution will move on to the next condition:

```
} else if targetValue > currentValue {
```

The same thing happens here as before, except now the roles of `targetValue` and `currentValue` are reversed. The computer will only execute the following line when `targetValue` is the greater of the two values:

```
    difference = targetValue - currentValue
```

This time, you subtract `currentValue` from `targetValue` and store the result in the `difference` variable.

There is only one situation you haven't handled yet: when `currentValue` and `targetValue` are equal. If this happens, the player has put the slider exactly at the position of the target random number, a perfect score.

In that case the difference is 0:

```
  } else {
    difference = 0
  }
```

Since, by now, you've already determined that one value is not greater than the other, nor is it smaller, you can only draw one conclusion: The numbers must be equal.

Displaying the difference

➤ Let's put this code into action. Add it to the top of `showAlert()`:


```
  @IBAction func showAlert() {
    var difference: Int

    if currentValue > targetValue {
      difference = currentValue - targetValue
    } else if targetValue > currentValue {
      difference = targetValue - currentValue
    } else {
      difference = 0
    }

    let message = "The value of the slider is: \(currentValue)" +
                  "\nThe target value is: \(targetValue)" +
                  "\nThe difference is: \(difference)"
    . . .
  }
```

Just so you can see that it works, you add the `difference` value to the alert message as well.

➤ Run it and see for yourself.



The alert shows the difference between the target and the slider

Simplifying the algorithm

I mentioned earlier that there are other ways to calculate the difference between `currentValue` and `targetValue` as a positive number. The above algorithm works well, but it is eight lines of code. I think we can come up with a simpler approach that takes up fewer lines.

The new algorithm goes like this:

1. *Subtract the target value from the slider's value.*
2. *If the result is a negative number, then multiply it by -1 to make it a positive number.*

Here, you no longer avoid the negative number since computers can work just fine with negative numbers. You simply turn it into a positive number.

> **Exercise:** Convert the above algorithm into source code. Hint: The English description of the algorithm contains the words "if" and "then," which is a pretty good indication that you'll have to use an `if` statement.

You should have arrived at something like this:

```
var difference = currentValue - targetValue
if difference < 0 {
  difference = difference * -1
}
```

This is a pretty straightforward translation of the new algorithm.

You first do the subtraction and put the result into the `difference` variable.

Notice that you can create the new variable and assign the result of a calculation to it, all in one line. You don't need to put it onto two different lines, like so:

```
var difference: Int
difference = currentValue - targetValue
```

Also, in the one-liner version, you didn't have to tell the compiler that `difference` takes `Int` values. Because both `currentValue` and `targetValue` are `Int`s, Swift is smart enough to figure out that difference should also be an `Int`.

This feature, as mentioned before, is called *type inference* and it's one of the big selling points of Swift.

Once you have the subtraction result, you use an `if` statement to determine whether `difference` is negative, i.e., less than zero. If it is, you multiply by -1 and put the new result — now a positive number — back into the `difference` variable.

When you write:

```
difference = difference * -1
```

the computer first multiplies `difference`'s value by -1. Then, it puts the result of that calculation back into `difference`. In effect, this overwrites `difference`'s old contents (the negative number) with the positive number.

Because this is a common thing to do, there is a handy shortcut:

```
difference *= -1
```

The *= operator combines * and = into a single operation. The end result is the same: The variable's old value is gone and it now contains the result of the multiplication.

You could also have written this algorithm as follows:

```
var difference = currentValue - targetValue
if difference < 0 {
  difference = -difference
}
```

Instead of multiplying by -1, you now use the negation operator to ensure `difference`'s value is always positive. This works because negating a negative number makes it positive again. (Ask a math professor if you don't believe me.)

Using the new algorithm

➤ Give these new algorithms a try. You should replace the old stuff at the top of `showAlert()` as follows:

```
@IBAction func showAlert() {
  var difference = currentValue - targetValue
  if difference < 0 {
    difference *= -1
  }

  let message = . . .
}
```

When you run this new version of the app (try it!), it should work exactly the same as before. The result of the computation does not change, only the technique used changed.

Another variation

The final alternative algorithm I want to show you uses a function.

You've already seen functions a few times before. For example, when you used `lroundf()` for rounding off the slider's decimals. Similarly, to make sure a number is always positive, you can use the `abs()` function.

If you took math in school, you might remember the term "absolute value," which is the value of a number without regard to its sign.

That's exactly what you need here, and the standard library contains a convenient function for it, which allows you to reduce this entire algorithm down to a single line of code:

```
let difference = abs(targetValue - currentValue)
```

It really doesn't matter whether you subtract `currentValue` from `targetValue` or the other way around. If the number is negative, `abs()` turns it positive. It's a handy function to remember.

➤ Make the change to `showAlert()` and try it out:

```
@IBAction func showAlert() {
  let difference = abs(targetValue - currentValue)

  let message = . . .
}
```

It doesn't get much simpler than that!

> **Exercise:** Something else has changed... can you spot it?

Answer: You wrote **let** `difference` instead of **var** `difference`.

Variables and constants

Swift makes a distinction between variables and *constants*. Unlike a variable, the value of a constant, as the name implies, cannot change.

You can only put something into the box of a constant once and cannot replace it with something else afterwards.

The keyword `var` creates a variable while `let` creates a constant. That means `difference` is now a constant, not a variable.

In the previous algorithms, the value of `difference` could possibly change. If it was negative, you turned it positive. That required `difference` to be a variable, because only variables can have their value change.

Now that you can calculate the whole thing in a single line, `difference` will never have to change once you've given it a value. In that case, it's better to make it a constant with `let`. Why is that better? It makes your intent clear, which in turn helps the Swift compiler understand your program better.

By the same token, `message`, `alert`, and `action` are also constants (and have been all along!). Now, you know why you declared these objects with `let` instead of `var`. Once they've been given a value, they never need to change.

Constants are very common in Swift. Often, you only need to hold onto a value for a very short time. If, in that time, the value never has to change, it's best to make it a constant (`let`) and not a variable (`var`).

What's the score?

Now that you know how far off the slider is from the target, calculating the player's score for each round is easy.


➤ Change `showAlert()` to:

```
@IBAction func showAlert() {
  let difference = abs(targetValue - currentValue)
  let points = 100 - difference

  let message = "You scored \(points) points"
  . . .
}
```

The maximum score you can get is 100 points if you put the slider right on the target and the difference is 0. The farther away from the target you are, the fewer points you earn.

➤ Run the app and score some points!



The alert with the player's score for the current round

Exercise: Because the maximum slider position is 100 and the minimum is 1, the biggest difference is 100 - 1 = 99. That means the absolute worst score you can have in a round is 1 point. Explain why this is so. (Eek! It requires math!)

Showing the total score

In this game, you want to show the player's total score on the screen. After every round, the app should add the newly scored points to the total and then update the score label.

Storing the total score

Because the game needs to keep the total score around for a long time, you will need an instance variable.


➤ Add a new `score` instance variable to **ViewController.swift**:

```
class ViewController: UIViewController {

  var currentValue: Int = 0
  var targetValue = 0
  var score = 0              // add this line
```

Again, we make use of type inference to not specify a type for `score`.

> **Note:** If you are not sure about the inferred type of a variable, there is an easy way to find out. Simply hold down the **Alt** / **Option** key, and hover your cursor over the variable in question. The variable will be highlighted in blue and your cursor will turn into a question mark. Now, click on the variable and you will get a handy popup, which tells you the type of the variable, as well as the source file in which the variable was declared.



Discover the inferred type for a variable

➤ Now that you're using type inference, you can clean up `currentValue` as well (and make its initial value 0, if you haven't already):

```
  var currentValue = 0
```

Thanks to type inference, you only have to specify the data type when you're not giving the variable an initial value. But most of the time, you can safely make Swift guess at the type.

I think type inference is pretty sweet! It will definitely save you some, uh, typing (in more ways than one!).

Updating the total score

Now, `showAlert()` can be amended to update this `score` variable.

➤ Make the following changes:

```
@IBAction func showAlert() {
  let difference = abs(targetValue - currentValue)
  let points = 100 - difference

  score += points        // add this line

  let message = "You scored \(points) points"
  . . .
}
```

Nothing too shocking, here. You just added the following line:

```
score += points
```

This adds the points that the user scored in this round to the total score. You could also have written it like this:

```
score = score + points
```

Personally, I prefer the shorthand += version, but either one is OK. Both accomplish exactly the same thing.

Displaying the score

To display your current score, you're going to do the same thing that you did for the target label: hook up the score label to an outlet and put the score value into the label's `text` property.

> **Exercise:** See if you can do the above by yourself. You've already done these things before for the target value label, so you should be able to repeat those steps for the score label.

Done? You should have added this line to **ViewController.swift**:

```
@IBOutlet var scoreLabel: UILabel!
```

Then, you connect the relevant label on the storyboard (the one that says 999999) to the new `scoreLabel` outlet.

Unsure how to connect the outlet? There are several ways to make connections from user interface objects to the view controller's outlets:

- Control-click on the object to get a context-sensitive popup menu. Then, drag from New Referencing Outlet to View Controller (you did this with the slider).
- Go to the Connections Inspector for the label. Drag from New Referencing Outlet to View Controller (you did this with the target label).
- Control-drag **from** View Controller to the label (give this one a try now) — doing it the other way, Control-dragging from the label to the View Controller, won't work.

There is more than one way to skin a cat, or, connect outlets. :]


Great, that gives you a `scoreLabel` outlet that you can use to display the score. Now, where in the code can you do that? In `updateLabels()`, of course.

➤ Back in **ViewController.swift**, change `updateLabels()` to the following:

```
func updateLabels() {
  targetLabel.text = String(targetValue)
  scoreLabel.text = String(score)     // add this line
}
```

Nothing new here. You convert the score — which is an `Int` — into a `String` and then pass that string to the label's `text` property. In response to that, the label will redraw itself with the new score.

➤ Run the app and verify that the points for this round are added to the total score label whenever you tap the button.



The score label keeps track of the player's total score

One more round...

Speaking of rounds, you also have to increment the round number each time the player starts a new round.

> **Exercise:** Keep track of the current round number (starting at 1) and increment it when a new round starts. Display the current round number in the corresponding label. I may be throwing you into the deep end here, but if you've been able to follow the instructions so far, then you've already seen all the pieces you will need to pull this off. Good luck!

If you guessed that you had to add another instance variable, then you are right. You should add the following line (or something similar) to **ViewController.swift**:

```
var round = 0
```

It's also OK if you included the name of the data type, even though that is not strictly necessary:

```
var round: Int = 0
```

Also, add an outlet for the label:

```
@IBOutlet var roundLabel: UILabel!
```

As before, you should connect the label to this outlet in Interface Builder.

> **Don't forget to make those connections.**
>
> Forgetting to make the connections in Interface Builder is an often-made mistake, especially by yours truly.
>
> It happens to me all the time that I make the outlet for a button and write the code to deal with taps on that button but, when I run the app, it doesn't work. Usually, it takes me a few minutes and some head scratching to realize that I forgot to connect the button to the outlet or the action method.
>
> You can tap on the button all you want but, unless that connection exists, your code will not respond.

Finally, `updateLabels()` should be modified like this:

```
func updateLabels() {
  targetLabel.text = String(targetValue)
  scoreLabel.text = String(score)
  roundLabel.text = String(round)    // add this line
}
```


Did you also figure out where to increment the `round` variable? I'd say the `startNewRound()` method is a pretty good place. After all, you call this method whenever you start a new round. It makes sense to increment the round counter there.

➤ Change `startNewRound()` to:

```
func startNewRound() {
  round += 1           // add this line
  targetValue = ...
}
```

Note that when you declared the `round` instance variable, you gave it a default value of 0. Therefore, when the app starts up, `round` is initially 0. When you call `startNewRound()` for the very first time, it adds 1 to this initial value and, as a result, the first round is properly counted as round 1.

➤ Run the app and try it out. The round counter should update whenever you press the Hit Me! button.



The round label counts how many rounds have been played

You're making great progress; well done!

You can find the project files for the app up to this point under **05-Rounds-and-score** in the Source Code folder. If you get stuck, compare your version of the app with these source files to see if you missed anything.

Chapter 6: Polish

By Fahim Farook

At this point, your game is fully playable. The gameplay rules are all implemented and the logic doesn't seem to have any big flaws. As far as I can tell, there are no bugs either. But there's still some room for improvement.

This chapter will cover the following:

- **Tweaks:** Small UI tweaks to make the game look and function better.
- **The alert:** Updating the alert view functionality so that the screen updates *after* the alert goes away.
- **Start over:** Resetting the game to start afresh.

Tweaks

Obviously, the game is not very pretty yet — you will get to work on that soon. In the mean time, there are a few smaller tweaks you can make.

The alert title

Unless you already changed it, the title of the alert still says "Hello, World!" You could give it the name of the game, *Bull's Eye*, but I have a better idea. What if you change the title depending on how well the player did?

If the player put the slider right on the target, the alert could say: "Perfect!" If the slider is close to the target but not quite there, it could say, "You almost had it!" If the player is way off, the alert could say: "Not even close..." And so on. This gives the player a little more feedback on how well they did.

> **Exercise:** Think of a way to accomplish this. Where would you put this logic and how would you program it? Hint: there are an awful lot of "if's" in the preceding sentences.

The right place for this logic is `showAlert()`, because that is where you create the `UIAlertController`. You already do some calculations to create the message text and now you will do something similar for the title text.

➤ Here is the changed method in its entirety — replace the existing method with it:

```
@IBAction func showAlert() {
  let difference = abs(targetValue - currentValue)
  let points = 100 - difference
  score += points

  // add these lines
  let title: String
  if difference == 0 {
    title = "Perfect!"
  } else if difference < 5 {
    title = "You almost had it!"
  } else if difference < 10 {
    title = "Pretty good!"
  } else {
    title = "Not even close..."
  }

  let message = "You scored \(points) points"
```

```
    let alert = UIAlertController(
      title: title,  // change this
      message: message,
      preferredStyle: .alert)

    let action = UIAlertAction(
      title: "OK",
      style: .default,
      handler: nil)

    alert.addAction(action)
    present(alert, animated: true, completion: nil)

    startNewRound()
  }
```

You create a new string constant named `title`, which will contain the text that is set for the alert title. Initially, this `title` doesn't have any value. We'll discuss the `title` variable and how it is set up a bit more in detail just a little further on.

To decide which title text to use, you look at the difference between the slider position and the target:

- If it equals 0, then the player was spot-on and you set `title` to "Perfect!" .
- If the difference is less than 5, you use the text "You almost had it!"
- A difference less than 10 is "Pretty good!"
- However, if the difference is 10 or greater, then you consider the player's attempt "Not even close..."

Can you follow the logic here? It's just a bunch of `if` statements that consider the different possibilities and choose a string in response.

When you create the `UIAlertController` object, you now give it this `title` string instead of some fixed text.

Constant initialization

In the above code, did you notice that `title` was declared explicitly as being a `String` constant? And did you ask yourself why type inference wasn't used there instead? Also, if `title` is a constant, how do we have code which sets its value in multiple places?

The answer to all of these questions lies in how constants (or `let` values, if you prefer) are initialized in Swift.

You could certainly have used type inference to declare the type for `title` by setting the initial declaration to:

```
let title = ""
```

But do you see the issue there? Now you've actually set the value for `title` and since it's a constant, you can't change the value again. So, the following lines where the `if` condition logic sets a value for `title` would now throw a compiler error since you are trying to set a value to a constant which already has a value. (Go on, try it out for yourself! You know you want to … :])

One way to fix this would be to declare `title` as a variable rather than a constant. Like this:

```
var title = ""
```

The above would work great, and the compiler error would go away. But you've got to ask yourself, do you really need a variable there? Or, would a constant do? I personally prefer to use constants where possible since they have less risk of unexpected side-effects because the value was accidentally changed in some fashion — for example, because one of your team members changed the code to use a variable that you had originally depended on being unchanged. That is why the code was written the way it was. However, you can go with whichever option you prefer since either approach would work.

But if you do declare `title` as a constant, how is it that your code above assigns multiple values to it? The secret is in the fact that while there are indeed multiple values being assigned to `title` , only one value would be assigned per each call to `showAlert` since the branches of an `if` condition are mutually exclusive. So, since `title` starts out without a value (the `let title: String` line only assigns a type, not a value), as long as the code ensures that `title` would always be initialized to a value before the value stored in `title` is accessed, the compiler will not complain.


Again, you can test this by removing the `else` condition in the block of code where a value is assigned to `title`. Since an `if` condition is only one branch of a test, you need an `else` branch in order for the tests (and the assignment to `title`) to be exhaustive.

So, if you remove the `else` branch, Xcode will immediately complain with an error like: "Constant 'title' used before being initialized".

```
56      let title: String
57      if difference == 0 {
58        title = "Perfect!"
59      } else if difference < 5 {
60        title = "You almost had it!"
61      } else if difference < 10 {
62        title = "Pretty good!"
63  //    } else {
64  //      title = "Not even close..."
65      }
66      let message = "You scored \(points) points"
67
68      let alert = UIAlertController(
69        title: title,                    Constant 'title' used before being initialized
70        message: message,
71        preferredStyle: .alert)
72
73      let action = UIAlertAction(
74        title: "OK",
75        style: .default,
76        handler: nil)
```

A constant needs to be initialized exhaustively

Run the app and play the game for a bit. You'll see that the title text changes depending on how well you're doing. That `if` statement sure is handy!



The alert with the new title

Bonus points

Exercise: Give players an additional 100 bonus points when they get a perfect score. This will encourage players to really try to place the bull's eye right on the target. Otherwise, there isn't much difference between 100 points for a perfect score and 98 or 95 points if you're close but not quite there.

Now there is an incentive for trying harder – a perfect score is no longer worth just 100 but 200 points! Maybe you can also give the player 50 bonus points for being just one off.

➤ Here is how I would have made these changes:

```
@IBAction func showAlert() {
  let difference = abs(targetValue - currentValue)
  var points = 100 - difference     // change let to var

  let title: String
  if difference == 0 {
    title = "Perfect!"
    points += 100                   // add this line
  } else if difference < 5 {
    title = "You almost had it!"
    if difference == 1 {            // add these lines
      points += 50                  // add these lines
    }                               // add these lines
  } else if difference < 10 {
    title = "Pretty good!"
  } else {
    title = "Not even close..."
  }
  score += points                   // move this line here from
the top
  . . .
}
```


You should notice a few things:

- In the first `if` you'll see a new statement between the curly brackets. When the difference is equal to zero, you now not only set `title` to "Perfect!" but also award an extra 100 points.
- The second `if` has changed too. There is now an `if` inside another `if`. Nothing wrong with that! You want to handle the case where `difference` is 1 in order to give the player bonus points. That happens inside the new `if` statement.

  After all, if the difference is more than 0 but less than 5, it could be 1 (but not necessarily all the time). Therefore, you perform an additional check to see if the difference truly is 1, and if so, add 50 extra points.
- Because these new `if` statements add extra points, `points` can no longer be a constant; it now needs to be a variable. That's why you change it from `let` to `var`.
- Finally, the line `score += points` has moved below the `if`s. This is necessary because the app updates the `points` variable inside those `if` statements (if the conditions are right) and you want those additional points to count towards the final score.

If your code is slightly different, then that's fine too, as long as it works! There is often more than one way to program something, and if the results are the same, then any approach is equally valid.

➤ Run the app to see if you can score some bonus points!



Raking in the points...

Local variables recap

I would like to point out once more the difference between local variables and instance variables. As you should know by now, a local variable only exists for the duration of the method that it is defined in, while an instance variable exists as long as the view controller (or any object that owns it) exists. The same thing is true for constants.

In `showAlert()`, there are six locals and you use three instance variables:

```
let difference = abs(targetValue - currentValue)
var points = 100 - difference
let title = . . .
score += points
let message = . . .
let alert = . . .
let action = . . .
```

Exercise: Point out which are the locals and which are the instance variables in the `showAlert()` method. Of the locals, which are variables and which are constants?

Locals are easy to recognize, because the first time they are used inside a method their name is preceded with `let` or `var`:

```
let difference = . . .
var points = . . .
let title = . . .
let message = . . .
let alert = . . .
let action = . . .
```

This syntax creates a new variable (`var`) or constant (`let`). Because these variables and constants are created inside the method, they are locals.

Those six items – `difference`, `points`, `title`, `message`, `alert`, and `action` – are restricted to the `showAlert()` method and do not exist outside of it. As soon as the method is done, the locals cease to exist.

You may be wondering how `difference`, for example, can have a different value every time the player taps the Hit Me! button, even though it is a constant – after all, aren't constants given a value just once, never to change afterwards?

Here's why: each time a method is invoked, its local variables and constants are created anew. The old values have long been discarded and you get brand new ones.

When `showAlert()` is called a second time, it creates a completely new instance of `difference` that is unrelated to the previous one. That particular constant value is only used until the end of `showAlert()` and then it is discarded.

The next time `showAlert()` is called after that, it creates yet another new instance of `difference` (as well as new instances of the other locals `points`, `title`, `message`, `alert`, and `action`). And so on... There's some serious recycling going on here!

But inside a single invocation of `showAlert()`, `difference` can never change once it has a value assigned. The only local in `showAlert()` that can change is `points`, because it's a `var`.

The instance variables, on the other hand, are defined outside of any method. It is common to put them at the top of the file:

```
class ViewController: UIViewController {
  var currentValue = 0
  var targetValue = 0
  var score = 0
  var round = 0
```

As a result, you can use these variables inside any method, without the need to declare them again, and they will keep their values till the object holding them (the view controller in this case) ceases to exist.

If you were to do this:

```
@IBAction func showAlert() {
  let difference = abs(targetValue - currentValue)
  var points = 100 - difference

  var score = score + points       // doesn't work!
  . . .
}
```

Then things wouldn't work as you'd expect them to. Because you now put `var` in front of `score`, you have made it a new local variable that is only valid inside this method.

In other words, this won't add `points` to the *instance variable* `score` but to a new *local variable* that also happens to be named `score`. In this case, the instance variable `score` never changes, even though it has the same name.

Obviously that is not what you want to happen here. Fortunately, the above won't even compile. Swift knows there's something fishy about that line.

> **Note:** To make a distinction between the two types of variables, so that it's always clear at a glance how long they will live, some programmers prefix the names of instance variables with an underscore.
>
> They would name the variable `_score` instead of just `score`. Now there is less confusion because names beginning with an underscore won't be mistaken for being locals. This is only a convention. Swift doesn't care one way or the other how you name your instance variables.
>
> Other programmers use different prefixes, such as "m" (for member) or "f" (for field) for the same purpose. Some even put the underscore *behind* the variable name. Madness!

The alert

There is something that bothers me about the game. You may have noticed it too...

As soon as you tap the Hit Me! button and the alert pops up, the slider immediately jumps back to its center position, the round number increments, and the target label already gets the new random number.

What happens is that the new round has already begun while you're still watching the results of the last round. That's a little confusing (and annoying). It would be better to wait on starting the new round until *after* the player has dismissed the alert popup. Only then is the current round truly over.

Asynchronous code execution

Maybe you're wondering why this isn't already happening? After all, in `showAlert()` you only call `startNewRound()` after you've shown the alert popup:

```
@IBAction func showAlert() {
  . . .
  let alert = UIAlertController(. . .)
  let action = UIAlertAction(. . .)
  alert.addAction(action)

  // Here you make the alert visible:
  present(alert, animated: true, completion: nil)

  // Here you start the new round:
  startNewRound()
}
```

Contrary to what you might expect, `present(alert:animated:completion:)` doesn't hold up execution of the rest of the method until the alert popup is dismissed. That's how alerts on other platforms tend to work, but not on iOS.

Instead, `present(alert:animated:completion:)` puts the alert on the screen and immediately returns control to the next line of code in the method. The rest of the `showAlert()` method is executed right away, and the new round starts before the alert popup has even finished animating.

In programmer-speak, alerts work *asynchronously*. We'll talk much more about that in a later chapter, but what it means for you right now is that you don't know in advance when the alert will be done. But you can bet it will be well after `showAlert()` has finished.

Alert event handling

So, if your code execution can't wait in `showAlert()` until the popup is dismissed, then how do you wait for it to close?

The answer is simple: events! As you've seen, a lot of the programming for iOS involves waiting for specific events to occur – buttons being tapped, sliders being moved, and so on. This is no different.

You have to wait for the "alert dismissed" event somehow. In the mean time, you simply do nothing.

Here's how it works:

For each button on the alert, you have to supply a `UIAlertAction` object. This object tells the alert what the text on the button is – "OK" – and what the button looks like (you're using the default style here):

```
let action = UIAlertAction(title: "OK", style: .default,
handler: nil)
```

The third parameter, `handler`, tells the alert what should happen when the button is pressed. This is the "alert dismissed" event you've been looking for!

Currently `handler` is `nil`, which means nothing happens. In case you're wondering, a `nil` in Swift indicates "no value". You will learn more about `nil` values later on.

You can however, give the `UIAlertAction` some code to execute when the OK button is tapped. When the user finally taps OK, the alert will remove itself from the screen and jump to your code. That's your cue to start a new round.

This is also known as the *callback* pattern. There are several ways this pattern manifests on iOS. Often you'll be asked to create a new method to handle the event. But here you'll use something new: a *closure*.

➤ Change the bottom bit of `showAlert()` to:

```
@IBAction func showAlert() {
  . . .
  let alert = UIAlertController(. . .)

  let action = UIAlertAction(
    title: "OK",
    style: .default,
    handler: { _ in
      self.startNewRound()
    })
```

```
    alert.addAction(action)
    present(alert, animated: true, completion: nil)
  }
```

Two things have happened, here:

1. You removed the call to `startNewRound()` from the bottom of the method. (Don't forget this part!)
2. You placed it inside a block of code that you gave to `UIAlertAction`'s `handler` parameter. Such a block of code is called a *closure*. You can think of it as a method without a name. This code is not performed right away. Rather, it's performed only when the OK button is tapped. This particular closure tells the app to start a new round (and update the labels) when the alert is dismissed.

➤ Run the app and see for yourself. I think the game feels a lot better this way.

Self

You may be wondering why in the handler block you did `self.startNewRound()` instead of just writing `startNewRound()` like before.

The `self` keyword allows the view controller to refer to itself. That shouldn't be too strange a concept. When you say, "I want ice cream," you use the word "I" to refer to yourself. Similarly, objects can talk about (or to) themselves as well.

Normally you don't need to use `self` to send messages to the view controller, even though it is allowed. The exception: inside closures you *do* have to use `self` to refer to the view controller.

This is a rule in Swift. If you forget `self` in a closure, Xcode will complain (try it out). This rule exists because closures can "capture" variables, which comes with surprising side effects. You'll learn more about that in later chapters.

★ ★ ★

Trailing Closures

Now that you've learnt about closures, there's one more thing you should know about closures in Swift — trailing closure syntax. Remember the closure you just added to the alert? (How can you forget, you literally just added it, right?)

Well, that same code can be written like this as well:

```
let action = UIAlertAction(
  title: "OK",
  style: .default) {_ in
  self.startNewRound()
}
```

Do you see what's different? We don't have the `handler` parameter any longer. Instead, the method has the closure *outside* the method. This is a feature in Swift — if the final parameter (or parameters) in your method/function is a closure, you can put the closure outside the closing parenthesis of the method/function. Plus, you can omit the parameter name for the first trailing closure — do note that if you have multiple trailing closure parameters, all closures after the first one have to have the parameter name.

This is called *syntactic sugar* — a "shortcut" provided by a programming language to write a bit of code which also makes it easier to read that code.

Some people prefer using trailing closures, to including the closure within the method call itself because they feel that the code is much easier to read/scan. As always, you should pick the method which works best for you :]



Start over

No, you're not going to throw away the source code and start this project all over! I'm talking about the game's "Start Over" button. This button is supposed to reset the score and start over from the first round. One use of the Start Over button is for playing against another person. The first player does ten rounds, then the score is reset and the second player does ten rounds. The player with the highest score wins.

> **Exercise:** Try to implement the Start Over button on your own. You've already seen how you can make the view controller react to button presses, and you should be able to figure out how to change the `score` and `round` variables.

How did you do? If you got stuck, then follow the instructions below.

The new method

First, add a method to **ViewController.swift** that starts a new game. I suggest you put it near `startNewRound()` because the two are conceptually related.

➤ Add the new method:

```
func startNewGame() {
  score = 0
  round = 0
  startNewRound()
}
```

This method resets `score` and `round` to zero, and starts a new round as well.

Notice that you set `round` to 0 here, not to 1. You use 0 because incrementing the value of `round` is the first thing that `startNewRound()` does. If you were to set `round` to 1, then `startNewRound()` would add another 1 to it and the first round would actually be labeled round 2. So, you begin at 0, let `startNewRound()` add one and everything works great.

It's probably easier to figure this out from the code than from my explanation. This should illustrate why we don't program computers in English. You also need an action method to handle taps on the Start Over button. You could write a new method like the following:

```
@IBAction func startOver() {
  startNewGame()
}
```

But you'll notice that this method simply calls the previous method you added :] So, why not cut out the middleman? You can simply change the method you added previously to be an action instead, like this:

```
@IBAction func startNewGame() {
  score = 0
  round = 0
  startNewRound()
}
```

You could follow either of the above approaches since both are equally valid. Personally, I like to have less code since that means there's less stuff to maintain (and less of a chance of screwing something up :]). Sometimes, there could also be legitimate reasons for having a separate action method which calls your own method, but in this particular case, it's better to keep things simple.

Just to keep things consistent, in `viewDidLoad()` you should replace the call to `startNewRound()` with `startNewGame()`. Because `score` and `round` are already 0 when the app starts, it won't really make any difference to how the app works, but it does make the intention of the source code clearer. (If you wonder whether you can call an `IBAction` method directly instead of hooking it up to an action in the storyboard, yes, you certainly can do so.)

➤ Make this change:

```
override func viewDidLoad() {
  super.viewDidLoad()
  startNewGame()        // this line changed
}
```

Connect the outlet


Finally, you need to connect the Start Over button to the action method.

➤ Open the storyboard and Control-drag from the **Start Over** button to **View Controller**. Let go of the mouse button and pick **startNewGame** from the popup if you opted to have `startNewGame()` as the action method. Otherwise, pick the name of your action method. That connects the button's Touch Up Inside event to the action you have just defined.

➤ Run the app and play a few rounds. Press Start Over and the game puts you back at square one.

Tip: If you're losing track of what button or label is connected to what method, you can click on **View Controller** in the storyboard to see all the connections that you have made so far.

You can either right-click on View Controller to get a popup, or simply view the connections in the **Connections inspector**. This shows all the connections for the view controller.



All the connections from View Controller to the other objects

Now your game is pretty polished and your task list has gotten really short. You can find the project files for the current version of the app under **06-Polish** in the Source Code folder.

Chapter 7: The New Look

By Fahim Farook

Bull's Eye is looking good, the gameplay elements are done, and there's one item left in your to-do list — "Make it look pretty".

You have to admit the game still doesn't look great. If you were to put this on the App Store in its current form, I'm not sure many people would be excited to download it. Fortunately, iOS makes it easy for you to create good-looking apps, so let's give *Bull's Eye* a makeover and add some visual flair.

This chapter covers the following:

- **Landscape orientation revisited:** Project changes to make landscape orientation support work better.
- **Spice up the graphics:** Replace the app UI with custom graphics to give it a more polished look.
- **The about Screen:** Add an about screen to the app and make it look spiffy.

Landscape orientation revisited


First, let's quickly revisit another item in the to-do list — "Put the app in landscape orientation." You already did this, right? But there's a little bit of clean up to be done with regards to that item.

Apps in landscape mode do not display the iPhone status bar, unless you tell them to. That's great for your app — games require a more immersive experience and the status bar detracts from that.

Even though the system automatically handles hiding the status bar for your game, there is still one thing you can do to improve the way *Bull's Eye* handles the status bar.

➤ Go to the **Project Settings** screen and scroll down to **Deployment Info**. Under **Status Bar Style**, check **Hide status bar**.

This will ensure that the status bar is hidden during application launch.



Hiding the status bar when the app launches

It's a good idea to hide the status bar while the app is launching. It takes a few seconds for the operating system to load the app into memory and start it up, and during that time the status bar remains visible, unless you hide it using this option.

It's only a small detail, but the difference between a mediocre app and a great app is that great apps get all the small details right.

➤ That's it. Run the app and you'll see that the status bar is history.


★ ★ ★

Info.plist and Info Tab

Before Xcode 13, most of the options from the Project Settings screen, such as the supported device orientations and whether the status bar is visible during launch, used to be stored in your app's Info.plist file.

However, in Xcode 13, the Info.plist file, if it exists at all, will be pretty empty. Let's take a look.


➤ Go to the **Project navigator** and select the file named **Info.plist** to take a peek at its contents.



Most of the project settings that used to be stored in Info.plist are now stored in the Xcode project file itself. Since you can make changes to the settings via the Xcode interface (as you did above for the status bar style), not having the settings in Info.plist makes sense.

But if you still want to see all these settings in one place as you used to be able to via Info.plist, you still can do that. You just have to go to the project's Info tab.

➤ Go to the **Project Settings** screen and select the **Info** tab.



The Xcode Info tab


You should now see a list of configuration options and their values just as you used to do formally via the Info.plist file. Most of these may not make sense to you, but that's OK – they don't always make sense to me either.

Notice the option **Status bar is initially hidden**. It has the value YES. This is the option that you just changed.

★ ★ ★


Spice up the graphics

Getting rid of the status bar is only the first step. We want to go from this:



Yawn...

To something that's more like this:



Cool :-]


The actual controls won't change. You'll simply be using images to smarten up their look, and you will also adjust the colors and typefaces. You can put an image in the background, on the buttons, and even on the slider, to customize the appearance of each. The images you use should generally be in PNG format, though JPG files would work too.

Add the image assets

If you are artistically challenged, then don't worry, I have provided a set of images for you. But if you do have mad Photoshop skillz, then by all means feel free to design (and use) your own images. The Resources folder that comes with this book contains a subfolder named Images. You will first import these images into the Xcode project.


➤ In the **Project navigator**, find **Assets.xcassets** and click on it.

This item is known as the asset catalog for the app and it contains all the app's images. Right now, it is empty and contains just a couple of placeholders.




The asset catalog is initially empty

➤ At the bottom of the secondary pane, the one with AppIcon, there is a + button. Click it and then select the **Import...** option:




Choose Import to put existing images into the asset catalog

Xcode shows a file picker. Select the **Images** folder from the resources and press **⌘+A** to select all the files inside this folder.



Choosing the images to import

Click **Open** and Xcode copies all the image files from that folder into the asset catalog:



The images are now inside the asset catalog

If Xcode added a folder named "Images" instead of the individual image files, then try again and this time make sure that you select the files *inside* the Images folder rather than the folder itself before you click Open.

> **Note:** Instead of using the **Import...** menu option as above, you could also simply drag the necessary files from Finder on to the Xcode asset catalog view. As ever, there's more than one way to do the same thing in Xcode.

★ ★ ★

1x, 2x, and 3x displays

Each image set in the asset catalog has a slot for a "2x" image, but you can also specify 1x and 3x images. Having multiple versions of the same image in varying sizes allows your apps to support the wide variety of iPhone and iPad displays in existence.

1x is for low-resolution screens, the ones with the big, chunky pixels. There are no low-resolution devices in existence that can actually run iOS 15 – they are too old to bother with – so you're not likely to come across many 1x images anymore. 1x is only a concern if you're working on an app that still needs to support iOS 9 or older.

2x is for high-resolution Retina screens. This covers most modern iPhones, iPod touches, and iPads. Retina images are twice as big as the low-res images, hence the 2x. The images you imported just now are 2x images.

3x is for the super high-resolution Retina HD screen of the iPhone Plus devices. If you want your app to have extra sharp images on these top-of-the-line iPhone models, then you can drop them into the "3x" slot in the asset catalog.

There is a special naming convention for image files. If the filename ends in **@2x** or **@3x** then that's considered the Retina or Retina HD version. Low-resolution 1x images have no special name (you don't have to write @1x).


★ ★ ★

Put up the wallpaper

Let's begin by changing the drab white background in *Bull's Eye* to something more fancy.


➤ Open **Main.storyboard**, open the **Library** panel (via the top toolbar) and locate an **Image View**.

Tip: if you type "image" into the search box at the top of the Library panel, it will quickly filter out all the other views.



The Image View control in the Objects Library


➤ Drag the image view on top of the existing user interface. It doesn't really matter where you put it, as long as it's inside the Bull's Eye View Controller.



Dragging the Image View into the view controller

➤ With the image view still selected, go to the **Size inspector** (that's the one next to the Attributes inspector) and set X and Y to 0, Width to 667 and Height to 375.


This will make the image view cover the entire screen.



The Size inspector settings for the Image View

➤ Go to the **Attributes inspector** for the image view. At the top there is an option named **Image**. Click the downward arrow and choose **Background** from the list.

This will put the image named "Background" from the asset catalog into the image view.



Setting the background image on the Image View


There is only one problem: the image now covers all the other controls. There is an easy fix for that; you have to move the image view behind the other views.

➤ With the image view selected, in the **Editor** menu in Xcode's menu bar at the top of the screen, choose **Arrange ▸ Send to Back**.

Sometimes Xcode gives you a hard time with this (it still has a few bugs) and you might not see the Send to Back item enabled. If so, try de-selecting the Image View and then selecting it again. Now the menu item should be available.

Alternatively, select the image view in the Document Outline and drag it to the top of the list of views, just below Safe Area, to accomplish the same thing. (The items in the Document Outline view are listed so that the backmost item is at the top of the list and the frontmost one is at the bottom.)

Your interface should now look something like this:




The game with the new background image

That takes care of the background. Run the app and marvel at the new graphics.

Change the labels


Because the background image is quite dark, the black text labels have become hard to read. Fortunately, Interface Builder lets you change label color. While you're at it, you might change the font as well.

➤ Still in the storyboard, select the label at the top, open the **Attributes inspector** and click on the **Color** item to show a dropdown for color values. Select **Custom...** at the bottom of the list.



Setting the text color on the label

This opens the Color Picker, which has several ways to select colors. I prefer the sliders (second tab). If all you see is a gray scale slider, then select **RGB Sliders** from the picker at the top.



The Color Picker

➤ Pick a pure white color, Red: 255, Green: 255, Blue: 255, Opacity: 100%. Alternatively, you can simply pick **White Color** from the initial dropdown instead of opening the Color Picker at all, but it's good to know that the Color Picker is there in case you want to do custom colors.

➤ Click on the **Shadow** item from the Attributes inspector. This lets you add a subtle shadow to the label. By default this color is transparent (also known as "Clear Color") so you won't see the shadow. Using the Color Picker, choose a pure black color that is half transparent, Red: 0, Green: 0, Blue: 0, Opacity: 50%.


Note: Sometimes when you change the Color or Shadow attributes, the background color of the view also changes. This is a bug in Xcode. Put it back to Clear Color if that happens.

➤ Change the **Shadow Offset** to Width: 0, Height: 1. This puts the shadow below the label.

The shadow you've chosen is very subtle. If you're not sure that it's actually visible, then toggle the height offset between 1 and 0 a few times. Look closely and you should be able to see the difference. As I said, it's very subtle.


➤ Click on the **[T]** icon of the **Font** attribute. This opens the Font Picker.

By default, the System font is selected. That uses whatever is the standard system font for the user's device. The system font is nice enough but we want something more exciting for this game.



Font picker with the System font

➤ Choose **Font: Custom**. That enables the Family field. Choose **Family: Arial Rounded MT Bold**. Set the Size to 16.



Setting the label's font

➤ The label also has an attribute **Autoshrink**. Make sure this is set to **Fixed Font Size**.

If enabled, Autoshrink will dynamically change the size of the font if the text is larger than will fit into the label. That is useful in certain apps, but not in this one. Instead, you'll change the size of the label to fit the text rather than the other way around.

➤ With the label selected, press ⌘= on your keyboard, or choose **Size to Fit Content** from the **Editor** menu.

(If the Size to Fit Content menu item is disabled, then de-select the label and select it again. Sometimes Xcode gets confused about what is selected. Poor thing.)


The label will now become slightly larger or smaller so that it fits snugly around the text. If the text got cut off when you changed the font, now all the text will show again.

You don't have to set these properties for the other labels one by one; that would be a big chore. You can speed up the process by selecting multiple labels and then applying these changes to that entire selection.

➤ Click on the **Score:** label to select it. Hold ⌘ and click on the **Round:** label. Now both labels will be selected. Repeat what you did above for these labels:

- Set Color to pure white, 100% opaque.
- Set Shadow to pure black, 50% opaque.
- Set Shadow Offset to width 0, height 1.
- Set Font to Arial Rounded MT Bold, size 16.
- Make sure Autoshrink is set to Fixed Font Size.


As you can see, in my storyboard the text no longer fits into the Score and Round labels:



The font is too large to fit all the text in the Score and Round labels

You can either make the labels larger by dragging their handles to resize them manually, or you can use the **Size to Fit Content** option (⌘=). I prefer the latter because it's less work.

Tip: Xcode is smart enough to remember the colors you have used recently. Instead of going into the Color Picker all the time, you can simply choose a color from the Recently Used Colors menu which is part of the dropdown you get when you click on any color option:




Quick access to recently used colors and several handy presets

Exercise: You still have a few labels to go. Repeat what you just did for the other labels. They should all become white, have the same shadow and have the same font. However, the two labels on either side of the slider (1 and 100) will have font size 14, while the other labels (the ones that will hold the target value, the score and the round number) will have font size 20 so they stand out more.

Because you've changed the sizes of some of the labels, your carefully constructed layout may have been messed up a bit. You may want to clean it up a little.

At this point, the game screen should look something like this:



What the storyboard looks like after styling the labels

All right, it's starting to look like something now. By the way, feel free to experiment with the fonts and colors. If you want to make it look completely different, then go right ahead. It's your app!

The buttons

Changing the look of the buttons works very much the same way.

➤ Select the **Hit Me!** button. In the **Size inspector** set its Width to 100 and its Height to 37.

➤ Center the position of the button on the inner circle of the background image.

➤ Go to the **Attributes inspector**. Change **Type** from System to **Custom**.

A "system" button just has a label and no border. By making it a custom button, you can style it any way you wish.

➤ Change **Style** to **Default**. The Library has multiple types of Button — Button, Gray Button, Tinted Button, and Filled Button — but if you'd selected the plain Button, then your Style would have been set to Plain.

A plain button does not show different states when you tap it. You change the Style to Default to indicate that you want a button with different states for highlighted, selected, disabled etc.

Note that you now have a State Config dropdown which is set to Default. We'll come back to that in a bit.

➤ Still in the **Attributes inspector**, press the arrow on the **Background** field and choose **Button-Normal** from the list.

➤ Set the **Font** to **Arial Rounded MT Bold**, size 20.

➤ Set the **Text Color** to red: 96, green: 30, blue: 0, opacity: 100%. This is a dark brown color.


➤ Set the **Shadow Color** to pure white, 50% opacity. The shadow offset should be Width 0, Height 1.

Blending in

Setting the opacity to anything less than 100% will make the color slightly transparent (with opacity of 0% being fully transparent). Partial transparency makes the color blend in with the background and makes it appear softer.

Try setting the shadow color to 100% opaque pure white and notice the difference.

This finishes the setup for the Hit Me! button in its "Default" state:



The attributes for the Hit Me button in the default state

As I mentioned above, Default Style buttons can have more than one state. When you tap a button and hold it down, it should appear "pressed down" to let you know that the button will be activated when you lift your finger. This is known as the *highlighted* state and is an important visual cue to the user.


➤ With the button still selected, click the **State Config** setting and pick **Highlighted** from the menu. Now the attributes in this section reflect the highlighted state of the button.

➤ In the **Background** field, select **Button-Highlighted**.

➤ Make sure the highlighted **Text Color** is the same color as before (red 96, green 30, blue 0, or simply pick it from the Recently Used Colors menu). Change the **Shadow Color** to half-transparent white again.

➤ Check the **Reverses On Highlight** option. This will give the appearance of the label being pressed down when the user taps the button.

You could change the other properties too, but don't get too carried away. The highlight effect should not be too jarring.



The attributes for the highlighted Hit Me button

To test the highlighted look of the button in Interface Builder you can toggle the **Highlighted** box in the **Control** section, but make sure to turn it off again or the button will initially appear highlighted when the screen is shown.

That's it for the Hit Me! button. Styling the Start Over button is very similar, except you will replace its title text with an icon.


➤ Select the **Start Over** button and change the following attributes:

- Set Type to Custom.
- Set Style to Default.
- Remove the text "Start Over" from the button.
- For Image choose **StartOverIcon**
- For Background choose **SmallButton**
- Check the Size Inspector to ensure that Width and Height are set to 32. This should be done automatically when you set the background image, but it's good to verify.

You won't set a highlighted state on this button — let UIKit take care of this. If you don't specify a different image for the highlighted state, UIKit will automatically darken the button to indicate that it is pressed.

➤ Make the same changes to the ⓘ button, but this time choose **InfoButton** for the image.

The user interface is almost done. Only the slider is left...



Almost done!

The slider

Unfortunately, you can only customize the slider a little bit in Interface Builder. For the more advanced customization that this game needs – putting your own images on the thumb and the track – you have to resort to writing code.

Do note that everything you've done so far in Interface Builder you could also have done in code. Setting the color on a button, for example, can be done by sending the `setTitleColor()` message to the button. (You would normally do this in `viewDidLoad`.)

However, I find that doing visual design work is much easier and quicker in a visual editor such as Interface Builder than writing the equivalent source code. But for the slider you have no choice.

➤ Go to **ViewController.swift**, and add the following to `viewDidLoad()`:

```
let thumbImageNormal = UIImage(named: "SliderThumb-Normal")!
slider.setThumbImage(thumbImageNormal, for: .normal)

let thumbImageHighlighted = UIImage(
```

```
    named: "SliderThumb-Highlighted")!
  slider.setThumbImage(thumbImageHighlighted, for: .highlighted)

  let insets = UIEdgeInsets(
    top: 0,
    left: 14,
    bottom: 0,
    right: 14)

  let trackLeftImage = UIImage(named: "SliderTrackLeft")!
  let trackLeftResizable = trackLeftImage.resizableImage(
    withCapInsets: insets)
  slider.setMinimumTrackImage(trackLeftResizable, for: .normal)


  let trackRightImage = UIImage(named: "SliderTrackRight")!
  let trackRightResizable = trackRightImage.resizableImage(
    withCapInsets: insets)
  slider.setMaximumTrackImage(trackRightResizable, for: .normal)
```

This sets four images on the slider: two for the thumb and two for the track. (And if you're wondering what the "thumb" is, that's the little circle in the center of the slider, the one that you drag around to set the slider value.)

The thumb works like a button so it gets an image for the normal (un-pressed) state and one for the highlighted state.

The slider uses different images for the track on the left of the thumb (green) and the track to the right of the thumb (gray).

➤ Run the app. You have to admit it looks fantastic now!



The game with the customized slider graphics

To .png or not to .png

If you recall, the images that you imported into the asset catalog had filenames like **SliderThumb-Normal@2x.png** and so on.

When you create a `UIImage` object, you don't use the original filename but the name that is listed in the asset catalog, **SliderThumb-Normal**.

That means you can leave off the **@2x** bit and the **.png** file extension.


The About screen

Your game looks awesome and your to-do list is done. So, does this mean that you are done with *Bull's Eye*?

Not so fast! :] Remember the ⓘ button on the game screen? Try tapping it. Does it do anything? No?

Oops! Looks as if we forgot to add any functionality to that button! It's time to rectify that — let's add an "about" screen to the game which shows some information about the game and have it display when the user taps on the ⓘ button.

Initially, the screen will look something like this (but we'll prettify it soon enough):



The new About screen

This new screen contains a *text view* with the gameplay rules and a button to close the screen.


Most apps have more than one screen, even very simple games. So, this is as good a time as any to learn how to add additional screens to your apps.

I have pointed it out a few times already: each screen in your app will have its own view controller. If you think "screen", think "view controller".

Xcode automatically created the main `ViewController` object for you, but you'll have to create the view controller for the About screen yourself.


Add a new view controller

➤ Go to Xcode's **File** menu and choose **New ▸ File...** In the window that pops up, choose the **Cocoa Touch Class** template (if you don't see it, then make sure **iOS** is selected at the top).



Choosing the file template for Cocoa Touch Class

Click **Next**. Xcode gives you some options to fill out:




The options for the new file

Choose the following:

- Class: **AboutViewController**
- Subclass of: **UIViewController**
- Also create XIB file: Leave this box unchecked.
- Language: **Swift**

Click **Next**. Xcode will ask you where to save this new view controller.



Saving the new file

➤ Choose the **BullsEye** folder (this folder should already be selected).

Also make sure **Group** says **BullsEye** and that there is a checkmark in front of BullsEye in the list of **Targets**. (If you don't see this panel, click the Options button at the bottom of the dialog.)

➤ Click **Create**.


Xcode will create a new file and add it to your project. As you might have guessed, the new file is **AboutViewController.swift**.

Design the view controller in Interface Builder

To design this new view controller, you need to pay a visit to Interface Builder.

➤ Open **Main.storyboard**. There is no scene representing the About view controller in the storyboard yet. So, you'll have to add this first.

➤ From the **Library**, choose **View Controller** and drag it on to the canvas, to the right of the main View Controller.




Dragging a new View Controller from the Objects Library

This new view controller is totally blank. You may need to rearrange the storyboard so that the two view controllers don't overlap. Interface Builder isn't very tidy about where it puts things.

➤ Drag a new **Button** on to the screen and give it the title **Close**. Put it somewhere around the bottom center of the view (use the blue guidelines to help with positioning).

➤ Drag a **Text View** on to the view and make it cover most of the space above the button. Note that there is also a Text Field, which is a single-line text component — that's not what you want. You're looking for Text View, which can contain multiple lines of text.

After dragging both the text view and the button on to the canvas, it should look something like this:



The About screen in the storyboard

➤ Double-click the text view to make its content is editable. By default, the Text View contains a bunch of Latin placeholder text (also known as "Lorem Ipsum").

Enter this new text into the Text View:


```
*** Bull's Eye ***

Welcome to the awesome game of Bull's Eye where you can win
points and fame by dragging a slider.

Your goal is to place the slider as close as possible to the
target value. The closer you are, the more points you score.
Enjoy!
```

You can also enter that text into the Attributes inspector's **Text** property for the text view if you find that easier.

➤ Make sure to uncheck the **Editable** checkbox in the Attribute Inspector. Otherwise, the user can actually type into the text view and you don't want that.




The Attributes inspector for the text view

That's the design of the screen done for now.

Show the new view controller


Now that you have an About screen, how do you open this new screen when the user presses the ⓘ button? Storyboards have a neat trick for this: *segues* — pronounced "seg-way" like the silly scooters. A segue is a transition from one screen to another. They are really easy to add.

➤ Click the ⓘ button in the **View Controller** to select it. Then hold down **Control** and drag over to the **About** screen.



Control-drag from one view controller to another to make a segue


➤ Let go of the mouse button and a popup appears with several options. Choose **Present Modally**.



Choosing the type of segue to create


Now an arrow will appear between the two screens. This arrow represents the segue from the main scene to the About scene.

➤ Click the arrow to select it. Segues also have attributes. In the **Attributes inspector**, choose **Transition**, **Flip Horizontal**. That is the animation that UIKit will use to move between these screens.



Changing the attributes for the segue

➤ Now you can run the app. Press the ⓘ button to see the new screen.



The About screen appears with a flip animation

The About screen should appear with a neat animation. Good, that seems to work.

Dismiss the About view controller

Did you notice that there's an obvious issue here? Tapping the Close button seems to have no effect. Once the user enters the About screen they can never leave… that doesn't sound like good user interface design, does it?

The problem with segues is that they only go one way. To close this screen, you have to hook up some code to the Close button. As a budding iOS developer you already know how to do that: use an action method!

This time you will add the action method to `AboutViewController` instead of `ViewController`, because the Close button is part of the About screen, not the main game screen.

➤ Open **AboutViewController.swift** and replace its contents with the following:

```
import UIKit


class AboutViewController: UIViewController {
  @IBAction func close() {
    dismiss(animated: true, completion: nil)
  }
}
```

The code in the `close()` action method tells UIKit to close the About screen with an animation.

If you had said `dismiss(animated: false, …)`, then there would be no page flip and the main screen would instantly reappear. From a user experience perspective, it's often better to show transitions from one screen to another via an animation.

That leaves you with one final step, hooking up the Close button's Touch Up Inside event to this new `close` action.

➤ Open the storyboard and Control-drag from the **Close** button to the About scene's View Controller. Hmm, strange, the **close** action should be listed in this popup, but it isn't. Instead, this is the same popup you saw when you made the segue:



The "close" action is not listed in the popup

> **Exercise:** Bonus points if you can spot the error. It's a very common – and frustrating! – mistake.


The problem is that this scene in the storyboard doesn't know yet that it is supposed to represent the `AboutViewController`.

Set the class for a view controller

You first added the AboutViewController.swift source file, and then dragged a new view controller on to the storyboard. But, you haven't told the storyboard that the design for this new view controller belongs to `AboutViewController` — that's why in the Document Outline it just says View Controller and not About View Controller.

➤ Fortunately, this is easily remedied. In Interface Builder, select the About scene's **View Controller** and go to the **Identity inspector** (that's the tab/icon to the left of the Attributes inspector).

➤ Under **Custom Class**, for **Class** enter **AboutViewController**.



The Identity inspector for the About screen

Xcode should auto-complete this for you once you type the first few characters. If it doesn't, then double-check that you really have selected the View Controller and not one of the views inside it. (The view controller should also have a blue border on the storyboard to indicate it is selected.)

Now you should be able to connect the Close button to the action method.

➤ Control-drag from the **Close** button to **About View Controller** in the Document Outline (or to the yellow circle at the top of the scene in the storyboard). This should be old hat by now. The popup menu now does have an option for the **close** action (under Sent Events). Connect the button to that action.

➤ Run the app again. You should now be able to return from the About screen.

OK, that does get us a working about screen, but it does look a little plain doesn't it? What if you added some of the design changes you made to the main screen?

> **Exercise:** Add a background image to the About screen. Also, change the Close button on the About screen to look like the Hit Me! button and play around with the Text View properties in the Attribute Inspector. You should be able to do this by yourself now. Piece of cake! Refer back to the instructions for the main screen if you get stuck.

When you are done, you should have an About screen which looks something like this:



The new and improved About screen

That looks good, but it could be better :] So how do you improve upon it?

Use a web view for HTML content


➤ Now select the **text view** and press the **Delete** key on your keyboard. (Yep, you're throwing it away, and after all those changes, too! But don't grieve for the Text View too much, you'll replace it with something better.)

➤ Put a **WebKit View** in its place — as always, you can find this view in the Objects Library. There are two web view options — an older Web View, which is deprecated, or ready to be retired, and the WebKit View. Make sure that you select the WebKit View.

This view can show web pages. All you have to do is give it the URL to a web site or the name of a file to load. The WebKit View object is named `WKWebView`.


For this app, you will make it display a static HTML page from the application bundle, so it won't actually have to go online and download anything.

➤ Go to the **Project navigator** and right-click on the **BullsEye** group (the folder, not the blue icon for the root of the project). From the menu, choose **Add Files to "BullsEye"...**



Using the right-click menu to add existing files to the project

➤ In the file picker, select the **BullsEye.html** file from the Resources folder. This is an HTML5 document that contains the gameplay instructions.



Choosing the file to add


Make sure that **Copy items if needed** is selected and that under **Add to targets**, there is a checkmark in front of **BullsEye**. (If you don't see these options, click the Options button at the bottom of the dialog.)

➤ Press **Add** to add the HTML file to the project.

➤ In **AboutViewController.swift**, add an outlet for the web view:

```
class AboutViewController: UIViewController {
  @IBOutlet var webView: WKWebView!
  . . .
}
```

Xcode will complain soon after you add the above line. The error should look something like this:



Xcode complains about WKWebView

What does this error mean? It means that Xcode, or rather the compiler, does not know what `WKWebView` is.

But how can that be? We selected the component from Xcode's own Objects Library and so it should be supported, right? The answer to this lies with this line of code at the top of both your view controller source files:

```
import UIKit
```

I'm sure you saw this line and wondered what it was about. That statement tells the compiler that you want to use the objects from the `UIKit` framework. Frameworks, or libraries if you prefer, bundle together one or more objects which perform a particular type of task (or tasks). The `UIKit` library provides all the UI components for iOS.

So why does `UIKit` not contain `WKWebView`, you ask? That's because the previously mentioned deprecated WebView is the one which is included with `UIKit`. The newer (and improved) `WKWebView` comes from a different framework called `WebKit`.

➤ Add the following line at the top of **AboutViewController.swift**, right below the existing `import` statement:

```
import WebKit
```

That tells the compiler that we want to use objects from the `WebKit` framework and since now the compiler knows about all the objects in the `WebKit` framework, the Xcode error will go away.

➤ In the storyboard file, connect the `WKWebView` to this new outlet. The easiest way to do this is to Control-drag from **About View Controller** (in the Document Outline) to the **Web View**.

➤ In **AboutViewController.swift**, add a `viewDidLoad()` implementation:

```
override func viewDidLoad() {
  super.viewDidLoad()

  if let url = Bundle.main.url(
    forResource: "BullsEye", withExtension: "html") {
    let request = URLRequest(url: url)
    webView.load(request)
  }
}
```

This displays the HTML file using the web view.

The code first gets the URL (Uniform Resource Locator) for the **BullsEye.html** file in the application bundle. A URL, as you might be familiar with from the Interwebs, is a way to identify the location of a resource, like a web page. Here, the URL provides the location of the HTML file in your application bundle.

It then creates a `URLRequest` using that URL since that's one of the easiest ways to send a load request to the web view. Finally, the code asks the web view to load the contents specified by the URL request.


➤ Run the app and press the info button. The About screen should appear with a description of the gameplay rules, this time in the form of an HTML document:



The About screen in all its glory

Minimap

With two screens on your Interface Builder canvas, you might now begin to see how the minimap on the top right-hand corner of Interface Builder works.



The minimap

First of all, the minimap does not have to remain on the top right-hand corner. You can drag it around and place it anywhere you want — the trick is to drag it when the cursor is over the minimap and it is an arrow icon. You will not be able to drag it when the cursor is over the minimap and it is a hand icon. Try it.

When the cursor is a hand icon, you can move the viewport — or the portion of the canvas that is visible to you — within the minimap area so as to focus on a particular part of the canvas or to quickly navigate to the scene that you are looking for.

You can also focus on a particular scene by simply double-clicking it on the minimap.

When you have a fairly big canvas with lots of scenes, the minimap can be a very useful tool to navigate around and to find the scene you want quickly.

Congrats! This completes the game. All the functionality is there and — as far as I can tell — there are no bugs to spoil the fun. You can find the project files for the finished app under **07-The-new-look** in the Source Code folder.

8 Chapter 8: The Final App

By Fahim Farook

You might be thinking, "OK, *Bull's Eye* is now done, and I can move on to the next app!" If you were, I'm afraid you are in for disappointment — there's just a teensy bit more to do in the game.

"What? What's left to do? We finished the task list!" you say? You are right. The game is indeed complete. However, all this time, you've been developing and testing for a 4.7" screen found on devices such as the iPhone 6 - 8 and and SE (2nd generation). But what about other iPhones which have bigger screens? Or the iPad with its multiple screen sizes? Will the game work correctly on all these different screen sizes?

And if not, shouldn't we fix it?


This chapter covers the following:

- **Support different screen sizes:** Ensure that the app will run correctly on all the different iPhone and iPad screen sizes.
- **Crossfade:** Add some animation to make the transition to the start of a new game a bit more dynamic.
- **The icon:** Add the app icon.
- **Display name:** Set the display name for the app.
- **Run on device:** How to configure everything to run your app on an actual device.

Support different screen sizes


First, let's check if there is indeed an issue running Bull's Eye on a device with a larger screen. It's always good to verify that there's indeed an issue before we do extra work, right? Why fix it, if it isn't broken? :]

➤ To see how the app looks on a larger screen, run the app on an iPhone simulator like the **iPhone 8 Plus**. You can switch between Simulators using the selector at the top of the Xcode window:



Using the scheme selector to switch to the iPhone 8 Plus Simulator

The result might not be what you expected:



On the iPhone 8 Plus Simulator, the app doesn't fill up the entire screen

Obviously, this won't do. Not everybody is going to be using a 4.7" iOS device. And you don't want the game to display on only part of the screen for the rest of the people!


This is a good opportunity to learn about *Auto Layout*, a core UIKit technology that makes it easy to support many different screen sizes in your apps.

Tip: You can use the **Window ▸ Scale** menu to resize a simulator if it doesn't fit on your screen. Some of those simulators, like the iPad one, can be monsters! Also, you can resize a simulator window by simply dragging on one corner of the window — just like you do to resize any other window on macOS.

Interface Builder has a few handy tools to help you make the game fit on any screen.

The background image

➤ Go to **Main.storyboard**. Using the Interface Builder toolbar at the bottom choose the **iPhone 8 Plus** device.



Viewing the storyboard on iPhone 8 Plus

The storyboard should look like your screen from when you ran on the iPhone 8 Plus Simulator. This shows you how changes on the storyboard affect the bigger iPhone screens.

First, let's fix the background image. At its normal size, the image is too small to fit on the larger screens.

This is where Auto Layout comes to the rescue.

➤ In the storyboard, select the **Background image view** on the main **View Controller** and click the small **Add New Constraints** button at the bottom of the Xcode window:




The Add New Constraints button

This button lets you define relationships, called *constraints*, between the currently selected view and other views in the scene. When you run the app, UIKit evaluates these constraints and calculates the final layout of the views. This probably sounds a bit abstract, but you'll see soon how it works in practice.


In order for the background image to stretch from edge-to-edge on the screen, the left, top, right, and bottom edges of the image should be flush against the screen edges. Let's use Auto Layout to do this.

➤ In the **Add New Constraints** menu, set the **left**, **top**, **right**, and **bottom** spacing to zero and make sure that the red I-beam markers next to (or above/below) each item is enabled. (The red I-beams are used to specify which constraints are enabled when adding new constraints.):




Using the Add New Constraints menu to position the background image

➤ Press **Add 4 Constraints** to finish. The background image will now cover the view fully — if you'd like to see the difference, press Undo and Redo a few times.



The background image now covers the whole view

You might have also noticed that the Document Outline now has a new item called **Constraints**:



The new Auto Layout constraints appear in the Document Outline

There should be four constraints listed there, one for each edge of the image.

➤ Run the app again on the iPhone 8 Plus Simulator and also on the iPhone SE Simulator. In both cases, the background should display correctly now. (Of course, the other controls are still off-center, but we'll fix that soon.)

If you use the Interface Builder toolbar to switch the storyboard back to the iPhone SE, the background should display correctly there too.

The About screen


Let's repeat the background image fix for the About screen, too. (Remember, you can use the minimap to quickly switch to the About screen on Interface Builder.)

➤ Use the **Add New Constraints** button to pin the About screen's background image view to the parent view.

The background image is now fine. Of course, the Close button and web view are still completely off.

➤ In the storyboard, drag the **Close** button so that it snaps to the center of the view as well as the bottom guide.


Interface Builder shows a handy guide, the dotted blue line, near the edges of the screen, which is useful for aligning objects by hand.



The dotted blue lines are guides that help position your UI elements

You want to create a centering constraint that keeps the Close button in the middle of the screen, regardless of how wide the screen is.

➤ Click the **Close** button to select it. From the **Align** menu (which is to the left of the Add New Constraints button), choose **Horizontally in Container** and click **Add 1 Constraint**.



The Align menu

Interface Builder now draws a blue bar to represent the constraint, and a red box around the button as well.



The Close button has red borders

That's a problem: the red box indicates that something is wrong with the constraints, usually that there aren't enough of them.

The thing to remember is this: for each view, there must always be enough constraints to define both its position and its size. The Close button already knows its size – you typed this into the Size inspector earlier – but for its position there is only a constraint for the X-coordinate (the alignment in the horizontal direction). You also need to add a constraint for the Y-coordinate.

As you've noticed, there are different types of constraints — there are alignment constraints and spacing constraints, like the ones you added via the Add New Constraints button.

➤ With the **Close** button still selected, click on the **Add New Constraints** button.

You want the Close button to always sit at a distance of 20 points from the bottom of the screen.


➤ In the **Add New Constraints** menu, in the **Spacing to nearest neighbor** section, set the bottom spacing to **20** and make sure that the I-beam above the text box is enabled.



The red I-beams decide the sides that are pinned down

➤ Click **Add 1 Constraint** to finish.

The red border will now turn blue, meaning that everything is OK:



The constraints on the Close button are valid

If at this point you don't see blue bars but orange ones, then something's still wrong with your Auto Layout constraints:



The views are not positioned according to the constraints

This happens when the constraints are valid (otherwise some, or all, of the bars/borders would be red) but the view is not in the right place in the scene. The dashed orange box off to the side is where Auto Layout has calculated the view should be, based on the constraints you have given it.

To fix this issue, select the **Close** button again and click the **Update Frames** button at the bottom of the Interface Builder canvas.



The Update Frames button

You can also use the **Editor ▸ Resolve Auto Layout Issues ▸ Update Frames** item from the menu bar.


The Close button should now always be perfectly centered, regardless of the device screen size.

> **Note:** What happens if you don't add any constraints to your views? In that case, Xcode will automatically add constraints when it builds the app. That is why you didn't need to bother with any of this before.

> However, these default constraints may not always do what you want. For example, they will not automatically resize your views to accommodate larger (or smaller) screens. If you want that to happen, then it's up to you to add your own constraints — after all, Auto Layout can't read your mind!
>
> As soon as you add just one constraint to a view, Xcode will no longer add any other automatic constraints to that view. From then on, you're responsible for adding enough constraints so that UIKit always knows what the position and size of the view will be.

There is one thing left to fix in the About screen and that is the web view.


➤ Select the **Web View** and open the **Add New Constraints** menu. First, make sure **Constrain to margins** is unchecked. Then click all four I-beam icons so they become solid red and set their spacing to 20 points, except the bottom one which should be 8 points:



Creating the constraints for the web view

➤ Finish by clicking **Add 4 Constraints**.

There are now four constraints on the web view — indicated by the blue bars on each side:



The four constraints on the web view


Three of these pin the web view to the main view, so that it always resizes along with it, and one connects it to the Close button. This is enough to determine the size and position of the web view in any scenario.

Fix the rest of the main scene

Back to the main game scene, which still needs some work.

The game looks a bit lopsided now on bigger screens. You will fix that by placing all the labels, buttons, and the slider into a new "container" view. Using Auto Layout, you'll center that container view in the screen, regardless of how big the screen is.


➤ Select all the labels, buttons, and the slider. You can hold down ⌘ and click them individually, but an easier method is to go to the **Document Outline**, click on the first view (for me that is the "Put the Bull's Eye as close as you can to:" label), then hold down Shift and click on the last view (in my case the Hit Me! button):



Selecting the views from the Document Outline

You should have selected everything but the background image view.


➤ From Xcode's menu bar, choose **Editor ▸ Embed In ▸ View**. This places the selected views inside a new container view:



The views are embedded in a new container view

This new view is completely white, which is not what you want eventually, but it does make it easier to add the constraints.

➤ Select the newly added **container view** and open the **Add New Constraints** menu. Check the boxes for **Width** and **Height** in order to make constraints for them and leave the width and height at the values specified by Interface Builder. Click **Add 2 Constraints** to finish.



Pinning the width and height of the container view


Interface Builder now draws several bars around the view that represent the Width and Height constraints that you just made, but they are red. Don't panic! It only means there are not enough constraints yet. No problem, you'll add the missing constraints next.

➤ With the container view still selected, open the **Align menu**. Check the **Horizontally in Container** and **Vertically in Container** options. Click **Add 2 Constraints**.

All the Auto Layout bars should be blue now and the view is perfectly centered.

➤ Finally, change the **Background** color of the container view to **Clear Color** (in other words, 100% transparent).

You now have a layout that works correctly on any iPhone display! Try it out:



The game running on 4-inch and 5.5-inch iPhones

Auto Layout may take a while to get used to. Adding constraints in order to position UI elements is a little less obvious than just dragging them into place.

But this also buys you a lot of power and flexibility, which you need when you're dealing with devices that have different screen sizes.

You'll learn more about Auto Layout in the other parts of *The UIKit Apprentice*.

Exercise: As you try the game on different devices, you might notice something — the controls for the game are always centered on screen, but they do not take up the whole area of the screen on bigger devices! This is because you set the container view for the controls to be a specific size. If you want the controls to change position and size depending on how much screen space is available, then you have to remove the container view (or set it to resize depending on screen size) and then set up the necessary autolayout constraints for each control separately.

Are you up to the challenge of doing this on your own?


Compiler warning

There's a compiler warning about views without any layout constraints being clipped which has been there since from almost the first time we created the main game view. At that point, I mentioned that we'd tackle that warning later.

But where are these views without constraints? The Issue navigator certainly does not give any clue! We have to go to a different screen to find out the list of affected views.

If you look at the Document Outline, you'll notice that there's a small yellow circle with an arrow inside it next to the View Controller Scene — an indication that there are some warnings (not errors).

If you click this circle, you will be taken to a list of Auto Layout issues in the scene:



List of Auto Layout issues for scene

You'll notice that all the controls inside the container view have warnings. This is because none of those views have any Auto Layout constraints and so will remain at their original positions when the view is displayed.

So how do you fix these warnings? Simple enough — add some Auto Layout constraints for each view so that the view's size and position can be determined via Auto Layout when the view is displayed. Of course, you have the necessary knowledge at this point to do this yourself. So I'll leave it to you to tackle as a personal challenge :]


If you get stuck, check out the final project provided for this chapter — that should show you how I fixed the issues.

Testing on a notched iPhone

So it looks as if we got the app working correctly for all devices, right?

Well ... not quite. :]

Try running the app on the iPhone 12 simulator — or any device with a notch. you should see something like this:



The game on iPhone X

Whoa! What happened?


With the advent of the iPhones with notches, Apple introduced a new mechanism to go along with Auto Layout to work with the notched iPhone screens. Given the notch at the top, you don't want most apps to display their content beneath the notch since that content would not display properly.

So, Apple introduced what is known as *safe layout guides* to define where it is safe to display content. If you take a look at the Auto Layout constraints for the background image on the main scene (or even the About scene for that matter), you will notice that the background image aligns to the safe area.

Just to be clear, this is the correct behavior for most apps — you want your content to stick to the safe area. However, in the case of a game like *Bull's Eye* where you have a custom background, you want the background to cover the entire screen.


So how do we fix it? Simple enough... Just change the image constraints so that they align with the superview, which is the main view for the scene.

➤ Select the background image in the main scene and switch to the **Size inspector**. It should show the four constraints set on the image:




Auto Layout constraints for image

➤ Double-click the first one. You should get a detailed editor for that Auto Layout constraint:



Auto Layout constraint editor

➤ Click the drop down for **First Item** and change it from Safe Area to Superview. Also, if the **Constant** field has a non-zero value, change it to 0.




Edit Auto Layout constraint

➤ Do the same for the other three constraints. Note that for two of the constraints, Safe Area will be the Second Item and not the First Item. So change either one based on which one specifies Safe Area.

➤ Run your app on a notched iPhone simulator and check the results.

Content Mode for Images

What you see should be something like this:



The background does not cover the entire screen

Not quite what you were hoping for, right?

This is because the background image is only wide enough to cover the area that you see in the screenshot above. There are several solutions to this issue:

1. Create a new background image which is wider so that it covers the entire area of the screen.

2. Change the Content Mode for the image in your story board.

The second sounds like an easier solution than creating a new background image, right? So let's give that a shot ...

➤ Select the background image view in Interface Builder and in **Attributes Inspector** find the **Content Mode** property. Change the value to **Aspect Fill**.

➤ Run your app on both a notched iPhone simulator and at least one of the other non-notched simulators like the iPhone 8 Plus, to make sure that your change works correctly on all devices.

Wondering what just happened? Let me explain …

The Content Mode property defines how an image is displayed. It is set to Aspect Fit by default. This means that an image is displayed within an image view so that the whole image is shown in such a way that the shortest side (either the width or height) fits completely within the available space.

This is why the background image showed white on the left and right — it wasn't wide enough to fill the available space at the current image size.

When you changed the content mode to Aspect Fill, you were specifying that the image should be displayed in such a way that the longest side filled the image view fully. For this particular background image, this will mean that parts of the image along the top and the bottom will extend beyond the visible area, but that's better than having the two white strips along the sides, right?

You could also have selected Scale to Fill as the Content Mode. That would have stretched the image to fit the available display space. However, this stretching does not respect the aspect ratio (the ratio between width and height) and so the resulting image can look skewed — like something you see in a funhouse mirror.

Experiment with the various Content Modes to see how each affects how the image is displayed.

Crossfade

There's one final bit of knowledge I want to impart before calling the game complete — Core Animation. This technology makes it very easy to create really sweet animations, with just a few lines of code, in your apps. Adding subtle animations (with emphasis on subtle!) can make your app a delight to use.

You will add a simple crossfade after the Start Over button is pressed, so the transition back to round one won't seem so abrupt.


➤ In **ViewController.swift**, change `startNewGame()` to:

```
@IBAction func startNewGame() {
  ...
  startNewRound()
  // Add the following lines
  let transition = CATransition()
  transition.type = CATransitionType.fade
  transition.duration = 1
  transition.timingFunction = CAMediaTimingFunction(
    name: CAMediaTimingFunctionName.easeOut)
  view.layer.add(transition, forKey: nil)
}
```

Everything after the comment telling you to add the following lines, all the `CATransition` stuff, is new.

I'm not going to go into too much detail here. Suffice it to say you're setting up an animation that crossfades from what is currently on the screen to the changes you're making in `startNewRound()` – reset the slider to center position and reset the values of the labels.

➤ Run the app and move the slider so that it is no longer in the center. Press the Start Over button and you should see a subtle crossfade animation.




The screen crossfades between the old and new states

The icon

You're almost done with the app, but there are still a few loose ends to tie up. You may have noticed that the app has a really boring white icon. That won't do!


➤ Open the asset catalog (**Assets.xcassets**) and select **AppIcon**:



The AppIcon group in the asset catalog

This has several icon groups for the different types of icons the app needs.


➤ In Finder, open the **Icon** folder from the resources. Drag the **Icon-40.png** file into the first slot, **iPhone Notification 20pt**:



Dragging the icon into the asset catalog


You may be wondering why you're dragging the Icon-40.png file and not the Icon-20.png into the slot for 20pt. Notice that this slot says **2x** and that it also says 40x40px within the dotted frame. This icon is for Retina devices and on Retina screens one point counts as two pixels. So, 20pt = 40px. And the 40 in the icon name is for the size of the icon in pixels. Makes sense?

Similarly, fill in the rest of the icon spots based on their size.



The full set of icons for the app

➤ Run the app and close it. You'll see that the icon has changed on the Simulator's springboard. If not, remove the app from the Simulator and try again (sometimes the Simulator keeps using the old icon and re-installing the app will fix this).




The icon on the Simulator's springboard

Display name

One last thing. You named the project **BullsEye** and that is the name that shows up under the icon. However, I'd prefer to spell it "**Bull's Eye**".

There is only limited space under the icon and for apps with longer names you have to get creative to make the name fit. For this game, however, there is enough room to add the space and the apostrophe.


➤ Go to the **Project Settings** screen. The very first option is **Display Name**. Change this to **Bull's Eye**.



Changing the display name of the app

Like many of the project's settings you can also find the display name in the app's Info tab. Let's have a look.

➤ From the **Project Settings**, select the **Info** tab.



The display name of the app in the Info tab

The row **Bundle display name** contains the new name you've just entered.

> **Note:** If **Bundle display name** is not present, the app will use the value from the field **Bundle name**, which has the project name, BullsEye, as the value. By providing a **Bundle display name** you can override this default name and give the app any name you want.

➤ Run the app and quit it to see the new name under the icon.



The bundle display name setting changes the name under the icon

Awesome, that completes your very first app!

You can find the project files for the finished app under **08-The-final-app** in the Source Code folder.

Run on device

So far, you've run the app on the Simulator. That's nice and all but probably not why you're learning iOS development. You want to make apps that run on real iPhones and iPads! There's hardly a thing more exciting than running an app that you made on your own phone. And, of course, to show off the fruits of your labor to other people!

Don't get me wrong: developing your apps on the Simulator works very well. When developing, I spend most of my time with the Simulator and only test the app on my iPhone every so often.

However, you do need to run your creations on a real device in order to test them properly. There are some things the Simulator simply cannot do. If your app needs the iPhone's camera, for example, you have no choice but to test that functionality on an actual device.


Until a few years back, you needed a paid Developer Program account to run apps on your iPhone. Now, you can do it for free. All you need is an Apple ID. And the latest Xcode makes it easier than ever before.

Configure your device for development

➤ Connect your iPhone, iPod touch, or iPad to your Mac using a USB cable.

➤ From the Xcode menu bar select **Window ▸ Devices and Simulators** to open the Devices and Simulators window.

Mine looks like this:



The Devices and Simulators window

On the left is a list of devices that are currently connected to my Mac and which can be used for development.

➤ Click on your device name to select it.

If this is the first time you're using the device with Xcode, the Devices window will say something like, "iPhone is not paired with your computer." To pair the device with Xcode, you need to unlock the device first (hold the home button, or use Face ID, depending on your device). After unlocking, an alert will pop up on the device asking you to trust the computer you're trying to pair with. Tap on **Trust** to continue.

Xcode will now refresh the page and let you use the device for development. Give it a few minutes (see the progress bar in the main Xcode window). If it takes too long, you may need to unplug the device and plug it back in.

At this point it's possible you may get the error message, "An error was encountered while enabling development on this device." You'll need to unplug the device and reboot it. Make sure to restart Xcode before you reconnect the device.


Also, note the checkbox which says **Connect via network**? That checkbox (gasp!) allows you to run and debug code on your iPhone over WiFi!

Cool, that is the device sorted.

Add your developer account to Xcode

The next step is setting up your Apple ID with Xcode. It's OK to use the same Apple ID that you're already using with iTunes and your iPhone, but if you run a business, you might want to create a new Apple ID to keep things separate. Of course, if you've already registered for a paid Developer Program account, use that Apple ID.


➤ Open the **Accounts** pane in the Xcode Preferences window:



The Accounts preferences

➤ Click the + button at the bottom and select **Apple ID** from the list of options.

Xcode will ask for your Apple ID:



Adding your Apple ID to Xcode

➤ Type your Apple ID username and click **Next** to have the dialog show you a new password field.

➤ Enter your password and click **Next** again.


Xcode verifies your account details and adds it to the stored list of accounts.

> **Note:** It's possible that Xcode is unable to use the Apple ID you provided — for example, if it has been used with a Developer Program account in the past that is now expired. The simplest solution is to make a new Apple ID. It's free and only takes a few minutes. appleid.apple.com

You still need to tell Xcode to use this account when building your app.

Code signing

➤ Go to the **Project Settings** screen for your app target and the select the **Signing & Capabilities** tab.



The Signing options in the Project Settings screen

In order to allow Xcode to put an app on your iPhone, the app must be *digitally signed* with your **Development Certificate**. A *certificate* is an electronic document that identifies you as an iOS application developer and is valid only for a specific amount of time.

Apps that you want to submit to the App Store must be signed with another certificate, the **Distribution Certificate**. To create (and use) a distribution certificate, you must be a member of the paid Developer Program. However, creating/using a development certificate is free.


In addition to a valid certificate, you also need a **Provisioning Profile** for each app you make. Xcode uses this profile to sign the app for use on your particular device (or devices). The specifics don't really matter, just know that you need a provisioning profile or the app won't go on your device.

Making the certificates and provisioning profiles used to be a really frustrating and error-prone process. Fortunately, those days are over: Xcode now makes it really easy. When the **Automatically manage signing** option is enabled, Xcode will take care of all this business with certificates and provisioning profiles and you don't have to worry about a thing.

➤ Click on **Team** to select your Apple ID.

Xcode will now automatically register your device with your account, create a new Development Certificate, and download and install the Provisioning Profile on your device. These are all steps you had to do by hand in the past, but now Xcode takes care of all that.


You could get some signing errors like these:



Signing/team set up errors

The app's Bundle Identifier must be unique. If another app is already using that identifier, then you cannot use it anymore. That's why you're supposed to start the Bundle ID with your own domain name. The fix is easy: change the Bundle Identifier field to something else and try again.

It's also possible you get this error (or something similar):




No devices registered

Xcode must know about the device that you're going to run the app on. That's why I asked you to connect your device first. Double-check that your iPhone or iPad is still connected to your Mac and that it is listed in the Devices window.

Run on device

If everything goes smoothly, go back to Xcode's main window and click on the dropdown in the toolbar to change where you will run the app. The name of your device should be in that list somewhere.

On my system it looks like this:



Setting the active device

You're all set and ready to go!

➤ Press **Run** to launch the app.

At this point you may get a popup with the question "codesign wants to sign using key ... in your keychain". If so, answer with **Always Allow**. This is Xcode trying to use the new Development Certificate you just created — you just need to give it permission first.

Does the app work? Awesome! If not, read on...

When things go wrong...


There are a few things that can go wrong when you try to put the app on your device, especially if you've never done this before, so don't panic if you run into problems.

The device is not connected

Make sure your iPhone, iPod touch, or iPad is connected to your Mac. The device must be listed in Xcode's Devices window and there should not be a yellow warning icon.

The device does not trust you

You might get this warning:




Quick, call security!

On the device itself there might be a popup with the text, "Untrusted Developer. Your device management settings do not allow using apps from developer ...".

If this happens, open the Settings app on the device and go to **General ▸ Device Management**. Your Apple ID should be listed in that screen. Tap it, and select the option to Trust your profile in the next screen. Then try running the app again.

The device is locked

If your phone locks itself with a passcode after a few minutes, you might get this warning:




The app won't run if the device is locked

Simply unlock your device — hold the home button, type in the 4-digit passcode, or use FaceID — and if you had not clicked the Cancel Running button, the app will run on your device once you unlock.

Signing certificates

If you're curious about the certificates used to sign the app, open the **Preferences** window and go to the **Accounts** tab. Select your account and click the **Manage Certificates...** button in the bottom-right corner.


This brings up another panel, listing your signing certificates:



The Manage Certificates panel

When you're done, close the panel and go to the **Devices and Simulators** window.

You can see the provisioning profiles that are installed on your device by right-clicking the device name and choosing **Show Provisioning Profiles...**.




The provisioning profiles on your device

The "iOS Team Provisioning Profile:" is the one that allows you to run the app on your device. (By the way, they call it the "team" profile because often there is more than one developer working on an app and they can all share the same profile.)

You can have more than one certificate and provisioning profile installed. This is useful if you're on multiple development teams or if you prefer to manage the provisioning profiles for different apps by hand.

To see how Xcode chooses which profile and certificate to sign your app with, go to the **Project Settings** screen and switch to the **Build Settings** tab. There are a lot of settings in this list, so filter them by typing **signing** in the search box. (Also make sure **All** is selected, not Basic.)

The screen will look something like this:



The Code Signing settings

Under **Code Signing Identity** it says **Apple Development**. This is the certificate that Xcode uses to sign the app. If you click on that line, you can choose another certificate. Under **Provisioning Profile** you can change the active profile. Most of the time you won't need to change these settings, but at least you know where to find them now.

And that concludes everything you need to know about running your app on an actual device.

The end... or the beginning?

It has been a bit of a journey to get to this point — if you're new to programming, you've had to get a lot of new concepts into your head.

I hope your brain didn't explode! At least you should have gotten some insight into what it takes to develop an app.

I don't expect you to totally understand everything that you did, especially not the parts that involved writing Swift code. It is perfectly fine if you didn't, as long as you're enjoying yourself and you sort of get the basic concepts of objects, methods and variables.

If you were able to follow along and do the exercises, you're in good shape!

I encourage you to play around with the code a bit more. The best way to learn programming is to do it, and that includes making mistakes and messing things up. I hereby grant you full permission to do so! Maybe you can add some cool new features to the game (and if you do, please let me know).

In the Source Code folder for this book you can find the complete source code for the *Bull's Eye* app. If you're still unclear about something we did, it might be a good idea to look at this cleaned up source code.

If you're interested in how I made the graphics, then take a peek at the Photoshop files in the Resources folder. The wood background texture was made by Atle Mo from subtlepatterns.com.

If you're feeling exhausted after all that coding, pour yourself a drink and put your feet up for a bit. You've earned it! On the other hand, if you just can't wait to get to grips with more code, let's move on to our next app!

Section 2: Checklists

This section builds upon what you learnt in the previous section by introducing you to your second app. *Checklists* takes you from a single-screen app to a multi-screen app where you learn the concepts of navigation flow, displaying data lists, and the idea of modeling and persisting your data.

If you want to build any sort of list-based iOS app, this section is a good starting point for learning the basics. Of course, even if you aren't building a list-based app, this section has some basic concepts such as handling the navigation flow from one screen to another (and back again) that would be very useful to an apprentice iOS developer.


9 Chapter 9: Table Views

By Fahim Farook

Ready to get started on your next app? Let's go!

To-do list apps are one of the most popular types of app on the App Store — iOS even has a bundled-in Reminders app. Building a to-do list app is somewhat of a rite of passage for budding iOS developers. So, it makes sense that you create one as well.

Your own to-do list app, ***Checklists***, will look like this when you're finished:



The finished Checklists app

The app lets you organize to-do items into lists and then check off these items once you've completed them. You can also set a reminder on a to-do item that will make the iPhone pop up an alert on the due date, even when the app isn't running.

As far as to-do list apps go, *Checklists* is very basic, but don't let that fool you. Even a simple app such as this already has five different screens and a lot of complexity behind the scenes.

This chapter covers the following:

- **Table views and navigation controllers:** A basic introduction to navigation controllers and table views.
- **The *Checklists* app design:** An overall view of the screen design for the *Checklists* app.
- **Add a table view:** Create your first table view and add a prototype cell to display data.
- **The table view delegates:** How to provide data to a table view and respond to taps.

Table views and navigation controllers


Checklists will introduce you to two of the most commonly used UI elements in iOS apps: the table view and the navigation controller.

A **table view** shows a list of things. The three screens above all use a table view. In fact, all of this app's screens use table views. This component is extremely versatile and the most important one to master in iOS development.

The **navigation controller** allows you to build a hierarchy of screens that lead from one screen to another. It adds a navigation bar at the top with a title and a back button.

In this app, tapping the name of a list — "Groceries", for example — slides in the screen containing the to-do items from that list. The button in the upper-left corner takes you back to the previous screen with a smooth animation. Moving between those screens is the job of the navigation controller.


Navigation controllers and table views are often used together.



The grey bar at the top is the navigation bar. The list of items is the table view.

Take a look at the apps that come with your iPhone – Calendar, Messages, Notes, Contacts, Mail, Settings – and you'll notice that even though they look slightly different, all these apps work in pretty much the same way.

That's because they all use table views and navigation controllers:



These are all table views inside navigation controllers

(The Music app also has a *tab bar* at the bottom, something you'll learn about later on.)

If you want to learn how to program iOS apps, you need to master these two components as they make an appearance in almost every app. That's exactly what you'll focus on in this section of the book. You'll also learn how to pass data from one screen to another, a very important topic that often puzzles beginners.

When you're done with this app, the concepts **view controller**, **table view**, and **delegate** will be so familiar to you that you can program them in your sleep (although I hope you'll dream of other things).

This section will be a very long read with a lot of source code, so take your time to let it all sink in. I encourage you to experiment with the code that you'll be writing. Change stuff and see what it does, even if it breaks the app.


Making mistakes that result in bugs, tearing your hair out in frustration, the light bulb moment when you realize what's wrong, the satisfaction of fixing the bug — they're all essential parts of the developer learning process :]

There's no doubt: playing with code is the quickest way to learn!

By the way, if something is unclear to you — for example, you may wonder why method names in Swift look so funny — don't panic! Have some faith and keep going... everything will be explained in due course.

The Checklists app design

Just so you know what you're in for, here is an overview of how the *Checklists* app will work:



All the screens of the Checklists app

The main screen of the app shows all your "checklists" (1). You can create multiple lists to organize your to-do items.

A checklist has a name, an icon, and zero or more to-do items. You can edit the name and icon of a checklist in the Add/Edit Checklist screens (2) and (3).

You tap on the checklist's name to view its to-do items (4).

A to-do item has a description, a checkmark to indicate that the item is done, and an optional due date. You can edit the item in the Add/Edit Item screen (5).

iOS will automatically notify the user of checklist items that have their "remind me" option set (6), even if the app isn't running (7). That's a pretty advanced feature, but I think you'll be up for the task.

You can find the full source code of this app in the Source Code folder, so have a play with it to get a feel for how it works. Done playing? Then let's get started!

> **Important:** The *UIKit Apprentice* projects are for **Xcode 13.0** (or later) only. If you're still using an older version of Xcode, please update to the latest version of Xcode from the Mac App Store.
>
> But don't get carried away either — often Apple makes beta versions of upcoming Xcode releases available. Please do *not* use an Xcode beta to follow along. Often, the beta versions break things in unexpected ways and you'll only end up confused. Stick to the official versions for now!

Add a table view

Seeing as table views are so important, you will start out by examining how they work. Making lists has never been this much fun!


Because smart developers split up the workload into small, simple steps, this is what you're going to do in this chapter:

1. Put a table view on the app's screen.
2. Put data into that table view.
3. Allow the user to tap a row in the table to toggle a checkmark on and off.

Once you have these basics up and running, you'll keep adding new functionality over the next few chapters until you end up with a full-blown app.


Create the project

➤ Launch Xcode and start a new project. Choose the **App** template.



Choosing the Xcode template

Xcode will ask you to fill out a few options:



Choosing the template options

➤ Fill out these options as follows:

- Product Name: **Checklists**
- Team: Since you already set up your developer account for the previous app (you did, didn't you?) you can select your team here. Or, you can just leave this at the default setting.
- Organization Identifier: Use your own identifier here, using reverse domain name notation

- Interface: **Storyboard**
- Life Cycle: **UIKit App Delegate**
- Language: **Swift**
- Use Core Data, Include Tests: these should be **unchecked**.


➤ Press **Next** and choose a location for the project.

You can run the app if you want, but as you might remember from the *Bull's Eye* app, at this point it's just a white screen.

Set the app orientation

Checklists will run in portrait orientation only. So let's ensure that we specify that.

➤ Click on the Checklists project item at the top of the project navigator and go to the **General** tab. Under **Deployment Info**, **Device Orientation**, make sure that only **Portrait** is selected.



The Device Orientation setting

With the landscape options disabled, rotating the device will no longer have any effect. The app always stays in portrait orientation.

> **Upside down**
>
> There is also an Upside Down orientation, but you typically won't use it.
>
> If your app supports Upside Down, users are able to rotate their iPhone so that the home button is at the top of the screen instead of at the bottom.
>
> That may be confusing, especially when the user receives a phone call: the microphone is at the wrong end with the phone upside down.
>
> iPad apps, on the other hand, are supposed to support all four orientations including upside-down.


Edit the storyboard

Xcode created a basic app that consists of a single view controller. Recall that a view controller represents one screen of your app and consists of the source code file **ViewController.swift** and a user interface design in **Main.storyboard**.

The storyboard contains the designs of all your app's view controllers inside a single document, with arrows showing the flow between them. In storyboard terminology, each view controller is named a *scene*.

You already used a storyboard in *Bull's Eye*, but in this app you will unlock the full power of storyboarding.

➤ Click on **Main.storyboard** to open Interface Builder.



The storyboard editor with the app's only scene

Use the **Device** button in the Interface Builder toolbar to switch to **iPhone SE (2nd Generation)**. I do this for two reasons:

1. The images take up less room in the book :]
2. It's better to develop for a smaller screen device so that you know that your app UI will fit on almost any screen out there.

For you, it should not matter which device size you choose to edit the storyboard: the app will automatically resize to fit all iPhone models.

➤ Select **View Controller Scene** in the Document Outline on the left.

Tip: Recall that the Document Outline shows the view hierarchy of all the scenes in the storyboard. If you cannot see the Document Outline, then click the leftmost small square button on the Interface Builder toolbar to toggle the Document Outline.



This button shows and hides the Document Outline

➤ Press **delete** on your keyboard to remove the **View Controller Scene** from the storyboard. The canvas should be empty and the Document Outline say "No Scenes".

You do this because you don't want a regular view controller. Instead, you'll add a **table view controller**, which is a special type of view controller that makes working with table views easier.

The view controller code

But remember, the scene on the storyboard is just half the equation — there's also the Swift code file. And the view type specified in code has to match the scene's type. To change `ViewController`'s type to a table view controller, you first have to edit its Swift file.

➤ Click on **ViewController.swift** to open it in the source code editor. Change the following line from this:

```
class ViewController: UIViewController {
```

To this:

```
class ChecklistViewController: UITableViewController {
```

With this change you tell the Swift compiler that your view controller is now a `UITableViewController` object instead of a regular `UIViewController`. Remember that everything starting with "UI" is part of UIKit. These pre-fabricated components serve as the building blocks for your own app.


When Xcode made the project, it assumed you wanted the `ViewController` object to be built on top of a basic `UIViewController`, but here you're changing it to use the `UITableViewController` building block instead.

You also renamed `ViewController` to `ChecklistViewController` to give it a more descriptive name. This is *your* object — you can tell because its name *doesn't* start with UI.

Over the course of this section, you will add data and functionality to the `ChecklistViewController` object to make the app actually do things. You'll also add several new view controllers to the app.

➤ In the Project navigator on the left, click once to select **ViewController.swift**, and then click again to edit its name. (Don't double-click too fast or you'll open the Swift file in the source code editor.)

Change the filename to **ChecklistViewController.swift**:




Renaming the Swift file

You might get a warning: "The document could not be saved. The file has been changed by another application." Click **Save Anyway** to make it go away.

Set the view controller class in the storyboard

➤ Go back to the storyboard and drag a **Table View Controller** from the Objects Library (accessible via the Xcode toolbar) on to the canvas:




Dragging a Table View Controller into the storyboard

This adds a new Table View Controller scene to the storyboard.

➤ Make sure that the table view controller is selected, go to the **Identity inspector** (the fourth tab in the inspectors pane on the right of the Xcode window), and under **Custom Class** type **ChecklistViewController** as the Class (or, choose it using the dropdown list).

Tip: When you do this, make sure the actual Table View Controller is selected, not the Table View inside it. There should be a thin blue border around the scene.




Changing the Custom Class of the Table View Controller

The name of the scene in the Document Outline on the left should change to "Checklist View Controller Scene". You have successfully changed `ChecklistViewController` from a regular view controller object into a table view controller.

As its name implies, and as you'll see in the Document Outline, the view controller contains a Table View object. We'll go into the difference between controllers and views soon, but for now, remember that the controller is the whole screen while the table view is the object that actually draws the list.

Set the initial view controller

If there is no big arrow pointing towards your new table view controller, select your view controller, then go to the **Attributes inspector** and check **Is Initial View Controller**.




The arrow points at the initial view controller

The initial view controller is the first screen that your users will see. Without one, iOS won't know which view controller to load from your storyboard when the app starts up and you'll end up staring at a black screen.

➤ Run the app on the Simulator.

You should see an empty screen - just as you had initially with the Bull's Eye app.



The app shows an empty white screen

By the way, it doesn't really matter which Simulator you use. Table views resize themselves to fit the dimensions of the device, and the app will work equally well on the small iPhone SE or the huge iPhone Pro Max.

Personally, I use the iPhone SE Simulator because it's compact, but remember that you can open any of the simulators and then simply resize the simulator window by dragging on the corners, just like you resize any macOS window.

> **Note:** When you build the app, Xcode gives the warning "Prototype table cells must have reuse identifiers". Don't worry about this for now, we'll fix it soon.


★ ★ ★

The anatomy of a table view

First, let's talk a bit more about table views. A `UITableView` object displays a list of items.

> **Note:** I'm not sure why it's named a *table*, because a table is commonly thought of as a spreadsheet-type object that has multiple rows and multiple columns, whereas the `UITableView` only has rows. It's more of a list than a table, but I guess we're stuck with the name now. UIKit also provides a `UICollectionView` object that works similar to a `UITableView` but allows for multiple columns.

There are two styles of tables: "plain" and "grouped". They work mostly the same, but there are a few small differences. The most visible difference is that rows in the grouped style table are placed into boxes (the groups) on a light gray background.



A plain-style table (left) and a grouped table (right)

The plain style is used for rows that all represent something similar, such as contacts in an address book where each row contains the name of one person.

The grouped style is used when the items in the list can be organized by a particular attribute, like book categories for a list of books. The grouped style table could also be used to show related information which doesn't necessarily have to stand together — like the address information, contact information, and e-mail information for a contact.


You will use both table styles in the *Checklists* app.

The data for a table comes in the form of **rows**. In the first version of *Checklists*, each row will correspond to a to-do item that you can check off when you're done with it.

You can potentially have many rows (even tens of thousands) but that kind of design isn't recommended. Most users will find it incredibly annoying to scroll through ten thousand rows to find the one they want. And who can blame them?

Tables display their data in **cells**. A cell is related to a row but it's not exactly the same. A cell is a view that shows a row of data that happens to be visible at that moment. If your table can show 10 rows at a time on the screen, then it only has 10 cells, even though there may be hundreds of rows of actual data.

Whenever a row scrolls off the screen and becomes invisible, its cell will be re-used for a new row that becomes visible.




Cells display the contents of rows

★ ★ ★

Add a prototype cell

In the past, you had to put in quite a bit of effort to create cells for your tables. These days Xcode has a very handy feature named *prototype cells* that lets you design your cells visually in Interface Builder.


➤ Open the storyboard and click the empty cell (the white row below the Prototype Cells label) to select it.



Selecting the prototype cell

Sometimes it can be hard to see exactly what is selected, so keep an eye on the Document Outline to make sure you've picked the right thing. Or, use the Document Outline to select the cell directly.

➤ Drag a **Label** from the Objects Library on to the white area in the table view representing the cell. Make sure the label spans the entire width of the cell (but leave a small margin on the sides).




Adding the label to the prototype cell

> **Note:** If you simply drag the label on to the table view, it might not work. You need to drag the label on to the cell itself. You can check where the label ended up using the Document Outline. It has to be inside the Content View for the table view cell.

Besides the label you will also add a checkmark to the cell's design. The checkmark is provided by something called the **accessory**, a built-in view that appears on the right side of the cell. You can choose from a few standard accessory controls or provide your own.


➤ Select the **Table View Cell** again. In the **Attributes inspector**, set the **Accessory** field to **Checkmark**:



Changing the accessory to get a checkmark

If you don't see this option, then make sure you selected the Table View Cell, not the Content View or Label below it.

Your design should now look something like this:



The design of the prototype cell: a label and a checkmark

Note: You may want to resize the label a bit so that it doesn't overlap the checkmark.


You also need to set a *reuse identifier* on the cell. This is an internal name that the table view uses to find free cells to reuse when rows scroll off the screen and new rows must become visible.

The table needs to assign cells for those new rows, and recycling existing cells is more efficient than creating new cells. This technique is what makes table views scroll smoothly.

Reuse identifiers are also important for when you want to display different types of cells in the same table. For example, one type of cell could have an image and a label and another could have a label and a button. You would give each cell type its own identifier, so the table view can assign the right cell for a given row type.

Checklists has only one type of cell but you still need to give it an identifier.

➤ Type **ChecklistItem** into the Table View Cell's **Identifier** field — you can find this in the **Attributes inspector**.



Giving the table view cell a reuse identifier

Compiler warnings

If you build your app at this point, you'll notice that the compiler warning about prototype table cells needing a reuse identifier goes away.

But ... you've got a new warning — one about views without any layout constraints clipping or overlapping other views. Sounds familiar?

Yes, this is the same warning you saw in *Bull's Eye* when you had views without any Auto Layout constraints! And you know how to find the affected views now, right?

➤ In the storyboard, click on the yellow warning circle for the table view to see the list of views with issues. It is the new label you just added to the prototype table cell.

That's simple enough to fix, right? Simply select the label, select the **Add New Constraints** icon at the bottom of the Interface Builder window, and add 4 constraints for the left, top, right, and bottom of the label.

You can go with the current defaults for everything except for the right as long as you have the label positioned correctly. If you added the checkmark accessory after you positioned the label, you might have to adjust the right margin for the label to compensate for the checkmark.

➤ Run the app and you'll see... zip, zilch, nada — exactly the same as before :] The table is still empty.

This is because you only added a cell design to the table, not actual data. Remember that the cell is just the visual representation of the row, not the actual data. To add data to the table, you have to write some code.

The table view delegates

➤ Switch to **ChecklistViewController.swift** and add the following methods just before the closing bracket at the bottom of the file:

```
// MARK: - Table View Data Source
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return 1
}

override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "ChecklistItem",
    for: indexPath)
  return cell
}
```

These methods look a bit more complicated than the ones you've seen in *Bull's Eye*, but that's because each takes two parameters and returns a value to the caller. Other than that, they work the same way as the methods you've dealt with before.

Protocols

The above two methods are part of `UITableView`'s **data source** protocol.

What's a protocol, you ask? Well, it's a standard set of methods that a class must adhere to — a protocol to be followed, so to speak. It allows code to be written in such a way that you know that a given class would implement certain methods (with specific parameters of a given type) but where you don't need to know all the implementation details of the class — such as all it's methods. A protocol usually allows you to add functionality for a certain type of operation to a class — for example, handling data for a table view.

The data source is the link between your data and the table view. Usually, the view controller plays the role of data source and implements the necessary methods. So, essentially, the view controller is acting as a delegate on behalf of the table view. (This is the delegate pattern that we've talked about before – where an object does some work on behalf of another object.)


The table view needs to know how many rows of data it has and how it should display each of those rows. But you can't simply dump that data into the table view's lap and be done with it. You don't say: "Dear table view, here are my 100 rows, now go show them on the screen."

Instead, you say to the table view: "This view controller is now your data source. You can ask it questions about the data anytime you feel like it."

Once it is hooked up to a data source — i.e., your view controller — the table view sends a `numberOfRowsInSection` message to find out how many data rows there are.

And when the table view needs to draw a particular row on the screen it sends a `cellForRowAt` message to ask the data source for a cell.

You see this pattern all the time in iOS: one object does something on behalf of another object. In this case, the `ChecklistViewController` works to provide the data to the table view, but only when the table view asks for it.



The dating ritual of a data source and a table view

Your implementation of `tableView(_:numberOfRowsInSection:)` — the first method that you added — returns the value 1. This tells the table view that you have just one row of data.

The `return` statement is very important in Swift. It allows a method to send data back to its caller. In the case of `tableView(_:numberOfRowsInSection:)`, the caller is the `UITableView` object and it wants to know how many rows are in the table.

The statements inside a method usually perform some kind of computation using instance variables and any data received through the method's parameters.


When the method is done, `return` says, "Hey, I'm done. Here is the answer I came up with." The return value is often called the *result* of the method.

For `tableView(_:numberOfRowsInSection:)` the answer is really simple: there is only one row, so `return 1`.

Now that the table view knows it has one row to display, it calls the second method you added — `tableView(_:cellForRowAt:)` — to obtain a cell for that row. This method grabs a copy of the prototype cell and gives that back to the table view, again with a `return` statement.

Inside `tableView(_:cellForRowAt:)` is also where you would normally put the row data into the cell, but the app doesn't have any row data yet.

➤ Run the app and you'll see there is a single cell in the table:



The table now has one row


★ ★ ★

Method signatures

In the above text, you might have noticed some special notation for the method names, like `tableView(_:numberOfRowsInSection:)` or `tableView(_:cellForRowAt:)`. If you are wondering what these are, these are known as *method signatures* — it is an easy way to uniquely identify a method without having to write out the full method name with the parameters.

The method signature identifies where each parameter would be (and the parameter name, where necessary) by separating out the parameters with a colon. In the method for `tableView(_:numberOfRowsInSection:)` for example, you might notice an underscore for the first parameter — that means that that method does not need to have the parameter name specified when calling the method — it is simply a convenience in Swift where the parameter can generally be inferred from the method name. (You might have more questions about this — but we'll come back to that later.)

If you are not sure about the signature for a method, take a look at the Xcode **Jump bar** (the tiny toolbar right above the source editor) and click on the last item of the file path elements to get a list of methods (and properties) in the current source file.



The Jump Bar shows the method signatures

Also, do note that in the above examples, `tableView` is not the method name — or rather, `tableView` by itself is not the method name. The method name is the `tableView` plus the parameter list — everything up to the closing bracket for the parameter list. That's how you get multiple unique methods such as `tableView(_:numberOfRowsInSection:)` and `tableView(_:cellForRowAt:)` even though they all look as if they are methods called `tableName`, the complete signature uniquely identifies the method, if that makes sense?

Special comments

You might have noticed the following line in the code you just added:

```
// MARK: - Table View Data Source
```

If you were wondering what that was for, here's the scoop. Of course, you already know that line is a comment, because the line begins with `//`, but it's not *just* a comment. As the keyword at the beginning of the comment line, MARK, indicates, it is a marker. But a marker for what?

It's a marker to organize the code and for you to find a section of code (for example, a set of related methods, like for the table view data source) via the Xcode Jump Bar.

Take a look at the previous screenshot showing the Xcode Jump Bar. Do you notice the separator line in the middle of the list of methods? Do you notice the bolded text title right after? Does that title seem familiar?

The text you provide after the `MARK:` keyword defines how the section title is displayed in the menu.

If you put in a hyphen (-), you get a separator line followed by any text after the hyphen as the section title. If you don't provide a hyphen but provide some text, then you simply get a section title but no separator. If you provide neither, then you just get a section icon with no text and no separator. (Try these out.)

There are a couple of other comment tags besides `MARK:` that you can use in your Swift files. These are `TODO:` and `FIXME:`. The first is generally used to indicate portions of your code that need to be completed, while the latter is used to mark portions of code that need re-writing or fixing.

Consider using these tags to organize your code better. When you are in a hurry and need to find that particular bit of code in a long source file, they come in very handy. I certainly use them all the time in my own code :]



Testing the table view data source

> **Exercise:** Modify the app so that it shows five rows.

That shouldn't have been too hard:


```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return 5
}
```

If you were tempted to go into the storyboard and duplicate the prototype cell five times, then you were confusing cells with rows :]

When you make `tableView(_:numberOfRowsInSection:)` return the number 5, you tell the table view that there will be five rows.

The table view then sends the `cellForRowAt` message five times, once for each row.

Because `tableView(_:cellForRowAt:)` currently just returns a copy of the prototype cell, your table view will show five identical rows:



The table now has five identical rows

There are several ways to create cells in `tableView(_:cellForRowAt:)`, but by far the easiest approach is what you've done here:


1. Add a prototype cell to the table view in the storyboard.
2. Set a reuse identifier on the prototype cell.
3. Call `tableView.dequeueReusableCell(withIdentifier:for:)`. This makes a new copy of the prototype cell if necessary, or, recycles an existing cell that is no longer in use.

Once you have a cell, you should set it up with the data from the corresponding row and give it back to the table view. That's what you'll do in the next section.

Putting row data into the cells

Currently, the rows (or rather the cells) all contain the placeholder text "Label". Let's add some unique text for each row.

➤ Open the storyboard and select the **Label** inside the table view cell. Go to the **Attributes inspector** and set the **Tag** field to 1000.



Set the label's tag to 1000

A *tag* is a numeric identifier that you can give to a user interface control in order to uniquely identify it later. Why the number 1000? No particular reason. It should be something other than 0, as that is the default value for all tags. 1000 is as good a number as any.

Double-check to make sure you set the tag on the *Label*, not on the Table View Cell or its Content View. It's a common mistake to set the tag on the wrong view and then the results won't be what you expected!

➤ In **ChecklistViewController.swift**, change `tableView(_:cellForRowAt:)` to the following:

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "ChecklistItem",
    for: indexPath)

  // Add the following code
  let label = cell.viewWithTag(1000) as! UILabel

  if indexPath.row == 0 {
    label.text = "Walk the dog"
  } else if indexPath.row == 1 {
    label.text = "Brush my teeth"
  } else if indexPath.row == 2 {
    label.text = "Learn iOS development"
  } else if indexPath.row == 3 {
    label.text = "Soccer practice"
  } else if indexPath.row == 4 {
    label.text = "Eat ice cream"
  }
  // End of new code block

  return cell
}
```

You've already seen the first line. It gets a copy of the prototype cell — either a new one or a recycled one — and puts it into a local constant named `cell`. (Recall that this is a constant because it's declared with `let`, not `var`. It is local because it's defined inside a method.)

The first new line that you've just added is:

```
  let label = cell.viewWithTag(1000) as! UILabel
```

Here you ask the table view cell for the view with tag 1000. That is the tag you just set on the label in the storyboard. So, this returns a reference to the corresponding `UILabel`.

Using tags is a handy trick to get a reference to a UI element without having to make an `@IBOutlet` variable for it.

> **Exercise:** Why can't you simply add an `@IBOutlet` variable to the view controller and connect the cell's label to that outlet in the storyboard? After all, that's how you created references to the labels in *Bull's Eye*... so why won't that work here?

Answer: There will be more than one cell in the table and each cell will have its own label. If you connected the label from the prototype cell to an outlet on the view controller, that outlet could only refer to the label from *one* of these cells, not all of them. Since the label belongs to the cell and not to the view controller as a whole, you can't make an outlet for it on the view controller. Confused? We'll circle around to this topic soon, so don't worry about it for now.

Back to the code. What is this `indexPath` thing?

`IndexPath` is simply an object that points to a specific row in the table. When the table view asks the data source for a cell, you can look at the row number inside the `indexPath.row` property to find out the row for which the cell is intended.

> **Note:** As I mentioned before, it is also possible for tables to group rows into sections. In an address book app you might sort contacts by last name. All contacts whose last name starts with "A" are grouped into their own section, all contacts whose last name starts with "B" are in another section, and so on.
>
> To find out which section a row belongs to, you'd look at the `indexPath.section` property. The *Checklists* app has no need for this kind of grouping, so you'll ignore the `section` property of `IndexPath` for now.

Now that you know about `indexPath`, the following code should make sense to you:


```
if indexPath.row == 0 {
  label.text = "Walk the dog"
} else if indexPath.row == 1 {
  label.text = "Brush my teeth"
} else if indexPath.row == 2 {
```

```
    label.text = "Learn iOS development"
  } else if indexPath.row == 3 {
    label.text = "Soccer practice"
  } else if indexPath.row == 4 {
    label.text = "Eat ice cream"
  }
```

You have seen this `if – else if – else` structure before. It simply looks at the value of `indexPath.row`, which contains the row number, and changes the label's text accordingly. The cell for the first row gets the text "Walk the dog", the cell for the second row gets the text "Brush my teeth", and so on.

> **Note:** Computers generally start counting at 0 for lists of items. If you have a list of 4 items, they are counted as 0, 1, 2 and 3. It may seem a little silly at first, but that's just the way programmers do things.
>
> For the first row in the first section, `indexPath.row` is 0. The second row has row number 1, the third row is row 2, and so on.
>
> Counting from 0 may take some getting used to, but after a while it becomes second nature and you'll start counting at 0 even when you're out for groceries. :]

➤ Run the app; it now has five rows, each with its own text:



The rows in the table now have their own text

That is how you write the `tableView(_:cellForRowAt:)` method to provide data to the table. You first get a `UITableViewCell` object and then change the contents of that cell based on the row number of the `indexPath`.

Just for the heck of it, let's put 100 rows into the table.

➤ Make `tableView(_:numberOfRowsInSection:)` return 100.

➤ Also, change the code you added earlier to the following:

```
if indexPath.row % 5 == 0 {
  label.text = "Walk the dog"
} else if indexPath.row % 5 == 1 {
  label.text = "Brush my teeth"
} else if indexPath.row % 5 == 2 {
  label.text = "Learn iOS development"
} else if indexPath.row % 5 == 3 {
  label.text = "Soccer practice"
} else if indexPath.row % 5 == 4 {
  label.text = "Eat ice cream"
}
```

This uses the **remainder operator** (also known as the **modulo operator**), represented by the `%` sign, to determine what row you're on.

The `%` operator returns the remainder of a division operation. You may remember this from doing math in school. For example 13 % 4 = 1, because four goes into thirteen 3 times with a remainder of 1. However, 12 % 4 is 0 because there is no remainder.

The first row, as well as the sixth, eleventh, sixteenth and so on, will show the text "Walk the dog". The second, seventh and twelfth row will show "Brush my teeth". The third, eight and thirteenth row will show "Learn iOS development". And so on...

I think you get the picture: every five rows these lines repeat. Rather than typing in all the possibilities all the way up to a hundred, you let the computer calculate this for you (after all, that is what they are good at):


```
First row:     0 % 5 = 0
Second row:    1 % 5 = 1
Third row:     2 % 5 = 2
Fourth row:    3 % 5 = 3
Fifth row:     4 % 5 = 4

Sixth row:     5 % 5 = 0  (same as first row)  *** The sequence
Seventh row:   6 % 5 = 1  (same as second row)     repeats here
Eighth row:    7 % 5 = 2  (same as third row)
Ninth row:     8 % 5 = 3  (same as fourth row)
Tenth row:     9 % 5 = 4  (same as fifth row)

Eleventh row: 10 % 5 = 0  (same as first row)  *** The sequence
Twelfth row:  11 % 5 = 1  (same as second row)     repeats again
and so on...
```

If this makes no sense to you at all, then feel free to ignore it. You're just using this trick to quickly fill up a large table with data.

➤ Run the app and you should see this:



The table now has 100 rows

> **Note:** To scroll through this table view on the Simulator, you have to pretend you're using an actual iPhone. Click the mouse to "grab" the table view and then drag up or down. Simply swiping without clicking first — the way you'd normally scroll things on the Mac — doesn't work.

> **Exercise:** How many cells do you think this table view uses?

Answer: There are a 100 rows, but only about 14 (or more, depending on your device screen height) fit on the screen at a time. If you count the number of visible rows in the screenshot above you'll get up to 13, but it's possible to scroll the table in such a way that the top cell is still visible while a new cell is pulled in from below. So that makes at least 14 cells.

If you scroll really fast, then I guess it is possible that the table view needs to make a few more temporary cells, but I'm not sure about that. Is this important to know? Not really. You should let the table view take care of juggling the cells behind the scenes. All you have to do is give the table view a cell when it asks for it and fill it up with the data for the corresponding row.

You'll usually have fewer cells than rows. If the app always made a cell for each row, iOS would run out of memory really fast, especially on large tables. Because not all rows can be visible at once, that would be very wasteful and slow. iOS is a good citizen and recycles cells whenever it can.

Now you know why `UITableView` makes the distinction between rows — the data, of which you'll usually have lots, and cells — the visible representation of that data on the screen, of which there are only about a dozen.

As the song goes, "Rows and cells, rows and cells, tables all the way. Oh what fun it is to learn about new things every day!"


★ ★ ★

Strange crashes?

A common question on the *UIKit Apprentice* forums is, "I'm just following along with the book and suddenly my app crashes... What went wrong?"

If that happens to you, then make sure you haven't set a *breakpoint* on your code by accident. A breakpoint is a debugging tool that stops your program execution at a specific line and jumps into the Xcode debugger. It may appear like a crash, but your program simply paused.


A breakpoint looks like a blue arrow in the left-hand margin (also known as the **gutter**) of the source editor:



The blue arrow sets a breakpoint

If your app suddenly pauses and the source editor shows a blue arrow on a particular line, then you simply hit a breakpoint. Sometimes people click in the margin by mistake and set a breakpoint without even realizing it (I've certainly done that!).

To remove the breakpoint, drag it out of the Xcode window. Or, you can deactivate a breakpoint by simply clicking on it — it will still be there, ready to be activated again by a click, but will not pause code execution. A deactivated breakpoint is indicated by a faded blue arrow.




A deactivated breakpoint



Tap on the rows

When you tap on a row , the cell color changes to indicate it is selected. The cell remains selected till you tap another row. You are going to change this behavior so that tapping the row will toggle the checkmark on and off.



A tapped row stays gray

Taps on rows are handled by the table view's **delegate**. Remember I said before that in iOS you often find objects doing something on behalf of other objects? The data source is one example of this, but the table view also depends on another little helper, the table view delegate.

The concept of delegation is very common in iOS. An object will often rely on another object to help it out with certain tasks. This *separation of concerns* keeps the system simple, as each object does only what it is good at and lets other objects take care of the rest. The table view offers a great example of this.

Because every app has its own requirements for what its data looks like, the table view must be able to deal with lots of different types of data. Instead of making the table view very complex, or requiring that you modify it to suit your own apps, the UIKit designers have chosen to delegate the duty of providing the cells to display to another object, the data source.


The table view doesn't really care who its data source is or what kind of data your app deals with, just that it can send the `cellForRowAt` message and receive a cell in return. This keeps the table view component simple and moves the responsibility for handling the data to where it belongs: your code.

Likewise, the table view knows how to recognize when the user taps a row, but what it should do in response depends on the app. In this app, you'll make it toggle the checkmark; another app will likely do something totally different.

Using the delegation system, the table view can simply send a message that a tap occurred and let the delegate sort it out.

Usually, components will have just one delegate. But the table view splits up its delegate duties into two separate helpers: the `UITableViewDataSource` for putting rows into the table, and the `UITableViewDelegate` for handling taps on the rows and several other tasks.

➤ To see this, open the storyboard and **Control-click** on the table view to bring up its connections.



The table's data source and delegate are hooked up to the view controller

You can see that the table view's data source and delegate are both connected to the view controller. That is standard practice for a `UITableViewController`. (You can also use table views in a basic `UIViewController` but then you'll have to connect the data source and delegate manually.)

➤ Add the following method to **ChecklistViewController.swift**:

```
// MARK: - Table View Delegate
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  tableView.deselectRow(at: indexPath, animated: true)
}
```

The `tableView(_:didSelectRowAt:)` method is one of the table view delegate methods and gets called whenever the user taps on a cell. Run the app and tap a row — the cell briefly turns gray and then becomes de-selected again.

➤ Let's make `tableView(_:didSelectRowAt:)` toggle the checkmark. Change the method to the following:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  if let cell = tableView.cellForRow(at: indexPath) {
    if cell.accessoryType == .none {
      cell.accessoryType = .checkmark
    } else {
      cell.accessoryType = .none
    }
  }

  tableView.deselectRow(at: indexPath, animated: true)
}
```

The checkmark is part of the cell (the accessory, remember?). So, you first need to find the `UITableViewCell` object for the tapped row. You simply ask the table view: what is the cell at this `indexPath` you've given me?

It is theoretically possible that there is no cell at the specified index-path, for example if that row isn't visible. So, you need to use the special `if let` statement.

The `if let` tells Swift that you only want to perform the the code inside the `if` condition only if there really is a `UITableViewCell` object. In this app there always will be one — after all, that's what the user just tapped — but Swift doesn't know that.

Once you have the `UITableViewCell` object, you look at the cell's accessory type, which you can access via the `accessoryType` property. If it is "none", then you change the accessory to a checkmark; if it is already a checkmark, you change it back to none.

Note: In the above code, to find the cell you call `tableView.cellForRow(at:)`.

It's important to realize this is not the same method as the data source method `tableView(_:cellForRowAt:)` that you added earlier.


Despite the similar names they are different methods in different objects, performing different tasks. Tricky, eh?

The purpose of your data source method is to deliver a new (or recycled) cell object to the table view when a row becomes visible. You never call this method yourself; only the `UITableView` may call its data source methods.

The purpose of `tableView.cellForRow(at:)` is also to return a cell object, but this is an existing cell for a row that is currently being displayed. It won't create any new cells. If there is no cell for that row yet, it will return the special value `nil`, meaning that no cell could be found. (You use the `if let` statement to "catch" such `nil` values.)

Remember how I said methods should have clear, descriptive names? UIKit is generally pretty good with its names, but this is a case where a very similar name used in two different places can lead to confusion and despair. Beware this pitfall!

➤ Run the app and try it out. You should be able to toggle the checkmarks on the rows. Sweet!



You can now tap on a row to toggle the checkmark

Note: If the checkmark does not appear or disappear right away but only after you select *another* row, then make sure the method name is not `tableview(_:didDeselectRowAt:)`! You want `didSelect`, not `didDeselect`. Xcode's autocompletion may have fooled you into picking the wrong method name.

Unfortunately, the app has a bug. Here's how to reproduce it:

➤ Tap a row to remove the checkmark. Scroll that row off the screen and scroll back again (try scrolling really fast). The checkmark has reappeared!

In addition, the checkmark seems to spontaneously disappear from other rows. What is going on here?

Again, it's a matter of cells vs. rows: you have toggled the checkmark on the cell but the cell may be reused for another row when you're scrolling. Whether a checkmark is set or not should be a property of a given row (or rather, the data underlying that row), not the cell.

Instead of using the cell's accessory to remember to show a checkmark or not, you need some way to keep track of the checked status for each row. That means it's time to expand the data source and make it use a proper *data model*, which is the topic of the next section.

★ ★ ★

Methods with multiple parameters

Most of the methods you used in the *Bull's Eye* app took only one parameter or did not have any parameters at all, but these new table view data source and delegate methods take two:

```
override func tableView(
  _ tableView: UITableView,              // parameter 1
  numberOfRowsInSection section: Int     // parameter 2
) -> Int {                               // return value
  . . .
}
override func tableView(
  _ tableView: UITableView,               // parameter 1
  cellForRowAt indexPath: IndexPath       // parameter 2
) -> UITableViewCell {                    // return value
  . . .
}
override func tableView(
  _ tableView: UITableView,               // parameter 1
  didSelectRowAt indexPath: IndexPath     // parameter 2
) {
  . . .
}
```

The first parameter is the `UITableView` object on whose behalf these methods are invoked. This is done for convenience, so you won't have to make an `@IBOutlet` in order to send messages back to the table view.

For `numberOfRowsInSection` the second parameter is the section number. For `cellForRowAt` and `didSelectRowAt` it is the index-path.

Methods are not limited to just one or two parameters, they can have many. But for practical reasons two or three is usually more than enough, and you won't see many methods with more than five parameters.

In other programming languages a method typically looks like this:

```
Int numberOfRowsInSection(UITableView tableView, Int section) {
  . . .
}
```

In Swift we do things a little differently, mostly to be compatible with the iOS frameworks, which are all written in the Objective-C programming language. Let's take a look again at `numberOfRowsInSection`:

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  . . .
}
```

The method signature for the above method, as discussed before, is `tableView(_:numberOfRowsInSection:)`. If you say that out loud (without the underscores and colons, of course), it actually makes sense. It asks for the number of rows in a particular section of a particular table view.

The first parameter looks like this:

```
_ tableView: UITableView
```

The name of this parameter is `tableView`. The name is followed by a colon and the parameter's type, `UITableView`.

The second parameter looks like this:

```
numberOfRowsInSection section: Int
```

This one has two names, `numberOfRowsInSection` and `section`.

You use the first name, `numberOfRowsInSection`, when calling the method. This is the *external* parameter name. Inside the method itself you use the second name, `section`, known as the *local* parameter name. The data type of this parameter is `Int`.

The _ underscore is used when you don't want a parameter to have an external name. You'll often see the _ on the first parameter of methods that come from Objective-C frameworks. With such methods the first parameter only has one name but the other parameters have two. Strange? Yes.

It makes sense if you've ever programmed in Objective-C, but no doubt it looks weird if you're coming from another language. Once you get used to it, you'll find that this notation is actually quite readable.

Sometimes people with experience in other languages get confused because they think that ChecklistViewController.swift contains three functions that are all named `tableView()`. But that's not how it works in Swift: the names of the parameters are part of the full method name. That's why these three methods are actually named:

```
tableView(_:numberOfRowsInSection:)
tableView(_:cellForRowAt:)
tableView(_:didSelectRowAt:)
```

By the way, the return type of the method is at the end, after the –> arrow. If there is no arrow, as in `tableView(_:didSelectRowAt:)`, then the method is not supposed to return a value.

★ ★ ★

Phew! That was a lot of new stuff to take in, so I hope you're still with me. If not, then take a break and start at the beginning again. You're being introduced to a whole bunch of new concepts all at once and that can be overwhelming.

But don't worry, it's OK if everything doesn't make perfect sense yet. As long as you get the gist of what's going on, you're good to go.

If you want to check your work up to this point, you can find the project files for the app under **09-Table-views** in the Source Code folder.

Chapter 10: The Data Model

By Fahim Farook

In the previous chapter, you created a table view for *Checklists*, got it to display rows of items, and added the ability to mark items as completed (or not completed). However, this was all done using hardcoded, fake data. This would not do for a real to-do app since your users want to store their own custom to-do items.

In order to store, manage, and display to-do information efficiently, you need a data model that allows you to store (and access) to-do information easily. And that's what you're going to do in this chapter.

This chapter covers the following:

- **Model-View-Controller:** A quick explanation of the MVC fundamentals which are central to iOS programming.
- **The data model:** Creating a data model to hold the data for *Checklists*.
- **Clean up the code:** Simplify your code so that it is easier to understand and maintain.

Model-View-Controller

First, a tiny detour into programming-concept-land so that you understand some of the principles behind using a data model. No book on programming for iOS can escape an explanation of **Model-View-Controller**, or MVC for short.

MVC is one of the three fundamental design patterns of iOS. You've already seen the other two: *delegation*, making one object do something on behalf of another; and *target-action*, connecting events such as button taps to action methods.

The Model-View-Controller pattern states that the objects in your app can be split into three groups:

- **Model objects.** These objects contain your data and any operations on the data. For example, if you were writing a cookbook app, the model would consist of the recipes. In a game, it would be the design of the levels, the player score, and the positions of the monsters.


  The operations that the data model objects perform are sometimes called the *business rules* or the *domain logic*. For *Checklists*, the checklists and their to-do items form the data model.

- **View objects.** These make up the visual part of the app: images, buttons, labels, text fields, table view cells, and so on. In a game, the views form the visual representation of the game world, such as the monster animations and a frag counter.

  A view can draw itself and responds to user input, but it typically does not handle any application logic. Many views, such as `UITableView`, can be re-used in many different apps because they are not tied to a specific data model.

- **Controller objects.** The controller is the object that connects your data model objects to the views. It listens to taps on the views, makes the data model objects do some calculations in response, and updates the views to reflect the new state of your model. The controller is in charge. On iOS, the controller is called the "view controller".

Conceptually, this is how these three building blocks fit together:



How Model-View-Controller works

The view controller has one main view, accessible through its `view` property, that contains a bunch of subviews. It is not uncommon for a screen to have dozens of views all at once. The top-level view usually fills the whole screen. You design the layout of the view controller's screen in the storyboard.

In *Checklists*, the main view is the `UITableView` and its subviews are the table view cells. Each cell also has several subviews of its own, namely the text label and the accessory.

Generally, a view controller handles one screen of the app. If your app has more than one screen, each of these is handled by its own view controller and has its own views. Your app flows from one view controller to another.

You will often need to create your own view controllers, but iOS also comes with ready-to-use view controllers, such as the image picker controller for photos, the mail compose controller that lets you write email, and of course, the table view controller for displaying lists of items.

Views vs. view controllers

Remember that a view and a view controller are two different things.

A view is an object that draws something on the screen, such as a button or a label. The view is what you see.

The view controller is what does the work behind the scenes. It is the bridge that sits between your data model and the views.

A lot of beginners give their view controllers names such as `FirstView` or `MainView`. That is very confusing! If something is a view controller, its name should end with "ViewController", not "View".

I sometimes wish Apple had left the word "view" out of "view controller" and just called it "controller" as that is a lot less misleading.

The data model


So far, you've put a bunch of fake data into the table view. The data consists of a text string and a checkmark that can be on or off.

As you saw in the previous chapter, you cannot use the cells to remember the data as cells get re-used all the time and their old contents get overwritten.

Table view cells are part of the view. Their purpose is to display the app's data, but that data actually comes from somewhere else: the data model.

Remember this well: the rows are the data, the cells are the views.

The table view controller is the thing that ties them together through the act of implementing the table view's data source and delegate methods.



The table view controller (data source) gets the data from the model and puts it into the cells

The data model for this app will be a list of to-do items. Each of these items will get its own row in the table.

For each to-do item you need to store two pieces of information: the text ("Walk the dog", "Brush my teeth", "Eat ice cream") and whether the checkmark is set or not.

That is two pieces of information per row, so you need two variables for each row.

The first iteration

First, I'll show you the cumbersome way to program this. It will work but it isn't very smart. Even though this is not the best approach, I'd still like you to follow along and copy-paste the code into Xcode and run the app so that you understand how this approach works.

Understanding why this approach is problematic will help you appreciate the proper solution better.

➤ In **ChecklistViewController.swift**, add the following constants right after the `class ChecklistViewController` line.

```
class ChecklistViewController: UITableViewController {
  let row0text = "Walk the dog"
  let row1text = "Brush teeth"
  let row2text = "Learn iOS development"
  let row3text = "Soccer practice"
  let row4text = "Eat ice cream"
  . . .
```

These constants are defined outside of any method (they are not "local"), so they can be used by all of the methods in `ChecklistViewController`.

➤ Change the data source methods to:

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return 5
}

override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "ChecklistItem",
    for: indexPath)
```

```
    let label = cell.viewWithTag(1000) as! UILabel

    if indexPath.row == 0 {
      label.text = row0text
    } else if indexPath.row == 1 {
      label.text = row1text
    } else if indexPath.row == 2 {
      label.text = row2text
    } else if indexPath.row == 3 {
      label.text = row3text
    } else if indexPath.row == 4 {
      label.text = row4text
    }
    return cell
  }
```

➤ Run the app. It still shows the same five rows as originally.

What have you done here? For every row, you have added a constant with the text for that row. Together, those five constants are your data model. (You could have used variables instead of constants, but since the values won't change for this particular example, it's better to use constants.)

In `tableView(_:cellForRowAt:)` you look at `indexPath.row` to figure out which row to display, and put the text from the corresponding constant into the cell.

Handle checkmarks

Now, let's fix the checkmark toggling logic. You no longer want to toggle the checkmark on the cell but at the row (or data) level. To do this, you add five new instance variables to keep track of the "checked" state of each of the rows. (This time the values have to be variables instead of constants since you will be changing the checked/unchecked state for each row.) These new variables are also part of your data model.

➤ Add the following instance variables:

```
  var row0checked = false
  var row1checked = false
  var row2checked = false
  var row3checked = false
  var row4checked = false
```

These variables have the data type `Bool`. You've seen the data types `Int` (whole numbers), `Float` (decimal/fractional numbers), and `String` (text) before. A `Bool` variable can hold only two possible values: `true` or `false`.

`Bool` is short for "boolean", after Englishman George Boole who long ago invented a kind of logic that forms the basis of all modern computing. The fact that computers talk in ones and zeros is largely due to him.

You use `Bool` variables to remember whether something is true (1) or not (0). As a convention, the names of boolean variables often start with the verb "is" or "has", as in `isHungry` or `hasIceCream`.

The instance variable `row0checked` is `true` if the first row has its checkmark set and `false` if it doesn't. Likewise, `row1checked` reflects whether the second row has a checkmark or not, and so on.

> **Note:** How does the compiler know that the type of these variables is `Bool`? You never specified that anywhere.
>
> Remember *type inference* from your code in *Bulls's Eye*? Because you said `var row0checked = false`, the compiler infers that you intended to make this a `Bool`, as `false` is valid only for `Bool` values.

The delegate method that handles taps on table cells will now use these new instance variables to determine whether the checkmark for a row needs to be toggled on or off.

The code in `tableView(_:didSelectRowAt:)` should be something like the following. *Don't make these changes just yet!* Just try to understand what happens first.

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  if let cell = tableView.cellForRow(at: indexPath) {
    if indexPath.row == 0 {
      row0checked = !row0checked
      if row0checked {
        cell.accessoryType = .checkmark
      } else {
        cell.accessoryType = .none
      }
    } else if indexPath.row == 1 {
      row1checked = !row1checked
      if row1checked {
        cell.accessoryType = .checkmark
      } else {
        cell.accessoryType = .none
```

```
        }
      } else if indexPath.row == 2 {
        row2checked = !row2checked
        if row2checked {
          cell.accessoryType = .checkmark
        } else {
          cell.accessoryType = .none
        }
      } else if indexPath.row == 3 {
        row3checked = !row3checked
        if row2checked {
          cell.accessoryType = .checkmark
        } else {
          cell.accessoryType = .none
        }
      } else if indexPath.row == 4 {
        row4checked = !row4checked
        if row4checked {
          cell.accessoryType = .checkmark
        } else {
          cell.accessoryType = .none
        }
      }
    }
    tableView.deselectRow(at: indexPath, animated: true)
  }
```

It should be clear that the code looks at `indexPath.row` to find the row that was tapped, and then performs some logic with the corresponding "row checked" instance variable. But there's also some new stuff you may not have seen before.

Let's look at the first `if indexPath.row` statement in detail:

```
  if indexPath.row == 0 {
    row0checked = !row0checked
    if row0checked {
      cell.accessoryType = .checkmark
    } else {
      cell.accessoryType = .none
    }
  } . . .
```

If `indexPath.row` is 0, the user tapped on the very first row and the corresponding instance variable is `row0checked`.

You do the following to flip that boolean value around:

```
  row0checked = !row0checked
```

The `!` symbol is the **logical not** operator. There are a few other logical operators that work on `Bool` values, such as **and** and **or**, which you'll encounter soon enough.

What `!` does is simple: it reverses the meaning of the value. If `row0checked` is `true`, then `!` makes it `false`. Conversely, `!false` is `true`.

Think of `!` as "not": not yes is no and not no is yes. Yes?

Once you have the new value of `row0checked`, you can use it to show or hide the checkmark:

```
if row0checked {
  cell.accessoryType = .checkmark
} else {
  cell.accessoryType = .none
}
```

The same logic is used for the other four rows.

In fact, the other rows use the *exact* same logic. The only thing that is different between each of these code blocks is the name of the "row checked" instance variable.

Toggling Booleans

The toggling of `Bool` values from `true` to `false` (or vice versa) is such a common action, that Swift has added a method to do this easily without worrying what the `Bool` variable's value is. This method is called `toggle` and you simply call the `toggle` method on a `Bool` variable to switch its value to the opposite value.

So, let's improve upon the above code a little bit in two ways:

1. Use the `toggle` method to flip boolean values.
2. Since the code looks so similar from one `if` statement to the next, simplify it a bit more.

➤ Replace the current `tableView(_:didSelectRowAt:)` implementation with the following:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  if let cell = tableView.cellForRow(at: indexPath) {
    var isChecked = false
```

```
      if indexPath.row == 0 {
        row0checked.toggle()
        isChecked = row0checked
      } else if indexPath.row == 1 {
        row1checked.toggle()
        isChecked = row1checked
      } else if indexPath.row == 2 {
        row2checked.toggle()
        isChecked = row2checked
      } else if indexPath.row == 3 {
        row3checked.toggle()
        isChecked = row3checked
      } else if indexPath.row == 4 {
        row4checked.toggle()
        isChecked = row4checked
      }
      if isChecked {
        cell.accessoryType = .checkmark
      } else {
        cell.accessoryType = .none
      }
    }
    tableView.deselectRow(at: indexPath, animated: true)
  }
```

Now isn't that a lot shorter than the previous iteration (that you weren't supposed to type in)?

Notice how the logic that sets the checkmark on the cell has moved to the bottom of the method. There is now only one place where this happens.

To make this possible, you store the value of the "row checked" instance variable into the `isChecked` local variable. This temporary variable is just used to remember whether the selected row needs a checkmark or not.

By using a local variable you were able to remove a lot of duplicated code, which is a good thing. You've taken the logic that all rows had in common and moved it out of the `if` statements into a single place.

> **Note:** Code duplication makes programs a lot harder to read. Worse, it invites subtle mistakes that cause hard-to-find bugs. Always be on the lookout for opportunities to remove duplicate code!

Exercise: There was actually a bug in the previous, longer version of this method – did you spot it? That's what happens when you use copy-paste to create duplicate code, like I did when I wrote that method.

➤ Run the app and observe... that it still doesn't work very well. Initially, you have to tap a couple of times on a row to actually make the checkmark go away.

What's wrong here? Simple: when you declared the `rowXchecked` variables you set their values to `false`.

So `row0checked` and the others indicate that there is no checkmark on their row, but the table draws one anyway. That's because you enabled the checkmark accessory on the prototype cell.

In other words: the data model (the "row checked" variables) and the views (the checkmarks inside the cells) are out-of-sync.

There are a few ways you could try to fix this: you could set the `Bool` variables to `true` to begin with, or you could remove the checkmark from the prototype cell in the storyboard.

Neither is a foolproof solution. What goes wrong here isn't so much that you initialized the "row checked" values wrong or designed the prototype cell wrong, but that you didn't set the cell's `accessoryType` property to the right value in `tableView(_:cellForRowAt:)`.

When you are asked for a new cell, you always should configure all of its properties. The call to `tableView.dequeueReusableCell(withIdentifier:)` could return a cell that was previously used for a row with a checkmark. If the new row shouldn't have a checkmark, then you have to remove it from the cell at this point (and vice versa). Let's fix that.

➤ Add the following method to **ChecklistViewController.swift**. (If you're wondering where to add the code, probably best to add it either before or after the marked sections for the table view delegates. Not that the position matters, but purely from an organizational perspective.):

```
func configureCheckmark(
  for cell: UITableViewCell,
  at indexPath: IndexPath
) {
  var isChecked = false

  if indexPath.row == 0 {
```

```
      isChecked = row0checked
    } else if indexPath.row == 1 {
      isChecked = row1checked
    } else if indexPath.row == 2 {
      isChecked = row2checked
    } else if indexPath.row == 3 {
      isChecked = row3checked
    } else if indexPath.row == 4 {
      isChecked = row4checked
    }

    if isChecked {
      cell.accessoryType = .checkmark
    } else {
      cell.accessoryType = .none
    }
  }
```

This new method looks at the cell for a certain row, specified as usual by `indexPath`, and makes the checkmark visible if the corresponding "row checked" variable is `true`, or hides the checkmark if the variable is `false`.

This logic should look very familiar! The only difference with before is that here you don't toggle the state of the "row checked" variable. You only read it and then set the cell's accessory.

You'll call this method from `tableView(_:cellForRowAt:)`, just before you return the cell.

➤ Change `tableView(_:cellForRowAt:)` to the following (recall that `. . .` means that the existing code at that spot doesn't change):

```
  override func tableView(
    _ tableView: UITableView,
    cellForRowAt indexPath: IndexPath
  ) -> UITableViewCell {
    . . .

    configureCheckmark(for: cell, at: indexPath)
    return cell
  }
```

➤ Run the app again.

Now the app works just fine. Initially all the rows are unchecked. Tapping a row checks it, tapping it again unchecks it. The rows and cells are now always in sync. This code guarantees that each cell always has the value that corresponds to its underlying data row.

★ ★ ★

External and internal parameter names

The new `configureCheckmark` method has two parameters, `for` and `at`. Its full name is therefore `configureCheckmark(for:at:)`.

`for` and `at` are the *external* names of these parameters.

Adding short prepositions such as "at", "with", or "for" is very common in Swift. It makes the name of the method sound like a proper English phrase: "configure checkmark for this cell at that index-path". Doesn't it just roll off your tongue?

When you call the method, you always have to include those external parameter names:

```
configureCheckmark(for: someCell, at: someIndexPath)
```

Here, `someCell` is a variable that refers to a `UITableViewCell` object. Likewise, `someIndexPath` is a variable of type `IndexPath`.

You can't write the following:

```
configureCheckmark(someCell, someIndexPath)
```

This won't compile. The app doesn't have a `configureCheckmark` method that doesn't take parameter names, only `configureCheckmark(for:at:)`. The `for` and `at` are an integral part of the method name!

Inside the method you use the *internal* labels `cell` and `indexPath` to refer to the parameters.

```
func configureCheckmark(
  for cell: UITableViewCell,
  at indexPath: IndexPath
) {
  if indexPath.row == 0 {
    . . .
  }

  cell.accessoryType = .checkmark
  . . .
}
```

You can't write `if at.row == 0` or `for.accessoryType = .checkmark`. That also sounds a little odd, doesn't it?

This split between external and internal labels is unique to Swift and Objective-C and takes some getting used to if you're familiar with other languages.

This naming convention primarily exists so that Swift can talk to older Objective-C code, and this is a good thing since most of the iOS frameworks are still written in Objective-C.



Simplify the code

Why was `configureCheckmark(for:at:)` set up as a method of its own anyway? Well, because you can use it to simplify `tableView(_:didSelectRowAt:)`.

Notice how similar these two methods currently are. That's another case of code duplication that you can get rid of!

You can simplify `didSelectRowAt` by letting `configureCheckmark(for:at:)` do some of the work.

➤ Replace `tableView(_:didSelectRowAt:)` with the following:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  if let cell = tableView.cellForRow(at: indexPath) {
    if indexPath.row == 0 {
      row0checked.toggle()
    } else if indexPath.row == 1 {
      row1checked.toggle()
    } else if indexPath.row == 2 {
      row2checked.toggle()
    } else if indexPath.row == 3 {
      row3checked.toggle()
    } else if indexPath.row == 4 {
      row4checked.toggle()
    }
    configureCheckmark(for: cell, at: indexPath)
  }
  tableView.deselectRow(at: indexPath, animated: true)
}
```


This method no longer sets or clears the checkmark from the cell, but only toggles the "checked" state in the data model and then calls `configureCheckmark(for:at:)` to update the view.

➤ Run the app again and it should still work.

➤ Change the declarations of the instance variables to the following and run the app again:

```
var row0checked = false
var row1checked = true
var row2checked = true
var row3checked = false
var row4checked = true
```

Now rows 1, 2 and 4 (the second, third and fifth rows) initially have a checkmark while the others don't.



The data model and the table view cells are now always in-sync


Arrays

The approach that we've taken above to remember which rows are checked or not works just fine... when there's five rows of data.

But what if you have 100 rows and they all need to be unique? Should you add another 95 "row text" and "row checked" variables to the view controller, as well as that many additional `if` statements? I hope not!


There is a better way: arrays.

An **array** is an ordered list of objects. If you think of a variable as a container of one value (or one object) then an array is a container for multiple objects.



Arrays are ordered lists containing multiple objects

Of course, the array itself is also an object (named `Array`) that you can put into a variable. And because arrays are objects, arrays can contain other arrays.



Arrays can also include other arrays

The objects inside an array are indexed by numbers, starting at 0 as usual. To ask the array for the first object, you write `array[0]`. The second object is at `array[1]`, and so on.

The array is *ordered*, meaning that the order of the objects it contains matters. The object at index 0 always comes before the object at index 1.

> **Note:** An array is a *collection* object. There are several other collection objects and they all organize their objects in a different fashion. `Dictionary`, for example, contains *key-value pairs*, just like a real dictionary contains a list of words and a description for each of those words. You'll use some of these other collection types in later chapters.

The organization of an array is very similar to the rows for a table — they are both lists of objects in a particular order — so it makes sense to put your data model's rows into an array.


Arrays store one object per index, but your rows currently consist of two separate pieces of data: the text and the checked state. It would be easier if you made a single object for each row, because then the row number from the table simply becomes the index in the array.

The second iteration

Let's combine the text and checkmark state into a new object of your own!


The object

➤ Select the **Checklists** group in the project navigator and right click. Choose **New File...** from the popup menu:




Adding a new file to the project

Under the **Source** section choose **Swift File**:



Choosing the Swift File template

Click **Next** to continue. Save the new file as **ChecklistItem** (you don't really need to add the **.swift** file extension since it will be automatically added for you).



Saving the new Swift file

Press **Create** to add the new file to the project.

➤ Add the following to the new **ChecklistItem.swift** file, below the `import` line:

```
class ChecklistItem {
  var text = ""
  var checked = false
}
```

What you see here is the absolute minimum amount of code you need in order to make a new object. The `class` keyword names the object and the two lines with `var` add data items (instance variables) to it.

The `text` property will store the description of the checklist item (the text that will appear in the table view cell's label) and the `checked` property determines whether the cell gets a checkmark or not.

> **Note:** You may be wondering what the difference is between the terms *property* and *instance variable* — we've used both to refer to an object's data items. You'll be glad to hear that these two terms are interchangeable.
>
> In Swift terminology, a property is a variable or constant that is used in the context of an object. That's exactly what an instance variable is.

> (In Objective-C, properties and instance variables are closely related but not quite the same thing. In Swift they are the same.)

That's all for **ChecklistItem.swift** for now. The `ChecklistItem` object currently only serves to combine the `text` and the `checked` variables into one object. Later you'll do more with it.

Using the object

Before you try using an array, replace the `String` and `Bool` instance variables in the view controller with these new `ChecklistItem` objects to see how that approach would work.

➤ In **ChecklistViewController.swift**, remove the old properties (both the `let` and `var` values) and replace them with `ChecklistItem` objects:

```
class ChecklistViewController: UITableViewController {
  var row0item = ChecklistItem()
  var row1item = ChecklistItem()
  var row2item = ChecklistItem()
  var row3item = ChecklistItem()
  var row4item = ChecklistItem()
```

These replace the `row0text`, `row0checked`, etc. instance variables.

Wait a minute though ... We've had variable declarations with a type, or with explicit values like an empty string or a number, but what are these? These variables are being assigned with what looks like a method!

And you are right about the method — it's a special method that all classes have called an *initializer* method. An initializer method creates a new instance of the given object, in this case `ChecklistItem` . This creates an empty instance of `ChecklistItem` with the the default values you defined when you added the class implementation — an empty string ("") for `text` and `false` for `checked`.

Instead of the above, you could have used what's known as a *type annotation* to simply indicate the type of `row0Item` like this:

```
var row0item: ChecklistItem
```

If you did that, `row0item` won't have a value yet, it would just be an empty container for a `ChecklistItem` object. And you'd still have to create the `ChecklistItem` instance later in your code (for example, in `viewDidLoad`).

The way we've done the code now, we initialize the variables above immediately with an empty instance of `ChecklistItem` and let Swift's type inference do the work in letting the compiler figure out the type of the variables. Handy, right?

Just to clarify the above a bit more, the data type is like the brand name of a car. Just saying the words "Porsche 911" out loud doesn't magically get you a new car — you actually have to go to the dealer to buy one.

The parentheses `()` behind the type name are like going to the object dealership to buy an object of that type. The parentheses tell Swift's object factory, "Build me an object of the type `ChecklistItem`."

It is important to remember that just declaring that you have a variable does not automatically make the corresponding object for you. The variable is just the container for the object. You still have to instantiate the object and put it into the container. The variable is the box and the object is the thing inside the box.

So until you order an actual `ChecklistItem` object from the factory and put that into `row0item`, the variable is empty. And empty variables are a big no-no in Swift.

Fixing existing code

Because some methods in the view controller still refer to the old variables, Xcode will throw up multiple errors at this point. Before you can run the app again, you need to fix these errors. So, let's do that now.

> **Note:** I generally encourage you to type in the code from this book by hand (instead of copy-pasting), because that gives you a better feel for what you're doing, but in the following instances it's easier to just copy-paste from the PDF or using the **Copy** button in our online reader.
>
> Unfortunately, copying from the PDF sometimes adds strange or invisible characters that confuse Xcode. It's best to first paste the copied text into a plain text editor such as TextMate and then copy/paste from the text editor into Xcode.
>
> Of course, if you're reading the print edition of this book, copying & pasting from the book isn't going to work, but you can still use copy-paste to save yourself some effort. Make the changes on one line and then copy that line to create the other lines. Copy-paste is a programmer's best friend, but don't forget to update the lines you pasted to use the correct variable names!

➤ In `tableView(_:cellForRowAt:)`, replace the `if` statements with the following:

```
if indexPath.row == 0 {
  label.text = row0item.text
} else if indexPath.row == 1 {
  label.text = row1item.text
} else if indexPath.row == 2 {
  label.text = row2item.text
} else if indexPath.row == 3 {
  label.text = row3item.text
} else if indexPath.row == 4 {
  label.text = row4item.text
}
```

➤ In `tableView(_:didSelectRowAt:)`, again change the `if` statement block to:

```
if indexPath.row == 0 {
  row0item.checked.toggle()
} else if indexPath.row == 1 {
  row1item.checked.toggle()
} else if indexPath.row == 2 {
  row2item.checked.toggle()
} else if indexPath.row == 3 {
  row3item.checked.toggle()
} else if indexPath.row == 4 {
  row4item.checked.toggle()
}
```

➤ And finally, in `configureCheckmark(for:at:)`, change the `if` block to:

```
if indexPath.row == 0 {
  isChecked = row0item.checked
} else if indexPath.row == 1 {
  isChecked = row1item.checked
} else if indexPath.row == 2 {
  isChecked = row2item.checked
} else if indexPath.row == 3 {
  isChecked = row3item.checked
} else if indexPath.row == 4 {
  isChecked = row4item.checked
}
```

Basically, all of the above changes do one thing — instead of using the separate `row0text` and `row0checked` variables, you now use `row0item.text` and `row0item.checked`. That takes care of all of the errors and you can even build and run the app. But if you do, you'll notice that you get an empty table. Try clicking on the first few rows. You'll notice that you get checkmarks toggling on and off for them. Curiouser, and curiouser … So what went wrong?

Set up the objects

Remember how I said that the new `row0item` etc. variables are initialized with empty instances of `ChecklistItem`? That means that the text for each variable is empty. You still need to set up the values for these new variables!

➤ Modify `viewDidLoad` in **ChecklistViewController.swift** as follows:

```
override func viewDidLoad() {
  super.viewDidLoad()

  // Add the following lines
  row0item.text = "Walk the dog"

  row1item.text = "Brush my teeth"
  row1item.checked = true

  row2item.text = "Learn iOS development"
  row2item.checked = true

  row3item.text = "Soccer practice"

  row4item.text = "Eat ice cream"
  row4item.checked = true
}
```

This code simply sets up each of the new `ChecklistItem` variables that you created. If you're wondering why some variables have a line to set the `checked` property and some don't, remember that you initialize `checked` to `false` in the `ChecklistItem` class implementation. That default value is applied to the new object when you instantiate it. So, while you could still add a line to set `checked` to `false`, it isn't necessary since the `checked` property is already set to `false`.

The above code is essentially doing the same thing as before, except that this time the `text` and `checked` variables are not separate instance variables of the view controller, but instead are properties of a `ChecklistItem` object.

➤ Run the app just to make sure that everything works now.

Putting the `text` and `checked` properties into their own `ChecklistItem` object already improved the code, but it is still a bit unwieldy.

Using Arrays

With the current approach, you need to keep around a `ChecklistItem` instance variable for each row. That's not ideal, especially if you want more than just a handful of rows. Time to bring that array into play!

➤ In **ChecklistViewController.swift**, remove all the instance variables and replace them with a single array variable named `items`:

```
class ChecklistViewController: UITableViewController {
  var items = [ChecklistItem]()
```

Instead of five different instance variables, one for each row, you now have just one variable for the array.

This looks similar to how you declared the previous variables but this time there are square brackets around `ChecklistItem`. Those square brackets indicate that the variable is going to be an array containing `ChecklistItem` objects. And the brackets at the end `()` simply indicate that you are creating an instance of this array — it will create an empty array with no items in the array.

➤ Modify `viewDidLoad` as follows:

```
override func viewDidLoad() {
  super.viewDidLoad()

  // Replace previous code with the following
  let item1 = ChecklistItem()
  item1.text = "Walk the dog"
  items.append(item1)

  let item2 = ChecklistItem()
  item2.text = "Brush my teeth"
  item2.checked = true
  items.append(item2)

  let item3 = ChecklistItem()
  item3.text = "Learn iOS development"
  item3.checked = true
  items.append(item3)

  let item4 = ChecklistItem()
  item4.text = "Soccer practice"
  items.append(item4)

  let item5 = ChecklistItem()
  item5.text = "Eat ice cream"
  items.append(item5)
}
```

This is not that different from before, except that you now have to first create — or *instantiate* — each `ChecklistItem` object and add each instance to the array. Once the above code completes, the `items` array contains five `ChecklistItem` objects. This is your new data model.

Simplify the code — again

Now you have all your rows in the `items` array.

You can simplify the table view data source and delegate methods once again.

➤ Change these methods:

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "ChecklistItem",
    for: indexPath)

  let item = items[indexPath.row]       // Add this

  let label = cell.viewWithTag(1000) as! UILabel
  // Replace everything after the above line with the following
  label.text = item.text
  configureCheckmark(for: cell, at: indexPath)
  return cell
}
```

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  if let cell = tableView.cellForRow(at: indexPath) {
    // Replace everything inside this `if` condition
    // with the following
    let item = items[indexPath.row]
    item.checked.toggle()

    configureCheckmark(for: cell, at: indexPath)
  }
  tableView.deselectRow(at: indexPath, animated: true)
}
```

```
func configureCheckmark(
  for cell: UITableViewCell,
  at indexPath: IndexPath
) {
  // Replace full method implementation
  let item = items[indexPath.row]

  if item.checked {
    cell.accessoryType = .checkmark
  } else {
```

```
      cell.accessoryType = .none
    }
  }
```

That's a lot simpler than what you had before! Each method is now only a handful of lines long.

In each method, you do:

```
  let item = items[indexPath.row]
```

This asks the array for the `ChecklistItem` object at the index that corresponds to the row number. Once you have that object, you can simply look at its `text` and `checked` properties and do whatever you need to do.

If the user were to add 100 to-do items to this list, none of this code would need to change. It works equally well with five items as with a hundred (or a thousand).

Speaking of the number of items, you can now change `numberOfRowsInSection` to return the actual number of items in the array, instead of a hard-coded number.

➤ Change the `tableView(_:numberOfRowsInSection:)` method to:

```
  override func tableView(
    _ tableView: UITableView,
    numberOfRowsInSection section: Int
  ) -> Int {
    return items.count
  }
```

Not only is the code a lot shorter and easier to read, it can now also handle an arbitrary number of rows. That is the power of arrays!

➤ Run the app and see for yourself. It should still work exactly the same as before, but the internal structure of the code is way better.

Exercise: Add a few more rows to the table. You should only have to change `viewDidLoad` for this to work.

Clean up the code

There are a few more things you can do to improve the source code.

➤ Replace `configureCheckmark(for:at:)` with this one:

```
func configureCheckmark(
  for cell: UITableViewCell,
  with item: ChecklistItem
) {
  if item.checked {
    cell.accessoryType = .checkmark
  } else {
    cell.accessoryType = .none
  }
}
```

Instead of an index-path, you now directly pass the `ChecklistItem` object to the method.

Note that now the full name of the method becomes `configureCheckmark(for:with:)` and that's how you will call it from other places in the app.

Why did you change this method? Previously it received an index-path and then did the following to find the corresponding `ChecklistItem`:

```
let item = items[indexPath.row]
```

But in both `cellForRowAt` and `didSelectRowAt` you already do that. So, it's simpler to pass that `ChecklistItem` object directly to `configureCheckmark` instead of making it do the same work twice. Anything that simplifies the code is good.

➤ Also add this new method:

```
func configureText(
  for cell: UITableViewCell,
  with item: ChecklistItem
) {
  let label = cell.viewWithTag(1000) as! UILabel
  label.text = item.text
}
```

This sets the checklist item's text on the cell's label. Previously you did that in `cellForRowAt` but it's clearer to put that in its own method.

➤ Update `tableView(_:cellForRowAt:)` so that it calls these new methods:

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "ChecklistItem",
    for: indexPath)

  let item = items[indexPath.row]

  configureText(for: cell, with: item)
  configureCheckmark(for: cell, with: item)
  return cell
}
```

➤ Also update `tableView(_:didSelectRowAt:)`:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  if let cell = tableView.cellForRow(at: indexPath) {
    let item = items[indexPath.row]
    item.checked.toggle()
    configureCheckmark(for: cell, with: item)
  }
  tableView.deselectRow(at: indexPath, animated: true)
}
```

➤ Run the app. It should still work exactly the same as before, but the code is a lot better. You can now have lists with thousands of to-do items, for those especially industrious users.

Clean up that mess!

So what's the point of making all of these changes if the app still works exactly the same? For one, the code is much cleaner and that helps with avoiding bugs. By using an array you've also made the code more flexible. The table view can now handle any number of rows.

You'll find that when you program you are constantly restructuring your code to make it better. It's impossible to do the whole thing 100% perfect from the get go.

So you write code until it becomes messy and then you clean it up. After a little while it becomes a big mess again and you clean it up again. The process for cleaning up code is called *refactoring* and it's a cycle that never ends.

There are a lot of programmers who never refactor their code. The result is what we call "spaghetti code" and it's a horrible mess to maintain.

If you haven't looked at your code for several months but need to add a new feature or fix a bug, you may need some time to read it through to understand again how everything fits together. This task becomes that much harder when you have spaghetti code.

So, it's in your own best interest to write code that is as clean as possible.

If you want to check your work, you can find the project files for the current version of the app in the folder **10-The-data-model** in the Source Code folder.


Chapter 11: Navigation Controllers

By Fahim Farook

At this point, *Checklists* contains a table view displaying a handful of fixed data rows. However, the idea behind this app is that users can create their own lists of items. Therefore, you need to give the user the ability to add to-do items.

In this chapter you'll expand the app to have a **navigation bar** at the top. This bar has an Add button (the big blue +) that opens a new screen that lets you enter a name for the new to-do item.

When you tap Done, the new item will be added to the list.



The + button in the navigation bar opens the Add Item screen

Presenting a new screen to add items is a common pattern in a lot of apps. Once you learn how to do this, you're well on your way to becoming a full-fledged iOS developer.

This chapter covers the following:


- **Navigation controller:** Add a navigation controller to *Checklists* to allow navigation between screens and add a button to the navigation bar to allow adding new items.
- **Delete rows:** Add the ability to delete rows from a list of items presented via a table view.
- **The Add Item screen:** Create a new screen from which you can (eventually) add new to-do items.

Navigation controller

First, let's add the navigation bar. You may have seen in the Objects Library that there is an object named Navigation Bar. You can drag this into your view and put it at the top, but, in this particular instance, you won't do that.

Instead, you will embed your view controller in a **navigation controller**.

Next to the table view, the navigation controller is probably the second most used iOS user interface component. It is the thing that lets you go from one screen to another:



A navigation controller in action


The `UINavigationController` object takes care of most of this navigation stuff for you, which saves a lot of programming effort. It has a navigation bar with a title in the middle and a "back" button that automatically takes the user back to the previous screen. You can put a button — or several buttons — of your own on the right.

Add a navigation controller

Adding a navigation controller is really easy.


➤ Open **Main.storyboard** and select the **Checklist View Controller**.

➤ From the menu bar at the top of the screen, choose **Editor ▸ Embed In ▸ Navigation Controller**.



Putting the view controller inside a navigation controller


That's it. Interface Builder has now added a new Navigation Controller scene and made a relationship between it and your view controller.



The navigation controller is now linked with your view controller

When the app starts up, the Checklist View Controller is automatically put inside a navigation controller.

➤ Run the app and try it out.




The app now has a navigation bar at the top

The only thing different (visually) is that the app now has a navigation bar at the top.

Set the navigation bar title

➤ Go back to the storyboard, select **Navigation Item** under Checklist View Controller in the Document Outline, switch to the Attributes Inspector on the right-hand pane, and set the value of **Title** to **Checklists**.




Changing the title in the navigation bar

What you're doing here is changing a **Navigation Item** object that was automatically added to the view controller when you chose the Embed In command.

The Navigation Item object contains the title and buttons that appear in the navigation bar when this view controller becomes active. Each embedded view controller has its own Navigation Item that it uses to configure what shows up in the navigation bar.

When the navigation controller slides a new view controller in, it replaces the contents of the navigation bar with the new view controller's Navigation Item.

Run your app and your screen should look something like this:



Navigation bar with title

Display large titles

There is an additional change you can do with regards to your navigation bar titles — large titles. Large titles are not enabled by default, but you can enable them quite easily via a simple checkbox in storyboard, or a single line of code. So, let's do that!

➤ Switch to **ChecklistViewController.swift** and add the following line to `viewDidLoad`, right after the existing `super.viewDidLoad()` line:

```
navigationController?.navigationBar.prefersLargeTitles = true
```


There are a few interesting things in that bit of code but we don't want to get into all of it now. For now, the important things to remember are these:

1. Generally, there is a single navigation controller for a given navigation flow.
2. A single navigation controller could present multiple view controllers as part of its navigation flow.
3. Each view controller in a navigation hierarchy has a reference to the navigation controller which presented it.

Given the above information, the previous code snippet simply uses the view controller's reference to the navigation controller to access the navigation bar for the app. Then, it sets the `prefersLargeTitles` property on the navigation bar to `true`. And it is this property, as the name implies, which enables large titles.

> **Note:** If you wanted to make the same change via storyboard instead of code, you'd select the Navigation Bar under your Navigation Controller in your storyboard and set the **Prefers Large Titles** checkbox in the **Attributes inspector**.

Run your app again. Do you see a difference?



Navigation bar with large title

> **Note:** Apple does not recommend using large titles for all of your screens. Rather, their recommendation is to use large titles on your main screen and any other subsequent screens where it might make sense to have a prominent title. You will learn how to turn off large titles for secondary views later on.


Interesting, huh? Of course, you might wonder why there is so much space above the title — that seems like a waste of space, right? That space will be utilized by the navigation items — the back button on the left (if you are in a secondary screen), and any other button(s) you assign to the right.

Add a navigation button to add items

Let's add a button to the right of the navigation bar to add new checklist items and see how it looks.

➤ Open your main storyboard.

➤ Go to the Objects Library and look for **Bar Button Item**. Drag it into the right-side slot of the navigation bar — be sure to use the navigation bar on the Checklist View Controller, not the one from the navigation controller!




Dragging a Bar Button Item into the navigation bar

> **Note:** If you enabled large titles via the storyboard, your navigation bar will look taller than the above screenshot. This is normal — it's not a bug :]

By default, this new button is named "Item" but for this app you want it to have a big + sign.

➤ In the **Attributes inspector** for the bar button item, choose **System Item: Add**.




Bar Button Item attributes

If you look through the list for the System Item dropdown, you'll see a lot of predefined bar button types: Add, Compose, Reply, Camera, and so on.

You can use these in your own apps, but be sure to use them only for their intended purpose — you shouldn't use the camera icon on a button that sends an email, for example. Improper use of these icons may lead Apple to reject your app from the App Store. And that sucks.

OK, that gives us a button. If you run the app, it should look like this:



The app with the Add button

Now it looks a little less bare, right? If you're still not happy with the amount of space taken up by large titles, you can always turn off large titles, but do note that when you have a screenful of items and you need to scroll to see more information, the large title will retract into the top navigation bar and give you the "classic"-look navigation bar. So you might want to try this out a bit before deciding to disable it.

Make the navigation button do something

If you tap on your new add button, it doesn't actually do anything. That's because you haven't hooked it up to an action. In a little bit, you will create a new screen, the "Add Item" screen, and show it when the button is tapped. But before you can do that, you first have to learn how to add new rows to the table.

Let's hook up the Add button to an action. You got plenty of exercise with this for *Bull's Eye*, so it should be child's play for you by now.


➤ Add a new action method to **ChecklistViewController.swift**:

```
// MARK: - Actions
@IBAction func addItem() {
}
```

You're leaving the method empty for the moment, but it needs to be there so you have something to connect the button to.

> **Note:** As you might have noticed, I have added a new jumpbar section called Actions along with the above action. I usually put all my action methods in one place. You don't really have to follow what I've done, but it's always a good idea to organize your code in some way to make finding a particular method easy.


➤ Open the storyboard and connect the Add button to this action. To do this, **Control-drag** from the + button to the yellow circle in the bar above the view (this circle represents the Checklist View Controller):



Control-drag from Add button to Checklist View Controller

Actually, you can Control-drag from the Add button to almost anywhere in the same scene to make the connection.

➤ After dragging, pick **addItem** from the popup (under **Sent Actions**):



Connecting to the addItem action

➤ Let's give `addItem()` something to do. Back in **ChecklistViewController.swift**, add some code to the method as follows:

```
@IBAction func addItem() {
  let newRowIndex = items.count

  let item = ChecklistItem()
  item.text = "I am a new row"
  items.append(item)

  let indexPath = IndexPath(row: newRowIndex, section: 0)
  let indexPaths = [indexPath]
  tableView.insertRows(at: indexPaths, with: .automatic)
}
```

The new code creates a new `ChecklistItem` object and adds it to the data model — the `items` array. You also have to tell the table view, "I've inserted a row at this index, please update yourself."

Let's review the code section-by-section:

```
  let newRowIndex = items.count
```

You need to know what the index of the new row in your array would be. This is necessary in order to properly update the table view later.

When you start the app there are 5 items in the array and 5 rows on the screen. Computers start counting at 0, so the existing rows have indexes 0, 1, 2, 3 and 4. To add the new row to the end of the array, the index for that new row must be 5.

In other words, when you add a row to the end of an array, the index for the new row is always equal to the number of items currently in the array. Let that sink in for a second.

You store the index for the new row in the local constant `newRowIndex`. This can be a constant instead of a variable because it never has to change.

The following few lines should look familiar:

```
  let item = ChecklistItem()
  item.text = "I am a new row"
  items.append(item)
```

You have seen this code before in `viewDidLoad`. It creates a new `ChecklistItem` object and adds it to the end of the array.

The data model now consists of 6 `ChecklistItem` objects inside the `items` array. Note that at this point `newRowIndex` is still 5 even though `items.count` is now 6. That's why you read the item count and stored this value in `newRowIndex` *before* you added the new item to the array.

Just adding the new `ChecklistItem` object to the data model's array isn't enough. You have to tell the table view about this new row so it can add a new cell for that row.

```
    let indexPath = IndexPath(row: newRowIndex, section: 0)
```

As you know by now, table views use index-paths to identify rows. So, you first make an `IndexPath` object that points to the new row, using the row number from the `newRowIndex` variable. This index-path object now points to row 5 (in section 0).

The next line creates a new, temporary array holding just the one index-path item:

```
    let indexPaths = [indexPath]
```

You use the table view method `insertRows(at:with:)` to tell the table view about the new row. While you only have one inserted row here, as its name implies, this method actually lets you insert multiple rows at the same time, if you wanted to.

So, instead of a single `IndexPath` object, you need to pass an array of index-paths to the method. Fortunately, it is easy to create an array that contains a single index-path object by writing `[indexPath]`. The notation `[]` creates a new `Array` object that contains the objects between the brackets. Of course, if the array has more than one item, you have to separate the items with commas.

Finally, you tell the table view to insert this new row. The `with: .automatic` parameter makes the table view use a nice animation when it inserts the row:


```
    tableView.insertRows(at: indexPaths, with: .automatic)
```

To recap, you:

1. Created a new `ChecklistItem` object.
2. Added it to the data model.
3. Inserted a new row for it in the table view.

When you call `tableView.insertRows(at:with:)` to insert a new row, the table view makes a cell for this new row by calling your `tableView(_:cellForRowAt:)` data source method — but it only does this if the new row is actually in the visible portion of the table view.

➤ Try it out. You can now add many new rows to the table. You can also tap these new rows to turn their checkmarks on and off again. When you scroll the table up and down, the checkmarks stay with the proper rows.



After adding new rows with the + button

> **Note:** If you were concerned by the change to large titles, also notice how the large title becomes a smaller title (and vice versa) when you scroll up and down.

Remember, the rows always have to be added to both your data model and the table view. When you send the `insertRows(at:with:)` message to the table view, you say: "Hey table, my data model has a bunch of new items added to it."

This is important! If you forget to tell the table view about your new items or if you tell the table view there are new items, but you don't actually add them to your data model, then your app will crash. The data model and the table view always have to be in sync.


> **Exercise:** Give the new items checkmarks by default.

Delete rows

While you're at it, you might as well give users the ability to delete rows.

A common way to do this in iOS apps is "swipe-to-delete". You swipe your finger over a row and a Delete button slides into view.

A tap on the Delete button confirms the removal, tapping anywhere else will cancel.



Swipe-to-delete in action

Swipe-to-delete

Swipe-to-delete is very easy to implement.

➤ Add the following method to **ChecklistViewController.swift**. Just to keep things organized, I suggest you put this with the other table view delegate methods.

```
override func tableView(
  _ tableView: UITableView,
  commit editingStyle: UITableViewCell.EditingStyle,
  forRowAt indexPath: IndexPath
) {
  // 1
  items.remove(at: indexPath.row)

  // 2
  let indexPaths = [indexPath]
  tableView.deleteRows(at: indexPaths, with: .automatic)
}
```

When the `commitEditingStyle` method is present in your view controller — it is a method defined by the table view data source protocol —, the table view will automatically enable swipe-to-delete.

All you have to do is:

1. Remove the item from the data model.
2. Delete the corresponding row from the table view.

This mirrors what you did in `addItem()`. Again, you make a temporary array with the index-path object and then tell the table view to remove the rows with an animation.

➤ Run the app to try it out!

★ ★ ★

Destroying objects

When you call `items.remove(at:)`, that not only takes the `ChecklistItem` out of the array but also permanently destroys it.

We'll talk more about this later on, but if there are no more references to an object, it is automatically destroyed. As long as a `ChecklistItem` object sits inside an array, that array has a reference to it.

But when you pull that `ChecklistItem` out of the array, the reference goes away and the object is destroyed. Or in computer-speak, it is *deallocated*.


What does it mean for an object to be destroyed? Each object occupies a small section of the computer's memory. When you create an object instance, a chunk of memory is reserved to hold the object's data. If the object is deallocated, that memory becomes available again and will eventually be occupied by new objects. After it has been deleted, the object does not exist in memory any more and you can no longer use it.

On older versions of iOS, you had to take care of this memory management by hand. Fortunately times have changed for the better. Swift uses a mechanism called **A**utomatic **R**eference **C**ounting, or ARC, to manage the lifetime of the objects in your app, freeing you from having to worry about it. I like not having to worry about things!

★ ★ ★

The Add Item screen

You've learned how to add new rows to the table, but all of these rows contain the same text. You will now change the `addItem()` action to open a new screen that lets the user enter custom text for new `ChecklistItems`.




The Add Item screen

Add a new view controller to the storyboard

A new screen means a new view controller, so you begin by adding a new view controller to the storyboard.


➤ Go to the Objects Library and drag a new **Table View Controller** (not a regular view controller) on to the storyboard canvas.



Dragging a new Table View Controller into the canvas


You may need to zoom out to fit everything properly. Right-click on the canvas to get a popup with zoom options, or use the **-** **100%** **+** controls at the bottom of the Interface Builder canvas. Or, if you have a Trackpad, simply pinch with two fingers to zoom in or out.

➤ With the new view controller in place, select the **Add button** from the Checklist View Controller. **Control-drag** to the new view controller.



Control-drag from the Add button to the new table view controller

Let go of the mouse and a list of options pops up.




The Action Segue popup

The options in this menu are the different types of connections you can make between the Add button and the new screen.

➤ Choose **Show** from the menu.

As I mentioned when adding the About screen for *Bull's Eye*, this type of connection is named a segue.


The segue is represented by the arrow between the two view controllers:



A new segue is added between the two view controllers

➤ Run the app to see what it does.

When you press the Add button, a new empty table view slides in from the right. You can press the back button — the one that says "Checklists" —, to go back to the previous screen.




The screen that shows up after you press the Add button

You didn't even have to write much code and you now have yourself a working navigation controller where you can go from one screen to another!

> **Note:** Xcode may be giving you the warning, "Prototype table cells must have reuse identifiers". You might remember this issue from before — you will fix this issue soon.

Note that the Add button no longer adds a new row to the table. That connection has been broken and is replaced by the segue. Just in case, you should remove the button's connection with the `addItem` action.

➤ Select the Add button, go to the **Connections inspector** and press **X** next to `addItem`.



Removing the addItem action from the Add button

Notice that this inspector also shows the connection with the segue that you've just made (under **Triggered Segues**).

★ ★ ★

Segue Types

When showing the new view controller above, you opted for a Show segue. But what does it mean? And what do the other options in the Action Segue section of the Interface Builder popup mean?

Here is a brief explanation of each type of segue:

- **Show:** Pushes the new view controller onto the navigation stack so that the new view controller is at the top of the navigation stack. It also provides a back button to return to the previous view controller. If the view controllers are not embedded in a navigation controller, then the new view controller will be presented modally — see *Present Modally* in the list below as to what this means.

  Example: Navigating folders in the *Mail* app

- **Show Detail:** For use in a split view controller — you'll learn more about those when developing the last app in this book. The new view controller replaces the detail view controller of the split view when in an expanded two-column interface. Otherwise, if in single-column mode, it will push in a navigation controller.

  Example: In *Messages*, tapping a conversation will show the conversation details — replacing the view controller on the right when in a two-column layout, or push the conversation when in a single column layout

- **Present Modally:** Presents the new view controller to cover the previous view controller — most commonly used to present a view controller that covers the entire screen on iPhone, or on iPad it's common to present it as a centered box that darkens the presenting view controller. Usually, if you had a navigation bar at the top or a tab bar at the bottom, those are covered by the modal view controller too.

  Example: Selecting Touch ID & Passcode in *Settings*

- **Present as Popover:** When run on an iPad, the new view controller appears in a popover, and tapping anywhere outside of this popover will dismiss it. On an iPhone, will present the new view controller modally over the full screen.

  Example: Tapping the + button in *Calendar*

- **Custom:** Allows you to implement your own custom segue and have control over its behavior. You will learn more about this in a later chapter.




Customize the navigation bar

So now you have a new table view controller that slides into the screen when you press the Add button. However, this is not quite what you want.

Data input screens usually have a navigation bar with a Cancel button on the left and a Done button on the right — in some apps, the button on the right is called Save or Send. Pressing either of these buttons will close the screen, but only Done will save your changes.

If you check the Document Outline, you will notice that the new table view controller scene has a Navigation Item — if it doesn't, then drag one from the Object Library on to the new scene since we are not able to customize the navigation elements — such as the navigation buttons, or the title — for this table view controller, without the Navigation Item.

➤ Drag two **Bar Button Items** on to the navigation bar of the new scene, one to the left slot (removing the existing back button) and one to the right slot.



The navigation bar items for the new screen

➤ In the **Attributes inspector** for the left button choose **System Item**: **Cancel**.

➤ For the right button choose **Done** for both **System Item** and **Style** attributes.

Don't type anything into the button's Title field. The Cancel and Done buttons are built-in button types that automatically use the proper text. If your app runs on an iPhone where the language is set to something other than English, these predefined buttons are automatically translated into the correct language.

➤ Double-click the navigation bar for the new table view controller to edit its title and change it to **Add Item** — you can also change this via the Attributes inspector as you did before.

➤ Run the app, tap the Add button on the main screen, and you'll see that your new screen has Cancel and Done buttons.



The Cancel and Done buttons in the app

The new buttons look good, but — as you would have noticed from the storyboard if you had enabled large titles from the storyboard — the title is huge! If Apple recommends using large titles only on main screens, we probably should change this screen to have smaller titles. But how do we do that?

While some view controller (or table view controller) customizations can be done via storyboard (and this one can too), some require writing some code. Our new view controller does not have a matching source file. So, in the next section we'll create the source file and add the custom code instead of doing the changes via storyboard just so you know how to do it via code.

> **Note:** If you'd prefer to make the change via storyboard, then simply select the Navigation Item for the new view controller, go to the **Attributes inspector** and select **Never** from the **Large Title** dropdown.

Make your own view controller class

You created a custom view controller in *Bull's Eye* for the About screen. Do you remember how to do it on your own? If not, here are the steps:

➤ In the Project Navigator, right-click on the Checklists group (the grey folder) in the project navigator and choose **New File...** Choose the **Cocoa Touch Class** template.

➤ In the next dialog, set the Class to **AddItemViewController** and Subclass to **UITableViewController**. When you change the subclass, the class name will automatically change — so either set the subclass first or change the class name back after the change. Leave the language at **Swift** (or change it if it is not set to Swift).

➤ Save the file to your project folder, which should be the default location.

➤ The file should have a lot of source and commented code — this is known as *boilerplate code*, or code that is generally always needed. In this particular case, you don't need most of it. So remove everything except for `viewDidLoad` (and remove the comments from inside `viewDidLoad` as well) so that your code looks like this:


```
import UIKit

class AddItemViewController: UITableViewController {
  override func viewDidLoad() {
    super.viewDidLoad()
  }
}
```

This tells Swift that you have a new object for a table view controller that goes by the name of `AddItemViewController`. You'll add the rest of the code soon. First, you have to let the storyboard know about this new view controller.

➤ In the storyboard, select the Add Item view controller and go to the **Identity inspector**. Under **Custom Class**, type **AddItemViewController**.

This tells the storyboard that the view controller from this scene is actually your new `AddItemViewController` object.



Changing the class name of the AddItemViewController

Don't forget this step! Without it, the Add Item screen will simply not work.

Make sure that it is really the view controller that is selected before you change the fields in the Identity inspector (the scene needs to have a blue border). A common mistake is to select the table view and change that.


Turn off large titles

Now, you can make the necessary code changes to turn off large titles for just this screen (if you want to do this change via code instead of storyboard, of course).

➤ Add the following line to the end of `viewDidLoad` in **AddItemViewController.swift**:

```
navigationItem.largeTitleDisplayMode = .never
```

The above code customizes the Navigation Item for the Add Item screen to never show large titles. Try running the app now.



Large titles begone!

Make the navigation buttons work

Much better, right? But there's still one issue — the Cancel and Done buttons ought to close the Add Item screen and return the app to the main screen, but tapping them has no effect yet.

> **Exercise:** Do you know why the Cancel and Done buttons do not return you to the main screen?

Answer: Because those buttons have not yet been hooked up to any actions!

You will now implement the necessary action methods in **AddItemViewController.swift**.

➤ Add these new `cancel()` and `done()` action methods:


```
// MARK: - Actions
@IBAction func cancel() {
  navigationController?.popViewController(animated: true)
}

@IBAction func done() {
  navigationController?.popViewController(animated: true)
}
```

This tells the navigation controller to close the Add Item screen with an animation and to go back to the previous screen, which in this case is the main screen.

You still need to hook up the Cancel button to the `cancel()` action and the Done button to the `done()` action.

➤ Open the storyboard and find the Add Item View Controller. **Control-drag** from the bar buttons to the yellow circle icon and pick the proper action from the popup menu.



Control-dragging from the bar button to the view controller

➤ Run the app to try it out. The Cancel and Done buttons now return the app to the main screen.

What do you think happens to the `AddItemViewController` object when you dismiss it? After the view controller disappears from the screen, its object is destroyed and the memory it was using is reclaimed by the system.

Every time the user opens the Add Item screen, the app makes a new instance of it. This means a view controller object is only alive for the duration that the user is interacting with it; there is no point in keeping it around afterwards.

★ ★ ★

Container view controllers

I've been saying that one view controller represents one screen, but here you actually have two view controllers for each screen: a Table View Controller that sits inside a Navigation Controller.

The Navigation Controller is a special type of view controller that acts as a container for other view controllers. It comes with a navigation bar and has the ability to easily go from one screen to another, by sliding them in and out of sight. The container essentially "wraps around" these screens.

The Navigation Controller is just the frame that contains the view controllers that do the real work, which are known as the "content" controllers. Here, the `ChecklistViewController` provides the content for the first screen; the content for the second screen comes from the `AddItemViewController`.

Another often-used container is the Tab Bar Controller, which you'll see in the next app.

On the iPad, container view controllers are even more commonplace. View controllers on the iPhone are full-screen but on the iPad they often occupy only a portion of the screen, such as the content of a popover or one of the panes in a split-view.

★ ★ ★


This completes the implementation of the navigation functionality for your app's two screens. If at any point you got stuck, you can refer to the project files for the app from the **11-Navigation-controllers** folder in the Source Code folder.

Chapter 12: Add Item Screen

By Fahim Farook

Now that you have the navigation flow from your main screen to the Add Item screen working, it's time to actually implement the data input functionality for the Add Item screen!

Let's change the look of the Add Item screen. Currently it is an empty table with a navigation bar on top, but I want it to look like this:



What the Add Item screen will look like when you're done

This chapter covers the following:

- **Static table cells:** Add a static table view cell to the table to display the text field for data entry.
- **Read from the text field:** Access the contents of the text field.
- **Polish it up:** Improve the look and functionality of the Add Item screen.


Static table cells

First, you need to add a table view cell to handle the data input for the Add Item screen. As is generally the case with UI changes, you start with the storyboard.

Storyboard changes

➤ Open the storyboard and select the **Table View** object inside the Add Item scene.

➤ In the **Attributes inspector**, change the **Content** setting from Dynamic Prototypes to **Static Cells**.




Changing the table view to static cells

You use static cells when you know beforehand how many sections and rows the table view will have. This is handy for screens that require the user to enter data, such as the one you're building here.

With static cells, you can design the rows directly in the storyboard. For a table with static cells you don't need to provide a data source, and you can hook up the labels and other controls from the cells directly to outlets on the view controller.


As you'll see in the Document Outline, the table view now has a Table View Section object under it, and three Table View Cells in that section — you may need to expand the Table View item first by clicking the disclosure triangle.



The table view has a section with three static cells

➤ Select the bottom two cells and delete them by pressing the **delete** key on your keyboard. You only need one cell for now.

➤ Select the Table View again and in the **Attributes inspector** set its **Style** to **Grouped**. That gives us the look we want.




The table view with grouped style

Next up, you'll add a text field component inside the table view cell that lets the user type text.

➤ Drag a **Text Field** object into the cell and size it up nicely. You might want to add left, top, right, and bottom Auto Layout constraints to the text field if you don't want any Xcode warnings. You know how to do that on your own, right? (Hint: use the Add New Constraints button at the bottom of the Interface Builder screen after you've sized/positioned the field as you want.)


➤ In the **Attributes inspector** for the text field, set the **Border Style** to **no border** (select the dotted box):



Adding a text field to the table view cell

➤ Run the app and press the + button to open the Add Item screen. Tap on the cell and you'll see the keyboard slide in from the bottom of the screen.

Any time you make a text field active, the keyboard automatically appears. You can type into the text field by tapping on the letters. On the Simulator, you can also type using your Mac's keyboard.




You can now type text into the table view cell

Note: If the keyboard does not appear in the Simulator, press ⌘K or use the **I/O ▸ Keyboard ▸ Toggle Software Keyboard** menu option. You can also use your normal Mac keyboard to type into the text field, even if the on-screen keyboard is not visible. If that doesn't work, also select **I/O ▸ Keyboard ▸ Connect Hardware Keyboard** from the menu.

Disable cell selection

Look what happens when you tap just outside the text field's area, but still in the cell (try tapping in the margins that surround the text field):



Whoops, that looks a little weird

The row turns gray because you selected it. Oops, that's not what you want — you should disable selections for this row. You can do this easily via code by adding the following table view delegate method to **AddItemViewController.swift**:

```
// MARK: - Table View Delegates
override func tableView(
  _ tableView: UITableView,
  willSelectRowAt indexPath: IndexPath
) -> IndexPath? {
  return nil
}
```

When the user taps on a cell, the table view sends the delegate a `willSelectRowAt` message that says: "Hi delegate, I am about to select this particular row."


By returning the special value `nil`, the delegate answers: "Sorry, but you're not allowed to!"

★ ★ ★

Return to sender

You've seen the `return` statement a few times now. You use `return` to send a value from a method back to the method that called it.

Let's take a more detailed look at what happens.



Methods call other methods and receive values in return.

You cannot just return any value. The value you return must be of the data type that is specified after the –> arrow that follows the method name.

For example, `tableView(_:numberOfRowsInSection:)` must return an `Int` value:

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return 1
}
```

If instead your code was like this:

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return "1"
}
```

Then, the compiler would give an error message, as `"1"` is a string, not an `Int`. To a human reader they look similar and you can easily understand the intent, but Swift isn't that tolerant. Data types have to match or they just aren't allowed.

Your most recent version of this method looks like this:

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return items.count
}
```

That is also a valid return statement because `items` is an `Array` and the `count` property from `Array` is also of the type `Int`.

The `tableView(_:cellForRowAt:)` method is supposed to return a `UITableViewCell` object:

```
override func tableView(
  _tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "TheCellIdentifier",
    for: indexPath)
  . . .
  return cell
}
```

The local constant `cell` contains a `UITableViewCell` object, so it's OK to return the value of `cell` from the method.

The `tableView(_:willSelectRowAt:)` method is supposed to return an `IndexPath` object. However, you can also make it return `nil`, indicating no value/object.

```
override func tableView(
  _ tableView: UITableView,
  willSelectRowAt indexPath: IndexPath
) -> IndexPath? {
  return nil
}
```

That's what the `?` behind `IndexPath` is for: The question mark tells the Swift compiler that you can also return `nil` from this method. Note that returning `nil` from a method is only allowed if there is a question mark (or exclamation point) behind the return type. A type declaration with a question mark behind it is known as an *optional* — you'll learn more about optionals in the next chapter.

The special value `nil` represents "no value" but it's used to mean different things throughout the iOS SDK. Sometimes it means "nothing found" or "don't do anything". Here it means that the row should not be selected when the user taps it.

How do you know what `nil` means for a certain method? You can find that in the documentation of the method in question.

In the case of `willSelectRowAt`, the iOS documentation says:

> Return Value: An index-path object that confirms or alters the selected row. Return an IndexPath object other than indexPath if you want another cell to be selected. Return nil if you don't want the row selected.

This means you can either:

1. Return the same index-path you were given. This confirms that this row can be selected.
2. Return another index-path in order to select a different row.
3. Return `nil` to prevent the row from being selected, which is what you did.

So remember, you need to use the `return` statement to exit a method that expects to return something. If you forget, then Xcode will give the following error: "Missing return in a function expected to return <data type>".

You've also seen methods that do not return anything:

```
@IBAction func addItem()
```

and:

```
func configureCheckmark(for cell: UITableViewCell, with item:
ChecklistItem)
```

These methods do not have an arrow (–>) indicating a return value. Such a method does not pass a value back to the caller and therefore does not need a `return` statement. You can still use `return` to exit from such methods, but the `return` statement should not be followed by a value.

Strictly speaking, even methods without a return type *do* return a value, an *empty tuple*. Think of this as a special object that embodies the concept of "nothing" — don't confuse this with *nil*, which is an actual value.

You sometimes see this written as:

```
func methodThatDoesNotReturnValue() -> ()

func anotherMethodThatDoesNotReturnValue() -> Void
```

The notation for an empty tuple is `()`, so in this context the parentheses mean there is no return value. The term `Void` is a synonym for `()`.

But really, if a method does not return anything it's just as easy to leave out the `->` arrow. Also note that `@IBAction` methods never return a value — this is a rule.

★ ★ ★

While it's already impossible to select the row, as you've just told the table view you won't allow it, there is one more thing you need to do to prevent the row from going gray. In fact, most of the time, this second change is enough to not show cell selection, even without the code change above. Table view cells have a selection color property. Even if you make it impossible for a row to be selected, sometimes UIKit still briefly draws the cell gray when you tap it. Therefore, it is best to also disable this selection color.

➤ In the storyboard, select the table view cell and go to the **Attributes inspector**. Set the **Selection** attribute to **None**. Now if you run the app, it is impossible to select the row and make it turn gray. Try and prove me wrong! :]

Read from the text field

You have a text field in a table view cell that the user can type into, but how do you read the text that the user has typed?


Add an outlet for the text field

When the user taps Done, you need to get that text and somehow put it into a new `ChecklistItem` and add it to the list of to-do items. This means the `done()` action needs to be able to refer to the text field.

You already know how to refer to controls from within your view controller: use an outlet. When you added outlets for the previous app, I told you to type in the `@IBOutlet` declaration in the source file and make the connection in the storyboard.

I'm going to show you a trick now that will save you some typing. You can let Interface Builder do all of this automatically by Control-dragging from the control in question directly into your source code file!

➤ First, go to the storyboard and select the **Add Item View Controller**. Then open the **Assistant** editor using the **Adjust Editor Options** toolbar button.




Click the toolbar button to open the Assistant editor

This may make the screen a little crowded – there might now be up to five horizontal panels open. If you're running out of space, you might want to close the Project navigator, the Utilities pane, and/or the Document Outline using the relevant toolbar buttons.

The Assistant editor opens a new pane on the right of the screen by default — it might give you horizontal split views instead, if you have changed your default view settings.

In the Jump Bar (the bar below the toolbar) it should say **Automatic** and the Assistant editor should be displaying the **AddItemViewController.swift** file:




The Assistant editor

"Automatic" means the Assistant editor tries to figure out what other file is related to the one you're currently editing. When you're editing a storyboard, the related file is generally the selected view controller's Swift file.


Sometimes Xcode can be a little dodgy here. If it shows you something other than **AddItemViewController.swift**, then click in the Jump Bar and manually select the correct file.

➤ With the storyboard and the Swift file side by side, select the text field. Then **Control-drag** from the text field into the Swift file.



Control-dragging from the text field into the Swift file

When you let go, a popup appears:



The popup that lets you add a new outlet

➤ Choose the following options:

- Connection: Outlet
- Name: **textField**
- Type: UITextField
- Storage: Weak

> **Note:** If "Type" does not say UITextField, but instead says UITableViewCell or UIView, then you selected the wrong component on Interface Builder.
>
> Make sure you're Control-dragging from the text field inside the cell, not the cell itself. Granted, it's kinda hard to see, being white on white. If you're having trouble selecting the text field, click that area several times in succession.
>
> You can also Control-drag from "No Border Style Text Field" in the Document Outline.

➤ Press **Connect** and voila, Xcode automatically inserts an `@IBOutlet` for you and connects it to the text field object.

The new code looks like this:

```
@IBOutlet weak var textField: UITextField!
```

Just by dragging you have successfully hooked up the text field object with a new property named `textField`. How easy was that?

Read the contents of the text field

Now you'll modify the `done()` action to write the contents of this text field to the Xcode Console, the pane at the bottom of the screen where `print()` messages show up. This is a quick way to verify that you can access what the user typed.

➤ In **AddItemViewController.swift**, change `done()` to:

```
@IBAction func done() {
  // Add the following line
  print("Contents of the text field: \(textField.text!)")

  navigationController?.popViewController(animated: true)
}
```

You can make these changes directly inside the Assistant editor. It's very handy that you can edit the source code and the storyboard side-by-side.

➤ Run the app, press the + button and type something in the text field. When you press Done, the Add Item screen should close and Xcode should reveal the Debug pane with a message like this:

```
Contents of the text field: Hello, world!
```

Great, so that works! `print()` should be an old friend by now. It's one of my faithful debugging companions :]

Recall that you can print the value of a variable by placing it inside `\(` and `)` in a string. Here you used `\(textField.text!)` to print out the contents of the text field's `text` property — I'll explain what the exclamation point is for later.

> **Note:** Because the iOS Simulator already outputs a lot of debug messages of its own, it may be a bit hard to find your `print()` messages in the Console. Luckily there is a Filter box at the bottom that lets you search for your own messages — just type in what you're looking for into the filter box.

Polish it up

Before you write the code to take the text and insert it as a new item into the items list, let's improve the design and workings of the Add Item screen a little.

Give the text field focus on screen opening

For instance, it would be nice if you didn't have to tap on the text field in order to bring up the keyboard. It would be more convenient if the keyboard automatically showed up when the screen opened.

➤ To accomplish this, add a new method to **AddItemViewController.swift**.

```
override func viewWillAppear(_ animated: Bool) {
  super.viewWillAppear(animated)
  textField.becomeFirstResponder()
}
```

The view controller receives the `viewWillAppear()` message just before it becomes visible. That is a perfect time to make the text field active. You do this by sending it the `becomeFirstResponder()` message.

If you've done programming on other platforms, this is often called "giving the control focus". In iOS terminology, the control becomes the *first responder*.

➤ Run the app and go to the Add Item screen; you can start typing right away.

Again, note that the keyboard may not appear on the Simulator. Press **⌘+K** to bring it up. The keyboard will always appear when you run the app on an actual device, though.


It's often little features like these that make an app a joy to use. Having to tap on the text field before you can start typing gets old really fast. In this fast-paced age, using their mobiles on the go, users don't have the patience for that. Such minor annoyances may be reason enough for users to switch to a competitor's app. I always put a lot of effort into making my apps as frictionless as possible.

Style the text field

With that in mind, let's style the input field a bit.

➤ Open the storyboard and select the text field. Go to the **Attributes inspector** and set the following attributes:

- Font: System 17
- Placeholder: **Name of the Item**
- Adjust to Fit: Uncheck this
- Capitalization: Sentences
- Return Key: Done



The text field attributes

There are several options here that let you configure the keyboard that appears when the text field becomes active.


If this were a field that only allowed numbers, for example, you would set the Keyboard Type to Number Pad. If it were an email address field, you'd set it to E-mail Address. For our purposes, the Default keyboard is appropriate.

You can also change the text that is displayed on the keyboard's Return Key. By default it says "return" but you set it to "Done". This is just the text on the button; it doesn't automatically close the screen. You still have to make the keyboard's Done button trigger the same action as the Done button from the navigation bar.

Handle the keyboard Done button

➤ Make sure the text field is selected and open the **Connections inspector**. Drag from the **Did End on Exit** event to the view controller and pick the **done** action.

If you still have the assistant editor open, you can also drag directly to the source code for the `done()` method.



Connecting the text field to the done() action method

To see the connections for the done action, click on the circle in the gutter next to the method name. The popup shows that done() is now connected to both the bar button and the text field:



Viewing the connections for the done() method

➤ Run the app. Pressing Done on the keyboard will now close the screen and print the text to the debug area.

Disallow empty input


Now that you have user input working, It's always good to validate what the user entered to make sure that the input is acceptable. For instance, what should happen if the user immediately taps the Done button on the Add Item screen without entering any text?

Adding a to-do item to the list that has no description text is not very useful. So, in order to prevent this, you should disable the Done button when no text has been typed yet.

Of course, you have two Done buttons to take care of, one on the keyboard, and one in the navigation bar. Let's start with the Done button from the keyboard as this is the simplest one to fix.

➤ On the **Attributes inspector** for the text field, check **Auto-enable Return Key**.

That's it. Now when you run the app, the Done button on the keyboard is disabled when there is no text in the text field. Try it out!



The Auto-enable Return Key option disables the return key when there is no text

For the Done button in the navigation bar, you have to do a little more work. You have to check the contents of the text field after every keystroke to see if it is now empty or not. If it is, then you disable the button.

The user can always press Cancel, but Done only works when there is text.

In order to listen to changes to the text field – which may come from taps on the keyboard but also from cut/paste – you need to make the view controller a delegate for the text field.

The text field will send events to its delegate to let it know what is going on. The delegate, which will be the `AddItemViewController`, can then respond to these events and take appropriate actions.

A view controller is allowed to be the delegate for more than one object. The `AddItemViewController` is already a delegate (and data source) for the `UITableView` — because it is a `UITableViewController`. Now it will also become the delegate for the text field object, `UITextField`.

These are two different delegates and you make the view controller play both roles. Later on you'll add even more delegates for this app.

How to become a delegate

Delegates are used everywhere in the iOS SDK, so it's good to remember that it always takes three steps to become a delegate.

1. You declare yourself capable of being a delegate. To become the delegate for `UITextField` you need to include `UITextFieldDelegate` in the `class` line for the view controller. This tells the compiler that this particular view controller can actually handle the notification messages that the text field sends to it.
2. You let the object in question, in this case the `UITextField`, know that the view controller wishes to become its delegate. If you forget to tell the text field that it has a delegate, it will never send you any notifications.
3. Implement the delegate methods. It makes no sense to become a delegate if you're not responding to the messages you're being sent!

Often, delegate methods are optional, so you don't need to implement all of them. For example, `UITextFieldDelegate` actually declares seven different methods but you only care about `textField(_:shouldChangeCharactersIn:replacementString:)` for this app.

➤ In **AddItemViewController.swift**, add `UITextFieldDelegate` to the class declaration:


```
class AddItemViewController: UITableViewController,
UITextFieldDelegate {
```

The view controller now says, "I can be a delegate for text field objects."

You also have to let the text field know that you have a delegate for it.

➤ Go to the storyboard and select the text field.

There are several different ways in which you can hook up the text field's delegate outlet to the view controller. I prefer to go to its **Connections inspector** and drag from **delegate** to the view controller's little yellow icon:



Drag from the Connections inspector to connect the text field delegate

Configure the Done button

You also have to add an outlet for the Done bar button item, so you can send it messages from within the view controller in order to enable or disable it.

➤ Open the **Assistant editor** and make sure **AddItemViewController.swift** is visible in the assistant pane.

➤ **Control-drag** from the Done bar button into the Swift file and let go. Name the new outlet `doneBarButton`.

This adds the following outlet:

```
@IBOutlet weak var doneBarButton: UIBarButtonItem!
```

➤ Add the following to **AddItemViewController.swift**, at the bottom (before the final curly brace):

```
// MARK: - Text Field Delegates
func textField(
  _ textField: UITextField,
  shouldChangeCharactersIn range: NSRange,
  replacementString string: String
) -> Bool {
  let oldText = textField.text!
  let stringRange = Range(range, in: oldText)!
  let newText = oldText.replacingCharacters(
    in: stringRange,
    with: string)
  if newText.isEmpty {
    doneBarButton.isEnabled = false
  } else {
    doneBarButton.isEnabled = true
  }
  return true
}
```

This is one of the `UITextField` delegate methods. It is invoked every time the user changes the text, whether by tapping on the keyboard or via cut/paste.

First, you figure out what the new text will be:

```
let oldText = textField.text!
let stringRange = Range(range, in:oldText)!
let newText = oldText.replacingCharacters(
  in: stringRange,
  with: string)
```

The `textField(_:shouldChangeCharactersIn:replacementString:)` delegate method doesn't give you the new text, only which part of the text should be replaced — the range — and the text it should be replaced with — the replacement string.

You need to calculate what the new text will be by taking the text field's text and doing the replacement yourself. This gives you a new string object that you store in the `newText` constant.

NSRange vs. Range and NSString vs. String

In the above code, you get a parameter as `NSRange` and you convert it to a `Range` value. If you're wondering what a range is, the clue is in the name :] A range object gives you a range of values, or in this case, a range of characters — with a lower bound and an upper bound.

So, why did we convert the original `NSRange` value to a `Range` value, you ask? `NSRange` is an Objective-C structure whereas `Range` is its Swift equivalent — they are similar, but not exactly the same. So, while an `NSRange` parameter is used by the `UITextField` (which internally, and historically, is Objective-C based) in its delegate method, in our Swift code, if we wanted to do any String operations, such as `replacingCharacters`, then we need a `Range` value instead. Swift methods generally use `Range` values and do not understand `NSRange` values, which is why we converted the `NSRange` value to a Swift-understandable `Range` value.

There was a different way to approach this problem as well — though it might not be as "Swift-y" :] We could have converted the Swift `String` value into its Objective-C equivalent — `NSString`. `String` and `NSString` are "bridged", meaning that you can use `NSString` in place of `String`. And `NSString` too has a `replacingCharacters(in:with:)` method, and that method takes an `NSRange` as a parameter!

So, you could have simply converted the `String` value to an `NSString` value and then used the `NSString` `replacingCharacters(in:with:)` method with the passed in range value instead of the above code.

But personally, I prefer to use Swift types and classes in my code as much as possible. So, I opted to go with the solution above :]

By the way, `String` isn't the only object that is bridged to an Objective-C type. Another example is `Array` and its Objective-C counterpart `NSArray`. Because the iOS frameworks are written in a different language than Swift, sometimes these little Objective-C holdovers pop up when you least expect them.

Once you have the new text, you check if it's empty, and enable or disable the Done button accordingly:

```
if newText.isEmpty {
  doneBarButton.isEnabled = false
} else {
  doneBarButton.isEnabled = true
}
```

However, you could simplify the above code even further. Since `newText.isEmpty` returns a `true` or `false` value, you can discard the `if` condition and use the value returned by `newText.isEmpty` to decide whether the Done button should be enabled or not.

```
doneBarButton.isEnabled = !newText.isEmpty
```

Basically, if the text is not empty, enable the button. Otherwise, don't enable it. That's much more compact, and concise, right?

Remember this trick – whenever you see code like this,

```
if some condition {
  something = true
} else {
  something = false
}
```

you can write it simply as:

```
something = (some condition)
```

In practice it doesn't really matter which version you use. I prefer the shorter one; that's what the pros do. Just remember that comparison operators such as == and > always return `true` or `false`, so the extra `if` really isn't necessary.


➤ Run the app and type some text into the text field. Now remove that text and you'll see that the Done button in the navigation bar properly gets disabled when the text field becomes empty.

Fixing issues

One problem: The Done button is initially enabled when the Add Item screen opens, but there is no text in the text field at that point. So, it really should be disabled. This is simple enough to fix.

➤ In the storyboard, select the **Done** bar button and go to the **Attributes inspector**. Uncheck the **Enabled** box.


The Done button is now properly disabled when you first enter the Add Item screen:



The Done button is not enabled if there is no text

There's one other possible issue here. You won't see the issue unless you enable the Clear Button though. I hear you ask "What's the Clear Button?".

Select the text field in the Add Item scene in the storyboard and take a look at the Attributes inspector. You will note that there's a setting named **Clear Button**. This enables a handy button in text fields which allows you to clear text.



The Clear Button

The Clear Button is set to "Never appears" by default, but you can set it to "Appears while editing" to give your users a quick and easy way to clear text. This can be a very user-friendly feature.

Unfortunately, if you enable this option and clear your text while you're in the Add Item screen, the Done button will not get disabled. This is because the Clear Button does not call the `textField(_:shouldChangeCharactersIn:replacementString:)` delegate method. Instead, the Clear Button calls a different delegate method — `textFieldShouldClear(_:)` method.

So, if you want to handle the Clear button correctly and disable the Done button, then you'd have to add the following delegate method to **AddItemViewController.swift**:


```
func textFieldShouldClear(_ textField: UITextField) -> Bool {
  doneBarButton.isEnabled = false
  return true
}
```

★ ★ ★

Using FileMerge to compare files


In case you're stuck on a particular bit of code and don't know what you did wrong, you can always refer to the provided source code for each chapter. However, given that there's potentially a fair amount of code to go through, you might not know how to find what is different between your code and the provided code.

You can compare your own work with my version of the app using the FileMerge tool. Open this tool from the Xcode menu bar, under **Xcode ▸ Open Developer Tool ▸ FileMerge**:




Open FileMerge


You give FileMerge two files or folders to compare:



After working hard for a few seconds or so, FileMerge tells you what is different:



Double-click on a filename from the list to view the differences between the two files:



FileMerge is a wonderful tool for spotting the differences between two files or even entire folders. I use it all the time!

If something from the book doesn't work as it should, then do a "diff" — that's what the difference between two source files is called — between your own files and the ones from the Source Code folder to see if you can find any anomalies.

★ ★ ★

You can find the project files for the app up to this point under **12-Add-item-screen** in the Source Code folder.

Chapter 13: Delegates & Protocols

By Fahim Farook

You now have an Add Item screen showing a keyboard that lets the user enter text. The app also properly validates the input so that you'll never end up with text that is empty.

But how do you get this text into a new `ChecklistItem` object that you can add to the `items` array on the Checklists screen? That is the topic that this chapter will explore.

Add new ChecklistItems

In order for a new item addition to work, you'll have to get the Add Item screen to notify the Checklist View Controller of the new item addition. This is one of the fundamental tasks that every iOS app needs to do: sending messages from one view controller to another.



Sending a ChecklistItem object to the screen with the items array

The messy way

> **Exercise:** How would you tackle this problem? The `done()` method needs to create a new `ChecklistItem` object with the text from the text field (easy), then add it to the `items` array and the table view in `ChecklistViewController` (not so easy).

Maybe you came up with something like this:

```
class AddItemViewController: UITableViewController, . . . {

  // This variable refers to the other view controller
  var checklistViewController: ChecklistViewController


  @IBAction func done() {
    // Create the new checklist item object
    let item = ChecklistItem()
    item.text = textField.text!

    // Directly call a method from ChecklistViewController
    checklistViewController.add(item)
  }
}
```

In this scenario, `AddItemViewController` has a variable that refers to the `ChecklistViewController`, and `done()` calls its `add()` method with the new `ChecklistItem` object.

This will work, but it's not the iOS way. The big downside to this approach is that it shackles these two view controller objects together.

As a general principle, if screen A launches screen B then you don't want screen B to know too much about the screen that invoked it (A). The less B knows of A, the better.



Screen A knows all about screen B, but B knows nothing of A

Giving `AddItemViewController` a direct reference to `ChecklistViewController` prevents you from opening the Add Item screen from somewhere else in the app. It can only ever talk back to `ChecklistViewController`. That's a big disadvantage.

You won't actually need to do this in *Checklists*, but in many apps it's common for one screen to be accessible from multiple places. For example, a login screen that appears after the user has been logged out due to inactivity. Or, a details screen that shows more information about a tapped item, no matter where that item is located in the app — you'll see an example of this in the next app.

Therefore, it's best if `AddItemViewController` doesn't know anything about `ChecklistViewController`.

But if that's the case, then how can you make the two communicate?

The solution is to make your own *delegate*.


The delegate way

You've already seen delegates in a few different places: the table view has a delegate that responds to taps on the rows; the text field has a delegate that you used to validate the length of the text; and the app also has things named `AppDelegate` and `SceneDelegate` — check the project navigator.

You can't turn a corner in this place without bumping into a delegate...

The delegate pattern is commonly used to handle the situation you find yourself in: Screen A opens screen B. At some point screen B needs to communicate back to screen A, usually when it closes.


The solution is to make screen A the delegate of screen B, so that B can send its messages to A whenever it needs to.



Screen A launches screen B and becomes its delegate

The cool thing about the delegate pattern is that screen B doesn't really know anything about screen A. It just knows that *some* object is its delegate, but doesn't really care who that is. Just like how `UITableView` doesn't really care about your view controller, only that it delivers table view cells when the table view asks for them.

This principle, where screen B is independent of screen A and yet can still talk to it, is called *loose coupling* and is considered good software design practice.



This is what Screen B sees: only the delegate part, not the rest of screen A

You will use the delegate pattern to let the `AddItemViewController` send notifications back to the `ChecklistViewController` without it having to know anything about the latter.

Delegates go hand-in-hand with *protocols*, a prominent feature of the Swift language.

The delegate protocol

➤ At the top of **AddItemViewController.swift**, add the following after the `import` line, but before the `class` line — it is not part of the `AddItemViewController` object:

```
protocol AddItemViewControllerDelegate: AnyObject {
  func addItemViewControllerDidCancel(
    _ controller: AddItemViewController)
  func addItemViewController(
    _ controller: AddItemViewController,
    didFinishAdding item: ChecklistItem
  )
}
```

This defines the `AddItemViewControllerDelegate` protocol. You should recognize the lines inside the `protocol { ... }` block as method declarations, but unlike the previous methods you've seen, these don't have any source code in them. The protocol just lists the names of the methods.

Think of the delegate protocol as a contract between screen B — in this case the Add Item View Controller — and any screens that wish to use it.

And if you're wondering why you have the keyword `AnyObject` after the colon in the protocol name, let me explain. You might have noticed that the syntax for the protocol declaration looks very similar to how you'd declared classes previously, giving the name of our class followed by a colon and then specifying the class our class inherited from.

This is exactly the same thing here with protocols, you can have one protocol inherit from another protocol. But you can also specify a particular type of object which can adopt your protocol. The `AnyObject` keyword identifies that we want the `AddItemViewControllerDelegate` protocol to be limited to all class types.

And if you ask me at this point, "Why is that?", I can give you a fairly long-winded explanation about why this is so, but it all boils down to the fact that we mark any references to this protocol as `weak` and in order to have weak references, we need a protocol which can only be used with a *reference type*.

We'll discuss `weak` references just a bit further along in this chapter and it might become a little bit more clearer at that point. :]

★ ★ ★

Protocols

In Swift, a *protocol* doesn't have anything to do with computer networks or meeting royalty. It is simply a name for a group of methods.

A protocol normally doesn't implement any of the methods it declares. It just says: any object that conforms to this protocol must implement methods X, Y and Z. There are special cases where you might want to provide a default implementation for a protocol, but that's an advanced topic that we don't need to get into right now :]

The two methods listed in the `AddItemViewControllerDelegate` protocol are:

- `addItemViewControllerDidCancel(_:)`
- `addItemViewController(_:didFinishAdding:)`

Delegates often have very long method names!

The first method is for when the user presses Cancel, the second is for when they press Done. In the latter case, the `didFinishAdding` parameter passes along the new `ChecklistItem` object.

To make the `ChecklistViewController` conform to this protocol, it must provide implementations for these two methods. From then on, you can refer to `ChecklistViewController` using the protocol name, instead of the class name.

If you've programmed in other languages before, you may recognize protocols as being very similar to "interfaces".

In `AddItemViewController`, you can use the following to refer back to `ChecklistViewController` — but don't add this line just yet:

```
var delegate: AddItemViewControllerDelegate
```

The variable `delegate` is nothing more than a reference to *some* object that implements the methods of the `AddItemViewControllerDelegate` protocol. You can send messages to the object referenced by the `delegate` variable without knowing what kind of object it really is.

Of course, *you* know the object referenced by `delegate` is the `ChecklistViewController`, but `AddItemViewController` doesn't need to be aware of that. All it sees is some object that implements its delegate protocol.

If you wanted to, you could make some other object implement the protocol and `AddItemViewController` would be perfectly OK with that. That's the power of delegation: you have removed – or *abstracted* away – the dependency between the `AddItemViewController` and the rest of the app.

It may seem a little overkill for a simple app such as this, but delegates are one of the cornerstones of iOS development. The sooner you master them, the better!



Notify the delegate

You're not done yet in **AddItemViewController.swift**. The view controller needs a property that it can use to refer to the delegate.

➤ Add this inside the `AddItemViewController` class, below the outlets:

```
weak var delegate: AddItemViewControllerDelegate?
```

It looks like a regular instance variable declaration, with two differences: `weak` and the question mark.

Delegates are usually declared as being *weak* – not a statement of their moral character but a way to describe the relationship between the view controller and its delegate. Delegates are also *optional* (the question mark — which you learnt a bit about in the previous chapter).

You'll learn more about those things in a moment.

➤ Replace the `cancel()` and `done()` actions with the following:

```
@IBAction func cancel() {
  delegate?.addItemViewControllerDidCancel(self)
}

@IBAction func done() {
  let item = ChecklistItem()
  item.text = textField.text!

  delegate?.addItemViewController(self, didFinishAdding: item)
}
```

Let's look at the changes you made. When the user taps the Cancel button, you send the `addItemViewControllerDidCancel(_:)` message back to the delegate.

You do something similar for the Done button, except that the message is `addItemViewController(_:didFinishAdding:)` and you pass along a new `ChecklistItem` object that has the text string from the text field.

> **Note:** It is customary for the delegate methods to have a reference to their owner as the first (or only) parameter.
>
> Doing this is not required, but still a good idea. For example, in the case of table views, it may happen that an object is the delegate or data source for more than one table view. In that case, you need to be able to distinguish between those table views. To allow for this, the table view delegate methods have a parameter for the `UITableView` object that sent the notification. Having this reference also saves you from having to make an `@IBOutlet` for the table view.
>
> That explains why you pass `self` to your delegate methods. Recall that `self` refers to the object itself, in this case `AddItemViewController`. It's also why all the delegate method names start with `addItemViewController`.

➤ Run the app and try the Cancel and Done buttons. They no longer work!

I hope you're not too surprised... The Add Item screen now depends on a delegate to make it close, but you haven't told the Add Item screen who its delegate is yet.

That means the `delegate` property has no value and the messages aren't being sent to anyone – there is no one listening for them.

★ ★ ★

Optionals

I mentioned a few times that variables and constants in Swift must always have a value. In other programming languages the special symbol `nil` or `NULL` is often used to indicate that a variable has no value. This is not allowed in Swift for normal variables.

The problem with `nil` and `NULL` is that they are a frequent cause of crashing apps. If an app attempts to use a variable that is `nil` when you don't expect it to be `nil`, the app will crash. This is the dreaded "null pointer dereference" error.

Swift stops this by preventing you from using `nil` with regular variables.

However, sometimes a variable does need to have "no value". In that case you can make it an *optional*. You mark something as optional in Swift using either a question mark `?` or an exclamation point `!`.

Only variables that are made optional can have the value `nil`.

You've already seen the question mark used with `IndexPath?`, the return type of `tableView(_:willSelectRowAt:)`. Returning `nil` from this method is a valid response; it means that the table should not select a particular row.

The question mark tells Swift that it's OK for the method to return `nil` instead of an actual `IndexPath` object.

Variables that refer to a delegate are usually marked as optional too. You can tell because there is a question mark behind the type:

```
weak var delegate: AddItemViewControllerDelegate?
```

Thanks to the `?` it's perfectly acceptable for a delegate to be `nil`.

You may be wondering why the delegate would ever be `nil`. Doesn't that negate the idea of having a delegate in the first place? There are two reasons.

Often, delegates are truly optional; a `UITableView` works fine even if you don't implement any of its delegate methods (but you do need to provide at least some of its data source methods).

More importantly, when `AddItemViewController` is loaded from the storyboard and instantiated, it won't know right away who its delegate is. Between the time the view controller is loaded and the delegate is assigned, the `delegate` variable will be `nil`. And variables that can be `nil`, even if it is only temporary, must be optionals.

When `delegate` is `nil`, you don't want `cancel()` or `done()` to send any of the messages. Doing that would crash the app because there is no one to receive the messages.

Swift has a handy shorthand for skipping the work when `delegate` is not set:

```
delegate?.addItemViewControllerDidCancel(self)
```

Here the `?` tells Swift not to send the message if `delegate` is `nil`. You can read this as, "Is there a delegate? Then send the message." This practice is called *optional chaining* and it's used a lot in Swift.

In this app it should never happen that `delegate` is `nil` – that would get users stuck on the Add Item screen. But Swift doesn't know that. So you'll have to pretend that it can happen anyway and use optional chaining to send messages to the delegate.

Optionals aren't common in other programming languages, so they may take some getting used to. I find that optionals do make programs clearer – most variables never have to be `nil`, so it's good to prevent them from becoming `nil` and avoid these potential sources of bugs.

Remember, if you see `?` or `!` in a Swift program, you're dealing with optionals. In the course of this app I'll come back to this topic a few more times and explain the finer points of using optionals in more detail.

★ ★ ★

Conform to the delegate protocol

Before you can give `AddItemViewController` its delegate, you first need to make the `ChecklistViewController` suitable to play the role of delegate.

➤ In **ChecklistViewController.swift**, change the class line to the following (this goes all on one line):

```
class ChecklistViewController: UITableViewController,
AddItemViewControllerDelegate {
```

This tells the compiler that `ChecklistViewController` now promises to do the things from the `AddItemViewControllerDelegate` protocol. Or, in programming terminology, that it *conforms* to the `AddItemViewControllerDelegate` protocol.

Xcode should now throw up an error: "Type ChecklistViewController does not conform to protocol AddItemViewControllerDelegate."



Xcode warns about not conforming to protocol

That is correct: You still need to add the methods that are listed in `AddItemViewControllerDelegate`. In Xcode there is an easy way to get started with fixing this issue — see that "Fix" button? Simply click it. :]

Xcode will add in the stubs — the bare minimum code — for the missing methods. You will have to add in the actual implementation for each method, of course.

➤ Add the implementations for the protocol methods to `ChecklistViewController`:

```
// MARK: - Add Item ViewController Delegates
func addItemViewControllerDidCancel(
  _ controller: AddItemViewController
) {
  navigationController?.popViewController(animated: true)
}

func addItemViewController(
  _ controller: AddItemViewController,
  didFinishAdding item: ChecklistItem
) {
  navigationController?.popViewController(animated: true)
}
```

Currently, both methods simply close the Add Item screen. This is what the `AddItemViewController` used to do in its `cancel()` and `done()` actions. You've simply moved that responsibility to the delegate.

The code that adds the new `ChecklistItem` object to the table view is yet to be added. You'll do that in a moment, but there's something else you need to do first.

Delegates in five easy steps

These are the steps for setting up the delegate pattern between two objects, where object A is the delegate for object B, and object B will send messages back to A. The steps are:

1. Define a delegate `protocol` for object B.
2. Give object B an optional `delegate` variable. This variable should be `weak`.
3. Update object B to send messages to its delegate when something interesting happens, such as the user pressing the Cancel or Done buttons, or when it needs a piece of information. You write `delegate?.methodName(self, . . .)`
4. Make object A conform to the delegate protocol. It should put the name of the protocol in its `class` line and implement the methods from the protocol.
5. Tell object B that object A is now its delegate.

You've done steps 1 - 4, so there is just one more thing you need to do — step 5: tell `AddItemViewController` that `ChecklistViewController` is its delegate.

The proper place to do that is in the `prepare(for:sender:)` method, also known as *prepare-for-segue*.

The `prepare(for:sender:)` method is invoked by UIKit when a segue from one screen to another is about to be performed. Recall that the segue is the arrow between two view controllers in the storyboard.

Using prepare-for-segue allows you to pass data to the new view controller before it is displayed. Usually you'll do this by setting one or more of the new view controller's properties.

➤ Add this method to **ChecklistViewController.swift**:

```
// MARK: - Navigation
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
```

```
    // 1
    if segue.identifier == "AddItem" {
      // 2
      let controller = segue.destination as! AddItemViewController
      // 3
      controller.delegate = self
    }
  }
```

This is what this code does, step-by-step:

1. Because there may be more than one segue per view controller, it's a good idea to give each segue a unique identifier and to check for that identifier first to make sure you're handling the correct segue. Swift's == comparison operator works on not just numbers but also on strings and some other types of objects.

2. The new view controller to be displayed can be found in `segue.destination`, but `destination` is of type `UIViewContoller` since the new view controller could be any view controller sub-class.

   So, you *cast* `destination` to `AddItemViewController` to get a reference to an object with the right type. (The `as!` keyword is known as a *type cast* or a *force downcast* since you are casting an object of one type to a different type. Do note that if you downcast objects of completely different types, you might get a `nil` value. The casting works here because `AddItemViewController` is a sub-class of `UIViewContoller`.)

3. Once you have a reference to the `AddItemViewController` object, you set its `delegate` property to `self` and the connection is complete. This tells `AddItemViewController` that from now on, the object identified as `self` is its delegate. But what is "self" here? Well, since you're editing **ChecklistViewController.swift**, `self` refers to `ChecklistViewController`.


Excellent! `ChecklistViewController` is now the delegate of `AddItemViewController`. It took some work, but you're almost set now — except for one teensy thing :]

Set the segue identifier

See the segue identifier mentioned in the code above? Where was it set? The answer is, that it wasn't! We need to set the identifier in order for the above code to work. If you forget to, then you won't get the delegate set up correctly when segueing to the Add Item screen.

➤ Open the storyboard and select the segue between the Checklist View Controller and the Add Item View Controller.

➤ In the **Attributes inspector**, type **AddItem** into the **Identifier** field:



Naming the segue between the Checklists scene and the Add Item scene

➤ Run the app to see if it works — make sure the storyboard is saved before you press Run, or the app may crash or not work correctly.

Pressing the + button will perform the segue to the Add Item screen with the Checklists screen set as its delegate.

When you press Cancel or Done, `AddItemViewController` sends a message to its delegate, `ChecklistViewController`. Currently the delegate simply closes the Add Item screen. But now that you know it works, you can make it do more.

Let's add the new `ChecklistItem` to the data model and the table view. Finally!

Add new to-do items

➤ Change the implementation of the `didFinishAdding` delegate method in **ChecklistViewController.swift** to the following:

```
func addItemViewController(
  _ controller: AddItemViewController,
  didFinishAdding item: ChecklistItem
) {
  let newRowIndex = items.count
  items.append(item)

  let indexPath = IndexPath(row: newRowIndex, section: 0)
  let indexPaths = [indexPath]
  tableView.insertRows(at: indexPaths, with: .automatic)
  navigationController?.popViewController(animated:true)
}
```

This is basically the same as what you did in `addItem()` before. In fact, I simply copied the contents of `addItem()` and pasted that into this method with some slight modifications. Compare the two methods and see for yourself.

The only difference is that you no longer create the `ChecklistItem` object here; that happens in the `AddItemViewController`. You merely insert this new object into the `items` array.


As before, you tell the table view you have a new row for it and then close the Add Items screen.

➤ Remove `addItem()` from **ChecklistViewController.swift** as you no longer need this method.

Just to make sure, open the storyboard and double-check that the + button is no longer connected to the `addItem` action. You should have already removed the connection to the action when you set up the segue to the Add Items scene, but it doesn't hurt to check since bad things happen if buttons are connected to methods that no longer exist...

You can check this in the Connections inspector for the + button, under **Sent Actions**. Nothing should be connected there. Only the segue under Triggered Segues should be present.

➤ Run the app and you should be able to add your own items to the list!



You can finally add new items to the to-do list

★ ★ ★

Weak


I still owe you an explanation about the `weak` keyword. Relationships between objects can be weak or strong. You use weak relationships to avoid what is known as an *ownership cycle*.

When object A has a strong reference to object B, and at the same time object B also has a strong reference back to A, then these two objects are involved in a dangerous kind of romance: an ownership cycle.

Normally, an object is destroyed – or *deallocated* – when there are no more strong references to it. But because A and B have strong references to each other, they keep each other alive.

The result is a potential *memory leak* where an object that ought to be destroyed, isn't, and the memory for its data is never reclaimed. With enough such leaks, iOS will run out of available memory and your app will crash. I told you it was dangerous!


Due to the strong references between them, A owns B and at the same time, B also owns A:



To avoid ownership cycles you can make one of these references weak.

In the case of a view controller and its delegate, screen A usually has a strong reference to screen B, but B only has a weak reference back to its delegate, A.

Because of the weak reference, B no longer owns A:



Now there is no ownership cycle.

Such cycles can occur in other situations too, but they are most common with delegates. Therefore, delegates are always made `weak`.

(There is another relationship type, `unowned`, that is similar to `weak` and can be used for delegates too. The difference is that weak variables are allowed to become `nil` again. You may forget this right now.)

`@IBOutlets` are usually also declared with the `weak` keyword. This isn't done to avoid an ownership cycle, but to make it clear that the view controller isn't really the owner of the views from the outlets.

In the course of this book, you'll learn more about `weak`, `strong`, optionals, and the relationships between objects. These are important concepts in Swift, but they may take a while to make sense. If you don't understand them immediately, don't lose any sleep over it!

★ ★ ★

You can find the project files for the app up to this point under **13-Delegates-and-protocols** in the Source Code folder.

Chapter 14: Edit Items

By Fahim Farook

Adding new items to the list is a great step forward for the app, but there are usually three things an app needs to do with data:

1. Add new items — you've tackled this already.
2. Deleting items — you allow that with swipe-to-delete.
3. Editing existing items — uhh…

The last is useful when you want to rename an item from your list — after all, we all make typos.


This chapter covers the following:

- **Edit items:** Edit existing to-do items via the app interface.
- **Refactor the code:** Using Xcode's built-in refactoring capability to rename code to be easily identifiable.
- **One more thing:** Fix missed code changes after the code refactoring using the Find navigator.

Edit items

You could make a completely new Edit Item screen, but it would be needless duplication of work — the edit screen would work mostly the same as the Add Item screen. The only difference is that it doesn't start out empty — instead, it works with an existing to-do item.

So, let's re-use the Add Item screen and make it capable of editing an existing `ChecklistItem` object.



Editing a to-do item

For the edit option, when the user presses Done, you won't have to make a new `ChecklistItem` object, instead, you will simply update the text in the existing `ChecklistItem`.

You'll also tell the delegate about these changes so that it can update the text label of the corresponding table view cell.

> **Exercise:** What changes would you need to make to the Add Item screen to enable it to edit existing items?

Answer:


1. The screen title must be changed to **Edit Item**.
2. You must be able to pass it an existing `ChecklistItem` object.
3. You have to place the `ChecklistItem`'s text into the text field.
4. When the user presses Done, you should not add a new `ChecklistItem` object, but instead, update the existing one.

There is a bit of a user interface problem, though... How will the user actually open the Edit Item screen? In many apps that is done by tapping on the item's row, but in *Checklists* that already toggles the checkmark on or off.

To solve this problem, you'll have to revise the UI a little first.

Revise the UI to allow editing

When a row is given two functions, the standard approach is to use a **detail disclosure button** for the secondary task:



The detail disclosure button

Tapping the row itself will still perform the row's main function — in this case, toggling the checkmark. But tapping the disclosure button will open the Edit Item screen.

> **Note:** An alternative approach is in Apple's *Reminders* app, where the checkmark is on the left and tapping only this part of the row will toggle the checkmark. Tapping anywhere else in the row will bring up the Edit screen for that item.
>
> There are also apps that can toggle the whole screen into "Edit mode" and then let you change the text of an item inline. Which solution you choose depends on what works best for your data.

➤ Go to the table view cell in the storyboard for the Checklists scene and in the **Attributes inspector** set its **Accessory** to **Detail Disclosure**.

Instead of the checkmark, you'll now see a chevron (>) and a blue info button on the cell. This means you'll have to place the checkmark somewhere else.


The new checkmark

➤ Drag a new **Label** on to the cell and place it to the left of the text label. Give it the following attributes:

- Text: √ (you can type this with **Alt/Option+V**)
- Font: Helvetica Neue, Bold, size 22
- Tag: 1001

You've given this new label its own tag, so you can easily find it later.

If typing Option-V does not work for you, or you'd prefer a different image, choose **Edit ▸ Emoji & Symbols** from the Xcode menu bar. Use the search bar to search for "check" – or whatever takes your fancy. Do note that not all of these special symbols may actually work on your iPhone.




The Emoji & Symbols palette

➤ Resize the text label so that it doesn't overlap the checkmark or the disclosure button. There should be about 8 points horizontal spacing between the two.

➤ Adjust the Auto Layout constraints on the original label and set new constraints on the new label after you've positioned everything to your satisfaction.

The best course of action is probably to retain all the existing layout constraints on the old label except for the **leading** one. You can delete any constraints by selecting the control (the label in this case) and then switching to the Size inspector, selecting the relevant constraint and tapping **Delete**. You can then set up Auto Layout constraints for the new label for **width**, **left**, **top**, **right**, and **bottom** via the **Add New Constraints** button to position everything correctly.

The design of the prototype cell should now look similar to this:



The new design of the prototype cell


➤ In **ChecklistViewController.swift**, change `configureCheckmark(for:with:)` to:

```
func configureCheckmark(
  for cell: UITableViewCell,
  with item: ChecklistItem
) {
  let label = cell.viewWithTag(1001) as! UILabel

  if item.checked {
    label.text = "√"
  } else {
    label.text = ""
  }
}
```

Instead of setting the cell's `accessoryType` property, this now changes the text in the new label.

➤ Run the app and you'll see that the checkmark has moved to the left. There is also a blue detail disclosure button on the right. Tapping the row still toggles the checkmark, but tapping the blue button doesn't do anything… yet.




The checkmarks are now on the other side of the cell

The edit screen segue


Next, you're going to make the detail disclosure button open the Add/Edit Item screen. This is pretty simple because Interface Builder also allows you to make a segue for a disclosure button.

➤ Open the storyboard. Select the table view cell for the Checklists scene and **Control-drag** to the Add Item scene to make a segue. From the popup, choose **Show** from the **Accessory Action** section and *not from Selection Segue*:



Making a segue from the detail disclosure button

There should now be two segues going from the Checklists screen to the navigation controller. One is triggered by the + button, the other by the detail disclosure button from the prototype cell.



Two arrows for two segues

For the app to make a distinction between these two segues, they must have unique identifiers.

➤ Give this new segue the identifier **EditItem** (in the **Attributes inspector**).

If you run the app now, tapping the blue ⓘ button will also open the Add Item screen. But the Cancel and Done buttons won't work.

> **Exercise:** Can you explain why not?

Answer: You haven't set the delegate yet. Remember that you set the delegate in `prepare(for:sender:)`, but only for when the + button is tapped to perform the *AddItem* segue. You haven't done the same for this new *EditItem* segue.

Before you do that though, you should first make the Add Item screen capable of editing existing `ChecklistItem` objects.

Update the Add Item screen to handle editing

➤ Add a new property for a `ChecklistItem` object below the other instance variables in **AddItemViewController.swift**:

```
var itemToEdit: ChecklistItem?
```

This variable contains the existing `ChecklistItem` object that the user will edit. But when adding a new to-do item, `itemToEdit` will be `nil`. That is how the view controller will make the distinction between adding and editing.

Because `itemToEdit` can be `nil`, it needs to be an optional. That explains the question mark.

➤ Update `viewDidLoad()` in **AddItemViewController.swift** as follows:

```
override func viewDidLoad() {
  . . .
  if let item = itemToEdit {
    title = "Edit Item"
    textField.text = item.text
  }
}
```

Recall that `viewDidLoad()` is called by UIKit when the view controller is loaded from the storyboard, but before it is shown on the screen. That gives you time to put the user interface in order.

In editing mode, when `itemToEdit` is not `nil`, you change the title in the navigation bar to "Edit Item". You do this by changing the `title` property.

Each view controller has a number of built-in properties and this is one of them. The navigation controller looks for the `title` property and automatically changes the text in the navigation bar.

You also set the text in the text field to the value from the item's `text` property.

★ ★ ★

if let

You cannot use optionals like you would regular variables. For example, if `viewDidLoad()` had the following code:

```
textField.text = itemToEdit.text
```

Xcode would complain with the error message, "Value of optional type ChecklistItem? must be unwrapped".

That's because `itemToEdit` is the optional version of `ChecklistItem`.

In order to use it, you first need to *unwrap* the optional. You do that with the following special syntax:

```
if let temporaryConstant = optionalVariable {
  // temporaryConstant now contains the unwrapped value of the
  // optional variable. temporayConstant is only available from
  // within this if block
}
```

If the optional is not `nil`, then the code inside the `if` statement is performed.

There are a few other ways to read the value of an optional, but using `if let` is the safest: if the optional has no value – i.e. it is `nil` – then the code inside the `if let` block is skipped over.

The new code you added to `viewDidLoad` can also be written like this:

```
if let itemToEdit = itemToEdit {
  title = "Edit Item"
  textField.text = itemToEdit.text
}
```

Looks a bit weird, doesn't it? Why are we assigning the value from `itemToEdit` back again to `itemToEdit`? And how come the compiler doesn't complain about optional unwrapping now if we write the code like that?

The above practice is called *variable shadowing* — you create a "shadow" instance of the `itemToEdit` variable just for the duration of the `if` condition and that shadow instance is an unwrapped instance of the originally optional `itemToEdit` variable. So, when you refer to `itemToEdit` when assigning text to the text field, you are actually referring to the unwrapped instance of the variable instead of the original optional instance.

This might be a bit confusing if you are new to Swift and optionals. So, whether you use variable shadowing to unwrap optionals, or not, is entirely up to you. Personally, I prefer shadowing because then the code is clear about the variable being referred to in the code at all times since the same variable name is used for both the optional and unwrapped versions.

The `AddItemViewController` is now capable of recognizing when it needs to edit an item. If the `itemToEdit` property is given a `ChecklistItem` object, then the screen magically changes into the Edit Item screen.

But where do you set that `itemToEdit` property? In prepare-for-segue, of course! That's the ideal place for placing values into the properties of the new screen before it becomes visible.

★★★

Set the item to be edited

➤ Change `prepare(for:sender:)` in **ChecklistViewController.swift** to the following:

```
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
```

```
    if segue.identifier == "AddItem" {
      . . .

    } else if segue.identifier == "EditItem" {
      let controller = segue.destination as! AddItemViewController
      controller.delegate = self

      if let indexPath = tableView.indexPath(
        for: sender as! UITableViewCell) {
        controller.itemToEdit = items[indexPath.row]
      }
    }
  }
```

As before, you get the `AddItemViewController` via the segue's `destination`.

You also set the view controller's `delegate` property so you're notified when the user taps Cancel or Done. Nothing new there. This is the same as for the `AddItem` segue.

This is the interesting new bit:

```
  if let indexPath = tableView.indexPath(for: sender as!
  UITableViewCell){
    controller.itemToEdit = items[indexPath.row]
  }
```

You're in the `prepare(for:sender:)` method, which has a parameter named `sender`. This parameter contains a reference to the control that triggered the segue, in this case, the table view cell whose disclosure button was tapped.

You use that `UITableViewCell` object to find the table view row number by looking up the corresponding index path using `tableView.indexPath(for:)`.

The return type of `indexPath(for:)` is `IndexPath?`, an optional, meaning it can possibly return `nil`. That's why you need to unwrap this optional value with `if let` before you can use it.

Once you have the index path, you obtain the `ChecklistItem` object to edit, and you assign this to `AddItemViewController`'s `itemToEdit` property.

Sending data between view controllers

We've talked about screen B (the Add/Edit Item screen) passing data back to screen A (the Checklists screen) via delegates. But here, you're passing a piece of data the other way around – from screen A to screen B – namely, the `ChecklistItem` to edit.

Data transfer between view controllers works two ways:

1. From A to B. When screen A opens screen B, A can give B the data it needs. You simply make a new instance variable in B's view controller. Screen A then puts an object into this property right before it makes screen B visible, usually in `prepare(for:sender:)`.

2. From B to A. To pass data back from B to A you use a delegate.

This illustration shows how screen A sends data to screen B by putting it into B's properties, and how screen B sends data back to the delegate:



I hope the flow between view controllers is starting to make sense to you now. You're going to do this sort of thing a few more times in this app, just to make sure you get comfortable with it.

Making iOS apps is all about creating view controllers and sending messages between them, so you want this to become second nature.

➤ With these steps done, you can now run the app. A tap on the + button opens the Add Item screen as before. But tap the accessory button on an existing row and the screen that opens is named Edit Item. It already contains the to-do item's text:



Editing an item

Enable the Done button for edits

One small problem: the Done button in the navigation bar is initially disabled. This is because you originally set it to be disabled in the storyboard.

➤ Change `viewDidLoad()` in **AddItemViewController.swift** to fix this:

```
override func viewDidLoad() {
  super.viewDidLoad()

  if let item = itemToEdit {
    title = "Edit Item"
    textField.text = item.text
    doneBarButton.isEnabled = true    // add this line
  }
}
```

When in edit mode, you simply enable the Done button since you are guaranteed to be passed some text for the item.

The problems don't end here, though. Run the app, tap a row to edit it, and press Done. Instead of changing the text on the existing item, a brand new to-do item with the new text is added to the list.

How come? You didn't write the code yet to update the data model! So, the delegate always thinks it needs to add a new row. To solve this, you will add a new method to the delegate protocol.

Handle edits in the delegate protocol

➤ Add the following line to the `protocol` section in **AddItemViewController.swift**:

```
func addItemViewController(
  _ controller: AddItemViewController,
  didFinishEditing item: ChecklistItem
)
```

The full protocol now looks like this:

```
protocol AddItemViewControllerDelegate: AnyObject {
  func addItemViewControllerDidCancel(
    _ controller: AddItemViewController)
  func addItemViewController(
    _ controller: AddItemViewController,
    didFinishAdding item: ChecklistItem
  )
  func addItemViewController(
    _ controller: AddItemViewController,
    didFinishEditing item: ChecklistItem
  )
}
```

There is a method that is invoked when the user presses Cancel and two methods for when the user presses Done.

After adding a new item you call `didFinishAdding`, but when editing an existing item, the new `didFinishEditing` method should now be called instead.

By using different methods, the delegate (the `ChecklistViewController`), can make a distinction between those two situations.

➤ In **AddItemViewController.swift**, change the `done()` method to:

```
@IBAction func done() {
  if let item = itemToEdit {
    item.text = textField.text!
    delegate?.addItemViewController(
      self,
      didFinishEditing: item)
  } else {
    let item = ChecklistItem()
    item.text = textField.text!
    delegate?.addItemViewController(self, didFinishAdding: item)
  }
}
```

First the code checks whether the `itemToEdit` property contains an object — you should recognize the `if let` syntax for unwrapping an optional.

If the optional is not `nil`, you put the text from the text field into the existing `ChecklistItem` object and then call the new delegate method.


In the case that `itemToEdit` *is* `nil`, the user is adding a new item and you do the stuff you did before (inside the `else` block).

Implement the new delegate method

➤ Try to build the app. It won't work.

Xcode says "Build Failed" but there don't seem to be any error messages in **AddItemViewController.swift**. So what went wrong?

You can see all errors and warnings from Xcode in the **Issue navigator**.



Xcode warns about incomplete implementation

The error is apparently in `ChecklistViewController` because it does not implement a method from the protocol. That is not so strange because you just added the new `addItemViewController(_:didFinishEditing:)` method to the delegate protocol. But you did not yet tell the view controller, which plays the role of the delegate, what to do about it.

> **Note:** The exact error message in my version of Xcode is "Method ... has different argument labels from those required by protocol ...". That's a bit of a strange error message, wouldn't you say? It doesn't really describe what's wrong, just what the compiler is confused about.
>
> As you write your own apps, you'll probably run into other strange or even undecipherable error messages. This should get better in time. The Swift compiler is quite new at the job and still needs to work on its bedside manner.

➤ Add the following to **ChecklistViewController.swift** and the compiler error will be history:

```
func addItemViewController(
  _ controller: AddItemViewController,
  didFinishEditing item: ChecklistItem
) {
  if let index = items.firstIndex(of: item) {
    let indexPath = IndexPath(row: index, section: 0)
    if let cell = tableView.cellForRow(at: indexPath) {
      configureText(for: cell, with: item)
    }
  }
  navigationController?.popViewController(animated: true)
}
```

The `ChecklistItem` object already has the new text — it was put there by `done()` — and the cell for it already exists in the table view. But you do need to update the label for its table view cell.

So, in this new method you look for the cell that corresponds to the `ChecklistItem` object and, using the `configureText(for:with:)` method you wrote earlier, tell it to refresh its label.

The first statement is the most interesting:


```
if let index = items.firstIndex(of: item) {
```

In order to create the `IndexPath` that you need to retrieve the cell, you first need to find the row number for this `ChecklistItem`. The row number is the same as the index of the `ChecklistItem` in the `items` array — you can use the `firstIndex(of:)` method to return the index of the first item from the array which matches the passed in `ChecklistItem`.

Now, it won't happen here, but in theory it's possible that you use `firstIndex(of:)` on an object that is not actually in the array. To account for the possibility, `firstIndex(of:)` does not return a normal value, it returns an optional. If the object is not part of the array, the returned value is `nil`.

That's why you need to use `if let` here to unwrap the return value from `firstIndex(of:)`.

➤ Try to build the app. Oops, Xcode has found another reason to complain: "Referencing instance method 'firstIndex(of:)' on 'Collection' requires that 'ChecklistItem' conform to 'Equatable'". What does *that* mean?



New Xcode error

This error is displayed because you can't use `firstIndex(of:)` on just any array, or collection of objects. An object has to be "equatable" if you are to use `firstIndex(of:)` on an array of that object type. This is because `firstIndex(of:)` must be able to somehow compare the object that you're looking for against the objects in the array, to see if they are equal.

Your `ChecklistItem` object does not have any functionality for that yet. There are a few ways you can fix this, but we'll go for the easy one.

➤ In **ChecklistItem.swift**, change the class line to:

```
class ChecklistItem: NSObject {
```

If you've programmed in Objective-C before, you'll be familiar with `NSObject`.

Almost all objects in Objective-C programs are based on `NSObject`. It's the most basic building block provided by iOS, and it offers a bunch of useful functionality that standard Swift objects don't have.

You can write many Swift programs without having to resort to `NSObject`, but in times like these it comes in handy.

Building `ChecklistItem` on top of `NSObject` is enough to satisfy the "equatable" requirement. In case you're interested, the other way to do this would have been to specify that `ChecklistItem` conforms to the `Equatable` protocol. But then, you'd have to implement an additional method to indicate how the comparison of two `ChecklistItem` instances would happen. So going with `NSObject` conformance is easier for the time being.

➤ Run the app again and verify that editing items works now. Excellent!

Refactor the code

At this point, you have an app that can add new items and edit existing items using the combined Add/Edit Item screen. Pretty sweet!

Given the recent changes, I don't think the name `AddItemViewController` is appropriate anymore as this screen is now used to both add and edit items.


I suggest you rename it to `ItemDetailViewController`.

Rename the view controller

Most IDEs (or **I**ntegrated **D**evelopment **E**nvironments) such as Xcode have a feature named *refactoring*, which allows you to change the name of a class, method, or variable throughout the entire project, safely.

There are a couple of ways to access the refactor functionality, but the easiest is to simply **right-click** (or, **Control-click**) on any class name, method, or variable.

You'll get a menu similar to this:




The Xcode context menu

You should notice two things about the above screenshot:

1. Notice how the class name (or method name, or variable name) that was under your cursor when you right-clicked was highlighted? That indicates that the highlighted name is the one that would be renamed.

2. Notice the **Rename…** option on the menu under **Refactor**? It's this menu option which provides the rename functionality. There are other refactoring options on that menu too — most of them should be fairly obvious based on the menu title.

➤ If you right-clicked over the `AddItemViewController` class name, select the **Refactor - Rename…** option now. If you right-clicked elsewhere, first move your cursor over the class name, right-click, and then select Rename… You should get a screen similar to the following:



Xcode rename view

The new screen shows you all the files and instances (including the storyboard and file names) in the project where the particular name you selected is used. Also notice how the name at the instance where you right-clicked is now editable.

Start typing in the new name you want and you'll notice that all the matching names for all the other instances in the view update in real-time. Cool!

When you've entered the correct name and verified that everything will be updated correctly, just click the **Rename** button on the top right corner and you're done :] It's as simple as that!

> **Note:** While the refactoring works flawlessly most of the time, I've sometimes had Xcode do all the renaming correctly except for renaming the current file itself. If this does happen to you, you might have to rename the file manually by looking for it in the project folder and renaming it via Finder.

Test the code after a refactor

Let's see if everything works correctly now.

➤ Press ⌘+**B** (or select **Product** ▸ **Build** from the Xcode menu) to compile the app.

> **Note:** Getting a "Build Failed" error? Sometimes this does happen after a massive change across the whole project like this. The first thing to try is to use the Xcode menu's **Product** ▸ **Clean Build Folder** option and try building again. It should work in most cases at that point.
>
> Because you made quite a few changes all over the place, it's a good idea to clean up the debris and detritus from old compiler runs so that Xcode picks up all the new changes. You don't have to be paranoid about this, but it's good practice to clean house once in a while.

If there are no build issues, run the app again and test the various features just to make sure everything still works.

If the build succeeds, but Xcode still shows red error icons in your source file, then close the project and open it again, or restart Xcode. Restarting Xcode is the solution that Almost Always Works™. And if it doesn't, restarting your computer is the last resort. That does get rid of even the most stubborn issues.

One more thing

The rename process appears to have gone through flawlessly, your app works fine when you test it, and there are no crashes. So, everything should be fine and you can move on to the next feature in the app, right?

Well ... not quite :] Switch to **ItemDetailViewController.swift** and check the protocol definition at the top. What do you see?

```
protocol AddItemViewControllerDelegate: class {
  func addItemViewControllerDidCancel(_ controller: ItemDetailViewController)
  func addItemViewController(
    _ controller: ItemDetailViewController,
    didFinishAdding item: ChecklistItem
  )
  func addItemViewController(
    _ controller: ItemDetailViewController,
    didFinishEditing item: ChecklistItem
  )
}
```

The protocol name has not changed after renaming

Looks as if the protocol name, `AddItemViewControllerDelegate`, did not change when you renamed `AddItemViewController`.

If you think about it, it makes sense. `AddItemViewControllerDelegate` is a different entity than `AddItemViewController`. So all the renaming did was to change all the references to the `AddItemViewController` class, not the `AddItemViewControllerDelegate` protocol.

You can easily change the name of the protocol to `ItemDetailViewControllerDelegate` by using Xcode's rename functionality yet again. Do that now.

You'll notice that that only changes the protocol name itself — not the protocol method names. Hmm … this is going to be a lot of work!

You can try renaming each protocol method separately and Xcode's rename functionality will do a stellar job with the renaming, but you'd have to do this three times for the three methods. This could get really time consuming, especially if you were dealing with a protocol with lots of methods. But … there's an easier way.

What is this easier way? To use Xcode's search and replace functionality, of course! As you'll notice, all that remains to change in the `ItemDetailViewControllerDelegate` is the method names, all of which begin with `addItemViewController`. So, if you can search for the term `addItemViewController` across the entire project and replace it with `itemDetailViewController`, you should be done, right?

Here's how you do it:


➤ Switch to the **Find navigator** — the fourth tab in the navigator pane.

➤ Click on **Find** to change it to **Replace**.

➤ Change Ignoring Case to **Matching Case**.

➤ Type as the search text: **addItemViewController**. Important: Make sure you spell it exactly like this since your search term is going to be case-sensitive!


➤ Type in the replacement field: **itemDetailViewController**, again making sure that you type it exactly.



The search & replace options


➤ Press **return** on your keyboard to start the search. This doesn't replace anything yet.

The Find navigator shows the files containing matches for the search term. You should see two Swift source files in this list.



The search results

➤ Click on any item in the file list above to be taken to that particular match in the relevant file with the match highlighted in the source code:



The results list allows you to verify each match

Have a look through the search results just to make sure Xcode isn't doing anything you'll regret later. It should only rename everything that says `addItemViewController` to `itemDetailViewController` but there's always the possibility that Xcode matched some unrelated code accidentally.

➤ If you are satisfied that the matches are correct, click **Replace All**. You could also select only some results in the list and then click **Replace** to have only those results be changed.

I always repeat the search afterwards, ignoring case, to make sure I didn't skip anything by accident.

Now Run the app and test its functionality once again to make sure that everything works. If it does, you are done with this particular task, finally :]

★ ★ ★

Iterative development

If you think this approach to development we've taken so far is a little messy, then you're absolutely right. You started out with one design, but as you continued development you found out that things didn't work out so well in practice, and that you had to refactor your approach a few times to find a way that works. This is actually how software development goes in practice.

You first build a small part of your app and everything looks and works fine. Then you add the next small part on top of that and suddenly everything breaks down. The proper thing to do is to go back and restructure your entire approach so that everything is hunky-dory again... Until the next change you make.

Software development is a constant process of refinement. In this book I didn't want to just give you a perfect piece of code and explain how each part works. That's not how software development happens in the real world.

Instead, you're working your way from zero to a full app, exactly the way a pro developer would, including the mistakes and dead ends. Sure, some processes, like setting up a data model, might have happened in a slightly different order if certain concepts did not have to be explained first — I did take some liberties there in order to make some concepts clear. But the basic process of building, tearing down, and re-building remains the same.

Isn't it possible to create a design up-front – sometimes called a "software architecture design" – that deals with all of these situations, something like a blueprint for software?

I don't believe in such designs. Sure, it's always good to plan ahead. Before writing this book, I made a few quick sketches of how I imagined each app would turn out. That was useful to envision the amount of work, but as usual, some of my assumptions and guesses turned out to be wrong and the design stopped being useful about halfway in. And this is only a simple app!

That doesn't mean you shouldn't spend any time on planning and design — just not too much. Simply start somewhere and keep going until you get stuck, then backtrack and improve on your approach. This is called *iterative development* and it's usually faster and provides better results than meticulous up-front planning.



You can find the project files for the app up to this point under **14-Edit-items** in the Source Code folder.

Chapter 15: Saving & Loading

By Fahim Farook

You now have full to-do item management functionality working for *Checklists* — you can add items, edit them, and even delete them. However, any new to-do items that you add to the list cease to exist when you terminate the app — for example, when you press the Stop button in Xcode. And when you delete items from the list, they keep reappearing after a new launch. That's not how a real app should behave!

So, it's time to consider *data persistence* — or, to put it simply, saving and loading items…

In this chapter you will cover the following:

- **The need for data persistence:** A quick look at why you need data persistence.
- **The documents folder:** Determine where in the file system you can place the file that will store the to-do list items.
- **Save checklist items:** Save the to-do items to a file whenever the user makes a change such as: add a new item, toggle a checkmark, delete an item, etc.
- **Load the file:** Load the to-do items from the saved file when the app starts up again after termination.

The need for data persistence


Thanks to the multitasking nature of iOS, an app stays in memory when you close it and go back to the home screen or switch to another app. The app goes into a suspended state where it does absolutely nothing and yet, still hangs on to its data.

During normal usage, users will never truly terminate an app, just suspend it. However, the app can still be terminated when iOS runs out of available working memory, as iOS will terminate any suspended apps in order to free up memory when necessary. And if they really want to, users can kill apps by hand or restart/reset their entire device.

Just keeping the list of items in memory is not good enough because there is no guarantee that the app will remain in memory forever, whether active or suspended.

Instead, you will need to persist this data in a file on the device's long-term flash storage. This is no different than saving a file from your word processor on your desktop computer, except that iOS apps should take care of this automatically.

The user shouldn't have to press a Save button just to make sure unsaved data is safely placed in long-term storage.



Apps need to persist data just in case the app is terminated

So let's get crackin' on that data persistence functionality!

The documents folder

iOS apps live in a sheltered environment known as the *sandbox*. Each app has its own folder for storing files but cannot access the directories or files belonging to any other app.

This is a security measure, designed to prevent malicious software such as viruses from doing any damage. If an app can only change its own files, it cannot modify (or affect) any other part of the system.

Your apps can store files in the "Documents" folder in the app's sandbox.

The contents of the Documents folder are backed up when the user syncs their device with iTunes or iCloud.

When you release a new version of your app and users install the update, the Documents folder is left untouched. Any data the app has saved into this folder stays there when the app is updated.

In other words, the Documents folder is the perfect place for storing your user's data files.

Get the save file path

Let's look at how this works in code.

➤ Add the following methods to **ChecklistViewController.swift**:

```
func documentsDirectory() -> URL {
  let paths = FileManager.default.urls(
    for: .documentDirectory,
    in: .userDomainMask)
  return paths[0]
}

func dataFilePath() -> URL {
  return
documentsDirectory().appendingPathComponent("Checklists.plist")
}
```

The `documentsDirectory()` returns the full path to the Documents folder.

The `dataFilePath()` method uses `documentsDirectory()` to construct the full path to the file that will store the checklist items. This file is named **Checklists.plist** and it lives inside the Documents folder.

Notice that both methods return a `URL` object. iOS uses URLs to refer to files in its filesystem. Where websites use `http://` or `https://` URLs, to refer to a file you use a `file://` URL.

> **Note:** Double check to make sure your code says `.documentDirectory` and not `.documentationDirectory`. Xcode's autocomplete can easily trip you up here!

➤ Still in **ChecklistViewController.swift**, add the following two `print` statements to the bottom of `viewDidLoad`:

```
override func viewDidLoad() {
  . . .
  items.append(item5)
  // Add the following
  print("Documents folder is \(documentsDirectory())")
  print("Data file path is \(dataFilePath())")
}
```

➤ Run the app. Xcode's Console will now show you where your app's Documents folder is actually located.

If I run the app from the Simulator, on my system it shows something like this:

```
Documents folder is
    file:///Users/fahim/Library/Developer/CoreSimulator/Dev
    ices/31DCE39D-CEC6-4228-B6DF-98FA08E5544F/data/Containe
    rs/Data/Application/304313FF-E6AD-40AE-A4E7-951DB8061CB
    9/Documents/
Data file path is
    file:///Users/fahim/Library/Developer/CoreSimulator/Dev
    ices/31DCE39D-CEC6-4228-B6DF-98FA08E5544F/data/Containe
    rs/Data/Application/304313FF-E6AD-40AE-A4E7-951DB8061CB
    9/Documents/Checklists.plist
```

Console output showing Documents folder and data file locations

If you run it on your iPhone, the path will look somewhat different. Here's what mine says:

```
Documents folder is file:///var/mobile/Applications/
FDD50B54-9383-4DCC-9C19-C3DEBC1A96FE/Documents

Data file path is file:///var/mobile/Applications/
FDD50B54-9383-4DCC-9C19-C3DEBC1A96FE/Documents/Checklists.plist
```

As you'll notice, the folder name is a random 32-character ID. Xcode picks this ID when it installs the app on the Simulator or the device. Anything inside that folder is part of the app's sandbox.


Browse the documents folder

For the rest of this app, run the app on the Simulator instead of a device. That makes it easier to look at the files you'll be writing into the Documents folder. Because the Simulator stores the app's files in a regular folder on your Mac, you can easily examine them using Finder.

➤ Open a new Finder window by clicking on the Desktop and typing **⌘+N**. Or, by clicking the Finder icon in your dock, if you have one. Then press **⌘+Shift+G** — or, select **Go ▸ Go to Folder...** from the menu, copy the Documents folder path from Xcode Console, and paste the full path to the Documents folder in the dialog. (Don't include the **file://** bit. The path starts with **/Users/<yourname>/...**)

➤ You will probably see an empty folder at this point. To navigate one level up in Finder to see the sandbox folder for the app, use the ⌘+↑ (command + up arrow) key combination or the **Go ▸ Enclosing Folder** menu option.

Keep this window open so you can verify that the Checklists.plist file is actually created when you get to that part.



The app's directory structure in the Simulator

> **Tip:** If you want to navigate to the Simulator's app directory by traversing your folder structure, then you should know that the Library folder, which is in your home folder, is normally hidden. If you can't see the Library folder, hold down the Alt/Option key and click on Finder's Go menu, or hold down the Alt key while the Go menu is open. This should reveal a shortcut to the Library folder on the Go menu, if it wasn't visible previously.


You can see several folders inside the app's sandbox folder:

- The Documents folder where the app will put its data files. Currently the Documents folder is empty.
- The Library folder has cache files and preferences files. The contents of this folder are managed by the operating system.
- The SystemData folder, as the name implies, is for use by the operating system to store any system level information relevant to the app.
- The tmp folder is for temporary files. Sometimes apps need to create files for temporary usage. You don't want these to clutter up your Documents folder, so tmp is a good place to put them. iOS will clear out this folder from time to time.

It is also possible to get an overview of the Documents folder of apps on your device.

➤ On your device, go to **Settings ▸ General ▸ iPhone Storage**, scroll down to the list of installed apps — you might have to wait for the list to load — and tap the name of an app.

You'll now see the size of the contents of its Documents folder, but not the actual contents themselves:



Viewing the Documents folder info on the device

Save checklist items

In this section you are going to write code that saves the list of to-do items to a file named Checklists.plist when the user adds a new item or edits an existing item. Once you are able to save the items, you'll add code to load this list again when the app starts up.

Plist files

So what is a **.plist** file?

You've already seen a file named Info.plist in the *Bull's Eye* lesson. All apps have one, including the *Checklists* app — see the project navigator. Info.plist contains several configuration options that give iOS additional information about the app, such as what name to display under the app's icon on the home screen.

"plist" stands for Property List and it is an XML file format that stores structured data, usually in the form of a list of settings and their values. Property List files are very common in iOS. They are suitable for many types of data storage, and best of all, they are simple to use. What's not to like?

To save the checklist items, you'll use Swift's `Codable` protocol, which lets objects which support the `Codable` protocol to store themselves in a structured file format.


You actually don't have to care much about the format used by `Codable`. In this case it happens to be a .plist file, but you're not going to mess with that file directly. All you care about is that the data gets stored in some kind of file in the app's Documents folder, and you'll leave the technical details to `Codable`.

Incidentally, you have already used `Codable`'s' Objective-C cousin, `NSCoder`, behind the scenes in storyboards. When you add a view controller to a storyboard, Xcode uses the `NSCoder` system to write this object to a file – encoding. Then when your application starts up, it uses `NSCoder` again to read the objects from the storyboard file – decoding. The `Codable` protocol works similarly.

The process of converting objects to files and back again is also known as **serialization**. It's a big topic in software engineering.

I like to think of this whole process as freezing objects. You take a living object and freeze it so that it is suspended in time.

You store that frozen object into a file on the device's flash drive where it will spend some time in cryostasis. Later, you can read that file into memory and defrost the object to bring it back to life again.



The process of freezing (saving) and unfreezing (loading) objects

Save data to a file

➤ Add the following method to **ChecklistViewController.swift**:

```
func saveChecklistItems() {
  // 1
  let encoder = PropertyListEncoder()
  // 2
  do {
    // 3
    let data = try encoder.encode(items)
    // 4
    try data.write(
      to: dataFilePath(),
      options: Data.WritingOptions.atomic)
    // 5
  } catch {
    // 6
    print("Error encoding item array: \
(error.localizedDescription)")
  }
}
```

This method takes the contents of the `items` array, converts it to a block of binary data, and then writes this data to a file. Let's take the commented lines step-by-step to understand the code:

1. First, create an instance of `PropertyListEncoder` which will encode the `items` array, and all the `ChecklistItems` in it, into some sort of binary data format that can be written to a file.

2. The `do` keyword, which you have not encountered before, sets up a block of code to catch Swift errors. Swift handles errors under certain conditions by *throwing* an error. In such cases, you need a block of code to catch the error and to handle it. The `do` keyword indicates the start of such a block. You will see the error catching code after comment #5, where the `catch` keyword is.

3. The encoder you created earlier is used to try to encode the `items` array. The `encode` method throws a Swift error if it is unable to encode the data for some reason — for example, the data is not in the expected format, or it is corrupted etc. The `try` keyword indicates that the call to `encode` can fail and if that happens, that it will throw an error. If you do not have the `try` keyword before a call to a method which throws an error, you will get an Xcode error. Try it and see.If the call to `encode` fails, execution will immediately jump to the `catch` block instead of proceeding on to the next line.

4. If the `data` constant was successfully created by the call to `encode` in the previous line, then you write the data to a file using the file path returned by a call to `dataFilePath()`. Note that the `write` method also can throw an error. So again, you have to precede the method call with another `try` statement.

5. The `catch` statement indicates the block of code to be executed if an error was thrown by any line of code in the enclosing `do` block.

6. Handle the caught error. Here, you simply print out an error message to the Xcode Console, but you might notice that the print statement references an `error` variable. Where did that come from?

   When you create a `do - catch` block of code, you can explicitly check for specific types of errors. We won't get into that at this point, but what you need to know is that if you simply have a `catch` block, Swift will automatically populate a local variable named `error` which will contain the error thrown by one of the statements within the `do` block.

   So, you can simply refer to that `error` variable in any code you write in the `catch` block. This can be handy for outputting a descriptive error message which indicates what the source of the error/failure was.

You will notice that Xcode shows an error at this point saying: Class 'PropertyListEncoder' requires that 'ChecklistItem' conform to 'Encodable'.

This is because any object encoded (or decoded) by a `PropertyListEncoder` — or for that matter, any of the other encoders/decoders compatible with the `Codable` protocol — must support the `Codable` protocol, and `ChecklistItem` does not.

The Codable protocol

Swift arrays — as well as most other standard Swift objects and structures — conform to the `Codable` protocol. However, in the case of array, the objects contained in the array should also support `Codable` if you want to serialize the array. That's why we need `ChecklistItem` class to be `Codable` compliant.

> **Note:** Sometimes when working with code dealing with `Codable` support, you will see error messages or references to `Encodable` or `Decodable` protocols. So, it might be good to know that `Codable` is actually a protocol which combines these two other protocols, `Encodable` and `Decodable` — one for each side of the serialization process.

➤ Switch to **ChecklistItem.swift** and modify the `class` line as follows:

```
class ChecklistItem: NSObject, Codable {
```

In the above, you tell the compiler that `ChecklistItem` will conform to the `Codable` protocol. That's all you need to do!

"Now, hold on," I hear you say. "We had to implement methods to support a protocol before. How come we don't have to do that here?"

Remember how I mentioned previously that protocols can have default implementations? No? OK, it was in the **Delegates and Protocols** chapter in the section about protocols :] Sometimes, it is useful to have a default implementation for a protocol to provide functionality that would make things easier — or would cover a lot of standard scenarios.

In our case, all of the properties of `ChecklistItem` are standard Swift types, and Swift already knows how to encode/decode those types. So, we can simply piggyback on existing functionality without having to write any code of our own to implement encoding/decoding in `ChecklistItem`. Handy, eh?

Using the new method

You have to call the new `saveChecklistItems()` method whenever the list of items is modified.

> **Exercise:** Where in the source code would you call this method?

Answer: Look at where the `items` array is modified. This happens inside the `ItemDetailViewControllerDelegate` methods. That's where the party's at!

➤ Add a call to `saveChecklistItems()` to the end of these methods in **ChecklistViewController.swift**:

```
func itemDetailViewController(
  _ controller: ItemDetailViewController,
  didFinishAdding item: ChecklistItem
) {
  . . .
  saveChecklistItems()
}
```

```
func itemDetailViewController(
  _ controller: ItemDetailViewController,
  didFinishEditing item: ChecklistItem
) {
  . . .
  saveChecklistItems()
}
```

➤ Let's not forget the swipe-to-delete function:

```
override func tableView(
  _ tableView: UITableView,
  commit editingStyle: UITableViewCellEditingStyle,
  forRowAt indexPath: IndexPath
) {
  . . .
  saveChecklistItems()
}
```

➤ And toggling the checkmark on a row:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  . . .
  saveChecklistItems()
}
```

Verify the saved file

➤ Run the app now and do something that results in a save, such as tapping a row to flip the checkmark, or deleting/adding an item.

➤ Go to the Finder window that has the app's Documents directory open:



The Documents directory now contains a Checklists.plist file

There is now a **Checklists.plist** file in the Documents folder, which contains the items from the list.


You can look inside this file if you want, but the contents won't make much sense. Even though it is XML, this file wasn't intended to be read by humans, only by something like `PropertyListDecoder`, the counterpart to the `PropertyListEncoder` that we already used.

If you're having trouble viewing the XML, it may be because the plist file isn't stored as text but as a binary format. Some text editors support this file format and can read it as if it were text — BBEdit is a good option and is a free download on the Mac App Store.

You can also use Finder's Quick Look feature to view the file. Simply select the file in Finder and press the space bar.

Naturally, you can also open the plist file with Xcode.

➤ Right-click the Checklists.plist file and choose **Open With ▸ Xcode**.



Checklist.plist in Xcode

It still won't make much sense but it's fun to look at anyway.


Expand some of the rows and you'll see that the names of the `ChecklistItems` are in there as well as their checked/unchecked state. But exactly how all these data items fit together, might not make much sense to you just yet.

★ ★ ★

"NS" objects & Documentation

Objects whose name start with the "NS" prefix, like `NSObject`, `NSString`, or `NSCoder`, are provided by the Foundation framework. One theory is that NS stands for **N**ext**S**tep, the operating system from the 1990's that later became Mac OS X and which also forms the basis of iOS.

If you are curious about exactly how objects such as `NSObbject` and `NSString` work, you can Alt/Option-click any item in your source code to bring up a popup with a brief description. And this works for non-NS prefixed objects too :] In fact, you can look up details about any class, object, variable, or method this way in Xcode.



I use this all the time to remind myself of how to use framework objects and their methods. You can click on any blue color items on the popup since they are links to detailed documentation that will take you to the Developer Documentation app which lets you read up further on the selected subject.

It's good to have a general idea of what objects are available in the frameworks, but no one can remember all the specifics. So get into the habit of looking up the documentation for any new objects and methods that you encounter. It'll help you learn the iOS frameworks that much quicker!

★ ★ ★

Load the file

Saving is all well and good, but pretty useless by itself. So, let's also implement the loading of the Checklists.plist file. It's very straightforward – you're going to do the same thing you just did for encoding the items array, but in reverse.

Read data from a file

➤ Switch to **ChecklistViewController.swift** and add the following new method:

```
func loadChecklistItems() {
  // 1
  let path = dataFilePath()
  // 2
  if let data = try? Data(contentsOf: path) {
    // 3
    let decoder = PropertyListDecoder()
    do {
      // 4
      items = try decoder.decode(
        [ChecklistItem].self,
        from: data)
    } catch {
      print("Error decoding item array: \
(error.localizedDescription)")
    }
  }
}
```

Let's go through this step-by-step:

1. First, you put the results of `dataFilePath()` in a temporary constant named `path`.

2. Try to load the contents of Checklists.plist into a new `Data` object. The `try?` command attempts to create the `Data` object, but returns `nil` if it fails. That's why you put it in an `if let` statement. Why would it fail? If there is no Checklists.plist file, then there are obviously no `ChecklistItem` objects to load. This is what happens when the app is started up for the very first time. In that case, you'll skip the rest of this method.

   Also, do notice that this is another way to use the `try` statement — instead of enclosing the `try` statement within a `do` block, like you did previously, you can have a `try?` statement which indicates that the `try` could fail and if it does, that it will return `nil`. Whether you use the `do` block approach or this one, is completely up to you.

3. When the app does find a Checklists.plist file, you'll load the entire array and its contents from the file using a `PropertyListDecoder`. So, create the decoder instance.

4. Load the saved data back into `items` using the decoder's `decode` method. The only item of interest here would be the first parameter passed to `decode` . The decoder needs to know what type of data will be the result of the decode operation and you let it know by indicating that it will be an array of `ChecklistItem` objects.

This populates the array with exact copies of the `ChecklistItem` objects that were frozen into the Checklists.plist file.

You now have your `loadChecklistItems()` method, but it needs to be called from somewhere in order for this to work. There are several places from which you can do this.

Take a look at the current code in **ChecklistViewController.swift** — it would seem that using `viewDidLoad()` is the obvious choice since that's where we currently load the static data for the app. So let's clear out the static data items and simply load the saved data from `viewDidLoad`!

Load the saved data on app start

Here's what you need to do:

➤ Remove the existing lines for creating the five static `ChecklistItem` instances and the print statements from `viewDidLoad` and replace that with a call to `loadChecklistItems` as follows:

```
override func viewDidLoad() {
  super.viewDidLoad()
  navigationController?.navigationBar.prefersLargeTitles = true
  // Load items
  loadChecklistItems()
}
```

> **Note:** If you opted to enable large titles via the storyboard, then you wouldn't have the line immediately after the call to `super.viewDidLoad()`.

You don't need to add the comments in there but its always good to have some comments in your source so that you can understand your own code a month or two (or a few years) down the line :] But as I mentioned before, if you have good method names, comments are really unnecessary most of the time.

All that's new in the above (apart from the deleted code) is the addition of a call to `loadChecklistItems()` to ensure that the saved item data is loaded back when the view controller is first loaded.

➤ Run the app and make some changes to the to-do items. Press Stop to terminate the app. Start it again and notice that your changes are still there.

➤ Stop the app again. Go to the Finder window with the Documents folder and remove the Checklists.plist file. Run the app once more. You should now have an empty list of items.

➤ Add an item and notice that the Checklists.plist file re-appears.

Awesome! You've written an app that not only lets you add and edit data, but which also persists the data between sessions. These techniques form the basis of many, many apps.

Being able to use a navigation controller, show secondary screens, and pass data around through delegates are also essential iOS development skills.

Initializers

Methods named `init` are special in Swift. They are only used when you're creating new objects, to make those new objects ready for use.

Think of it as having bought new clothes. The clothes are in your possession (the memory for the object is allocated) but they're still in the bag. You need to go change and put the new clothes on (initialization) before you're ready to go out and party.

When you write the following to create a new object,

```
let item = ChecklistItem()
```

Swift first allocates a chunk of memory big enough to hold the new object and then calls `ChecklistItem`'s `init()` method with no parameters.

It is pretty common for objects to have more than one init method. Which one is used depends on the circumstances.

For example, amongst the `init` methods for `UITableViewController` you'll find — `init(nibName:bundle:)`, `init(style:)` and `init?(coder:)`. `init?(coder:)` is used when the view controller is instantiated from a storyboard. But you can also create a `UITableViewController` instance directly by calling either `init(nibName:bundle:)` or `init(style:)` . So, how you initialize an object depends on the circumstances.

The implementations of these `init` methods, whether they're just called `init()` or `init?(coder:)` or something else, always follow the same series of steps. When you write your own `init` methods, you need to stick to those steps as well.

This is the standard way to write an `init` method:

```
init() {
  // Put values into your instance variables and constants.

  super.init()

  // Other initialization code, such as calling methods, goes
here.
}
```

Note that unlike other methods, `init` does not have the `func` keyword.

Sometimes you'll see it written as `override init` or `required init?`. That is necessary when you're adding the `init` method to an object that is a subclass of some other object. Much more about that later.

The question mark is for when `init?` can potentially fail and return a `nil` value instead of a real object. You can imagine that decoding an object can fail if not enough information is present in the plist file.

Inside the `init` method, you first need to make sure that all your instance variables and constants have a value. Recall that in Swift all variables must always have a value, except for optionals. When you declare an instance variable you can give it an initial value (or initialize it), like so:

```
var checked = false
```

It's also possible to write just the variable name and its type (or declare the variable), but not give the variable a value yet:

```
var checked: Bool
```

In the latter case, you have to give this variable a value in your `init` method:

```
init() {
  checked = false
  super.init()
}
```

You must use either one of these approaches; if you don't give the variable a value at all, Swift considers this an error. The only exception is optionals, they do not need to have a value (in which case they are `nil`). Once you've given all your instance variables and constants values, you call `super.init()` to initialize the object's superclass. If you haven't done any object-oriented programming at all, you may not know what a *superclass* is. That's fine; we'll completely ignore this topic till later.

Just remember that sometimes objects need to send messages to something called `super` and if you forget to do this, bad things are likely to happen. After calling `super.init()`, you can do additional initialization, such as calling the object's own methods. You're not allowed to do that before the call to `super.init()` because Swift has no guarantee that your object's variables all have proper values until then.

You don't always need to provide an `init` method. If your `init` method doesn't need to do anything — if there are no instance variables to fill in — then you can leave it out completely and the compiler will provide one for you. As an example, take a look at `ChecklistItem` — it doesn't have an `init()` method since all its variables are initialized when they are declared.

Swift's rules for initializers can be a bit complicated, but fortunately, the compiler will remind you when you forget to provide an `init` method.

What next?

Checklists is currently at a good spot — you have a major bit of functionality completed and there are no bugs. This is a good time to take a break, put your feet up, and daydream about all the cool apps you'll soon be writing :]

It's also smart to go back and repeat those parts you're still a bit fuzzy about. Don't rush through these chapters — there are no prizes for finishing first. Rather than going fast, take your time to truly understand what you've been doing.

As always, feel free to change the app and experiment. Breaking things is allowed — even encouraged — here at UIKit Apprentice Academy!

You can find the project files for the app up to this point under **15-Saving-loading** in the Source Code folder.

Chapter 16: Lists

By Fahim Farook

Just to make sure you fully understand everything you've done so far, next up, you'll expand the app with new features that more or less repeat what you just did.

But I'll also throw in a few twists to keep it interesting…

The app is named *Checklists* for a reason: it allows you to keep more than one list of to-do items. So far though, the app has only supported a single list. Now you'll add the capability to handle multiple checklists.

In order to complete the functionality for this chapter, you will need two new screens, and that means two new view controllers:

1. `AllListsViewController` shows all the user's lists.
2. `ListDetailViewController` allows adding a new list and editing the name and icon of an existing list.


This chapter covers the following:

- **The All Lists view controllers:** Add a new view controller to show all the lists of to-do items.
- **The All Lists UI:** Complete the user interface for the All Lists screen.
- **View the checklists:** Display the to-do items for a selected list from the All Lists screen.
- **Manage checklists:** Add a view controller to add/edit checklists.

The All Lists view controller

You will first add `AllListsViewController`. This becomes the new main screen of the app.

When you're done, this is what it will look like:



The new main screen of the app

This screen is very similar to what you created before. It's a table view controller that shows a list of `Checklist` objects (not `ChecklistItem` objects).

From now on, I will refer to this screen as the "All Lists" screen, and to the screen that shows the to-do items from a single checklist as the "Checklist" screen.

Add the new view controller

➤ Right-click the Checklists group in the project navigator and choose **New File**. Choose the **Cocoa Touch Class** template (under iOS, Source).

In the next step, choose the following options:

- Class: **AllListsViewController**
- Subclass of: **UITableViewController**
- Also create XIB file: Make sure this is **not** checked
- Language: **Swift**

> **Note:** Make sure the "Subclass of" field is set to **UITableViewController**, not "UIViewController". Also be careful that Xcode didn't rename what you typed into Class to "AllListsTableViewController" with the extra word "Table" when you change the "Subclass of" value. It can be sneaky like that...

➤ Press **Next** and then **Create** to finish.

As you might remember from a previous chapter, the Xcode template for a table view controller puts a lot of boilerplate code that you don't need. Let's clean that up first.

You'll also put some fake data in the table view just to get it up and running. As you know by now, I always like to take as small a step as possible and then run the app to see if it's working. Once everything works, you can move forward and put in the real data.

Clean up the boilerplate code

➤ In **AllListsViewController.swift**, remove all the commented out code from `viewDidLoad`.

➤ Remove the `numberOfSections(in:)` method. Without it, there will always be a single section in the table view.

➤ Change the `tableView(_:numberOfRowsInSection:)` method to:

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return 3
}
```

➤ Implement the `tableView(_:cellForRowAt:)` method to put some text into the cells, just so there is something to see.

Note that the boilerplate code already contains a commented-out version of this method. You can uncomment it by removing the `/*` and `*/` surrounding the method, and make your changes there.

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: cellIdentifier, for: indexPath)
  cell.textLabel!.text = "List \(indexPath.row)"
  return cell
}
```

In `ChecklistViewController` the table view used prototype cells that you designed in Interface Builder. Just for the fun of it, in `AllListsViewController` you will take a different approach where you'll create the cells in code instead.

The code approach is simplicity itself — you simply dequeue the cell from the table view and then set the cell up as normal.

➤ At this point you'll get an error about `cellIdentifier` being unknown. Let's add a constant to the class for the cell identifier — you'll see why in a moment. Add the following to at the top of the class implementation, where you normally add instance variables:

```
let cellIdentifier = "ChecklistCell"
```

You're using `dequeueReusableCell(withIdentifier:)` here too, just as you did with prototype cells. However, we don't have a prototype cell here. So, we need a way to let the app know what type of table view cell (or rather cell class) is to be created for a call to `dequeueReusableCell(withIdentifier:)` with our custom cell identifier specified in the `cellIdentifier` constant.

To do that, we need to add a bit of code to `viewDidLoad` to register the cell identifier with the underlying table view.

➤ Add the following code to the end of `viewDidLoad`:

```
tableView.register(UITableViewCell.self, forCellReuseIdentifier:
cellIdentifier)
```

The above registers our cell identifier with the table view so that the table view knows which cell class should be used to create a new table view cell instance when a dequeue request comes in with that cell identifier. Also, in this case, we have registered the standard table view cell class as the one to be used for creating new cells, But if you wanted, you could also register custom table view cell classes here.

You should now see why we set up the cell identifier to be at the class level — because we need access to the identifier from at least two different methods.


➤ Remove all the other commented-out cruft from **AllListsViewController.swift**. Xcode puts it there to be helpful, but it also makes a mess of things.

Storyboard changes

The final step is to add the new view controller to the storyboard.


➤ Open the storyboard and drag a new **Table View Controller** onto the canvas. Put it somewhere near the initial navigation controller.

➤ **Control-drag** from the navigation controller to this new table view controller:



Control-drag from the navigation controller to the new table view controller

From the pop-up menu choose **Relationship Segue - root view controller**:



Relationships are also segues

This will break the existing connection between the navigation controller and the `ChecklistViewController` so that "Checklists" is no longer the app's main screen.


➤ Select the new table view controller and set its **Class** in the **Identity inspector** to **AllListsViewController**.

➤ Select the new view controller's Navigation Item in the Document Outline and then change its title to **Checklists** via the Attributes Inspector.

This will result in Xcode renaming the view controller in the Document Outline from All Lists View Controller to just Checklists — sometimes it won't happen till you restart Xcode. This is a bit confusing because there's a Checklists view controller already.

It's simple enough to fix the scene names. Normally, the scene name is based on either the underlying view controller name or the navigation item title. But you can set whatever you want as the scene name by simply changing the displayed title on the Document Outline :]

➤ Tap the new view controller in the Document Outline — the yellow circle, not the rectangle representing the scene — and then tap it again to put the title into edit mode. Then, just rename it to **All Lists**.



Rename scene


➤ Repeat the above step to rename the remaining Checklists scene to **Checklist** (note the missing "s" at the end).

You may want to reorganize your storyboard at this point to make everything look neat again. The All Lists scene goes in between the other scenes.

As I mentioned, you're not going to use prototype cells for this table view. It would be perfectly fine if you did, and as an exercise you could rewrite the code to use prototype cells later, but I want to show you another way of making table view cells.

➤ Delete the empty prototype cell from the All Lists scene by simply selecting the Table View Cell and pressing **delete** on your keyboard.

➤ **Control-drag** from the yellow circle icon at the top of All Lists scene on to the Checklist scene and create a **Show** segue.



Control-dragging from the All Lists scene to the Checklist scene

This adds a "push" transition from the All Lists screen to the Checklist screen. It also puts the navigation bar back on the Checklist scene (the one on the right).

➤ Double-click the navigation bar on the Checklist scene to change its title to **(Name of the Checklist)**. This is just placeholder text.

Fix the titles

➤ If you enabled/disabled large titles via the storyboard, then disable large titles for the Checklist scene by setting the Navigation Item's **Large Title** attribute to **Never**.

➤ If you configured large titles via code, the second screen, Checklist, will have the large title while the first one won't! This is because you originally set up large titles for ChecklistViewController.swift.

> **Exercise:** Can you fix the titles on your own so that the large titles are enabled by AllListsViewController.swift and the Checklist screen does not show a large title?

The change is simple enough to implement.

➤ Move the following lines of code from `viewDidLoad` in **ChecklistViewController.swift** to `viewDidLoad` in **AllListsViewController.swift**:

```
// Enable large titles
navigationController?.navigationBar.prefersLargeTitles = true
```

➤ Add this code to `viewDidLoad` in **ChecklistViewController.swift**:

```
// Disable large titles for this view controller
navigationItem.largeTitleDisplayMode = .never
```

In each case, the comments explain what the code does :]

Perform a segue via code

Note that the new segue isn't attached to any button or table view cell.

There is nothing on the All Lists screen that you can tap or otherwise interact with in order to trigger this segue. That means you have to perform the segue programmatically.

➤ Click on the new segue to select it, go to the **Attributes inspector** and give it the identifier **ShowChecklist**.

The segue **Kind** should be **Show (e.g. Push)** because you're pushing the Checklist View Controller onto the navigation stack when performing this segue.

➤ In **AllListsViewController.swift**, add the `tableView(_:didSelectRowAt:)` method:


```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  performSegue(withIdentifier: "ShowChecklist", sender: nil)
}
```

Recall that this table view delegate method is invoked when you tap a row.

Previously, a tap on a row would automatically perform the segue because you had hooked up the segue to the prototype cell. However, the table view for this screen isn't using prototype cells. Therefore, you have to perform the segue manually.

That's simple enough: just call `performSegue(withIdentifier:sender:)` with the name of the segue and things will start moving.

➤ Run the app. It should now look like this:



The first version of the All Lists screen (left). Tapping a row opens the Checklist screen (right).

Tap a row and the familiar `ChecklistViewController` slides into the screen.

You can tap the "Back" button in the top-left to go back to the main list. Now you're truly using the power of the navigation controller!

The All Lists UI

You're going to duplicate most of the functionality from the Checklist View Controller for this new All Lists screen. There will be a + button at the top that lets users add new checklists, they can do swipe-to-delete, and they can tap the disclosure button to edit the name of the checklist.

Of course, you'll also save the array of `Checklist` objects to the Checklists.plist file.

As you've already seen how this works, we'll go through the steps a bit quicker this time.

The data model

You begin by creating a data model object that represents a checklist.

➤ Add a new file to the project based on the **Cocoa Touch Class** template. Name it **Checklist** and make it a subclass of **NSObject**. Also make sure that the language is set to **Swift**.

This adds the file Checklist.swift to the project. Just like `ChecklistItem`, you're building `Checklist` on top of `NSObject`. As you found out previously, this is a requirement when you need to compare objects – in order to find a list item in an array of lists.

➤ Give **Checklist.swift** a `name` property:

```
import UIKit

class Checklist: NSObject {
  var name = ""
}
```

Next, you'll give `AllListsViewController` an array that will store these new `Checklist` objects.

➤ Add a new instance variable to **AllListsViewController.swift**:

```
var lists = [Checklist]()
```

This is an array that will hold the `Checklist` objects.

> **Note:** You can also write the above as follows:
>
> `var lists = Array<Checklist>()`
>
> The version with the square brackets is another instance of *syntactic sugar* for the complete notation, which is `Array<`*type of the objects to put in the array*`>`.
>
> You will see both forms used in Swift programs and they do exactly the same thing. Because arrays are used a lot, the designers of Swift included the handy shorthand with the square brackets.

As a first step, you will fill this new array with test data, which you'll do from `viewDidLoad()` as before. Remember that UIKit automatically invokes this method when the view controller is first loaded.

Dummy data

In **AllListsViewController.swift** you could add the following to `viewDidLoad()` — don't actually add it just yet, just read along with the description:

```
// 1
var list = Checklist()
list.name = "Birthdays"
lists.append(list)

// 2
list = Checklist()
list.name = "Groceries"
```

```
lists.append(list)

list = Checklist()
list.name = "Cool Apps"
lists.append(list)

list = Checklist()
list.name = "To Do"
lists.append(list)
```

You've seen something very much like it a while ago when you added the fake test data to `ChecklistViewController`. Here is what it does step-by-step:

1. Create a new `Checklist` object, give it a name, and add it to the array.
2. You create three more `Checklist` objects. Because you declared the local variable `list` as `var` instead of `let`, you can re-use it.

Notice how this is performing the same two steps for every new `Checklist` object you're creating?

```
list = Checklist()
list.name = "Name of the checklist"
```

It seems likely that every `Checklist` you'll ever make will also have a name. You can make this a requirement by writing your own `init` method that takes the name as a parameter. Then you can simply write:

```
list = Checklist(name: "Name of the checklist")
```

➤ Go to **Checklist.swift** and add the new `init` method:

```
init(name: String) {
  self.name = name
  super.init()
}
```

This initializer takes one parameter, `name`, and places it into the property called `name`.

Notice that while the parameter and property are both named `name` — they are two distinct entities. So, you use `self.name` to refer to the property (or instance variable, if you prefer that term).

If you used this code instead:

```
init(name: String) {
  name = name
  super.init()
}
```

Then Swift wouldn't understand that the first `name` referred to the property.

To disambiguate, you use `self`. Recall that `self` refers to the object that you're in, so `self.name` means the `name` variable of the current `Checklist` object.

➤ Go back to **AllListsViewController.swift** and add the following code to the end of `viewDidLoad()`, for real this time:

```
override func viewDidLoad() {
  . . .
  // Add placeholder data
  var list = Checklist(name: "Birthdays")
  lists.append(list)

  list = Checklist(name: "Groceries")
  lists.append(list)

  list = Checklist(name: "Cool Apps")
  lists.append(list)

  list = Checklist(name: "To Do")
  lists.append(list)
}
```

That's a bit shorter than what I showed you before, and it guarantees that new `Checklist` objects will now always have their `name` property filled in.

Note that you didn't write:

```
var list = Checklist.init(name: "Birthdays")
```

Even though the method is named `init`, it's not a regular method. Initializers are only used to construct new objects and you write that as:

```
var object = ObjectName(parameter1: value1, parameter2:
value2, . . .)
```

Depending on the parameters that you specified, Swift will locate the corresponding `init` method and call that.

But it's important to understand that you *can* write the initializer using the `init` method as in the first example above — it's not incorrect and there would be no compiler errors. It's just shorter to write the initializer as in the second example.

Clear? Great! Let's continue building the All Lists screen.

Display data in table view

➤ Change the `tableView(_:numberOfRowsInSection:)` method to return the number of objects in the new array:


```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return lists.count
}
```

➤ Finally, change `tableView(_:cellForRowAt:)` to fill in the cells for the rows:

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: cellIdentifier,
    for: indexPath)
  // Update cell information
  let checklist = lists[indexPath.row]
  cell.textLabel!.text = checklist.name
  cell.accessoryType = .detailDisclosureButton

  return cell
}
```

➤ Run the app. It should look like this:



The table view shows Checklist objects

You now have a table view with cells representing `Checklist` objects. The rest of the screen doesn't do much yet, but it's a start.

The many ways to make table view cells

Creating a new table view cell in `AllListsViewController` is a little more involved than how it was done in `ChecklistViewController`.

There you just did the following to obtain a new table view cell:

```
let cell = tableView.dequeueReusableCell(withIdentifier:
"ChecklistItem", for: indexPath)
```

But here you have three separate bits of code to accomplish the same:

```
// At the top of the class implementation
let cellIdentifier = "ChecklistCell"
// In viewDidLoad
tableView.register(
  UITableViewCell.self,
  forCellReuseIdentifier: cellIdentifier)
// In tableView(_:cellForRowAt:)
let cell = tableView.dequeueReusableCell(
  withIdentifier: cellIdentifier,
  for: indexPath)
```

The call to `dequeueReusableCell(withIdentifier:for:)` is still there, except that previously the storyboard had a prototype cell with that identifier and now it doesn't.

There are four ways that you can make table view cells:

1. Using prototype cells. This is the simplest and quickest way. You did this in `ChecklistViewController`.
2. Using static cells. You did this for the Add/Edit Item screen. Static cells are limited to screens where you know in advance which cells you'll have. The big advantage with static cells is that you don't need to provide any of the data source methods (`cellForRowAt` etc.).
3. Using a *nib* file. A nib (also known as a XIB) is like a mini storyboard that only contains a single customized `UITableViewCell` object. This is very similar to using prototype cells, except that you can do it outside of a storyboard.
4. By hand, like what you did above. This is fairly similar to how you were supposed to do it in the early days of iOS, but you can get a little bit more closer to the metal, so to speak.

When you create a cell by hand, you can specify a certain **cell style**, which gives you a cell with a preconfigured layout that already has labels and an image view.

For the All Lists scene you're using the "Default" style. Later on you'll switch it to "Subtitle", which gives the cell a second, smaller label below the main label. Then you'll see how to go really old school. :]

Using standard cell styles means you don't have to design your own cell layout. For many apps these standard layouts are sufficient, so that saves you some work.

Prototype cells and static cells can also use these standard cell styles. The default style for a prototype or static cell is "Custom", which requires you to use your own labels, but you can change that to one of the built-in styles via Interface Builder.

And finally, a gentle warning: Sometimes I see code that creates a new cell for every row rather than trying to reuse cells by dequeuing them. Don't do that! Always use one of the `dequeueReusableCell` methods — the table view will automatically create a new cell if it can't find an existing one to reuse.

Creating a new cell for each row will cause your app to slow down, as object creation is slower than simply re-using an existing object. Creating all these new objects also takes up more memory, a precious commodity on mobile devices. For the best performance, reuse those cells!

In case you hadn't noticed, there are two `dequeueReusableCell` variants — you'll learn about the second one later.

View the checklists

Right now, the data model consists of the `lists` array from `AllListsViewController` that contains a handful of `Checklist` objects. There is also a separate `items` array in `ChecklistViewController` with `ChecklistItem` objects.

You may have noticed that when you tap the name of a list, the Checklist screen slides into view but it currently always shows the same to-do items, regardless of which list you tapped on.

Each checklist should really have its own list of to-do items. You'll work on that later on, as this requires a significant change to the data model.

As a start, let's set the title of the Checklist screen to reflect the chosen checklist.

Set the title of the screen

➤ Add a new instance variable to **ChecklistViewController.swift**:

```
var checklist: Checklist!
```

I'll explain why the exclamation mark is necessary in a moment.

➤ Change `viewDidLoad` in **ChecklistViewController.swift** to:

```
override func viewDidLoad() {
  . . .
  title = checklist.name
}
```

This changes the title of the screen, which is shown in the navigation bar, to the name of the `Checklist` object.

You'll pass the necessary `Checklist` object to `ChecklistViewController` when the segue is performed.

➤ In **AllListsViewController.swift**, update `tableView(_:didSelectRowAt:)` to the following:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  let checklist = lists[indexPath.row]
  performSegue(
    withIdentifier: "ShowChecklist",
    sender: checklist)
}
```

As before, you use `performSegue()` to start the segue. This method has a `sender` parameter that you previously set to `nil`. Now you'll use it to send along the `Checklist` object from the row that the user tapped on.

You can put anything you want into `sender`. If the segue is performed by the storyboard, rather than manually like you do here, then `sender` will refer to the control that triggered it, for example, the `UIBarButtonItem` object for the Add button, or the `UITableViewCell` for a row in the table.

But because you start this particular segue by hand, you can put whatever is most convenient into `sender`.

Putting the `Checklist` object into the `sender` parameter doesn't pass it to `ChecklistViewController` yet. That happens in "prepare-for-segue", which you still need to add for this view controller.

➤ Add the `prepare(for:sender:)` method to **AllListsViewController.swift**:


```
// MARK: - Navigation
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
  if segue.identifier == "ShowChecklist" {
    let controller = segue.destination as!
ChecklistViewController
    controller.checklist = sender as? Checklist
  }
}
```

You've seen this method before. `prepare(for:sender:)` is called right before a segue happens from a view controller. Here you get a chance to set the properties of the new view controller before it becomes visible.

Inside `prepare(for:sender:)`, you need to pass the `ChecklistViewController` the `Checklist` object from the row that the user tapped. That's why you put that object in the `sender` parameter earlier. Instead, you could have temporarily stored the `Checklist` object in an instance variable, but passing it along in the `sender` parameter is much easier and cleaner.

All of this happens a short time after `ChecklistViewController` is instantiated but just before `ChecklistViewController`'s view is loaded. That means its `viewDidLoad()` method is called after `prepare(for:sender:)`.

At this point, the view controller's `checklist` property is set to the `Checklist` object from `sender`, and `viewDidLoad()` can set the title of the screen accordingly.




The steps involved in performing a segue

This sequence of events is why the `checklist` property is declared as `Checklist!` with an exclamation point. That allows its value to be temporarily `nil` until `viewDidLoad()` happens.

`nil` is normally not an allowed value for non-optional variables in Swift, but by using the `!` you override that.

Does this sound an awful lot like optionals? The exclamation point turns `checklist` into a special kind of optional. It's very similar to optionals with a question mark, but you don't have to write `if let` to unwrap it. Such *implicitly unwrapped* optionals should be used sparingly and with care, as they do not have any of the anti-crash protection that normal optionals do.

➤ Run the app and notice that when you tap the row for a checklist, the next screen properly displays the checklist title.



The name of the chosen checklist now appears in the navigation bar

Note that passing the `Checklist` object to the `ChecklistViewController` does not make a copy of it. You only pass the view controller a *reference* to that object — any changes the user makes to that `Checklist` object are also seen by `AllListsViewController`. Both view controllers have access to the exact same `Checklist` object. You'll use that to your advantage later in order to add new `ChecklistItems` to the selected `Checklist`.

★ ★ ★

Type Casts

In `prepare(for:sender:)` you do this:

```
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
  . . .
  controller.checklist = sender as? Checklist
  . . .
}
```

What is that `as? Checklist` bit?

If you've been paying attention — of course you have! — then you've seen this "as something" used quite a few times now. This is known as a *type cast*.

A type cast tells Swift to interpret a value as having a different data type.

It's the opposite of what happens to certain actors in the movies. For them, typecasting results in always playing the same character; in Swift, a type cast actually changes the character of an object.

Here, `sender` has type `Any?`, meaning that it can be any sort of object: a `UIBarButtonItem`, a `UITableViewCell`, or in this case, a `Checklist`. Thanks to the question mark it can even be `nil`.

But the `controller.checklist` property always expects a `Checklist` object – it wouldn't know what to do with a `UITableViewCell`... Hence, Swift demands that you only put `Checklist` objects into the `checklist` property.

By writing `sender as? Checklist`, you tell Swift that it can safely treat `sender` as a `Checklist` object, if it can be used as a `Checklist` object, or to send `nil` if if there is an issue.

Another example of a typecast is:

```
let controller = segue.destination as! ChecklistViewController
```

The segue's `destination` property refers to the view controller on the receiving end of the segue. But obviously the engineers at Apple could not predict beforehand that we would call it `ChecklistViewController`. Unlike the previous `as?` type cast, this one force unwraps the value to be of the type that you specified, there is not supposed to be any possibility of the type cast failing.

So you have to cast it from its generic type (`UIViewController`) to the specific type used in this app (`ChecklistViewController`) before you can access any of the properties specific to `ChecklistViewController`.

Don't worry if some of this goes over your head right now. You'll see plenty more examples of type casting in action.

The main reason you need all these type casts is for interoperability with the iOS frameworks that are written in Objective-C. Swift is less forgiving about types than Objective-C and requires you to be much more explicit about specifying the types of the various data items you work with.



Manage checklists

Let's quickly add the Add / Edit Checklist screen. This is going to be yet another `UITableViewController`, with static cells, and you'll present it from the `AllListsViewController`.

If the previous sentence made perfect sense to you, then you're getting the hang of this!

Add the view controller

➤ Add a new file to the project, **ListDetailViewController.swift**. You can use the **Swift File** template for this since you'll be adding the complete view controller implementation by hand.

➤ Add the following to **ListDetailViewController.swift**:

```
import UIKit

protocol ListDetailViewControllerDelegate: AnyObject {
  func listDetailViewControllerDidCancel(
```

```
    _ controller: ListDetailViewController)

  func listDetailViewController(
    _ controller: ListDetailViewController,
    didFinishAdding checklist: Checklist
  )

  func listDetailViewController(
    _ controller: ListDetailViewController,
    didFinishEditing checklist: Checklist
  )
}

class ListDetailViewController: UITableViewController,
UITextFieldDelegate {
  @IBOutlet var textField: UITextField!
  @IBOutlet var doneBarButton: UIBarButtonItem!

  weak var delegate: ListDetailViewControllerDelegate?

  var checklistToEdit: Checklist?
}
```

I simply took the contents of **ItemDetailViewController.swift** and changed the names. Also, instead of a property for a `ChecklistItem` you're now dealing with a `Checklist`.

➤ Add the `viewDidLoad()` method:

```
override func viewDidLoad() {
  super.viewDidLoad()

  if let checklist = checklistToEdit {
    title = "Edit Checklist"
    textField.text = checklist.name
    doneBarButton.isEnabled = true
  }
}
```

This changes the title of the screen if the user is editing an existing checklist, and it puts the checklist's name into the text field.

➤ Also add the `viewWillAppear()` method to pop up the keyboard:

```
override func viewWillAppear(_ animated: Bool) {
  super.viewWillAppear(animated)
  textField.becomeFirstResponder()
}
```

The Cancel and Done buttons

➤ Add the action methods for the Cancel and Done buttons:

```
// MARK: - Actions
@IBAction func cancel() {
  delegate?.listDetailViewControllerDidCancel(self)
}

@IBAction func done() {
  if let checklist = checklistToEdit {
    checklist.name = textField.text!
    delegate?.listDetailViewController(
      self,
      didFinishEditing: checklist)
  } else {
    let checklist = Checklist(name: textField.text!)
    delegate?.listDetailViewController(
      self,
      didFinishAdding: checklist)
  }
}
```

This should look familiar as well. It's essentially the same as what the Add/Edit Item screen does. To create the new `Checklist` object in `done()`, you use its `init(name:)` method and pass the contents of `textField.text` as the `name` parameter.

You cannot write this the way you did for `ChecklistItems` – this won't work:

```
let checklist = Checklist()
checklist.name = textField.text!
```

Because `Checklist` does not have an `init()` method that takes no parameters, writing `Checklist()` results in a compiler error. It only has an `init(name:)` method, and you must always use that initializer to create new `Checklist` objects.

Other functionality

➤ Also make sure the user cannot select the table cell with the text field:

```
// MARK: - Table View Delegates
override func tableView(
  _ tableView: UITableView,
  willSelectRowAt indexPath: IndexPath
) -> IndexPath? {
  return nil
}
```

➤ And, finally, add the text field delegate methods that enable or disable the Done button depending on whether the text field is empty or not.

```
// MARK: - Text Field Delegates
func textField(
  _ textField: UITextField,
  shouldChangeCharactersIn range: NSRange,
  replacementString string: String
) -> Bool {
  let oldText = textField.text!
  let stringRange = Range(range, in: oldText)!
  let newText = oldText.replacingCharacters(
    in: stringRange,
    with: string)
  doneBarButton.isEnabled = !newText.isEmpty
  return true
}


func textFieldShouldClear(_ textField: UITextField) -> Bool {
  doneBarButton.isEnabled = false
  return true
}
```

Again, this is the same as what you did in `ItemDetailViewController` – there shouldn't be any surprises.

Let's create the user interface for this new view controller in Interface Builder.

The storyboard

➤ Open the storyboard. Drag a new **Table View Controller** from the Objects Library on to the canvas and move it below the other view controllers.



Adding a new table view controller to the canvas

➤ Select the new Table View Controller and go to the **Identity inspector**. Change its class to **ListDetailViewController**.

➤ **Control-drag** from the yellow circle at the top of the All Lists scene to the new scene. Select **Show** from the Manual Segue section of the popup menu.

➤ Set the navigation bar title to **Add Checklist**. The new scene should now appear as Add Checklist scene in the Document Outline.

➤ Select the Navigation Item and set **Large Title** in the Attributes inspector to **Never** — this saves you from having to add code to the view controller to turn off large titles.

➤ Add **Cancel** and **Done** bar button items to the navigation item and hook them up to the action methods in the Add Checklist scene. Also connect the Done button to the **doneBarButton** outlet and uncheck its **Enabled** option.

Remember, you can Control-drag from a button to the view controller to connect it to an action method. To connect an outlet, do it the other way around: Control-drag from the view controller to the button.

➤ Change the table view to **Static Cells**, style **Grouped**. You only need one cell, so remove the bottom two.

➤ Drop a new **Text Field** on to the cell, adjust it's size and position and then set up **left**, **top**, **right**, and **bottom** Auto Layout constraints. Then, set the following configuration options via the **Attributes inspector**:

- Font size: **17**
- Placeholder text: **Name of the List**
- Border Style: **none**
- (Optional) Clear Button: **Appears while editing**
- Adjust to Fit: **disabled**
- Capitalization: **Sentences**


- Return Key: **Done**
- Auto-enable Return key: **checked**

➤ Control-drag from the view controller to the Text Field and connect it to the **textField** outlet.

➤ Then Control-drag the other way around, from the Text Field back to the view controller, and choose **delegate** under **Outlets**. Now the view controller is the delegate for the text field.

➤ Connect the text field's **Did End on Exit** event to the **done** action on the view controller.

This completes setting up the new view controller to be the Add / Edit Checklist screen:



The finished design of the ListDetailViewController

Connect the view controllers


➤ Go to the **All Lists** scene (the one titled "Checklists") and drag a **Bar Button Item** on to its right navigation item. Change it to an **Add** button.

➤ **Control-drag** from this new bar button to the Add Checklist scene below to add a new **Show** segue.

➤ Click on the new segue and name it **AddChecklist**.

➤ Click on the other segue (the one not connected the the Add button) and name it **EditChecklist**.

Your storyboard should now look something like this:



The full storyboard: 1 navigation controller, 4 table view controllers

Set up the delegates

Almost there. You still have to make the `AllListsViewController` the delegate for the `ListDetailViewController` and then you're done. Again, it's very similar to what you did before.

➤ Declare the All Lists view controller to conform to the delegate protocol by adding `ListDetailViewControllerDelegate` to its class line.

You do this in **AllListsViewController.swift**:

```
class AllListsViewController: UITableViewController,
ListDetailViewControllerDelegate {
```

➤ Still in **AllListsViewController.swift**, extend `prepare(for:sender:)` to:

```
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
  if segue.identifier == "ShowChecklist" {
    . . .
  } else if segue.identifier == "AddChecklist" {
    let controller = segue.destination as!
ListDetailViewController
    controller.delegate = self
  }
}
```

The first `if` doesn't change. You've added a second `if` for the new "AddChecklist" segue that you just defined in the storyboard.

As before, you look for the view controller and set its `delegate` property to `self`.

➤ Next, implement the following delegate methods in **AllListsViewController.swift**:

```
// MARK: - List Detail View Controller Delegates
func listDetailViewControllerDidCancel(
  _ controller: ListDetailViewController
) {
  navigationController?.popViewController(animated: true)
}

func listDetailViewController(
  _ controller: ListDetailViewController,
  didFinishAdding checklist: Checklist
) {
  let newRowIndex = lists.count
  lists.append(checklist)

  let indexPath = IndexPath(row: newRowIndex, section: 0)
  let indexPaths = [indexPath]
  tableView.insertRows(at: indexPaths, with: .automatic)

  navigationController?.popViewController(animated: true)
}

func listDetailViewController(
  _ controller: ListDetailViewController,
  didFinishEditing checklist: Checklist
) {
  if let index = lists.firstIndex(of: checklist) {
    let indexPath = IndexPath(row: index, section: 0)
    if let cell = tableView.cellForRow(at: indexPath) {
```

```
        cell.textLabel!.text = checklist.name
      }
    }
    navigationController?.popViewController(animated: true)
  }
```

These methods are called when the user presses Cancel or Done inside the new Add/Edit Checklist screen.


None of this should be confusing — it's exactly what you did before but now for the `ListDetailViewController` and `Checklist` objects.

➤ Also add the table view data source method that allows the user to delete checklists:

```
  override func tableView(
    _ tableView: UITableView,
    commit editingStyle: UITableViewCell.EditingStyle,
    forRowAt indexPath: IndexPath
  ) {
    lists.remove(at: indexPath.row)

    let indexPaths = [indexPath]
    tableView.deleteRows(at: indexPaths, with: .automatic)
  }
```

➤ Run the app. Now you can add new checklists and delete them again:



Adding new lists

Note: If the app crashes, then go back and make sure you made all the connections properly in Interface Builder. It's really easy to miss just one tiny thing, but even the tiniest of mistakes can bring the app crashing down in flames...

You can't edit the names of existing lists yet though. That requires one last addition to the code.

To bring up the Edit Checklist screen, the user taps the blue accessory button in the `ChecklistViewController` that triggered a segue. You could use a segue here too. If you want to go that route, you've already set up a segue named "EditChecklist" on the storyboard that you can use for this purpose. But I want to show you another way.

This time you're not going to use a segue at all, but load the new view controller by hand from the storyboard. Just because you can — and because it is good to know multiple ways to do the same thing.

Load a view controller via code

➤ Add the following `tableView(_:accessoryButtonTappedForRowWith:)` method to **AllListsViewController.swift**. This method comes from the table view delegate protocol and the name is hopefully obvious enough for you to guess what it does.

```
override func tableView(
  _ tableView: UITableView,
  accessoryButtonTappedForRowWith indexPath: IndexPath
) {
  let controller = storyboard!.instantiateViewController(
    withIdentifier: "ListDetailViewController") as!
ListDetailViewController
  controller.delegate = self

  let checklist = lists[indexPath.row]
  controller.checklistToEdit = checklist

  navigationController?.pushViewController(
    controller,
    animated: true)
}
```

In this method, you create the view controller object for the Add/Edit Checklist screen and push it on to the navigation stack. This is roughly equivalent to what a segue would do behind the scenes. The view controller is embedded in a storyboard and you have to ask the storyboard object to load it.


Where did you get that storyboard object? As it happens, each view controller has a `storyboard` property that refers to the storyboard the view controller was loaded from. You can use that property to do all kinds of things with the storyboard, such as instantiating other view controllers.

The `storyboard` property is optional because view controllers are not always loaded from a storyboard. But this one is, which is why you can use `!` to *force unwrap* the optional. It's like using `if let`, but because you can safely assume `storyboard` will not be `nil` in this app, you don't have to unwrap it inside an `if` statement.

The call to `instantiateViewController(withIdentifier:)` takes an identifier string, `ListDetailViewController`. That is how you ask the storyboard to create the new view controller. In your case, this will be the `ListDetailViewController`. Note that the identifier does not have to match the view controller class name — it could be any unique string value — even though we opted to use the view controller class name here.

You still have to set this identifier on the navigation controller; otherwise the storyboard won't be able to find it. And if you try to run the app without setting the identifier, it will crash.

➤ Open the storyboard and select the List Detail View Controller. Go to the **Identity inspector** and set **Storyboard ID** to **ListDetailViewController**:



Setting the storyboard identifier

➤ That should do the trick. Run the app and tap some detail disclosure buttons.

If the app crashes, make sure the storyboard is saved before you press Run.

Are you still with me?

If at this point your eyes are glazing over and you feel like giving up: don't. Learning new things is hard and programming doubly so. Set the book aside, sleep on it, and come back in a few days.

Chances are that in the mean time you'll have an a-ha! moment where the thing that didn't make any sense suddenly becomes clear as day.

If you have specific questions, join us on the forums at: forums.raywenderlich.com. I am around most of the time and respond to questions fast — if I'm around. Many of our community members do as well. Don't be embarrassed to ask for help!

You can find the project files for the app up to this point under **16-Lists** in the Source Code folder.

Chapter 17: Improved Data Model

By Fahim Farook

Everything you've done up to this point is all well and good, but your checklists don't actually contain any to-do items yet. Or rather, if you select a checklist, you see the same old items for every list! There is no connection between the selected list and the items displayed for that list.


It's time for you to fix that. You'll do so by way of the following steps:

- **The new data model:** Update the data model so that the to-do items for a list are saved along with the list.
- **Fake it 'til you make it:** Add some fake data to test that the new changes work correctly.
- **Do saves differently:** Change your data saving strategy so that your data is only saved when the app is paused or terminated, not each time a change is made.
- **Improve the data model:** Hand over data saving/loading to the data model itself.

The new data model

So far, the list of to-do items and the actual checklists have been separate from each other.

Let's change the data model to look like this:



Each Checklist object has an array of ChecklistItem objects

There will still be the `lists` array that contains all the `Checklist` objects, but each of these `Checklist` instances will have its own array of `ChecklistItem` objects.

The to-do item array

➤ Add a new property to **Checklist.swift**:

```
class Checklist: NSObject {
  var name = ""
  var items = [ChecklistItem]()     // add this line
  . . .
```

This creates a new empty array that can hold `ChecklistItem` objects and assigns it to the `items` property.

If you're a stickler for completeness, you can also write it as follows:

```
var items: [ChecklistItem] = [ChecklistItem]()
```

I personally don't like this way of declaring variables because it violates the "DRY" principle – **D**on't **R**epeat **Y**ourself. Fortunately, thanks to Swift's type inference, you can save yourself some keystrokes. Another way you'll see it written sometimes is:

```
var items: [ChecklistItem] = []
```

The notation `[]` means: make an empty array of the specified type. There is no type inference at play there since you have to specify the type explicitly. If you don't specify a type and write the above line as:

```
var items = []
```

You will get an error since the compiler cannot determine the type of the array. That makes sense, right? Regardless of the way you choose to write it, the `Checklist` object now contains an array of `ChecklistItem` objects. Initially, that array is empty.

Pass the array

Earlier you fixed `prepare(for:sender:)` in AllListsViewController.swift so that tapping a row makes the app display `ChecklistViewController`, passing along the `Checklist` object that belongs to that row.

Currently `ChecklistViewController` still gets the `ChecklistItem` objects that it displays from its own private `items` array. You will change that so it reads from the `items` array inside the `Checklist` object instead.

➤ Remove the `items` instance variable from **ChecklistViewController.swift.**

➤ Then, anywhere it says `items`, change it to say `checklist.items` instead.

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return checklist.items.count
}
```

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  . . .
  let item = checklist.items[indexPath.row]
  . . .
}
```

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  . . .
  let item = checklist.items[indexPath.row]
  . . .
}
```

```
override func tableView(
  _ tableView: UITableView,
  commit editingStyle: UITableViewCellEditingStyle,
  forRowAt indexPath: IndexPath
) {
  checklist.items.remove(at: indexPath.row)
  . . .
}
```

```
func itemDetailViewController(
  _ controller: ItemDetailViewController,
  didFinishAdding item: ChecklistItem
) {
  let newRowIndex = checklist.items.count
  checklist.items.append(item)
  . . .
}
```

```
func itemDetailViewController(
  _ controller: ItemDetailViewController,
  didFinishEditing item: ChecklistItem
) {
  if let index = checklist.items.firstIndex(of:item) {
  . . .
}
```

```
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
    . . .
    controller.itemToEdit = checklist.items[indexPath.row]
    . . .
}
```

➤ Delete the following methods from **ChecklistViewController.swift**.

Tip: You may want to set aside the code from these methods in a temporary file somewhere; shortly you'll be using them again in a slightly modified form.

- `func documentsDirectory()`
- `func dataFilePath()`
- `func saveChecklistItems()`
- `func loadChecklistItems()`

You added these methods to load and save the checklist items from a file. That is no longer the responsibility of this view controller. It is better, from a design perspective, for the `Checklist` object to do that.

Loading and saving data model objects really belongs in the data model itself, rather than in a controller.

But before you get to that, let's first test whether these changes were successful. Xcode is throwing up a few errors because you still call `saveChecklistItems()` and `loadChecklistItems()` from several places in the code. You should remove those lines, as you will soon be saving the items from a different place.

➤ Remove the lines that call `saveChecklistItems()` and `loadChecklistItems()`.

➤ Press ⌘+**B** to make sure the app builds without errors.

Fake it 'til you make it

Let's add some fake data to the various `Checklist` objects so that you can test whether this new design actually works.

Add fake to-do data

In `AllListsViewController`'s `viewDidLoad()` you already put fake `Checklist` objects into the `lists` array. It's time to add something new to this method.

➤ Add the following to the bottom of **AllListsViewController.swift**'s `viewDidLoad()`:

```
// Add placeholder item data
for list in lists {
  let item = ChecklistItem()
  item.text = "Item for \(list.name)"
  list.items.append(item)
}
```

This introduces something you haven't seen before: the `for in` statement. Like `if`, this is a special language construct.

★ ★ ★

Programming language constructs

For the sake of review, let's go over the programming language stuff you've already seen. Most modern programming languages offer at least the following basic building blocks:

- The ability to remember values by storing things into variables. Some variables are simple, such as `Int` and `Bool`. Others can store objects — `ChecklistItem`, `UIButton` — or even collections of objects such as `Array`.
- The ability to read values from variables and use them for basic arithmetic — multiply, add — and comparisons — greater than, not equals, etc.
- The ability to make decisions. You've already seen the `if` statement, but there is also a `switch` statement that is shorthand for `if` with many `else ifs`.
- The ability to group functionality into units such as methods and functions. You can call those methods and receive back a result value that you can then use in further computations.
- The ability to bundle functionality (methods) and data (variables) together into objects.

- The ability to execute one or more lines of code inside a `do` block and to `catch` any errors thrown via a `try` statement. Or, to simply bypass the `do` block by using a `try?` statement instead.
- The ability to repeat a set of statements more than once. This is what the `for in` statement does. There are other ways to perform repetitions as well: `while` and `repeat`. Endlessly repeating things is what computers are good at.

Everything else is built on top of these building blocks. You've seen most of these already, but repetitions (or **loops** in programmer talk) are new.

If you grok the concepts from this list, you're well on your way to becoming a software developer. And if not, well, just hang in there!



The for loop

Let's go through that `for` loop line-by-line:

```
for list in lists {
  . . .
}
```

This means the following: for every `Checklist` object in the `lists` array, perform the statements between the curly braces.

The first time through the loop, the temporary `list` variable will hold a reference to the Birthdays checklist, as that is the first `Checklist` object that you created and added to the `lists` array.

Inside the loop you do:

```
let item = ChecklistItem()
item.text = "Item for \(list.name)"
list.items.append(item)
```

This should be familiar. You first create a new `ChecklistItem` object. Then you set its `text` property to "Item for Birthdays" because the `\(…)` placeholder gets replaced with the name of the `Checklist` object, `list.name`, which is "Birthdays".

Finally, you add this new `ChecklistItem` to the Birthdays `Checklist` object, or rather, to its `items` array.

That concludes the first pass through this loop. Now the `for in` statement will look at the `lists` array again and sees that there are three more `Checklist` objects in that array. So it puts the next one, Groceries, into the `list` variable and the process repeats.

This time the text is "Item for Groceries", which is put into its own `ChecklistItem` object that goes into the `items` array of the Groceries `Checklist` object.

After that, the loop adds a new `ChecklistItem` with the text "Item for Cool Apps" to the Cool Apps checklist, and "Item for To Do" to the To Do checklist.

Then there are no more objects left to look at in the `lists` array and the loop ends.

Using loops will often save you a lot of time. You could have written this code as follows:

```
var item = ChecklistItem()
item.text = "Item for Birthdays"
lists[0].items.append(item)

item = ChecklistItem()
item.text = "Item for Groceries"
lists[1].items.append(item)

item = ChecklistItem()
item.text = "Item for Cool Apps"
lists[2].items.append(item)

item = ChecklistItem()
item.text = "Item for To Do"
lists[3].items.append(item)
```


That's very repetitive, which is a good sign it's better to use a loop. Imagine if you had 100 `Checklist` objects... would you be willing to copy-paste that code a hundred times? I'd rather use a loop.

Most of the time you won't even know in advance how many objects you'll have, so it's impossible to write it all out by hand. By using a loop you don't need to worry about that. The loop will work just as well for three items as for three hundred.

As you can imagine, loops and arrays work quite well together.

➤ Run the app. You'll see that each checklist now has its own set of items.

Play with it for a minute, remove items, add items, and verify that each list indeed is completely separate from the others.



Each Checklist now has its own items

The new load/save code

Let's put the load/save code back in. This time you'll make `AllListsViewController` do the loading and saving. Yes, I know I said that `Checklist` should handle its own loading/saving and we'll get to that soon …

➤ Add the following to **AllListsViewController.swift** — you may want to copy this from that temporary file you might (or might not) have created, but be sure to make the changes mentioned in the comments:

```
// MARK: - Data Saving
func documentsDirectory() -> URL {
  let paths = FileManager.default.urls(
    for: .documentDirectory,
    in: .userDomainMask)
  return paths[0]
}

func dataFilePath() -> URL {
  return
documentsDirectory().appendingPathComponent("Checklists.plist")
}

// this method is now called saveChecklists()
func saveChecklists() {
  let encoder = PropertyListEncoder()
  do {
    // You encode lists instead of "items"
    let data = try encoder.encode(lists)
    try data.write(
      to: dataFilePath(),
      options: Data.WritingOptions.atomic)
  } catch {
    print("Error encoding list array: \
(error.localizedDescription)")
  }
```

```
  }

  // this method is now called loadChecklists()
  func loadChecklists() {
    let path = dataFilePath()
    if let data = try? Data(contentsOf: path) {
      let decoder = PropertyListDecoder()
      do {
        // You decode to an object of [Checklist] type to lists
        lists = try decoder.decode(
          [Checklist].self,
          from: data)
      } catch {
        print("Error decoding list array: \
(error.localizedDescription)")
      }
    }
  }
```

This is mostly identical to what you had before in `ChecklistViewController`, except that you load and save the `lists` array instead of the `items` array. Note that the decode type is now `[Checklist].self` instead of `[ChecklistItem].self`. Also, the names of the methods changed slightly, as well as the error messages for the `catch` blocks.

➤ Change `viewDidLoad()` to:

```
  override func viewDidLoad() {
    super.viewDidLoad()
    navigationController?.navigationBar.prefersLargeTitles = true
    tableView.register(
      UITableViewCell.self,
      forCellReuseIdentifier: cellIdentifier)
    // Load data
    loadChecklists()
  }
```

This gets rid of the test data you put there earlier and makes the `loadChecklists()` method do all the work.

You also have to make the `Checklist` object support the `Codable` protocol — but as you know, that's just a simple change.

➤ Add the `Codable` protocol in **Checklist.swift**:

```
  class Checklist: NSObject, Codable {
```

➤ **Important:** Before you run the app, remove the old **Checklists.plist** file from the Simulator's Documents folder.

If you don't, the app will most probably throw up an error message in the Console about a decoding error because the internal format of the file no longer corresponds to the new data you're loading and saving. This is because the Swift `Codable` protocol handles data encoding/decoding in a safe fashion.

Weird crashes

When I first wrote this book, I didn't think to remove the Checklists.plist file before running the app. That was a mistake, but the app appeared to work fine… until I added a new checklist. At that point the app aborted with a strange error message from `UITableView` that made no sense at all.

I started to wonder whether I tested the code properly. But then I thought of the old file, removed it and ran the app again. It worked perfectly. Just to make sure it was the fault of that file, I put a copy of the old file back and ran the app again. Sure enough, when I tried to add a new checklist it crashed.

The explanation for this kind of error is that somehow the code managed to load the old file, even though its format no longer corresponded to the new data model. This put the table view into a bad state. Any subsequent operations on the table view caused the app to crash. Do note though that this was before `Codable` when the book used a different mechanism for saving/loading data.

You'll run into this type of bug every so often, where the crash isn't directly caused by what you're doing but by something that went wrong earlier on. These kinds of bugs can be tricky to solve, because you can't fix them until you find the true cause.

There is a section devoted to debugging techniques towards the end of the book because it's inevitable that you'll introduce bugs in your code. Knowing how to find and eradicate bugs is an essential skill that any programmer should master – if only to save you a lot of time and aggravation!

➤ Run the app and add a checklist and a few to-do items.

➤ Exit the app using the Xcode Stop button and run it again. You'll see that the list is empty again. All your to-do items are gone!

You can add all the checklists and items you want, but nothing gets saved anymore. What's going on here?

Do saves differently

Previously, you saved the data whenever the user changed something: adding a new item, deleting an item, and toggling a checkmark all caused Checklists.plist to be re-saved. That used to happen in `ChecklistViewController`.

However, you just moved the saving logic to `AllListsViewController`. How do you make sure changes to the to-do items get saved now? The `AllListsViewController` doesn't know when a checkmark is toggled on or off.

You could give `ChecklistViewController` a reference to the `AllListsViewController` and have it call its `saveChecklists()` method whenever the user changes something, but that introduces a *child-parent dependency* and you've been trying hard to avoid those (ownership cycles, remember?).

★ ★ ★

Parents and their children


The terms *parent* and *child* are common in software development.

A parent is an object higher up in some hierarchy; a child is an object lower in the hierarchy.

In this case, the "hierarchy" represents the navigation flow between the different screens of the app.

The All Lists screen is the parent of the Checklist screen, because All Lists was "born" first. It creates a new `ChecklistViewController` "baby" every time the user views the item list for a checklist.

Likewise, All Lists is also the parent of the List Detail screen. The Item Detail screen, however, is the child of the Checklist view controller.



Generally speaking, it's OK if the parent knows everything about its children, but not the other way around — just like in real life, every parent has horrible secrets they don't want their kids to know about... or so I've been told.

As a result, you don't want parent objects to be dependent on their child objects, but the other way around is fine. So `ChecklistViewController` asking `AllListsViewController` to do things is a big no-no.



The new saving strategy

You may think: ah, I could use a delegate for this. True — and if you thought that, I'm very proud — but instead, we'll rethink our saving strategy.

Is it really necessary to save changes all the time? While the app is running, the data model sits in working memory and is always up-to-date.

The only time you have to load anything from the file (the long-term storage memory) is when the app first starts up, but never afterwards. From then on you always make the changes to the objects in the working memory.

But when changes are made, the file becomes out-of-date. That is why you save those changes – to keep the file in sync with what is in memory.

The reason you save to a file is so that you can restore the data model in working memory after the app gets terminated. But until that happens, the data in the short-term working memory will do just fine.

You just need to make sure that you save the data to the file just before the app is terminated. In other words, the only time you save is when you actually need to keep the data safe.

Not only is this more efficient, especially if you have a lot of data, it also is simpler to program. You no longer need to worry about saving every time the user makes a change to the data, only right before the app terminates.

There are three situations in which an app can terminate:

1. While the user is running the app. This doesn't happen very often anymore, but earlier versions of iOS did not support multitasking apps. Receiving an incoming phone call, for example, would kill the currently running app. As of iOS 4, the app will simply be suspended and sent to the background when that happens.

   There are still situations where iOS may forcefully terminate a running app, for example, if the app becomes unresponsive or runs out of memory.

2. When the app is suspended. Most of the time iOS keeps running apps around for a long time. Their data is frozen in memory and no computations are taking place. When you resume a suspended app, it literally continues from where it left off.

   Sometimes the OS needs to make room for an app that requires a lot of working memory — often a game — and then it simply kills the suspended apps and wipes them from memory. The suspended apps are not notified when this happens.

3. The app crashes. There are ways to detect crashes, but handling them can be very tricky. Trying to deal with the crash may actually make things worse. The best way to avoid crashes is to make no programming mistakes! :]

Fortunately for us, iOS will inform the app about significant changes such as, "you are about to be terminated", and, "you are about to be suspended". You can listen for these events and save your data at that point. That will ensure the on-file representation of the data model is always up-to-date when the app does terminate.

Save changes on app termination

The ideal place for handling app termination notifications is inside the **scene delegate**. You haven't spent much time with this object before, but every app has one. Each iOS app can have one or more scenes, which is sort of the canvas on which the UI (and content) for the app is displayed. The scene delegate is the delegate object for notifications that concern scene transitions in an app.

This is where you receive the "scene will terminate" and "scene will be suspended" notifications.

In fact, if you look inside **SceneDelegate.swift**, you'll see the methods:

```
func sceneDidDisconnect(_ scene: UIScene)
```

And:

```
func sceneDidEnterBackground(_ scene: UIScene)
```

There are a few others, but these are the ones you need. The Xcode template puts helpful comments inside these methods, so you know what to do with them.

Now the trick is, how do you call `AllListsViewController`'s `saveChecklists()` method from these delegate methods? The scene delegate does not know anything about `AllListsViewController` — at least, not yet.

You have to use some trickery to find the All Lists View Controller from within the scene delegate.

➤ Add this new method to **SceneDelegate.swift**:

```
// MARK: - Helper Methods
func saveData() {
  let navigationController = window!.rootViewController as!
UINavigationController
  let controller = navigationController.viewControllers[0] as!
AllListsViewController
  controller.saveChecklists()
}
```

The `saveData()` method looks at the scene's — or rather, the scene delegate's — `window` property to find the `UIWindow` object that contains the full UI hierarchy for your app.

`UIWindow` is the top-level container for all your app's views. There is only one `UIWindow` object per scene in your iOS app. On iOS, when you want to have multiple windows, you need to create additional scenes. But that's not something we will concentrate on at this point.

Exercise: Can you explain why you wrote `window!` with an exclamation point?

Unwrapping optionals

At the top of SceneDelegate.swift you can see that `window` is declared as an optional:

```
var window: UIWindow?
```

To *unwrap* an optional you normally use the `if let` syntax:

```
if let w = window {
  // if window is not nil, w is the real UIWindow object
  let navigationController = w.rootViewController
}
```

As a shorthand you can use *optional chaining*:

```
let navigationController = window?.rootViewController
```

If window is `nil`, then the app won't even bother to look at the rest of the statement and `navigationController` will also be `nil`.

For apps that use a storyboard — and quite a lot of them do —, you're guaranteed that `window` is never `nil`, even though it is an optional. UIKit promises that it will put a valid reference to the app's `UIWindow` object inside the `window` variable when the app starts up.

So why is it an optional? There is a brief moment between when the app is launched and the storyboard is loaded where the `window` property does not have a valid value yet. And if a variable can be `nil` – no matter how briefly – then Swift requires it to be an optional.

If you're *sure* an optional will not be `nil` when you're going to use it, you can *force unwrap* it by adding an exclamation point:


```
let navigationController = window!.rootViewController
```

That's exactly what you're doing in the `saveData()` method. Force unwrapping is the simplest way to deal with optionals, but it comes with some danger: if you're wrong and the optional *is* `nil`, the app will crash. Use with caution!

You've actually used force unwrapping already when you read the text from the `UITextField` objects in the Item Detail and List Detail view controllers. The `UITextField` `text` property is an optional `String` but it will never be `nil`, which is why you can read it with `textField.text!` – the exclamation point converts the optional `String` value to a regular `String`.

Normally you don't need to do anything with your `UIWindow`, but in cases such as this, you ask it for its `rootViewController`. The "root" or "initial" view controller is the very first scene from the storyboard — the navigation controller all the way over on the left.

You can see this in Interface Builder where the navigation controller has a big arrow pointing at it:



The navigation controller is the window's root view controller

The Attributes inspector for this navigation controller also has the **Is Initial View Controller** box checked, that's the same thing. In the Document Outline the arrow is called the Storyboard Entry Point.


Once you have the navigation controller, you can find the `AllListsViewController`. After all, that's the view controller that is embedded in the navigation controller.

Unfortunately, the `UINavigationController` does not have a "rootViewController" property of its own, so you have to look into its `viewControllers` array to find the `AllListsViewController`:

```
let controller = navigationController.viewControllers[0] as!
AllListsViewController
```

As usual, a type cast is necessary because the `viewControllers` array does not know anything about the exact types of your own view controllers. Once you have a reference to `AllListsViewController` you can call its `saveChecklists()`method.

It's a bit of work to dig through the window and navigation controller to find the view controller you need, but that's life as an iOS developer.



From the root view controller to the AllListsViewController

> **Note:** By the way, the `UINavigationController` does have a `topViewController` property, but you cannot use it here: the "top" view controller is the screen that is currently displaying, which may be the `ChecklistViewController` if the user is looking at to-do items. You don't want to send the `saveChecklists()` message to that screen — it has no method to handle that message and the app will crash!

➤ Change the `sceneDidEnterBackground(_:)` and `sceneDidDisconnect(_:)` methods in **SceneDelegate.swift** to call `saveData()`:

```
func sceneDidDisconnect(_ scene: UIScene) {
  saveData()
}

func sceneDidEnterBackground(_ scene: UIScene) {
  saveData()
}
```

➤ Run the app, add some checklists, add items to those lists, and set some checkmarks.

➤ Press the Simulator's home button, or press **Shift+⌘+H**, or pick **Device ▸ Home** from the Simulator's menu bar, to make the app go to the background. This simulates what happens when a user taps the home button on their iPhone.

Look inside the app's Documents folder using Finder. There should be a new Checklists.plist file there.

➤ Press Stop in Xcode to terminate the app. Run the app again and your data should still be there. Awesome!

> **Xcode's Stop button**
>
> Important note: When you press Xcode's Stop button, the scene delegate will *not* receive the `sceneDidDisconnect(_:)` notification. Xcode kills the app immediately, without mercy.
>
> Therefore, to test the saving behavior, always simulate a tap on the home button to make the app go into the background before you press Stop. If you don't to that, you'll lose your data. *Caveat developer*.

Improve the data model

The previous code works, but you can still do a little better. You have made data model objects for `Checklist` and `ChecklistItem` but the code for loading and saving the Checklists.plist file currently lives in `AllListsViewController`. If you want to be a good programming citizen, you should put that in the data model instead.

The DataModel class

I prefer to create a top-level `DataModel` object for many of my apps. For this app, `DataModel` will contain the array of `Checklist` objects. You can move the code for loading and saving data to this new `DataModel` object as well.

➤ Add a new file to the project using the **Swift File** template. Save it as **DataModel.swift** — you don't need to make this a subclass of anything.

➤ Change **DataModel.swift** to the following:

```
import Foundation

class DataModel {
  var lists = [Checklist]()
}
```

This defines the new `DataModel` object and gives it a `lists` property.

Unlike `Checklist` and `ChecklistItem`, `DataModel` does not need to be built on top of `NSObject`. It also does not need to conform to the `Codable` protocol since we will not be serializing `DataModel` objects, just the array of `Checklist` instances that a `DataModel` instance holds.

`DataModel` will take over the responsibilities for loading and saving the to-do lists from `AllListsViewController`.

➤ Cut the following methods out of **AllListsViewController.swift** and paste them into **DataModel.swift**:

- `func documentsDirectory()`
- `func dataFilePath()`
- `func saveChecklists()`
- `func loadChecklists()`

➤ Add an `init()` method to **DataModel.swift**:

```
init() {
  loadChecklists()
}
```

This makes sure that as soon as the `DataModel` object is created, it will attempt to load Checklists.plist.

You don't have to call `super.init()` because `DataModel` does not have a superclass – it is not built on `NSObject` or any other existing class.

Switch to **AllListsViewController.swift** and make the following changes:

➤ Remove the `lists` instance variable.

➤ Remove the call to `loadChecklists()` in `viewDidLoad`.

➤ Add a new instance variable:

```
var dataModel: DataModel!
```

The `!` is necessary because `dataModel` will temporarily be `nil` when the app starts up. It doesn't have to be a true optional – with `?` – because once `dataModel` is given a value, it will never become `nil` again.

You might be tempted to simply create a new instance of `DataModel` in the above line instead of declaring an instance variable which has to be populated later. There's a good reason for not doing it this way. You'll soon see why.

Xcode will find a number of errors in **AllListsViewController.swift**. You can no longer reference the `lists` variable directly, because it no longer exists. Instead, you'll have to ask the `DataModel` for its `lists` property.

➤ Wherever the code for `AllListsViewController` says `lists`, replace it with `dataModel.lists`. You need to do this in the following methods:

- `tableView(_:numberOfRowsInSection:)`
- `tableView(_:cellForRowAt:)`
- `tableView(_:didSelectRowAt:)`
- `tableView(_:commit:forRowAt:)`
- `tableView(_:accessoryButtonTappedForRowWith:)`
- `listDetailViewController(_:didFinishAdding:)`
- `listDetailViewController(_:didFinishEditing:)`

Phew, that's a big list! Fortunately, the change is very simple.

To recap, you created a new `DataModel` object that owns the array of `Checklist` objects and knows how to load and save the checklists and their items.

Instead of its own array, the `AllListsViewController` now uses this `DataModel` object, which it accesses through the `dataModel` property.

Create the DataModel object

But where/how does the `dataModel` instance variable get populated? There is no place in the code that currently says `dataModel = DataModel()`.

That's because the best place for that is in the scene delegate. You can consider the scene delegate to be the top-level object in your app. Therefore, it makes sense to make it the "owner" of the data model. Plus, since you do the data saving in the scene delegate, you need a reference to the data model from the scene delegate anyway. So it makes sense to create the data model instance in the scene delegate and then pass it on to any view controllers that needs it.

➤ In **SceneDelegate.swift**, add a new property:

```
let dataModel = DataModel()
```

This creates the `DataModel` object and puts it in a constant named `dataModel`.

Even though `AllListsViewController` also has an instance variable named `dataModel`, these two things are totally separate from each other. Here you're only putting the `DataModel` object into `SceneDelegate`'s `dataModel` property.

➤ Simplify the `saveData()` method to just this:

```
func saveData() {
  dataModel.saveChecklists()
}
```

If you run the app now, it will crash at once because `AllListsViewController`'s own reference to `DataModel` is still `nil`. I told you those `nil`s were no-gooders!

The best place to share the `DataModel` instance with `AllListsViewController` is in the `scene(_:willConnectTo:connectionOptions:)` method, which gets called as soon as the app starts up.

➤ Change that method to:

```
func scene(
  _ scene: UIScene,
  willConnectTo session: UISceneSession,
  options connectionOptions: UIScene.ConnectionOptions
) {
  let navigationController = window!.rootViewController as!
UINavigationController
  let controller = navigationController.viewControllers[0] as!
AllListsViewController
  controller.dataModel = dataModel
}
```

This finds the `AllListsViewController` by looking in the storyboard as before and then sets its `dataModel` property. Now the All Lists screen can access the array of `Checklist` objects again.

➤ Run the app again and verify that everything still works. It does? Great!

Still confused about var and let?

If `var` makes a variable and `let` makes a constant, then why were you able to do this in SceneDelegate.swift:

```
let dataModel = DataModel()
```

You'd think that when something is constant it cannot change, right? Then how come the app lets you add new `Checklist` objects to `DataModel`? Obviously the `DataModel` object *can* be changed...

Here's the thing: Swift makes a distinction between **value types** and **reference types**, and `let` works differently for value types as opposed to reference types.

An example of a value type is `Int`. Once you create a constant of type `Int` you can never change it afterwards:

```
let i = 100
i = 200       // not allowed
i += 1        // not allowed

var j = 100
j = 200       // allowed
j += 1        // allowed
```

The same goes for other value types such as `Float`, `String`, and even `Array`. They are called value types because the variable or constant directly stores their value.

When you assign the contents of one variable to another, the value is copied into the new variable:

```
var s = "hello"
var u = s          // u has its own copy of "hello"
s += " there"      // s and u are now different
```

But objects that you define with the keyword `class` — such as `DataModel` — are reference types. The variable or constant does not contain the actual object, only a reference to the object — the reference is simply the memory location where the object is stored.

```
var d = DataModel()
var e = d                  // e refers to the same object as d
d.lists.remove(at: 0)      // this also changes e
```

You can also write this using `let` and it would do the exact same thing:

```
let d = DataModel()
let e = d                  // e refers to the same object as d
d.lists.remove(at: 0)      // this also changes e
```

So what is the difference between `var` and `let` for reference types?

When you use `let` it is not the object that is constant but the *reference* to the object. That means you cannot do this:

```
let d = DataModel()
d = someOtherDataModel   // error: cannot change the reference
```

The constant `d` can never point to another object, but the object itself can still change.

It's OK if you have trouble wrapping your head around this. The distinction between value types and reference types is an important idea in software development, but it's also something which takes a while to understand.

My suggestion is that you use `let` whenever you can and change to `var` when the compiler complains. Note that optionals always need to be `var`, because being an optional implies that it can change its value at some point.

You can find the project files for the app up to this point under **17-Improved-data-model** in the Source Code folder.

Chapter 18: User Defaults

By Fahim Farook

You now have an app that lets you create lists and add to-do items to those lists. All of this data is saved to long-term storage so that even if the app gets terminated, nothing is lost.

There are some improvements — both to the user interface and to the code — that you can make though.

This chapter covers the following:

- **Remember the last open list:** Improve the user-experience by remembering the last open list on app re-launch.
- **Defensive programming:** Adding in checks to guard against possible crashes — coding defensively instead of reacting to crashes later.
- **The first-run experience:** Improving the first-run experience for the user so that the app looks more polished and user-friendly.

Remember the last open list

Imagine the user is on the Birthdays checklist and switches to another app. The *Checklists* app is now suspended. It is possible that at some point the app gets terminated and is removed from memory. When the user reopens the app some time later, it no longer is on Birthdays but on the main screen. Because it was terminated, the app didn't simply resume where it left off, but got launched anew.


You might be able to get away with this, as apps don't get terminated often unless, for example, your users play a lot of games that eat up memory, but little things like this matter in iOS apps.

Fortunately, it's fairly easy to remember whether the user had opened a checklist and to switch to it when the app starts up.

Use UserDefaults

You could store this information in the Checklists.plist file, but for simple settings such as this, there is another option — the `UserDefaults` object.

`UserDefaults` is an iOS mechanism which allows you to store small bits of information relevant to your application such as user preferences, application state, and configuration options. It works like a *dictionary*, which is a collection object for storing key-value pairs. You've already seen the array collection, which stores an ordered list of objects. The dictionary is another very common collection that looks like this:



A dictionary is a collection of key-value pairs

Dictionaries in Swift are handled by the `Dictionary` object (who would've guessed?).

You can put objects into the dictionary under a reference key and then retrieve it later using that key. This is, in fact, how Info.plist works.

The Info.plist file is read into a dictionary and then iOS uses the various keys (on the left hand) to obtain the values (on the right hand). Keys are usually strings but values can be any type of object.

To be accurate, `UserDefaults` isn't a true dictionary, but it certainly acts like one.

When you insert new values into `UserDefaults`, they are saved somewhere in your app's sandbox. So, these values persist even after the app terminates.

You don't want to store huge amounts of data inside `UserDefaults`, but it's ideal for small things like what screen the app was on when it closed.

This is what you are going to do:

1. On the segue from the main screen, `AllListsViewController`, to the checklist screen, `ChecklistViewController`, you write the row index of the selected list into `UserDefaults`. This is how you'll remember which checklist was active.

   You could have saved the name of the checklist instead of the row index, but what would happen if two checklists have the same name? Unlikely, but not impossible. Using the row index guarantees that you'll always select the proper one.

2. When the user presses the back button to return to the main screen, you have to remove this value from `UserDefaults` again. It is common to set a value such as this to -1 to mean "no value".

   Why -1? You start counting rows at 0, so you can't use 0. Positive numbers are also out of the question, unless you use a huge number such as 1000000 as it's very unlikely the user will make that many checklists. -1 is not a valid row index — and because it's a negative value it looks weird, making it easy to spot during debugging.

   If you're wondering why you're not using an optional for this — good question! — the answer is that `UserDefaults` cannot handle optionals. Sad face.

3. If the app starts up and the value from `UserDefaults` isn't -1, the user was previously viewing the contents of a checklist and you have to manually perform a segue to the `ChecklistViewController` for the corresponding row.

Phew, it's more work to explain this in English than writing the actual code. ;]

Let's start with the segue from the main screen. Recall that this segue is triggered from code rather than from the storyboard.

➤ In **AllListsViewController.swift**, change `tableView(_:didSelectRowAt:)` to the following:

```
override func tableView(
  _tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  // add this line:
  UserDefaults.standard.set(
    indexPath.row,
    forKey: "ChecklistIndex")
  . . .
}
```

In addition to what this method did before, you now store the index of the selected row into `UserDefaults` under the key "ChecklistIndex".

Navigation controller delegate

To be notified when the user presses the back button on the navigation bar, you have to become a delegate of the navigation controller. Being the delegate means that the navigation controller tells you when it pushes or pops view controllers on the navigation stack.

The logical place for this delegate is the `AllListsViewController`.

➤ Add the delegate protocol to the `class` line in **AllListsViewController.swift**:

```
class AllListsViewController: UITableViewController,
ListDetailViewControllerDelegate, UINavigationControllerDelegate
{
```

As you can see, a view controller can be a delegate for many objects at once.

`AllListsViewController` is now the delegate for both the `ListDetailViewController` and the `UINavigationController`, but also implicitly for the `UITableView` – because it is a table view controller.

➤ Add the following delegate method to **AllListsViewController.swift**:

```
// MARK: - Navigation Controller Delegates
func navigationController(
  _ navigationController: UINavigationController,
  willShow viewController: UIViewController,
```

```
    animated: Bool
  ) {
    // Was the back button tapped?
    if viewController === self {
      UserDefaults.standard.set(-1, forKey: "ChecklistIndex")
    }
  }
```

This method is called whenever the navigation controller shows a new screen.

If the back button was pressed, the new view controller is `AllListsViewController` itself and you set the "ChecklistIndex" value in `UserDefaults` to -1, meaning that no checklist is currently selected.

★ ★ ★

Equal or identical

To determine whether the `AllListsViewController` is the newly activated view controller, you wrote:

```
if viewController === self {
```

Yep, that's not a typo, that's three equals signs in a row.

Previously, to compare objects you used only two equals signs:

```
if segue.identifier == "AddItem" {
```

You may be wondering what the difference between these two operators is. It's a subtle but important question about identity. (Who said programmers couldn't be philosophical?)

If you use ==, you're checking whether two variables have the same value.

With === you're checking whether two variables refer to the exact same object.

Imagine two people who are both called Joe. They're different people who just happen to have the same name.

If we'd compare them using `joe1 === joe2` then the result would be false, as they're not the same person.

But `joe1.name == joe2.name` would be true.

On the other hand, if I'm telling you an amusing (or embarrassing!) story about Joe and this story seems awfully familiar to you, then maybe we happen to know the same Joe. In that case, `joe1 === joe2` would be true as well.

By the way, the previous code would have worked just fine if you had written,

```
if viewController == self
```

with just two equals signs. For objects such as view controllers, equality is tested by comparing the references, just like === would do. But technically speaking, === is more correct here than ==.



Show the last open list

The only thing that remains is to check at startup which checklist you need to show and then perform the segue to the to-do item list manually. You'll do that in `viewDidAppear()`.

➤ Add the `viewDidAppear()` method to **AllListsViewController.swift**:

```
override func viewDidAppear(_ animated: Bool) {
  super.viewDidAppear(animated)

  navigationController?.delegate = self

  let index = UserDefaults.standard.integer(
    forKey: "ChecklistIndex")
  if index != -1 {
    let checklist = dataModel.lists[index]
    performSegue(
      withIdentifier: "ShowChecklist",
      sender: checklist)
  }
}
```

UIKit automatically calls this method after the view controller becomes visible.

First, the view controller makes itself the delegate for the navigation controller.

Every view controller has a built-in `navigationController` property. To access its `delegate` property you use the notation `navigationController?.delegate` because the navigation controller is optional.

You could also have written `navigationController!` instead of `?`. The difference between the two is that `!` will crash the app if this view controller was ever to be shown outside of a `UINavigationController`, while `?` won't crash but simply ignore the rest of that line. For our app, this does not matter.

Then it checks `UserDefaults` to see whether it has to perform the segue.

If the value of the "ChecklistIndex" setting is -1, then the user was on the app's main screen before the app was terminated, and we don't have to do anything.

However, if the value of the "ChecklistIndex" setting is *not* -1, then the user was previously viewing a checklist and the app should segue to that screen. As before, you place the relevant `Checklist` object into the `sender` parameter of `performSegue(withIdentifier:sender:)`.

The `!=` operator means: not equal. It is the opposite of the == operator. If you're mathematically-inclined, with some imagination `!=` looks like ≠ — some languages use <> for not equal but that won't work in Swift.

> **Note:** It may not be immediately obvious what's going on here.
>
> `viewDidAppear()` isn't just called when the app starts up but also every time the navigation controller slides the main screen back into view.
>
> Checking whether to restore the checklist screen needs to happen only once when the app starts, so why did you put this logic in `viewDidAppear()` if it gets called more than once?
>
> Here's the reason:
>
> The very first time `AllListsViewController`'s screen becomes visible, you don't want the `navigationController(_:willShow:animated:)` delegate method to be called yet, as that would always overwrite the old value of "ChecklistIndex" with -1, before you've had a chance to restore the old screen.
>
> By waiting to register `AllListsViewController` as the navigation controller delegate until it is visible, you avoid this problem. `viewDidAppear()` is the ideal place for that, so it makes sense to do it from that method.
>
> However, as mentioned, `viewDidAppear()` also gets called after the user presses the back button to return to the All Lists screen. That shouldn't have any unwanted side effects, such as triggering the segue again.

Naturally, the navigation controller calls `navigationController(_:willShow:animated:)` when the back button is pressed, but this happens before `viewDidAppear()`. The delegate method always sets the value of "ChecklistIndex" back to -1, and as a result, `viewDidAppear()` does not trigger a segue again.

And so it all works out... The logic that you added to `viewDidAppear()` only does its job once during app startup. There are other ways to solve this particular issue but this approach is simple, so I like it.

Is all of this going way over your head? Don't fret about it. To get a better idea of what's going on, sprinkle `print()` statements around the various methods to see in which order they get called. Change things around to see what the effect is. Jumping into the code and playing with it is the quickest way to learn!

Double-check that all the lines with `UserDefaults` use the same key name, "ChecklistIndex". If one of them is misspelled, `UserDefaults` is reading from or writing to different items.

➤ Run the app and go to a checklist screen. Exit to the home screen via the Home button, followed by Stop to quit the app.

Tip: You need to exit to the home screen first because `UserDefaults` may not immediately save its settings to disk, and therefore, you may lose your changes if you kill the app from within Xcode.

Note: Does the app crash for you at this point? That happens if you didn't add any lists or to-do items yet. That's the exact problem we'll solve in the next section. You can either comment out the code in `viewDidAppear()`, add some to-do items, and enable the code again to try it. Or, simply move on to the next section.

➤ Run the app again and you'll notice that Xcode immediately switches to the screen where you were last at. Cool, huh?

Defensive programming

➤ Now do the following: stop the app and delete it from the Simulator by holding down on the app icon until it starts to wiggle and then deleting it. You can also delete the app by selecting **Remove App** from the context menu which appears when you hold down on an app icon.

Then, run the app again from within Xcode and watch it crash:

```
Fatal error: Index out of range
```

The app crashes in `viewDidAppear()` on the line:

```
let checklist = dataModel.lists[index]
```

What's going on here? Apparently, the value of `index` is not -1, because the code entered the `if` statement.

As it turns out `index` is 0, even though there should be nothing in `UserDefaults` yet because this is a fresh install of the app. The app didn't write anything in the "ChecklistIndex" key yet.

Here's the thing: `UserDefaults`'s `integer(forKey:)` method returns 0 if it cannot find the value for the key you specified. But in this app, 0 is a valid row index.

At this point, the app doesn't have any checklists yet. So, index 0 does not exist in the `lists` array. That is why the app crashes.

What should happen instead, is that `UserDefaults` returns -1 if nothing is set yet for "ChecklistIndex", because to your app -1 means: show the main screen instead of a specific checklist.

Set a default value for a UserDefaults key

Fortunately, `UserDefaults` will let you set default values for the default values. Yep, you read that correctly. Let's do that in the `DataModel` object.

➤ Add the following method to **DataModel.swift**:

```
func registerDefaults() {
  let dictionary = [ "ChecklistIndex": -1 ]
  UserDefaults.standard.register(defaults: dictionary)
}
```

This creates a new `Dictionary` instance and adds the value -1 for the key "ChecklistIndex".

The square bracket notation is not only used to make arrays, but also dictionaries. The difference is that for a dictionary it always looks like,

```
[ key1: value1, key2: value2, . . . ]
```

while an array is just:

```
[ value1, value2, value3, . . . ]
```

`UserDefaults` will use the values from this dictionary if you ask it for a key and it cannot find a value for that key.

➤ Change **DataModel.swift**'s `init()` to call this new method:

```
init() {
  loadChecklists()
  registerDefaults()
}
```

➤ Run the app again. Now, it should no longer crash.

Why did you do this in `DataModel`? Well, mostly because I don't really like to sprinkle all of these calls to `UserDefaults` throughout the code — it's better to centralize functionality where possible.

Clean up the code

In fact, let's move all of the `UserDefaults` stuff into `DataModel`.

➤ Add the following to **DataModel.swift**:

```
var indexOfSelectedChecklist: Int {
  get {
    return UserDefaults.standard.integer(
      forKey: "ChecklistIndex")
  }
  set {
    UserDefaults.standard.set(
      newValue,
      forKey: "ChecklistIndex")
  }
}
```

This does something you haven't seen before. It appears to declare a new instance variable `indexOfSelectedChecklist` of type `Int`, but what are these `get { }` and `set { }` blocks?

This is an example of a *computed property*.

There isn't any storage allocated for this property — so it's not really a variable. Instead, when the app tries to read the value of `indexOfSelectedChecklist`, the code in the `get` block is performed. And when the app tries to put a new value into `indexOfSelectedChecklist`, the `set` block is performed.

From now on, you can simply use `indexOfSelectedChecklist` and it will automatically update `UserDefaults`. How cool is that?

You're doing this so the rest of the code won't have to worry about `UserDefaults` anymore. The other objects just have to use the `indexOfSelectedChecklist` property on `DataModel`.

Hiding implementation details is an important object-oriented programming principle, and this is one way to do it.

If you decide later that you want to store these settings somewhere else, for example, in a database, or in iCloud, then you only have to change this in one place — in `DataModel`. The rest of the code will be oblivious to these changes. That's a good thing.

➤ Update the code in **AllListsViewController.swift** to use this new computed property:

```
override func viewDidAppear(_animated: Bool) {
  ...
  let index = dataModel.indexOfSelectedChecklist // change this
  if index != -1 {
  ...
  }
}
```

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  // change this line
  dataModel.indexOfSelectedChecklist = indexPath.row
  ...
}
```

```
func navigationController(
  _ navigationController: UINavigationController,
  willShow viewController: UIViewController,
  animated: Bool
) {
  if viewController === self {
    dataModel.indexOfSelectedChecklist = -1   // change this
  }
}
```

The intent of the code is now much clearer. `AllListsViewController` no longer has to worry about the "how" — storing values in `UserDefaults` — and can simply focus on the "what" — changing the index of the selected checklist.

➤ Run the app again and make sure everything still works.

A subtle bug

It's pretty nice that the app now remembers what screen you were on, but this new feature has also introduced a subtle bug in the app. Here's how to reproduce it:

➤ Start the app and add a new checklist. Also, add a new to-do item to this list. Now kill the app from within Xcode.

Because you did not exit to the home screen first, the new checklist and its item were not saved to Checklists.plist. However, `UserDefaults` has saved its changes to disk and now thinks this new list is selected. That's a problem because that list doesn't exist because it never made it into Checklists.plist.

➤ Run the app again and it will crash with:

```
Fatal error: Index out of range
```

The reason for the crash is that `UserDefaults` and the contents of Checklists.plist are out-of-sync. `UserDefaults` thinks the app needs to select a checklist that doesn't actually exist. Every time you run the app it will now crash. Yikes!

This situation shouldn't really happen during regular usage. It happened because you used the Xcode Stop button to kill the app before it had a chance to save the plist file. Under normal circumstances, the user would press the home button. As the app goes into the background, it properly saves both Checklists.plist and `UserDefaults` and everything is in sync again.

However, the OS can always decide to terminate the app unexpectedly and then this same situation could occur.

Even though there's only a small chance that this can go wrong in practice, you should really protect the app against this. These are the kinds of bug reports you don't want to receive because often, you have no idea what the user did to make it happen.

This is where the practice of *defensive programming* becomes important. Your code should always check for such boundary cases and be able to gracefully handle them even if they are unlikely to occur.

In our case, you can easily fix `AllListsViewController`'s `viewDidAppear()` method to deal with this situation.

➤ Change the `if` statement in `viewDidAppear()` to:

```
if index >= 0 && index < dataModel.lists.count {
```

Instead of just checking for `index != -1`, you now do a more precise check to determine whether `index` is valid. It should be between 0 and the number of checklists in the data model. If not, then you simply don't segue.

This prevents `dataModel.lists[index]` from asking for an object at an `index` that doesn't exist.

You haven't seen the `&&` operator before. This symbol means "logical and". It is used as follows:

```
if something && somethingElse {
  // do stuff
}
```

This reads: if something is true **and** something else is also true, then do stuff.

In `viewDidAppear()` you only perform the segue when `index` is 0 or greater and also less than the number of checklists, which means it's only valid if it lies in between those two values.

With this defensive check in place, you're guaranteed that the app will not try to segue to a checklist that doesn't exist, even if the data is out-of-sync.

Note: Even though the app remembers what checklist the user was on, it won't bother to remember whether the user had the Add/Edit Checklist or Add/Edit Item screen open.

These kinds of data input screens are supposed to be temporary. You open them to make a few changes and then close them again. If the app goes to the background and is terminated, then it's no big deal if the data input screen disappears.

At least, that is true for this app. If you have an app that allows the user to make many complicated edits in an input screen, you may want to persist those changes when the app closes so the user won't lose all their work in case the app is killed.

In this chapter you used `UserDefaults` to remember which screen was open, but iOS actually has a dedicated API for this kind of thing, State Preservation and Restoration. You can read more about this on raywenderlich.com/117471/state-restoration-tutorial.

The first-run experience

Let's use `UserDefaults` for something else. It would be nice if the first time you ran the app it created a default checklist for you, simply named "List", and switched over to that list. This enables you to start adding to-do items right away.

That's how the standard Notes app works too: you can start typing a note right after launching the app for the very first time, but you can also go one level back in the navigation hierarchy to see a list of all notes.

Check for first run

To implement the above feature, you need to keep track in `UserDefaults` whether this is the first time the user runs the app. If it is, you create a new `Checklist` object.

You can perform all of this logic inside `DataModel`.

It's a good idea to add a new default setting to the `registerDefaults()` method. The key for this value is "FirstTime".

➤ Change the `registerDefaults()` method in **DataModel.swift** (don't miss the comma after the first item in the dictionary):

```
func registerDefaults() {
  let dictionary = [
    "ChecklistIndex": -1,
    "FirstTime": true
  ] as [String: Any]
  UserDefaults.standard.register(defaults: dictionary)
}
```

The "FirstTime" setting can be a boolean value because it's either true (this is the first time) or false (this is any other than the first time).

The value of "FirstTime" needs to be true if this is the first launch of the app after a fresh install.

Also, note that there's now a type cast for `dictionary`. Why was that added? Try removing the type cast, the `as [String: Any]` bit, and see what happens. Xcode will throw up an error.

This is because originally, there was one value in the dictionary and it was an `Int`. But when you introduced the `FirstTime` key, its corresponding value is a `Bool`. Now your dictionary has a mixed set of values — an `Int` and a `Bool`. So, at this point, the compiler is unsure whether you meant to have a mixed bag of values, or if it was a mistake on your part. So it wants you to explicitly indicate what the dictionary type is, and that's why you declare it as `[String: Any]`, to indicate that the value could indeed be of any type.

➤ Still in **DataModel.swift**, add a new `handleFirstTime()` method:

```
func handleFirstTime() {
  let userDefaults = UserDefaults.standard
  let firstTime = userDefaults.bool(forKey: "FirstTime")

  if firstTime {
    let checklist = Checklist(name: "List")
    lists.append(checklist)

    indexOfSelectedChecklist = 0
    userDefaults.set(false, forKey: "FirstTime")
  }
}
```

Here you check `UserDefaults` for the value of the "FirstTime" key. If the value for "FirstTime" is true, then this is the first time the app is being run. In that case, you create a new `Checklist` object and add it to the array.

You also set `indexOfSelectedChecklist` to 0, which is the index of this newly added `Checklist` object, to make sure the app will automatically segue to the new list in `AllListsViewController`'s `viewDidAppear()` method.

Finally, you set the value of "FirstTime" to false, so this code won't be executed again the next time the app starts up.

➤ Call this new method from `DataModel`'s `init()`:


```
init() {
  loadChecklists()
  registerDefaults()
  handleFirstTime()    // Add this
}
```

➤ Remove the app from the Simulator and run it again from Xcode.

Because it's the first time you run the app — at least from the app's perspective — after a fresh install, it will automatically create a new checklist named List and switch to it.

Organizing Source Files

At this point, your Project navigator probably lists your files something like this:




Project navigator file listing

It's a bit messy since it's hard to find where a given file is. Sure, you know exactly where each file is now, but what happens when you have 20 or 30 files in there? Or a hundred? Xcode does provide a few different ways to organize your files.

The first thing you can do is a simple alphabetical sorting of files so that you can find a given file quickly — since it will be in alphabetical order. That is simple enough to accomplish.


➤ Right-click (or Control-click) on the grey **Checklists** folder. A context menu should pop up.



Context menu for folder

➤ Select **Sort by Name**.


Voila! All the files inside the Checklists folder are now in alphabetical order.



Sorted file listing

That certainly makes finding files a lot easier, but what if you had 20 or 30 files? Or even a hundred? You would still have to do a lot of scrolling around to find the exact file you wanted.

Xcode does provide a filter field at the bottom of the Navigator pane that you can use to filter files in the current list by name. You can type in, for example, "Controller" and it will display only the files with "Controller" in the file name – you can click the little circle icon with an "x" in the filter field to clear the filter.




Filter file list by name

But you can do better :] You can also organize your files into folders, called *groups*, so that you can organize the files by functionality. For example, you can put all your view controllers together into a folder called View Controllers, the data models into a Data Models folder and so on ...

You probably noticed the New Group menu option on the folder context menu when you right-clicked on the Checklists folder earlier. That's what you need to use in order to create a new group. Simply create a new group (or three), drag files into the group and you should be set.

Also, remember that you can drag files, or even groups, up or down the list to arrange things exactly as you want. Xcode will remember this positioning and so you can set specific files (or groups) to be exactly where you want them.

You could quite easily organize the file listing from above to look something like this:



Organized file listing

> **Note:** If you are moving files and folders around, do note that if you do move the Info.plist file into a folder, the next time you try to compile your project you'll get an error. This is because the Info.plist file contains information about your project and Xcode expects it to be in the root folder. You can change the location of the Info.plist file under Build Settings by searching for Info.plist if you do run into this issue, but you would have to know how to specify the new location for the file. And that's something that you might have to figure out on your own :]

You can find the project for the app up to this point under **18-User-defaults** in the Source Code folder.

Chapter 19: UI Improvements

By Fahim Farook


Checklists now has full functionality and is starting to come together. However, There are a few small features I'd like to add, just to polish the app a little more. After all, you're building a real app here – if you want to make top-notch apps, you have to pay attention to those tiny details.

This chapter covers the following:

- **Show counts:** Show the number of to-do items remaining for each list.
- **Sort the lists:** Sort the list of checklist items alphabetically.
- **Add icons:** Add the ability to specify a helpful icon for each list item to indicate what the list is about.
- **Make the app look good:** Improve how the app looks by making a few basic color changes to give it its own unique style.

Show counts

On the main screen, for each checklist, the app will show the number of to-do items that do not have checkmarks yet:



Each checklist shows how many items are still left to-do

Count the unchecked items

First, you need a way to count these items.

➤ Add the following method to **Checklist.swift**:

```
func countUncheckedItems() -> Int {
  var count = 0
  for item in items where !item.checked {
    count += 1
  }
  return count
}
```

This method asks the `Checklist` object how many of its `ChecklistItem` objects are still not checked. The method returns this count as an `Int` value.

You use a `for...in` to loop through the `ChecklistItem` objects from the `items` array. If an `item` object has its `checked` property set to `false`, you increment the local variable `count` by 1.

Remember that the `!` operator negates the result. So if `item.checked` is `true`, then `!item.checked` will make it `false`. You should read it as "where not item.checked".

> **Note:** If the `!` symbol is written in front of something then it is the logical **not** operator, as you see here. When the `!` is written behind something, it's related to optionals. This is another example of a symbol that has more than one meaning in Swift. The correct interpretation depends on the context where it is being used.

When the loop is over and you've looked at all the objects, you return the total value of the count to the caller.

> **Exercise:** What would happen if you used `let` instead of `var` to define the `count` variable?

Answer: When `count` is a constant, Swift won't let you change its value, so the line that does `+= 1` will show an error message.

By the way, you could also have written the loop as follows:

```
for item in items {
  if !item.checked {
    count += 1
  }
}
```

This uses the more familiar `if` statement instead. Personally, I like the brevity of the `for...in where` loop, but using an `if` is just as valid.

As the above code indicates, your own objects can have custom methods too. A good object-oriented principle is to let your own objects change their state or to provide information about themselves as much as possible.

Display the unchecked item count

Currently, the table view cells in the All Lists scene display one line of text. This is using the default table view cell style. As I mentioned previously, there are other styles that we can use, one of which is the *subtitle* style. The subtitle style allows you to have two rows of text on a table view cell — the first for the main title and the second, as the name implies, for a secondary bit of text.

However, our current way of creating cells — by calling `dequeueReusableCell(withIdentifier: for:)` — does not allow us to specify a custom table view cell style. So, we're going to have to modify the code a bit to get things to work.

➤ Go to **AllListsViewController.swift** and remove the `register(_:forCellReuseIdentifier:)` line from `viewDidLoad` since we will not require that. Instead, we will create the table view cells by hand if a cached cell is not available.

If you forget to remove the above line, your app will crash when you try to run it later. I will explain why in the next step.

➤ In `tableView(_:cellForRowAt:)` replace the first line — the one dequeuing a cell — with the following lines of code:

```
// Get cell
let cell: UITableViewCell!
if let tmp = tableView.dequeueReusableCell(
  withIdentifier: cellIdentifier) {
  cell = tmp
} else {
  cell = UITableViewCell(
    style: .subtitle,
    reuseIdentifier: cellIdentifier)
}
```

Here, you define a constant to hold the newly created cell and then see if you can dequeue a cell from the table view for the given identifier. If there is no cell — meaning that there are no cached cells that can be re-used — then you create a new `UITableViewCell` instance with the cell style, and the identifier, that you want. If there is a cell, then you assign its reference to the previously declared constant.

These new cells would, of course, be added to the available pool of table view cells and would be available for re-use from this point onwards.

If you did not remove the table view class registration in the previous step, the dequeue step in the above code will never fail since the `dequeueReusableCell( withIdentifier:)` method will automatically create a new cell of the registered class if a cached instance does not exist. However, this new table view cell instance would not be of the subtitle style — instead, it will have the default style. So, any references to the subtitle label in the table view cell — unless properly guarded against — will cause your app to crash.

The "subtitle" cell style adds a second, smaller label below the main label. You can use the cell's `detailTextLabel` property to access this subtitle label.

➤ Add the following line just before `return cell` in `tableView(_:cellForRowA:t)`:

```
cell.detailTextLabel!.text = "\(checklist.countUncheckedItems())
Remaining"
```

You call the `countUncheckedItems()` method on the `Checklist` object and put the count into a new string that you display using the `detailTextLabel`.

As usual, you use `\(…)` to do the string interpolation. Notice that you can even call methods inside interpolated strings. Sweet!

★ ★ ★

Force unwrapping

To put text into the cell's labels, you wrote:

```
cell.textLabel!.text = someString
cell.detailTextLabel!.text = anotherString
```

The `!` is necessary because `textLabel` and `detailTextLabel` are optionals.

The `textLabel` property is only present on table view cells that use one of the built-in cell styles; it is `nil` on custom cell designs. Likewise, not all of the cell styles have a detail label and `detailTextLabel` will be `nil` in those cases.

Here you're using the "subtitle" cell style, which is guaranteed to have both labels. Because these optionals will never be `nil` for a "subtitle" cell, you can use `!` to *force unwrap* them. This turns the optional into an actual object that you can use.

Be careful with this, though… using `!` on an optional that *is* `nil` will crash your app immediately.


You could also have written the above code as:

```
if let label = cell.textLabel {
  label.text = someString
}
if let label = cell.detailTextLabel {
  label.text = anotherString
}
```

That is safer — no chance of crashing here — but also a bit more cumbersome. Writing `!` was just more convenient in this case.

★ ★ ★

➤ Run the app. For each checklist it will now show how many items still remain unchecked.



The cells now have a subtitle label

Update the unchecked item count on changes

One problem: The to-do count never changes. If you toggle a checkmark on or off, or add new items, the "to do" count remains the same. That's because you create these table view cells once and never update their labels — try it out

> **Exercise:** Think of all the situations that will cause this "still to do" count to change.

Answer:

- The user toggles a checkmark on an item. When the checkmark is set, the count goes down. When the checkmark gets removed, the count goes up again.
- The user adds a new item. New items don't have their checkmark set, so adding a new item should increment the count.
- The user deletes an item. The count should go down but only if that item had no checkmark.

These changes all happen in the `ChecklistViewController` but the "still to do" label is shown in the `AllListsViewController`. So, how do you let the All Lists View Controller know about this?

If you thought, "That's easy, let's use a delegate!", then you're starting to get the hang of this. You could make a new `ChecklistViewControllerDelegate` protocol that sends messages when the following things happen:

- The user toggles a checkmark on an item
- The user adds a new item
- The user deletes an item

But what would the delegate — which would be `AllListsViewController` — do in response? It would simply set some new text on the cell's `detailTextLabel` in all cases.

The delegate approach sounds good, but you're going to cheat and not use a delegate at all :] There is a simpler solution, and a smart programmer always picks the simplest way to solve a problem.

➤ Go to **AllListsViewController.swift** and add the `viewWillAppear()` method to do the following:

```
override func viewWillAppear(_ animated: Bool) {
  super.viewWillAppear(animated)
  tableView.reloadData()
}
```

Don't confuse this method with `viewDidAppear()`. The difference is in the verb: *will* versus *did*. `viewWillAppear()` is called before `viewDidAppear()`, when the view is about to become visible but the animation hasn't started yet. `viewDidAppear()` is called after the view is visible on the screen and the animation has completed. There may be half a second or so difference between them as the animation takes place.

The iOS API often does this: there is a "will" method that is invoked before something happens and a "did" method that is invoked after that something happens. Sometimes you need to do things before, sometimes after, and having two methods gives you the ability to choose whichever situation works best for you.

> **API (ay-pee-eye)** stands for **A**pplication **P**rogramming **I**nterface. When people say "the iOS API" they mean all the frameworks, objects, protocols and functions that are provided by iOS that you as a programmer can use to write apps.
>
> The iOS API consists of everything from UIKit, Foundation, Core Graphics, and so on. Likewise, when people talk about "the Facebook API" or "the Google API", they mean the services that these companies provide that allow you to write apps for those platforms.

Here, `viewWillAppear()` tells the table view to reload its entire contents. That will cause `tableView(_:cellForRowAt:)` to be called again for every visible row.

When you tap the back button on the `ChecklistViewController`'s navigation bar, the `AllListsViewController` screen will slide back into view. Just before that happens, `viewWillAppear()` is called.

Thanks to the call to `tableView.reloadData()` the app will update all of the table cells, including the `detailTextLabels`.

Reloading all of the cells may seem like overkill, but in this situation you can easily get away with it. It's unlikely the All Lists screen will contain many rows (say, less than 100) and only about 14 visible cells, so reloading them is quite fast. And it saves you the work of having to create yet another delegate.

Sometimes a delegate is the best solution; sometimes you just reload the entire table :]

➤ Run the app and test that it works!

Display a completion message when all items are done

> **Exercise:** Change the label to read "All Done!" when there are no more to-do items left to check.

Answer: Change the relevant code in `tableView(_:cellForRowAt:)` to:

```
let count = checklist.countUncheckedItems()
cell.detailTextLabel!.text = count == 0 ? "All Done" : "\(count)
Remaining"
```

You put the count into a local constant because you will refer to it more than once. Calculating the count once and storing it into a temporary constant is more optimal than doing the same calculation twice.

But what about the second line of code? It has something new/interesting going on, right?

It's actually just a simpler way to do an `if...else` block. The `condition ? If true : else` construct is known as a *ternary conditional operator* — if the first part (the bit before the ?) evaluates to `true`, then the result of the expression would be the item after the ?. Otherwise, the result is the item after the :. It can be very handy in a lot of places to write simpler, more succinct code.

The same thing could have been done with an `if...else` block but that would have taken five lines. Personally, I prefer to use the ternary operator where possible.

Display an indicator when there are no items in a list


> **Exercise:** Now update the label to say "No Items" when the list is empty.

Answer:

```
let count = checklist.countUncheckedItems()
if checklist.items.count == 0 {
  cell.detailTextLabel!.text = "(No Items)"
} else {
  cell.detailTextLabel!.text = count == 0 ? "All Done" : "\
(count) Remaining"
}
```

Just looking at the result of `countUncheckedItems()` is not enough. If this returns 0, you don't know whether that means all items are checked off or if the list has no items at all. You also need to look at the total number of items in the checklist, with `checklist.items.count`.

You could have done the setting of the text as two nested ternary operators as well, but sometimes, it's better to write code that's clear rather than succinct :]



The text in the detail label changes depending on how many items are checked off

Little details like these matter – they make your app more fun to use. Ask yourself, what would make you feel better about having done your chores, the rather bland message "0 Remaining" or the joyous exclamation "All Done!"?

★ ★ ★

Functional Programming

Swift is primarily an object-oriented language. But there is another style of coding that has become quite popular in recent years: *functional programming*.

The term "functional" means that programs can be expressed purely in terms of mathematical functions that transform data.

Unlike the methods and functions in Swift, these mathematical functions are not allowed to have "side effects". For any given inputs, a function should always produce the same output. Methods are much less strict.

Even though Swift is not a purely functional language, it does let you use certain functional programming techniques in your apps. They can really make your code a lot shorter.

For example, let's look at `countUncheckedItems()` again:

```
func countUncheckedItems() -> Int {
  var count = 0
  for item in items where !item.checked {
    count += 1
  }
  return count
}
```

That's quite a bit of code for something that's fairly simple. You can actually write this in a single line of code:

```
func countUncheckedItems() -> Int {
  return items.reduce(0) {
    cnt,item in cnt + (item.checked ? 0 : 1)
  }
}
```

`reduce()` is a method that looks at each item in the array and performs the code in the `{ }` block. Initially, the `cnt` variable contains the value 0, but after each item it is incremented by either 0 or 1, depending on whether the item was checked — that check is done using our new friend, the ternary operator.

When `reduce()` is done, its return value is the total count of unchecked items.

You don't have to remember any of this for now, but it's pretty cool to see that Swift allows you to express this kind of algorithm very succinctly.

★ ★ ★

Sort the lists

Another thing you often need to do with lists is sort them in some particular order.

Let's sort the list of checklists by name. Currently when you add a new checklist it is always appended to the end of the table, regardless of alphabetical order.

When do you do the sorting?

Before we figure out how to sort an array, let's think about when you need to perform this sort:

- When a new checklist is added
- When a checklist is renamed

There is no need to re-sort when a checklist is deleted because that doesn't have any impact on the order of the other objects.

Currently you handle these two situations in `AllListsViewController`'s implementation of `didFinishAdding` and `didFinishEditing`.

➤ Change these methods to the following:

```
func listDetailViewController(
  _ controller: ListDetailViewController,
  didFinishAdding checklist: Checklist
) {
  dataModel.lists.append(checklist)
  dataModel.sortChecklists()
  tableView.reloadData()
  navigationController?.popViewController(animated: true)
}

func listDetailViewController(
  _ controller: ListDetailViewController,
  didFinishEditing checklist: Checklist
) {
  dataModel.sortChecklists()
  tableView.reloadData()
  navigationController?.popViewController(animated: true)
}
```

You were able to remove a bunch of code from both methods because you now always do `reloadData()` on the table view.

It is no longer necessary to insert the new row manually, or to update the cell's `textLabel`. Instead you simply call `tableView.reloadData()` to refresh the entire table's contents after you've sorted the data.

Again, you can get away with this because the table will only hold a handful of rows. If this table had hundreds of rows, a more advanced approach might be necessary — you could figure out where the new or renamed `Checklist` object should be inserted and just update that row.

The sorting algorithm

The `sortChecklists()` method on `DataModel` is new and you still need to add it. But before that, we need to have a short discussion about how sorting works.

When you sort a list of items, the app will compare the items one-by-one to figure out what the proper order is. But what does it mean to compare two `Checklist` objects?

In *Checklists* we obviously want to sort them by name, but we need some way to tell the app that's what we mean.

➤ Add the following method to **DataModel.swift**:

```
func sortChecklists() {
  lists.sort { list1, list2 in
    return list1.name.localizedStandardCompare(list2.name)
== .orderedAscending
  }
}
```

Here you tell the `lists` array that the `Checklists` it contains should be sorted using some specific logic.

Note that while `sort()` is a method, you don't have the brackets after the method because you are using a *trailing closure* to do the actual work of sorting. You can tell it's a closure by the `{ }` brackets around the sorting code:

```
lists.sort { /* the sorting code goes here */ }
```

You've briefly seen closures with the alert box in the *Bull's Eye* app. They wrap a piece of source code into an anonymous, inline method.

The purpose of the closure is to determine whether one `Checklist` object comes before another, based on our rules for sorting.

The sort algorithm will repeatedly ask one `Checklist` object from the list how it compares to the other `Checklist` objects using the logic from the closure, and then shuffle them around until the array is sorted.

This allows `sort()` to sort the contents of the array in any order you desire. If you wanted to sort on other criteria, all you'd have to do is change the logic inside the closure.

The actual sorting code is this:

```
list1.name.localizedStandardCompare(list2.name)
== .orderedAscending
```

To compare these two `Checklist` objects, you're only looking at their names.

The `localizedStandardCompare(_:)` method compares the two name strings while ignoring lowercase vs. uppercase (so "a" and "A" are considered equal) and taking into consideration the rules of the current *locale*.


A locale is an object that knows about country and language-specific rules. Sorting in German may be different than sorting in English, for example.

That's all you have to do to sort the array: call `sort()` and give it a closure with the logic that compares two `Checklist` objects.

➤ Just to make sure the existing lists are also sorted in the right order, you should also call `sortChecklists()` when the plist file is loaded:

```
func loadChecklists() {
    . . .
    lists = try decoder.decode([Checklist].self, from: data)
    sortChecklists()       // Add this
  } catch {
    ...
}
```

➤ Run the app and add some new checklists. Change their names and notice that the list is always sorted alphabetically.




New checklists are always sorted alphabetically

Add icons

Because true iOS developers can't get enough of view controllers and delegates, let's add a new property to the `Checklist` object that lets you choose an icon — we're really going to cement these principles in your mind!

When you're done, the Add/Edit Checklist screen will look like this:




You can assign an icon to a checklist

You are going to add a row to the Add/Edit Checklist screen that opens a new screen for picking an icon. This icon picker is a new view controller and you will show it by pushing it on to the navigation stack, just like your previous view controllers.

Add the icons to the project


The Resources folder for the book contains a folder named **Checklist Icons** with a selection of PNG images that depict different categories.



The various checklist icon images

➤ Add the images from this folder to the asset catalog. Select **Assets.xcassets** in the project navigator, click the + button at the bottom and choose **Import...**


➤ Navigate to the **Checklist Icons** folder and select all the files inside:



Selecting the image files to import

Note: Make sure to select the actual image files, not the folder.

➤ Click **Open** to import the images. The asset catalog should now look like this:



The asset catalog after importing the checklist icons

Each image comes with a 2x version for Retina devices and a 3x version for the Retina HD devices.

As I pointed out previously, you don't need low-resolution 1x graphics anymore. All iPhone, iPad, and iPod touch devices that can run iOS 15 have Retina 2x or 3x screens.

Update the data model

➤ Add the following property to **Checklist.swift**:

```
var iconName = ""
```

The `iconName` variable holds the name of the icon image.

The above code initializes `iconName` to have no icon set by default. But what if you actually wanted to create new `Checklist` objects with a default icon?

It's very easy to implement a default icon. Say, you want all new checklists to have the "Appointments" icon — then change the above line to this:

```
var iconName = "Appointments"
```

And that's all you need to do :]

Display the icon

At this point, you just want to see that you can make an icon — any icon — show up in the table view. When that works, you can worry about letting the user pick their own icons. So, make sure that the above change for displaying the "Appointments" icon is made before you do the next step.

➤ Change `tableView(_:cellForRowAt:)` in **AllListsViewController.swift** to put the icon into the table view cell:


```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  . . .

  cell.imageView!.image = UIImage(named: checklist.iconName)
  return cell
}
```

Cells using the standard `.subtitle` cell style come with a built-in `UIImageView` on the left. You can simply pass it an image and it will be displayed automatically. Easy peasy.

> **Note:** When you run the app, you will not see any of your previously saved checklist items. Can you guess why?The addition of `iconName` changed the `Checklist` object and the previously saved information for the object is no longer valid. So, the decoder will run into issues when trying to decode the previously saved file and so, you will end up with no saved items. Sorry.

➤ Run the app, create a few checklists and now each of them should have an alarm clock icon.



The checklists have an icon

The default icon


Now that you know it works, you can change `Checklist` to give each `Checklist` object an icon named "No Icon" by default.

➤ In **Checklist.swift**, change the `iconName` declaration to:

```
var iconName = "No Icon"
```

The "No Icon" image is a transparent PNG image with the same dimensions as the other icons. Using a transparent image is necessary to make all the checklists line up properly, even if they have no icon.

If you were to set `iconName` to an empty string instead, the image view in the table view cell would remain empty and the text would align with the left margin of the screen. That looks bad when other cells do have icons:



Using an empty image to properly align the text labels (right)

The icon picker class

Now, let's create the icon picker screen.

➤ Add a new Swift file to the project. Name it **IconPickerViewController**.

➤ Replace the contents of **IconPickerViewController.swift** with:

```
import UIKit

protocol IconPickerViewControllerDelegate: AnyObject {
  func iconPicker(
    _ picker: IconPickerViewController,
    didPick iconName: String)
}

class IconPickerViewController: UITableViewController {
  weak var delegate: IconPickerViewControllerDelegate?
}
```

This defines the `IconPickerViewController` object, which is a table view controller, and a delegate protocol that it uses to communicate with other objects in the app.

➤ Add a constant (inside the `class` implementation) to hold the array of icons:

```
let icons = [
  "No Icon", "Appointments", "Birthdays", "Chores",
  "Drinks", "Folder", "Groceries", "Inbox", "Photos", "Trips"
]
```

This is an array that contains a list of icon names. These strings are both the text you will show on the screen and the name of the PNG file inside the asset catalog.

The `icons` array is the data model for this table view. Note that it is a non-mutable array — it is defined with `let` and arrays are "value" types — because the user cannot add new icons or delete icons from the available list.

This new view controller is a `UITableViewController`, so you have to implement the data source methods for the table view.

➤ Add the following method to the source file:

```
// MARK: - Table View Delegates
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return icons.count
}
```

This simply returns the number of icons in the array.

➤ Next, add this method:

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "IconCell",
    for: indexPath)
  let iconName = icons[indexPath.row]
  cell.textLabel!.text = iconName
  cell.imageView!.image = UIImage(named: iconName)
  return cell
}
```

Here, you obtain a table view cell and give it a title and an image. You will design this cell in the storyboard momentarily. It will be a prototype cell with the "default" cell style, or "Basic" as it is called in Interface Builder. Cells with this style already contain a text label and an image view, which is very convenient.

The icon picker storyboard changes

➤ Open the storyboard. Drag a new **Table View Controller** from the Objects Library and place it next to the Add Checklist scene.

➤ In the **Identity inspector**, change the class of this new table view controller to **IconPickerViewController**.

➤ Select the prototype cell and set its **Style** to **Basic** and its (re-use) **Identifier** to **IconCell**.

That takes care of the design for the icon picker. Now you need to have some place to call it from. To do this, you will add a new row to the Add Checklist screen.

➤ Go to the **Add Checklist View Controller** and add a new section to the table view. You can do this by changing the **Sections** value in the **Attributes inspector** for the table view from 1 to 2. This will duplicate the existing section.


➤ Delete the Text Field from the cel in the new section; you don't need it.

➤ Add a **Label** to this cell and change its text to **Icon**.

➤ Set the cell's **Accessory** to **Disclosure Indicator**. That adds a gray chevron.

➤ Add an **Image View** to the right of the cell. Make it 36 × 36 points big – use the Size inspector for this.

➤ Once the Label and Image View are sized and positioned, add **width**, **height**, **top**, **right**, and **bottom** Auto Layout constraints to the Image View using the **Add New Constraints menu** available via the icon at the bottom of the canvas.



Adding constraints to the Image View

What you want to happen is that the image view stays glued to the right edge of the screen, always at the same distance from the disclosure indicator. When the view controller grows or shrinks to fit the iPhone screen, the image view should move along with it.

The image view should now look like this:



The Image View with the constraints


Make sure the bars representing the constraints are blue. If they are orange or red you may have forgotten something in the Add New Constraints menu. Either try again or use the **Editor ▸ Resolve Auto Layout Issues ▸ Update Frames** menu item.

The most important constraint is the one on the right. This tells UIKit that the right-hand side of the image view should always stick to the right-hand edge of the table view cell's content view.

In other words, no matter how wide or narrow the screen is, the image view will always have the same location relative to the disclosure indicator.

The other constraints — top, bottom, width, and height — were necessary only because all views must always have enough constraints to determine their position and size. You could have left out the bottom one, but here you need it because the whole cell size is determined based on the image view height and its top and bottom spacing.

➤ Add **left** and **right** constraints — where the right constraint is 8 points instead of whatever value you would get by default — to the Label via the **Add New Constraints menu**. Finally, **vertically center** the Label to the Image View by Control-dragging from the Label to the Image View in the Document Outline and selecting **Center Vertically** from the pop up menu.



The Image View with the constraints

➤ To verify that your changes do the right thing you don't necessarily need to run the app in the simulator. Use the Interface Builder toolbar at the bottom to switch between the different iPhone models right inside Interface Builder. If your constraints are correct, then the icon should always be in the right place.

➤ Use the **Assistant Editor** to add an outlet property for the image to **ListDetailViewController.swift** and name it **iconImage**.


That completes the designs for both screens — you can now connect them via a segue.

➤ **Control-drag** from the "Icon" table view cell to the Icon Picker View Controller and add a segue of type **Selection Segue – Show**. Make sure you're dragging from the Table View Cell, not its Content View or any of the other subviews. If you are unable to do this accurately from the scene, remember that you can also Control-drag from the Document Outline.

➤ Give the segue the identifier **PickIcon**.

➤ Thanks to the segue, the new view controller has been given a navigation bar. Double-click the navigation bar center, where the title should be, and set the title to **Choose Icon**.

This part of the storyboard should now look like this:



The Icon Picker view controller in the storyboard

Display the icon picker

➤ In **ListDetailViewController.swift**, change the `willSelectRowAt` table view delegate method to:


```
override func tableView(
  _ tableView: UITableView,
  willSelectRowAt indexPath: IndexPath
) -> IndexPath? {
  return indexPath.section == 1 ? indexPath : nil
}
```

Without this change you cannot tap the "Icon" cell to trigger the segue.

Previously this method always returned `nil`, which meant tapping on rows was not possible. Now, however, you want to allow the user to tap the Icon cell, so this method should return the index-path for that cell.

Because the Icon cell is the only row in the second section, you only have to check `indexPath.section`. There is no need to check the row number. Users still can't select the cell with the text field from section 0.

➤ Run the app and verify that there is now an Icon row in the Add/Edit Checklist screen. Tapping it will open the Choose Icon screen and show a list of icons.



The icon picker screen

Handle icon selection

You can press the back button to go back but selecting an icon doesn't do anything yet. It just colors the row gray but doesn't put the icon into the checklist.

To make this work, you have to hook up the icon picker to the Add/Edit Checklist screen through its own delegate protocol.

➤ First, add an instance variable in **ListDetailViewController.swift**:

```
var iconName = "Folder"
```

You use this variable to keep track of the chosen icon name.

Even though the `Checklist` object now has an `iconName` property, you cannot keep track of the chosen icon in the `Checklist` object for the simple reason that you may not always have a `Checklist` object, i.e. when the user is adding a new checklist.

So, you'll store the icon name in a temporary variable and copy that into the `Checklist`'s `iconName` property at the right time.

You should initialize the `iconName` variable with something reasonable. Let's go with the folder icon. This is only necessary for new `Checklists`, which get the Folder icon by default.

➤ Update `viewDidLoad()` to the following:

```
override func viewDidLoad() {
  . . .
  if let checklist = checklistToEdit {
    . . .
    iconName = checklist.iconName              // add this
  }
  iconImage.image = UIImage(named: iconName)   // add this
}
```

This has two new lines: If the `checklistToEdit` optional is not `nil`, then you copy the `Checklist` object's icon name into the `iconName` instance variable. You also load the icon's image file into a new `UIImage` object and set it as the cell's image so it shows up in the Icon row.

Earlier you created a push segue named "PickIcon". You still need to implement `prepare(for:sender:)` in order to tell the `IconPickerViewController` that this screen is now its delegate.

➤ First, add the name of that protocol to the `class` line in **ListDetailViewController.swift**:

```
class ListDetailViewController: UITableViewController,
UITextFieldDelegate, IconPickerViewControllerDelegate {
```

➤ Next, add the implementation of the method from that delegate protocol:

```
// MARK: - Icon Picker View Controller Delegate
func iconPicker(
  _ picker: IconPickerViewController,
  didPick iconName: String
) {
  self.iconName = iconName
  iconImage.image = UIImage(named: iconName)
  navigationController?.popViewController(animated: true)
}
```

This puts the name of the chosen icon into the `iconName` variable to remember it, and also updates the image view with the new image.

After you do all that, you use `popViewController(animated:)` to "pop" the Icon Picker View Controller off the navigation stack.

Recall that `navigationController` is an optional property of the view controller, so you need to use `?` (or `!`) to access the actual `UINavigationController` object.

➤ Now, add the following method to **ListDetailViewController.swift**:

```
// MARK: - Navigation
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
  if segue.identifier == "PickIcon" {
    let controller = segue.destination as!
IconPickerViewController
    controller.delegate = self
  }
}
```

This code should have no big surprises for you.

➤ Change the `done()` action so that it puts the chosen icon name into the `Checklist` object when the user closes the screen:

```
@IBAction func done() {
  if let checklist = checklistToEdit {
    checklist.name = textField.text!
    checklist.iconName = iconName                  // add this
    delegate?.listDetailViewController(
      self,
      didFinishEditing: checklist)
  } else {
    let checklist = Checklist(name: textField.text!)
    checklist.iconName = iconName                  // add this
    delegate?.listDetailViewController(
      self,
      didFinishAdding: checklist)
  }
}
```

Finally, you must change `IconPickerViewController` to actually call the delegate method when a row is tapped.

➤ Add the following method to the bottom of **IconPickerViewController.swift**:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  if let delegate = delegate {
    let iconName = icons[indexPath.row]
    delegate.iconPicker(self, didPick: iconName)
  }
}
```


And that's it. You can now set icons on the `Checklist` objects.

To recap, you:

- Added a new view controller object.
- Designed its user interface in the storyboard editor.
- Hooked it up to the Add/Edit Checklist screen using a segue and a delegate.

Those are the basic steps you need to take with any new screen that you add.

➤ Run the app to try it out.



You can now give each list its own icon

Achievement unlocked: users can pick icons!

Code refactoring

There's still a small improvement you can make to the code. In `done()`, you currently do this:

```
let checklist = Checklist(name: textField.text!)
checklist.iconName = iconName
```

Setting the icon name can be considered part of the initialization of `Checklist`, so it would be nice if you could pass the icon name to the `Checklist` initializer. And you can :]

➤ Switch to **Checklist.swift** and modify the `init` method as follows:

```
init(name: String, iconName: String = "No Icon") {
  self.name = name
  self.iconName = iconName
  super.init()
}
```

The modified `init` method looks almost the same as the previous one except for taking a new `iconName` parameter and assigning it to the object's `iconName` property.

But what is the `= "No Icon"` bit after the second parameter? That's called a *default parameter value*. When you specify a default parameter value for a method, when the method is called, you can omit the parameters with default values and the method call would still work, but the default values would be used for the parameters that were omitted. Nifty, huh?

➤ In **ListDetailViewController.swift**'s `done()` method, replace the code that creates the new `Checklist` object with this and remove the old line set the `iconName` property:

```
let checklist = Checklist(name: textField.text!, iconName:
iconName)
```

➤ Build the app to verify it still works.

Exercise: Give `ChecklistItem` an `init(text:)` method that is used instead of the parameter-less `init()`. Or how about an `init(text:checked:)` method?


Make the app look good

For *Checklists*, you're going to keep things simple as far as fancying up the graphics goes. The standard look of navigation controllers and table views is perfectly adequate, although a little bland. In the next apps you'll see how you can customize the look of these UI elements.

Change the tint color

Even though this app uses the stock visuals, there is a simple trick to give the app its own personality: changing the **tint color**.

The tint color is what UIKit uses to indicate that things, such as buttons, can be interacted with. The default tint color is a medium blue.




The buttons all use the same tint color

Changing the tint color is pretty easy.

➤ Open the storyboard and go to the **File inspector** (the first tab). Make sure you select a scene on the storyboard, otherwise you might not see the setting you need for the next step.

➤ Show the dropdown for **Global Tint**, click **Custom...** to open the color picker, and choose Red: 4, Green: 169, Blue: 235. That makes the tint color a lighter shade of blue.



Changing the Global Tint color for the storyboard


Tip: If the color picker only shows a black & white bar, then click the dropdown at the top that says Gray Scale Slider and change it to **RGB Sliders**.

Set the color of the checkmark

It would also look nice if the checkmark wasn't black but used the tint color too.

➤ To make that happen, select the checkmark label in the storyboard, switch to the Attributes inspector and change the **Color** setting to the same color as the global tint color.

➤ Run the app. It already looks a lot more interesting:




The tint color makes the app less plain looking

Add app icons

No app is complete without an icon. The Resources folder for this app contains a folder named **Icon** with the app icon image in various sizes. Notice that it uses the same blue as the tint color.

➤ Add these icons to the asset catalog – **Assets.xcassets**. Recall that icons go into the **AppIcon** section. Simply drag them from the Finder into the slots.



The app icons in the asset catalog


Set the launch image

Apps should also have a launch image or launch file. Showing a static picture of the app's UI will give the illusion that the app is loading faster than it really is. It's all smoke and mirrors :]

The Xcode template includes the file **LaunchScreen.storyboard** that is used as the launch file. With some effort you could make this look like the initial screen of the app, but there's an easier solution.

➤ Open the **Project Settings** screen. In the **General** tab, scroll down to the **App Icons and Launch Images** section.

➤ In the **Launch Screen File** box, press the arrow and select **Main.storyboard**.



Changing the launch screen file


This tells the app you'll be using the design from the storyboard as the launch file.

Upon startup, the app finds the initial view controller and converts it into a static launch image. For this app that is the All Lists View Controller inside its navigation controller.

➤ Delete **LaunchScreen.storyboard** from the project.

➤ From the **Product** menu choose **Clean Build Folder**. It's also a good idea to delete the app from the Simulator just so it no longer has any copies of the old launch file lying around — hold down on the icon until it starts to wiggle, just like on a real iPhone.

➤ Run the app. Just before the real UI appears you should briefly see the following launch screen:



The empty launch screen

The launch screen simply has a navigation bar and an empty table view. This gives the illusion the app's UI has already been loaded, though in reality, the data hasn't been filled in yet.

Using a proper launch screen makes the app look more professional – and faster!

For many apps, you can simply use the main storyboard as the launch file, making it a no-brainer to add.

Test on all iOS devices

The app should run without major problems on all current iOS devices, from the smallest (iPhone SE) to the largest (iPad Pro). Table view controllers are very flexible and will automatically resize to fit the screen, no matter how large or small. Give it a try in the different Simulators!

Of course, there's a bit of a gap between *should* and *does* — so make sure to test on all the different device types to make sure that nothing was missed :]

But if all your testing turns up nothing amiss, then you should be good to go!

You can find the project for the app up to this point under **19-UI-improvements** in the Source Code folder.

Chapter 20: Local Notifications

By Fahim Farook

I hope you're still with me! We have discussed view controllers, navigation controllers, storyboards, segues, table views and cells, and the data model in great detail. These are all essential topics to master if you want to build iOS apps because almost every app uses these building blocks.

In this chapter you're going to expand the app to add a new feature: **local notifications**, using the iOS User Notifications framework. A local notification allows the app to schedule a reminder to the user that will be displayed even when the app is not running.

You will add a "due date" field to the `ChecklistItem` object and then remind the user about this deadline with a local notification.

If this sounds like fun, then keep reading. :-)

The steps for this chapter are as follows:

- **Try it out:** Try out a local notification just to see how it works.
- **Set a due date:** Allow the user to pick a due date for to-do items.
- **Due date UI:** Create a date picker control.
- **Schedule local notifications:** Schedule local notifications for the to-do items, and update them when the user changes the due date.

Try it out

Before you think about how to integrate local notifications with *Checklists*, let's just schedule a local notification and see what happens.

By the way, local notifications are different from *push* notifications – also known as *remote* notifications. Push notifications allow your app to receive messages about external events, such as your favorite team winning the World Series and have to be sent to your device from a remote server.

Local notifications are more similar to an alarm clock: you set a specific time and then it "beeps". Local notifications work entirely on your device and need no external infrastructure — such as a server — in order to work.

Get permission to display local notifications

An app is only allowed to show local notifications after it has asked the user for permission. If the user denies permission, then any local notifications for your app simply won't appear. You only need to ask for permission once, so let's do that first.

➤ Open **AppDelegate.swift** and add a new import to the top of the file:

```
import UserNotifications
```

This tells the compiler that we're going to use the User Notifications framework.

➤ Add the following to `application(_:didFinishLaunchingWithOptions:)`, just before the `return true` line:

```
// Notification authorization
let center = UNUserNotificationCenter.current()
center.requestAuthorization(options: [.alert, .sound]) {granted,
error in
  if granted {
    print("We have permission")
  } else {
    print("Permission denied")
  }
}
```

The `application(_:didFinishLaunchingWithOptions:)` method of the app delegate is called when the app starts up. It is the *entry point* for the app, the first place in the code where you can do something after the app launches.

Because you're just playing with these local notifications now, this is a good place to ask for permission.

You tell iOS that the app wishes to send notifications of type "alert" with a sound effect. Later you'll move this code to a more appropriate location.

★ ★ ★

Things that start with a dot

Throughout the app you've seen things like `.none`, `.checkmark`, and `.subtitle` — and now `.alert` and `.sound`. These are *enumeration* symbols.

An enumeration, or enum for short, is a data type that consists of a list of possible symbols and their values.

For example, the `UNAuthorizationOptions` enum contains the following symbols (and a few others besides):

```
.badge
.sound
.alert
.carPlay
```

You can combine these enums in an array to define what sort of notifications the app will show to the user. Here you've chosen the combination of an alert and a sound effect by writing `[.alert, .sound]`.


It's easy to spot when an enum is being used because of the dot in front of the symbol name. This is actually shorthand notation; you could also have written it like this:

```
center.requestAuthorization(options:
[UNAuthorizationOptions.alert, UNAuthorizationOptions.sound]) {
  . . .
```

Fortunately, Swift is smart enough to realize that `.alert` and `.sound` are from the enum `UNAuthorizationOptions`, so you can save yourself some keystrokes.

★ ★ ★

➤ Run the app. You should immediately get a popup asking for permission:



The permission dialog

Tap **Allow**. The next time you run the app you won't be asked again; iOS remembers your choice.

If you tapped Don't Allow — naughty! — then you can always reset the Simulator to get the permissions dialog again. You can also change the notification options via the *Settings* app.

Show a test local notification

➤ Stop the app and add the following code to the end of `didFinishLaunchingWithOptions` before the `return`:

```
let content = UNMutableNotificationContent()
content.title = "Hello!"
content.body = "I am a local notification"
content.sound = UNNotificationSound.default

let trigger = UNTimeIntervalNotificationTrigger(
  timeInterval: 10,
  repeats: false)
let request = UNNotificationRequest(
  identifier: "MyNotification",
  content: content,
  trigger: trigger)
center.add(request)
```

This creates a new local notification. Because you wrote `timeInterval: 10`, it will fire exactly 10 seconds after the app has started.

The `UNMutableNotificationContent` describes what the local notification will say. Here, you set an alert message to be shown when the notification fires. You also set a sound.

Finally, you add the notification to the `UNUserNotificationCenter`. This object is responsible for keeping track of all the local notifications and displaying them at the scheduled time.

➤ Run the app. Immediately after it has started, exit to the home screen.

Wait 10 seconds... I know, it seems like an eternity! After an agonizing 10 seconds a message should pop up:



The local notification message

➤ Tap the notification and it should take you back to the app.

And that's a local notification. Pretty cool, huh?

Why did I want you to exit to the home screen? iOS will only show a notification alert if the app is not currently active.

➤ Stop the app and run it again. This time don't press Home and just wait.

Well, don't wait too long — nothing will happen. The local notification does get fired, but it is not shown to the user. To handle this situation, we must listen somehow to interesting events that concern these notifications. How? Through a delegate, of course!

Handle local notification events

➤ Add the notification delegate to `AppDelegate`'s `class` declaration:

```
class AppDelegate: UIResponder, UIApplicationDelegate,
UNUserNotificationCenterDelegate {
```

This makes `AppDelegate` the delegate for the `UNUserNotificationCenter`.

➤ Also add the following method to **AppDelegate.swift**:

```
// MARK: - User Notification Delegates
func userNotificationCenter(
  _ center: UNUserNotificationCenter,
  willPresent notification: UNNotification,
  withCompletionHandler completionHandler: @escaping
(UNNotificationPresentationOptions) -> Void
) {
  print("Received local notification \(notification)")
}
```

This method will be invoked when the local notification is posted and the app is still running. You won't do anything here except log a message to the debug pane.

When your app is active and in the foreground, it is supposed to handle any fired notifications on its own. Depending on the type of app, it may make sense to react to the notification, for example to show a message to the user or to refresh the screen.

➤ Finally, tell the `UNUserNotificationCenter` that `AppDelegate` is now its delegate. You do this in `application(_:didFinishLaunchingWithOptions:)`. Add this after you ask for permission — perhaps when permission is granted?:

```
center.delegate = self
```

➤ Run the app again and just wait – don't press Home.

After 10 seconds you should see a message in the Xcode Console. It displays something like this:

```
Received local notification <UNNotification: 0x600000f9f4b0;
source: com.razeware.Checklists date: 2021-07-17 19:37:44 +0000,
request: <UNNotificationRequest: 0x600000f9f450; identifier:
MyNotification, content: <UNNotificationContent: 0x600003de9900;
title: <redacted>, subtitle: (null),
. . .
```

> **Note:** In case you're wondering why some values are shown as `<redacted>`, that's due to privacy constraints in iOS which stops possibly sensitive information, such as the contents of a notification message, being captured/logged by an application.

All right, now you know that it works, you should remove the test code from **AppDelegate.swift** because you don't really want to schedule a new notification every time the user starts the app.

➤ Remove the the local notification code from `didFinishLaunchingWithOptions`, but keep these lines:

```
let center = UNUserNotificationCenter.current()
center.delegate = self
```

You can also keep the `userNotificationCenter(_:willPresent:withCompletionHandler:)` method, as it will come in handy when debugging the local notifications.

Set a due date

Let's think about how the app will handle these notifications. Each `ChecklistItem` will get a due date property (a `Date` object, which stores a date and time) and a `Bool` that says whether the user wants to be reminded of this item or not.

Users might not want to be reminded of everything, so you shouldn't schedule local notifications unless the user asks for it. Such a `Bool` variable is often called a *flag*. Let's name it `shouldRemind`.

When do you schedule a notification?

First, let's figure out how and when to schedule the notifications. I can think of the following situations:

- When the user adds a new `ChecklistItem` object that has the `shouldRemind` flag set, you must schedule a new notification.
- When the user changes the due date on an existing `ChecklistItem`, the old notification, if there is one, should be cancelled and a new one scheduled in its place if `shouldRemind` is still set.
- When the user toggles the `shouldRemind` flag from on to off, the existing notification should be cancelled. The other way around, from off to on, should schedule a new notification.
- When the user deletes a `ChecklistItem`, its notification, if it had one, should be cancelled.
- When the user deletes an entire `Checklist`, all the notifications for those items, if there are any, should be cancelled.

This makes it obvious that you don't need just a way to schedule new notifications, but also a way to cancel them.

You should probably also check that you don't create notifications for to-do items whose due dates are in the past. I'm sure iOS is smart enough to ignore those notifications, but let's be good citizens anyway.

Associate to-do items with notifications

We need some way to associate `ChecklistItem` objects with their local notifications. This requires some changes to our data model.

When you schedule a local notification, you create a `UNNotificationRequest` object. It is tempting to put the `UNNotificationRequest` object as an instance variable in `ChecklistItem`, so you always know what it is. However, this is not the correct approach.

Instead, you'll use an *identifier*. When you create a local notification, you need to give it an identifier, which is just a `String`. It doesn't really matter what is in this string, as long as it is unique for each notification.

To cancel a notification at a later point, you don't use the `UNNotificationRequest` object but the identifier you gave it. The right approach is to store this identifier in the `ChecklistItem` object.

Even though the identifier for the local notification is a `String`, you'll give give each `ChecklistItem` an identifier that is simply a number. You'll also save this item ID in the Checklists.plist file. When it's time to schedule or cancel a local notification, you'll turn that number into a string. Then, you can easily find the notification when you have the `ChecklistItem` object, or the `ChecklistItem` object when you have the notification object.

Assigning numeric IDs to objects is a common approach when creating data models — it is very similar to giving records in a relational database a numeric primary key, if you're familiar with that sort of thing.

➤ Add these properties to **ChecklistItem.swift**:

```
var dueDate = Date()
var shouldRemind = false
var itemID = -1
```

Note that you called the last variable `itemID` and not simply "id". The reason is that `id` is a special keyword in Objective-C, and this could cause trouble if you ever wanted to mix your Swift code with Objective-C code.

In the above code, you have initialized `itemID` with -1. However, what you really want is to have `itemID` set to a unique integer value when a new `ChecklistItem` instance is created. You can do this by adding a custom initializer to `ChecklistItem`.

But before you do that, you need to add a new method to `DataModel` to generate a unique item ID.

➤ Hop on over to **DataModel.swift** and add a new method:

```
class func nextChecklistItemID() -> Int {
  let userDefaults = UserDefaults.standard
  let itemID = userDefaults.integer(forKey: "ChecklistItemID")
  userDefaults.set(itemID + 1, forKey: "ChecklistItemID")
  return itemID
}
```

You're using your old friend `UserDefaults` again.

This method gets the current "ChecklistItemID" value from `UserDefaults`, adds 1 to it, and writes it back to `UserDefaults`. It returns the previous value to the caller.

You could add a default value for "ChecklistItemID" to the `registerDefaults()` method so as to customize the start value for the item ID, but you really don't have to in this case :] Remember that if there is no existing value for "ChecklistItemID", you'd get 0 back from a call to `UserDefaults` – if you didn't provide a default value via `registerDefaults()`. That is good enough for your use since your IDs would then start at 0 and count up.

The first time `nextChecklistItemID()` is called, it will return the ID 0. The second time it is called, it will return the ID 1, the third time it will return the ID 2, and so on. The number is incremented by one each time. You can call this method a few billion times before you run out of unique IDs.

★ ★ ★

Class methods vs. instance methods

If you are wondering why you wrote:

```
class func nextChecklistItemID()
```

And not just:

```
func nextChecklistItemID()
```

Then I'm glad you're paying attention!

The inclusion of the `class` keyword in the method declaration indicates a class method — this kind of method applies to the class as a whole. So far you've been using *instance methods*. They just have the word `func` — without `class` — and work only on a specific instance of that class.

We haven't discussed the difference between classes and instances before, and you'll get into that in more detail later in the book. For now, just remember that a method starting with `class func` allows you to call methods on an object even when you don't have a reference to that object.

Adding the `class` keyword means that you can call this method without having a reference to an instance of the `DataModel` object.

With a class method, you do:

```
itemID = DataModel.nextChecklistItemID()
```

Instead of:

```
itemID = dataModel.nextChecklistItemID()
```

This is because `ChecklistItem` objects do not have a `dataModel` property with a reference to a `DataModel` object. You could certainly pass them such a reference, but I decided that using a *class method* was easier.

I had to make a trade-off: is it worth giving each `ChecklistItem` object a reference to the `DataModel` object, or can I get away with a simple class method? To keep things simple, I chose the latter. It's certainly possible that, if you were to develop this app further, it would make more sense to give `ChecklistItem` a `dataModel` property instead. But that would be up to you :]

★ ★ ★

➤ Now, switch back to **ChecklistItem.swift** and add an `init()` method to set up the unique ID:

```
override init() {
  super.init()
  itemID = DataModel.nextChecklistItemID()
}
```

This asks the `DataModel` object for a new item ID whenever the app creates a new `ChecklistItem` object and replaces the initial value of -1 with that unique ID.

Display the new IDs

For a quick test to see if assigning these IDs works, you can add them to the text that's shown in the `ChecklistItem` cell label — this is just a temporary thing for testing purposes, as users couldn't care less about the internal identifier of these objects.

➤ In **ChecklistViewController.swift**, change the `configureText(for:with:)` method to:


```
func configureText(
  for cell: UITableViewCell,
  with item: ChecklistItem
) {
  let label = cell.viewWithTag(1000) as! UILabel
  //label.text = item.text
  label.text = "\(item.itemID): \(item.text)"
}
```

I have commented out the original line because you'll want to reuse it later. The new one uses `\( … )` to add the to-do item's `itemID` property to the text.

Before you run the app, do note that you have changed the format of the `ChecklistItem` and thus, by extension, the Checklists.plist file. So your existing data will not display when you run the app.

➤ Run the app and add some checklist items. Each new item should get a unique identifier. Exit to the home screen to make sure everything is saved properly, and stop the app.

➤ Run the app again and add some new items; the IDs for these new items should start counting at where the numbering previously left off.




The items with their IDs. Note that the item with ID 3 was deleted in this example.

OK, that takes care of the IDs. Now lets add the "due date" and "should remind" fields to the Add/Edit Item screen.

Keep `configureText(for:with:)` the way it is for the time being; that will come in handy with testing the notifications.

Due date UI

You will add settings for the two new fields to the Add/Edit Item screen and make it look like this:



The Add/Edit Item screen now has Remind Me and Due Date fields

The due date field will require some sort of date picker control. iOS comes with a cool date picker view that you'll add to the table view.

The UI changes

➤ Add the following outlets to **ItemDetailViewController.swift**:


```
@IBOutlet weak var shouldRemindSwitch: UISwitch!
@IBOutlet weak var datePicker: UIDatePicker!
```

➤ Open the storyboard and select the Table View in the Add Item scene.

➤ Add a new section to the table. The easiest way to do this is to increment the **Sections** value in the **Attributes inspector**. This duplicates the existing section and cell.

➤ Remove the Text Field from the new cell. Select the new section in the Document Outline and then increment its **Rows** value to 2 in the **Attributes inspector**.

You will now design the new cells to look as follows:



The new design of the Add/Edit Item screen

➤ Add a **Label** to the first cell and set its text to **Remind Me**. The font should be **System**, size **17**.

➤ Also drag a **Switch** control into the cell. Hook it up to the `shouldRemindSwitch` outlet on the view controller. In the Attributes inspector, set its **State** to **Off** so it is no longer green.

➤ Pin the Switch to the **top**, **right**, and **bottom** edges of the table view cell. This makes sure the control will be visible regardless of the width of the device's screen.

➤ **Center** the Label (vertically) with respect to the Switch, and then pin its **left** and **right** edges – make sure that the right edge is pinned with 8 points instead of the existing value.

➤ The third cell has two controls: a Due Date label on the left and a date picker control on the right. First, drag a label on to the left and change its title to **Due Date**. The font for the label should already be set to **System**, size **17**

➤ Now drag a **Date Picker** control on to the cell. Yes, it will be bigger than the cell. Don't worry, we'll fix that in a moment.

➤ Make sure that the **Style** is set to **Automatic** in the **Attributes Inspector** for the Date Picker and the **Mode** is set to **Date and Time**.

➤ Select the Date Picker and pin it to the **top**, **right**, and **bottom** edges of the table view cell with a value of **4** for the top and bottom and **16** for the right. Pin the **width** to **230** and **height** to **44**.

➤ Hook the **Date Picker** up to the `datePicker` outlet on the view controller.

➤ Select the **Due Date** label, **Center Vertically** with respect to the Date Picker, and then pin its **left** and **right** edges where the right edge should be **8**.

You may need to adjust the Auto Layout constraints for the Remind Me label and the switch to align them nicely with the labels from the "due date" cell.

Tip: select the "Due Date" label and Date Picker and look in the Size inspector to see what their positions are – should be 16 points from the edges.

> **Note:** Pre-iOS 14, the Date Picker control was 216 points tall and would not have fit in the table view cell. You had to do a lot more set up (and a lot more code) to set up a date picker to be usable in the app. But all that is no longer needed as of iOS 14.

Display the due date

Let's write the code for displaying the due date.

➤ Change `viewDidLoad()` as follows:

```
override func viewDidLoad() {
  . . .
  if let item = itemToEdit {
    . . .
    shouldRemindSwitch.isOn = item.shouldRemind  // add this
    datePicker.date = item.dueDate               // add this
  }
}
```

If there is an existing `ChecklistItem` object, you set the switch control to on or off, depending on the value of the object's `shouldRemind` property. If the user is adding a new item, the switch is initially off — remember, you already did that in the storyboard.

You also get the due date from the `ChecklistItem` and set the displayed date in the date picker.

But what about a new `ChecklistItem` item?

If you check the date picker on the storyboard, you'll notice that in the Attributes Inspector, the Date value is set to "Current Date". This means that, for a new `ChecklistItem` item, the due date will be right now. That sounds reasonable, but by the time the user has filled in the rest of the fields and pressed Done, that due date will be in the past.

But you do have to have a value there. You could set the Date value via code to be an alternative value such as this time tomorrow, or ten minutes from now. I'll leave that as an exercise for you to try.

Update edited values

➤ The last thing to change in this file is the `done()` action. Replace the current code with:

```
@IBAction func done() {
  if let item = itemToEdit {
    item.text = textField.text!

    item.shouldRemind = shouldRemindSwitch.isOn  // add this
    item.dueDate = datePicker.date               // add this
```

```
      delegate?.itemDetailViewController(
        self,
        didFinishEditing: item)
    } else {
      let item = ChecklistItem()
      item.text = textField.text!
      item.checked = false


      item.shouldRemind = shouldRemindSwitch.isOn  // add this
      item.dueDate = datePicker.date               // add this

      delegate?.itemDetailViewController(
        self,
        didFinishAdding: item)
    }
  }
```

Here you put the value of the switch control and the date picker back into the `ChecklistItem` object when the user presses the Done button.

➤ Run the app and change the position of the switch control.

➤ Now tap on the date picker – it should show you an on-screen calendar where you can pick the date you want. Nifty!



The date picker calendar

You can tap on the month and year on the top left to change the month and the year — and tap on the top left control again to get back to the calendar. You can also tap on the two arrows on the top right to go back/forward month-by-month. Of course, you can enter the date directly into the date field at the bottom.

Once you are done, tap outside the calendar to dismiss it. Simple. The app will remember your changes when you terminate it – be sure to exit to the home screen first though.

As I mentioned previously, this used to take a lot more code to get to this point before iOS 14. But now, it's as simple as dropping a couple of controls on to the storyboard and updating their values!

Change the switch color

There's one tiny issue with the UI still that you might have noticed – the switch for Remind Me shows up in green when it is on, instead of our cool blue tint color.

This is easy enough to fix.

➤ Open the storyboard, select the switch in the Add Item scene and change **On Tint** in the **Attributes Inspector** to the same blue that you set the Global Tint to. Generally, that color should be in your last used color list and you won't even have to enter the color values :]

➤ Run the app again and make sure that the switch now displays the correct color.

Schedule local notifications

One of the principles of object-oriented programming is that objects should do as much as possible themselves. Therefore, it makes sense that the `ChecklistItem` object should schedule its own notifications.

Schedule notifications

➤ Add the following method to **ChecklistItem.swift**:

```
func scheduleNotification() {
  if shouldRemind && dueDate > Date() {
    print("We should schedule a notification!")
  }
}
```

This compares the due date on the item with the current date — you can always get the current date (and time) by making a new `Date` object.

The statement `dueDate > Date()` compares the two dates and returns `true` if `dueDate` is in the future and `false` if it is in the past. If the due date is in the past, the `print()` will not be performed.

Note the use of the "and" (&&) operator. You only print the text when the Remind Me switch is set to "on" *and* the due date is in the future.

You will call this method when the user presses the Done button after adding or editing a to-do item.

➤ In the `done()` action in **ItemDetailViewController.swift**, add the following line just before the call to `didFinishEditing` and also before `didFinishaAdding`:

```
item.scheduleNotification()
```

➤ Run the app and try it out. Add a new item, set the switch to ON but don't change the due date. Press Done.

There should be no message in the Console because the due date has already passed — it is several seconds in the past by the time you press Done.

➤ Add another item, set the switch to ON, and choose a due date in the future.

When you press Done now, the text "We should schedule a notification!" should appear in the Console.

Now that you've verified the method is called in the proper place, let's actually schedule a new local notification object for the following three scenarios: adding a to-do item, editing a to-to item, deleting a to-do item.

Add a to-do item

➤ In **ChecklistItem.swift**, change `scheduleNotification()` to:

```
func scheduleNotification() {
  if shouldRemind && dueDate > Date() {
    // 1
    let content = UNMutableNotificationContent()
    content.title = "Reminder:"
    content.body = text
    content.sound = UNNotificationSound.default

    // 2
    let calendar = Calendar(identifier: .gregorian)
    let components = calendar.dateComponents(
      [.year, .month, .day, .hour, .minute],
      from: dueDate)
    // 3
    let trigger = UNCalendarNotificationTrigger(
      dateMatching: components,
      repeats: false)
    // 4
    let request = UNNotificationRequest(
      identifier: "\(itemID)",
      content: content,
```

```
        trigger: trigger)
      // 5
      let center = UNUserNotificationCenter.current()
      center.add(request)

      print("Scheduled: \(request) for itemID: \(itemID)")
    }
  }
```

You've seen this code before when you tried out local notifications for the first time, but there are a few differences.

1. Put the item's `text` into the notification message.
2. Extract the year, month, day, hour, and minute from the `dueDate`. We don't care about the number of seconds — the notification doesn't need to be scheduled with up-to-the-second precision, on the minute is precise enough.
3. To test local notifications you used a `UNTimeIntervalNotificationTrigger`, which scheduled the notification to appear after a number of seconds. Here, you're using a `UNCalendarNotificationTrigger`, which shows the notification at the specified date.
4. Create the `UNNotificationRequest` object. Important here is that we convert the item's numeric ID into a `String` and use it to identify the notification. That is how you'll be able to find this notification later in case you need to cancel it.
5. Add the new notification to the `UNUserNotificationCenter`.

Xcode is not so impressed with this new code and gives a bunch of error messages.

What is wrong here? `UNUserNotificationCenter` and the other objects are provided by the User Notifications framework — you can tell by the "UN" prefix in their names.

However, `ChecklistItem` hasn't used any code from that framework until now. The only framework objects it has used, `NSObject` and `Codable`, came from another framework, Foundation.

➤ To tell `ChecklistItem` about the User Notifications framework, you need to add the following line to the top of the file, below the other `import`:

```
import UserNotifications
```

Now the errors disappear like snow in the sun.

There's another small problem, though. If you've reset the Simulator recently, then the app no longer has permission to send local notifications.

➤ Try it out. Run the app, add a new checklist item, set the due date a minute into the future, and press Done. You might not see a notification.

Even if you do see a notification, since the authorization request code is no longer there, *Checklists* certainly won't have permission to display notifications on your user devices.

When you were just messing around at the beginning of this chapter, you placed the permission request code in the `AppDelegate` and ran it immediately upon launch.

That's not recommended.

Don't you just hate those apps that prompt you for ten different things before you've even had a chance to properly look at them? Let's be a bit more user friendly with our own app!

➤ Add the following method to **ItemDetailViewController.swift**:

```
@IBAction func shouldRemindToggled(_ switchControl: UISwitch) {
  textField.resignFirstResponder()

  if switchControl.isOn {
    let center = UNUserNotificationCenter.current()
    center.requestAuthorization(options: [.alert, .sound]) {_, _
in
      // do nothing
    }
  }
}
```


When the Remind Me switch is toggled to ON, this prompts the user for permission to send local notifications. Once the user has given permission, the app won't put up a prompt again.

➤ If the above method might not compile, add an `import UserNotifications` at the top of the file. This might not always be needed.

➤ Open the storyboard and connect the **shouldRemindToggled:** action to the switch control.

➤ Test it out. Run the app, add a new checklist item, set the due date a minute into the future, press Done and exit to the home screen.

Wait one minute (patience...) and the notification should appear. Pretty cool!



The local notification when the app is in the background

That takes care of the adding a new item scenario. There are two others left.

Edit an existing item

When the user edits an item, the following situations can occur with the Remind Me switch:

- Remind Me was switched off and is now switched on. You have to schedule a new notification.
- Remind Me was switched on and is now switched off. You have to cancel the existing notification.
- Remind Me stays switched on but the due date changes. You have to cancel the existing notification and schedule a new one.
- Remind Me stays switched on but the due date doesn't change. You don't have to do anything.
- Remind Me stays switched off. Here you also don't have to do anything.

Of course, in all those situations you'll only schedule the notification if the due date is in the future.

Phew, that's quite a list. It's always a good idea to take stock of all possible scenarios before you start programming because this gives you a clear picture of everything you need to tackle.

It may seem like you need to write a lot of logic here to deal with all these situations, but actually it turns out to be quite simple.

First you'll check if there is an existing notification for this to-do item. If there is, you simply cancel it. Then you determine whether the item should have a notification and if so, you schedule a new one.

That should take care of all the above situations, even if sometimes you simply could have left the existing notification alone. The algorithm is crude, but effective.

➤ Add the following method to **ChecklistItem.swift**:

```
func removeNotification() {
  let center = UNUserNotificationCenter.current()
  center.removePendingNotificationRequests(withIdentifiers: ["\
(itemID)"])
}
```

This removes the local notification for this `ChecklistItem`, if it exists. Note that `removePendingNotificationRequests()` requires an array of identifiers, so we first put our `itemID` into a string with `\(…)` and then into an array using `[]`.

➤ Call this new method from to the top of `scheduleNotification()`:

```
func scheduleNotification() {
  removeNotification()
  . . .
}
```

Let's try it out.

➤ Run the app and add a to-do item with a due date two minutes into the future. A new notification will be scheduled. Go to the home screen and wait until it shows up.

➤ Edit the item and change the due date to three minutes into the future. The old notification will be removed and a new one scheduled for the new time.

➤ Add a new to-do item with a due date two minutes into the future. Edit the to-do item but now set the switch to OFF. The old notification will be removed and no new notification will be scheduled.

➤ Edit again and put the time a few minutes into the future but don't change anything else; no new notification will be scheduled because the switch is still off.

These tests should also work if you terminate the app in between.

Delete a to-do item

There is one last case to handle: deletion of a `ChecklistItem`. This can happen in two ways:

1. The user can delete an individual item using swipe-to-delete.
2. The user can delete an entire checklist, in which case all its `ChecklistItem` objects are also deleted.

An object is notified when it is about to be deleted using the `deinit` message. You can simply implement this method, check if there is a scheduled notification for this item, and then cancel it.

➤ Add the following to **ChecklistItem.swift**:

```
deinit {
  removeNotification()
}
```

That's all you have to do. The special `deinit` method will be invoked when you delete an individual `ChecklistItem` but also when you delete a whole `Checklist` — because all its `ChecklistItems` will be destroyed as well, as the array they are in is deallocated.

➤ Run the app and try it out. First, schedule some notifications a minute or so into the future and then remove that to-do item or its entire checklist. Wait until the due date comes and you shouldn't get a notification.

Once you're convinced everything works, you can remove the `print()` statements. They are only temporary for debugging purposes. You probably don't want to leave them in the final app. The `print()` statements won't hurt, but the end user can't see those messages anyway.

➤ Also remove the item ID from the label in the `ChecklistViewController` – that was only used for debugging.


That's a wrap!

Things should be starting to make sense by now. I've thrown you into the deep end by writing an entire app from scratch. We've touched on a number of advanced topics already, but hopefully you were able to follow along quite well with what we've been doing. Kudos for sticking with it until the end!

It's OK if you're still a bit fuzzy on the details. Sleep on it for a bit and keep tinkering with the code. Programming requires its own way of thinking and you won't learn that overnight. Don't be afraid to do this app again from the start — it will make more sense the second time around!

This section focused mainly on UIKit and its most important controls and patterns. In the next section we'll take a few steps back to talk more about the Swift language itself. And of course, you'll build another cool app.

Here is the final storyboard for *Checklists*:



The final storyboard

Completing all of that is pretty impressive! Give yourself a well-deserved pat on the back :]

Take a break, and when you're ready, continue on to the next section, where you'll make an app that knows its place! :-)

Haven't had enough yet? Here are some challenges to sink your teeth into:

> **Exercise:** Display the due date in the table view cells, under the text of the to-do item.

> **Exercise:** Sort the to-do items list based on the due date. This is similar to what you did with the list of `Checklists` except that now you're sorting `ChecklistItem` objects and you'll be comparing `Date` objects instead of strings.

You can find the final project files for the Checklists app under **20-Local-notifications** in the Source Code folder.

Section 3: My Locations

With this third section and the *MyLocations* app, you get into Swift programming in earnest.

Sure, you've already coded apps in the previous two sections, but this section starts off with a good review of all the Swift coding principles you've learned so far and adds to it by introducing some new concepts too.

In addition to that, you learn about using GPS coordinates, displaying data on maps, and using the iOS image picker to take photos using your camera or to pick existing images from your photo album. There's a lot of valuable general information on Swift development as well as specific information about building location-aware apps.

This section also introduces you to building apps for Dark mode – a subject that you'll do a deep-dive into in the next section.

Chapter 21: Swift Review

By Fahim Farook

You have made great progress! You've learnt the basics of Swift programming and created two applications from scratch. You are on the threshold of creating your next app.

But, a good building needs a good foundation. And in order to strengthen the foundations of your Swift knowledge, you first need some additional theory. There is still a lot more to learn about Swift and object-oriented programming!

In the previous chapters I've shown you a fair bit of the Swift programming language already, but not quite everything. Previously, it was good enough if you could more-or-less follow along with what we were doing, but now is the time to fill in the gaps in theory. So, let's do a little refresher on what we've talked about so far.

In this chapter, you will cover the following:

- **Variables, constants, and types:** the difference between variables and constants, and what a type is.
- **Methods and functions:** what are methods and functions — are they the same thing?
- **Making decisions:** an explanation of the various programming constructs that can be used in the decision making process for your programs.
- **Loops:** how do you loop through a list of items?
- **Objects:** all you ever wanted to know about Objects — what they are, their component parts, how to use them, and how not to abuse them.
- **Protocols:** the nitty, gritty details about protocols.

Variables, constants and types

Variables and types

A **variable** is a temporary container for a specific type of value:

```
var count: Int
var shouldRemind: Bool
var text: String
var list: [ChecklistItem]
```

The **data type**, or just **type**, of a variable determines what kind of values it can contain. Some variables hold simple values such as `Int` or `Bool`, others hold more complex objects such as `String` or `Array`.

The basic types you've used so far are: `Int` for whole numbers, `Float` for numbers with decimals (also known as *floating-point* numbers), and `Bool` for boolean values (`true` or `false`).

There are a few other fundamental types as well:

- `Double`. Similar to a `Float` but with more precision. You will use `Doubles` later on for storing latitude and longitude data.
- `Character`. Holds a single character. A `String` is a collection of `Characters`.
- `UInt`. A variation on `Int` that you may encounter occasionally. The U stands for *unsigned*, meaning the data type can hold positive values only. It's called unsigned because it cannot have a negative sign (-) in front of the number. `UInt` can store numbers between 0 and 18 quintillion, but no negative numbers.
- `Int8`, `UInt8`, `Int16`, `UInt16`, `Int32`, `UInt32`, `Int64`, `UInt64`. These are all variations on `Int`. The difference is in how many bytes they have available to store their values. The more bytes, the bigger the values they can store. In practice, you almost always use `Int`, which uses 8 bytes for storage on a 64-bit platform (a fact that you may immediately forget) and can fit positive and negative numbers up to about 19 digits. Those are big numbers!
- `CGFloat`. This isn't really a Swift type but a type defined by the iOS SDK. It's a decimal point number like `Float` and `Double`. For historical reasons, this is used throughout UIKit for floating-point values. (The "CG" prefix stands for the **C**ore **G**raphics framework.)

Swift is very strict about types, more so than many other languages. If the type of a variable is `Int`, you cannot put a `Float` value into it. The other way around also won't work: an `Int` won't go into a `Float`.

Even though both types represent numbers of some sort, Swift won't automatically convert between different number types. You always need to convert the values explicitly.

For example:

```
var i = 10
var f: Float
f = i         // error
f = Float(i)  // OK
```

You don't always need to specify the type when you create a new variable. If you give the variable an initial value, Swift uses **type inference** to determine the type:

```
var i = 10              // Int
var d = 3.14            // Double
var b = true            // Bool
var s = "Hello, world"  // String
```

The integer value `10`, the floating-point value `3.14`, the boolean `true` and the string `"Hello, world"` are named **literal constants** or just **literals**.

Note that using the value 3.14 in the example above leads Swift to conclude that you want to use a `Double` here. If you intended to use a `Float` instead, you'd have to write:

```
var f: Float = 3.14
```

The `: Float` bit is called a **type annotation**. You use it to override the guess made by Swift's type inference mechanism, since it doesn't always get things right.

Likewise, if you wanted the variable `i` to be a `Double` instead of an `Int`, you'd write:

```
var i: Double = 10
```

Or a little shorter, by giving the value 10 a decimal point:

```
var i = 10.0
```

These simple literals such as `10`, `3.14`, or `"Hello world"`, are useful only for creating variables of the basic types — `Int`, `Double`, `String`, and so on. To use more complex types, you'll need to **instantiate** an object first.

When you write the following:

```
var item: ChecklistItem
```

It only tells Swift you want to store a `ChecklistItem` object into the `item` variable, but it does not create that `ChecklistItem` object itself. For that you need to write:

```
item = ChecklistItem()
```

The above code first reserves memory to hold the object's data, followed by a call to `init()` to properly set up the object for use. Reserving memory is also called **allocation**; filling up the object with its initial value(s) is **initialization**.

The whole process is known as **instantiating** the object — you're making an object **instance**. The instance is the block of memory that holds the values of the object's variables — that's why they are called "instance variables", get it?.

Of course, you can combine the above into a single line:

```
var item = ChecklistItem()
```

Here you left out the `: ChecklistItem` type annotation because Swift is smart enough to realize that the type of `item` should be `ChecklistItem`.

However, you can't leave out the `()` parentheses — this is how Swift knows that you want to make a new `ChecklistItem` instance.

Some objects allow you to pass **parameters** to their `init` method. For example:

```
var item = ChecklistItem(text: "Charge my iPhone", checked:
false)
```

This calls the corresponding `init(text:checked:)` method to prepare the newly allocated `ChecklistItem` object for usage.

You've seen two types of variables: **local variables**, whose existence is limited to the method they are declared in, and **instance variables** — also known as "ivars", or properties — that belong to the object and therefore can be used from within any method in the object.

The lifetime of a variable is called its **scope**. The scope of a local variable is smaller than that of an instance variable. Once the method ends, any local variables are destroyed.

```
class MyObject {
  var count = 0      // an instance variable

  func myMethod() {
    var temp: Int    // a local variable
    temp = count     // OK to use the instance variable here
  }

  // the local variable “temp” doesn’t exist outside the method
}
```

If you have a local variable with the same name as an instance variable, then it is said to **shadow** (or **hide**) the instance variable. You should avoid these situations as they can lead to subtle bugs where you may not be using the variable that you think you are:

```
class MyObject {
  var count = 7      // an instance variable

  func myMethod() {
    var count = 42   // local variable “hides” instance variable
    print(count)     // prints 42
  }
}
```

Some developers place an underscore in front of their instance variable names to avoid this problem: `_count` instead of `count`. An alternative is to use the keyword `self` whenever you want to access an instance variable:

```
  func myMethod() {
    var count = 42
    print(self.count)   // prints 7
  }
```

Constants

Variables are not the only code elements that can hold values. A variable is a container for a value that is allowed to *change* over the course of the app being run.

For example, in a note-taking app, the user can change the text of the note. So, you’d place that text into a `String` variable. Every time the user edits the text, the variable is updated.

Sometimes, you'll just want to store the result of a calculation or a method call into a temporary container, after which this value will never change. In that case, it is better to make this container a **constant** rather than a variable.

The following values cannot change once they've been set:

```
let pi = 3.141592
let difference = abs(targetValue - currentValue)
let message = "You scored \(points) points"
let image = UIImage(named: "SayCheese")
```

If a constant is local to a method, it's allowed to give the constant a new value the next time the method is called. The value from the previous method invocation is destroyed when the method ends, and the next time the app enters that method you're creating a new constant with a new value, but with the same name. Of course, for the duration of that method call, the constant's value must remain the same.

Tip: My suggestion is to use `let` for everything — that's the right solution 90% of the time. When you get it wrong, the Swift compiler will warn that you're trying to change a constant. Only then should you change it to a `var`. This ensures you're not making things variable that don't need to be.

Value types vs. reference types

When working with basic values such as integers and strings — which are **value types** — a constant created with `let` cannot be changed once it has been given a value:

```
let pi = 3.141592
pi = 3                // not allowed
```

However, with objects that are **reference types**, it is only the reference that is constant. The object itself can still be changed:

```
let item = ChecklistItem()
item.text = "Do the laundry"
item.checked = false
item.dueDate = yesterday
```

But this is not allowed:

```
let anotherItem = ChecklistItem()
item = anotherItem   // cannot change the reference
```

So how do you know what is a reference type and what is a value type?

Objects defined as `class` are reference types, while objects defined as `struct` or `enum` are value types. In practice, this means most of the objects from the iOS SDK are reference types but things that are built into the Swift language, such as `Int`, `String`, and `Array`, are value types. More about this important difference later.

Collections

A variable stores only a single value. To keep track of multiple objects, you can use a **collection** object. Naturally, I'm talking about arrays (`Array`) and dictionaries (`Dictionary`), both of which you've seen previously.

An **array** stores a list of objects. The objects it contains are ordered sequentially and you retrieve them by index.

```
// An array of ChecklistItem objects:
var items: Array<ChecklistItem>

// Or, using shorthand notation:
var items: [ChecklistItem]

// Making an instance of the array:
items = [ChecklistItem]()

// Accessing an object from the array:
let item = items[3]
```

You can write an array as `Array<Type>` or `[Type]`. The first one is the official version, the second is "syntactic sugar" that is a bit easier to read. Unlike other languages, in Swift you don't write `Type[]`. The type name goes inside the brackets.

A **dictionary** stores key-value pairs. An object, usually a string, is the key that retrieves another object.

```
// A dictionary that stores (String, Int) pairs, for example a
// list of people's names and their ages:
var ages: Dictionary<String, Int>

// Or, using shorthand notation:
var ages: [String: Int]

// Making an instance of the dictionary:
ages = [String: Int]()

// Accessing an object from the dictionary:
var age = dict["Jony Ive"]
```

The notation for retrieving an object from a dictionary looks very similar to reading from an array — both use the `[ ]` brackets. For indexing an array, you always use a positive integer, but for a dictionary you typically use a string.

There are other sorts of collections as well, but array and dictionary are the most common ones.

Generics

`Array` and `Dictionary` are known as **generics**, meaning that they are independent of the type of thing you want to store inside these collections.

You can have an `Array` of `Int` objects, but also an `Array` of `String` objects — or an `Array` of any kind of object, really – even an array of other arrays.

That's why you have to specify the type of object to store inside the array, before you can use it. In other words, you cannot write this:

```
var items: Array  // error: should be Array<TypeName>
var items: []     // error: should be [TypeName]
```

There should always be the name of a type inside the `[ ]` brackets or following the word `Array` in `< >` brackets. If you're coming from Objective-C, be aware that the `< >` mean something completely different there.

For `Dictionary`, you need to supply two type names: one for the type of the keys and one for the type of the values.

Swift requires that all variables and constants have a value. You can either specify a value when you declare the variable or constant, or by assigning a value inside an `init` method.

Optionals

Sometimes it's useful to have a variable that can have no value, in which case you need to declare it as an **optional**:

```
var checklistToEdit: Checklist?
```

You cannot use this variable immediately; you must always first test whether it has a value or not. This is called **unwrapping** the optional:

```
if let checklist = checklistToEdit {
  // "checklist" now contains the real object
```

```
} else {
  // the optional was nil
}
```

The `age` variable from the dictionary example in the previous section is actually an optional, because there is no guarantee that the dictionary contains the key "Jony Ive". Therefore, the type of `age` is `Int?` instead of just `Int`.

Before you can use a value from a dictionary, you need to unwrap it first using `if let`:

```
if let age = dict["Jony Ive"] {
  // use the value of age
}
```

If you are 100% sure that the dictionary contains a given key, you can also use **force unwrapping** to read the corresponding value:

```
var age = dict["Jony Ive"]!
```

With the `!` you tell Swift, "This value will not be `nil`. I'll stake my reputation on it!" Of course, if you're wrong and the value *is* `nil`, the app will crash and your reputation is down the drain. Be careful with force unwrapping!

A slightly safer alternative to force unwrapping is **optional chaining**. For example, the following will crash the app if the `navigationController` property is `nil`:

```
navigationController!.delegate = self
```

But this won't:

```
navigationController?.delegate = self
```

Anything after the `?` will simply be ignored if `navigationController` does not have a value. It's equivalent to writing:

```
if navigationController != nil {
  navigationController!.delegate = self
}
```

It is also possible to declare an optional using an exclamation point instead of a question mark. This makes it an **implicitly unwrapped** optional:

```
var dataModel: DataModel!
```

Such a value is potentially unsafe because you can use it as a regular variable without having to unwrap it first. If this variable has the value `nil` when you don't expect it — and don't they always — your app will crash.

Optionals exist to guard against such crashes, and using `!` undermines the safety of using optionals.

However, sometimes using implicitly unwrapped optionals is more convenient than using pure optionals. Use them when you cannot give the variable an initial value at the time of declaration, nor in `init()`.

But once you've given the variable a value, you really ought not to make it `nil` again. If the value can become `nil` again, it's better to use a true optional with a question mark.

Methods and functions

You've learned that objects, the basic building blocks of all apps, have both data and functionality. Instance variables and constants provide the data, **methods** provide the functionality.

When you call a method, the app jumps to that section of the code and executes all the statements in the method one-by-one. When the end of the method is reached, the app jumps back to where it left off:

```
let result = performUselessCalculation(314)
print(result)

. . .

func performUselessCalculation(_ a: Int) -> Int {
  var b = Int(arc4random_uniform(100))
  var c = a / 2
  return (a + b) * c
}
```

Methods often return a value to the caller, usually the result of a computation or looking up something in a collection. The data type of the result value is written after the –> arrow. In the example above, it is `Int`. If there is no –> arrow, the method does not return a value – also known as returning `Void`.

Methods are **functions** that belong to an object, but there are also standalone functions such as `print()`.

Functions serve the same purpose as methods — they bundle functionality into small re-usable units — but live outside of any objects. Such functions are also called *free* functions or *global* functions.

These are examples of methods:

```
// Method with no parameters, no return a value.
override func viewDidLoad()

// Method with one parameter, slider. No return a value.
// The keyword @IBAction means that this method can be connected
// to a control in Interface Builder.
@IBAction func sliderMoved(_ slider: UISlider)

// Method with no parameters, returns an Int value.
func countUncheckedItems() -> Int

// Method with two parameters, cell and item, no return value.
// Note that the first parameter has an extra label, for,
// and the second parameter has an extra label, with.
func configureCheckmarkFor(
  for cell: UITableViewCell,
  with item: ChecklistItem)

// Method with two parameters, tableView and section.
// Returns an Int. The _ means the first parameter does not
// have an external label.
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int) -> Int

// Method with two parameters, tableView and indexPath.
// The question mark means it returns an optional IndexPath
// object (may also return nil).
override func tableView(
  _ tableView: UITableView,
  willSelectRowAt indexPath: IndexPath) -> IndexPath?
```

To call a method on an object, you write `object.method(parameters)`. For example:

```
// Calling a method on the lists object:
lists.append(checklist)

// Calling a method with more than one parameter:
tableView.insertRows(at: indexPaths, with: .fade)
```

You can think of calling a method as *sending a message* from one object to another: "Hey `lists`, I'm sending you the `append` message for this `checklist` object."

The object whose method you're calling is known as the *receiver* of the message.

It is very common to call a method from the same object. Here, `loadChecklists()` calls the `sortChecklists()` method. Both are members of the `DataModel` object.

```
class DataModel {
  func loadChecklists() {
    . . .
    sortChecklists()  // this method also lives in DataModel
  }

  func sortChecklists() {
    . . .
  }
}
```

Sometimes this is written as:

```
  func loadChecklists() {
    . . .
    self.sortChecklists()
  }
```

The `self` keyword makes it clear that the `DataModel` object itself is the receiver of this message.

> **Note:** In this book I leave out the `self` keyword for method calls, because it's not necessary to have it. Objective-C developers are very attached to `self`, so you'll probably see it used a lot in Swift too. It is a topic of heated debate in developer circles, but except for a few specific scenarios, the compiler doesn't really care whether you use `self` or not.

Inside a method you can also use `self` to get a reference to the object itself:

```
@IBAction func cancel() {
  delegate?.itemDetailViewControllerDidCancel(self)
}
```

Here `cancel()` sends a reference to the object (i.e. `self`) along to the delegate, so the delegate knows who sent this `itemDetailViewControllerDidCancel()` message.

Also note the use of **optional chaining** here. The `delegate` property is an optional, so it can be `nil`. Using the question mark before the method call will ensure nothing bad happens if `delegate` is not set.

Parameters

Often methods have one or more **parameters**, so they can work with multiple data items. A method that is limited to a fixed set of data is not very useful or reusable. Consider `sumValuesFromArray()`, a method that has no parameters:

```
class MyObject {
  var numbers = [Int]()

  func sumValuesFromArray() -> Int {
    var total = 0
    for number in numbers {
      total += number
    }
    return total
  }
}
```

Here, `numbers` is an instance variable. The `sumValuesFromArray()` method is tied closely to that instance variable, and is useless without it.

Suppose you add a second array to the app that you also want to apply this calculation to. One approach is to copy-paste the above method and change the name of the variable to that of the new array. That certainly works, but it's not smart programming!

It is better to give the method a parameter that allows you to pass in the array object that you wish to examine. Then, the method becomes independent from any instance variables:

```
func sumValues(from array: [Int]) -> Int {
  var total = 0
  for number in array {
    total += number
  }
  return total
}
```

Now you can call this method with any `[Int]` (or `Array<Int>`) object as its parameter.

This doesn't mean methods should never use instance variables, but if you can make a method more general by giving it a parameter, then that is usually a good idea.

Often methods use two names for their parameters, the **external label** and the **internal label**. For example:

```
func downloadImage(
  for searchResult: SearchResult,
  withTimeout timeout: TimeInterval,
  andPlaceOn button: UIButton
) {
  . . .
}
```

This method has three parameters: `searchResult`, `timeout`, and `button`. Those are the internal parameter names you'd use in the code inside the method.

The external labels become part of the method name. The full name for the method is `downloadImage(for:withTimeout:andPlaceOn:)` — method names in Swift are often quite long!

To call this method, you'd use the external labels:

```
downloadImage(for: result, withTimeout: 10, andPlaceOn:
imageButton)
```

Sometimes you'll see a method whose first parameter does not have an external label, but has an _ underscore instead:

```
override func tableView(_ tableView: UITableView,
numberOfRowsInSection section: Int) -> Int
```

This is often the case with delegate methods. It's a holdover from the Objective-C days, where the label for the first parameter was embedded in the first part of the method name. For example, in Objective-C the `downloadImage()` method example above would be named `downloadImageForSearchResult()`. These kinds of names should become less and less common in the future as Swift moves away from Objective-C.

Swift is pretty flexible with how it lets you name your methods, but it's smart to stick to the established conventions.

Inside a method you can do the following things:

- Create local variables and constants.
- Do basic arithmetic with mathematical operators such as `+`, `–`, `*`, `/`, and `%`.
- Put new values into variables – both local and instance variables.

- Call other methods.
- Make decisions with `if` or `switch` statements.
- Perform repetitions with the `for` or `while` statements.
- Return a value to the caller.

Let's look at the `if` and `for` statements in more detail.

Making decisions

The `if` statement looks like this:

```
if count == 0 {
  text = "No Items"
} else if count == 1 {
  text = "1 Item"
} else {
  text = "\(count) Items"
}
```

The expression after `if` is called the **condition**. If a condition is true then the statements in the following `{ }` block are executed. The `else` section gets performed if none of the conditions are true.

Comparison operators

You use **comparison operators** to perform comparisons between two values:

`==` equal to

`!=` not equal

`>` greater than

`>=` greater than or equal

`<` less than

`<=` less than or equal

```
let a = "Hello, world"
let b = "Hello," + " world"
print(a == b)             // prints true
```

When you use the == operator, the contents of the objects are compared. The above code only returns true if `a` and `b` have the same value:

This is different from Objective-C, where == is only `true` if the two objects are the exact same instance in memory. However, in Swift == compares the values of the objects, not whether they actually occupy the same spot in memory.

If you need to see if two variables are stored in the same memory location, then use ===, the identity operator.

Logical Operators

You can use **logical** operators to combine two expressions:

`a && b` is true if both `a` *and* `b` are true

`a || b` is true when either `a` *or* `b` is true, or both are true.

There is also the logical **not** operator, `!`, that turns `true` into `false`, and `false` into `true` — don't confuse this with the `!` that is used with optionals.

You can group expressions with `( )` parentheses:

```
if ((this && that) || (such && so)) && !other {
  // statements
}
```

This reads as:

```
if ((this and that) or (such and so)) and not other {
  // statements
}
```

Or if you want to see clearly in which order these operations are performed:

```
if (
      (this and that)
            or
      (such and so)
   )
   and
      (not other)
```

Of course, the more complicated you make it, the harder it is to remember exactly what you're doing!

switch statement

Swift has another very powerful construct in the language for making decisions, the `switch` statement:

```
switch condition {
  case value1:
    // statements

  case value2:
    // statements

  case value3:
    // statements

  default:
    // statements
}
```

It works the same way as an `if` statement with a bunch of `else ifs`. The following is equivalent:

```
if condition == value1 {
  // statements
} else if condition == value2 {
  // statements
} else if condition == value3 {
  // statements
} else {
  // statements
}
```

In such a situation, the `switch` statement would be more convenient to use. Swift's version of `switch` is much more powerful than the one in Objective-C. For example, you can match on ranges and other patterns:

```
switch difference {
  case 0:
    title = "Perfect!"
  case 1..<5:
    title = "You almost had it!"
  case 5..<10:
    title = "Pretty good!"
  default:
    title = "Not even close..."
}
```

The `..<` is the **half-open range** operator. It creates a range between the two numbers, but the top number is exclusive. So the half-open range `1..<5` is the same as the **closed range** `1...4`.

You'll see the `switch` statement in action a little later on.

return statement

Note that `if` and `return` can be used to return early from a method:

```
func divide(_ a: Int, by b: Int) -> Int {
  if b == 0 {
    print("You really shouldn't divide by zero")
    return 0
  }
  return a / b
}
```

This can even be done for methods that don't return a value:

```
func performDifficultCalculation(list: [Double]) {
  if list.count < 2 {
    print("Too few items in list")
    return
  }

  // perform the very difficult calculation here
}
```

In this case, `return` simply means: "We're done with the method". Any statements following the `return` are skipped and execution immediately returns to the caller.

You could also have written it like this:

```
func performDifficultCalculation(list: [Double]) {
  if list.count < 2 {
    print("Too few items in list")
  } else {
    // perform the very difficult calculation here
  }
}
```

Which approach you use is up to you. I prefer an early `return` when it avoids multiple nested blocks of code with multiple levels of indentation — the code just looks cleaner :]

For example, sometimes you see code like this:

```
func someMethod() {
  if condition1 {
    if condition2 {
      if condition3 {
        // statements
      } else {
        // statements
      }
    } else {
      // statements
    }
  } else {
    // statements
  }
}
```

This can become very hard to read. So, I like to restructure that kind of code as follows:

```
func someMethod() {
  if !condition1 {
    // statements
    return
  }

  if !condition2 {
    // statements
    return
  }

  if !condition3 {
    // statements
    return
  }

  // statements
}
```

Both do exactly the same thing, but I find the second one much easier to understand. Note that the conditions now use the `!` operator to invert their meaning.

Swift even has a dedicated feature, `guard`, to help write this kind of code. It looks like this:

```
func someMethod() {
  guard condition1 else {
    // statements
    return
```

```
  }
  guard condition2 else {
    // statements
    return
  }
  . . .
```

As you become more experienced, you'll start to develop your own taste for what looks good and what is readable code.

Loops

You've seen the `for...in` statement for looping through an array:

```
for item in items {
  if !item.checked {
    count += 1
  }
}
```

Which can also be written as:

```
for item in items where !item.checked {
  count += 1
}
```

This performs the statements inside the `for...in` block once for each object from the `items` array matching the condition provided by the `where` clause.

Note that the scope of the variable `item` is limited to just this `for` statement. You can't use it outside this statement, so its lifetime is even shorter than a local variable.

Looping through number ranges

Some languages have a `for` statement that looks like this:

```
for var i = 0; i < 5; ++i {
  print(i)
}
```

When you run this code, it should print:

```
0
1
2
3
4
```

Swift had that type of `for` statement up to Swift 2. However, as of Swift 3.0 this kind of `for` loop was removed from the language. Instead, you can loop over a range. This has the same output as above:

```
for i in 0...4 {   // or 0..<5
  print(i)
}
```

By the way, you can also write this loop as:

```
for i in stride(from: 0, to: 5, by: 1) {
  print(i)
}
```

The `stride()` function creates a special object that represents the range 0 to 5 in increments of 1. If you wanted to show just the even numbers, you could change the `by` parameter to 2. You can even use `stride()` to count backwards if you pass the `by` parameter a negative number.

while statement

The `for` statement is not the only way to perform loops. Another very useful looping construct is the `while` statement:

```
while something is true {
  // statements
}
```

The `while` loop keeps repeating the statements until its condition becomes false. You can also write it as follows:

```
repeat {
  // statements
} while something is true
```

In the latter case, the condition is evaluated after the statements have been executed at least once.

You can rewrite the loop that counts the `ChecklistItems` as follows using a `while` statement:

```
var count = 0
var i = 0
while i < items.count {
  let item = items[i]
  if !item.checked {
    count += 1
  }
  i += 1
}
```

Most of these looping constructs are really the same, they just look different. Each of them lets you repeat a bunch of statements until some ending condition is met.

Still, using a `while` is slightly more cumbersome than "`for item in items`", which is why you'll see `for...in` used most of the time.

There really is no significant difference between using a `for`, `while`, or `repeat...while` loop, except that one may be easier to read than the others, depending on what you're trying to do.

> **Note:** `items.count` and `count` in this example are two different things with the same name. The first `count` is a property on the `items` array that returns the number of elements in that array; the second `count` is a local variable that contains the number of unchecked to-do items counted so far.

Just like you can prematurely exit from a method using the `return` statement, you can exit a loop at any time using the `break` statement:

```
var found = false
for item in array {
  if item == searchText {
    found = true
    break
  }
}
```

This example loops through the array until it finds an `item` that is equal to the value of `searchText` (presumably both are strings). Then it sets the variable `found` to `true` and jumps out of the loop using `break`. You've found what you were looking for, so it makes no sense to look at the other objects in that array — for all you know there could be hundreds of items.

There is also a `continue` statement that is somewhat the opposite of `break`. It doesn't exit the loop but immediately skips to the next iteration. You use `continue` to say, "I'm done with the current item, let's look at the next one."

Loops can often be replaced by *functional programming* constructs such as `map`, `filter`, or `reduce`. These are known as *higher order functions* and they operate on a collection, performing some code for each element, and return a new collection (or single value, in the case of `reduce`) with the results.

For example, using `filter` on an array will return items that satisfy a certain condition. To get a list of all the unchecked `ChecklistItem` objects, you'd write:

```
var uncheckedItems = items.filter { item in !item.checked }
```

That's a lot simpler than writing a loop. Functional programming is an advanced topic so we won't spend too much time on it here.

Objects

Objects are what it's all about. They combine data with functionality into coherent, reusable units — that is, if you write them properly! The data is made up of the object's instance variables and constants. We often refer to these as the object's **properties**. The functionality is provided by the object's methods.

In your Swift programs you will use existing objects, such as `String`, `Array`, `Date`, `UITableView`, and you'll also make your own.

To define a new object, you need a bit of code that contains a `class` section:

```
class MyObject {
  var text: String
  var count = 0
  let maximum = 100

  init() {
    text = "Hello world"
  }

  func doSomething() {
    // statements
  }
}
```

Inside the brackets for the class, you add properties — the instance variables and constants — and methods.

Properties

There are two types of properties:

- **Stored properties** are the usual instance variables and constants.
- **Computed properties** don't store a value, but perform logic when you read from, or write to, their values.

This is an example of a computed property:

```
var indexOfSelectedChecklist: Int {
  get {
    return UserDefaults.standard.integer(
      forKey: "ChecklistIndex")
  }
  set {
    UserDefaults.standard.set(
      newValue,
      forKey: "ChecklistIndex")
  }
}
```

The `indexOfSelectedChecklist` property does not store a value like a normal variable would. Instead, every time someone uses this property, it performs the code from the `get` or `set` block.

The alternative would be to write separate `setIndexOfSelectedChecklist()` and `getIndexOfSelectedChecklist()` methods, but that doesn't read as nicely.

If a property name is preceded by the keyword `@IBOutlet`, that means that the property can refer to a user interface element in Interface Builder, such as a label or button. Such properties are usually declared `weak` and optional.

Similarly, the keyword `@IBAction` is used for methods that will be performed when the user interacts with the app UI.

Methods

There are three kinds of methods:

- Instance methods
- Class methods
- Init methods

As mentioned previously, a method is a function that belongs to an object. To call such a method you first need to have an instance of the object:

```
let myInstance = MyObject()   // create the object instance
. . .
myInstance.doSomething()      // call the method
```

You can also have **class methods**, which can be used without an object instance. In fact, they are often used as "factory" methods, to create new object instances:

```
class MyObject {
  . . .

  class func makeObject(text: String) -> MyObject {
    let m = MyObject()
    m.text = text
    return m
  }
}

let myInstance = MyObject.makeObject(text: "Hello world")
```

Init methods, or **initializers**, are used during the creation of new object instances. Instead of the above factory method, you might as well use a custom `init` method:

```
class MyObject {
  . . .

  init(text: String) {
    self.text = text
  }
}

let myInstance = MyObject(text: "Hello world")
```

The main purpose of an `init` method is to set up (or, initialize) the object's properties. Any instance variables or constants that do not have a value yet must be given one in the `init` method.

Swift does not allow variables or constants to have no value (except for optionals), and `init` is your last chance to make this happen.

Objects can have more than one `init` method; which one you use depends on the circumstances.

A `UITableViewController`, for example, can be initialized either with `init?(coder:)` when automatically loaded from a storyboard, with `init(nibName:bundle:)` when manually loaded from a nib file, or with `init(style:)` when constructed without a storyboard or nib — sometimes you use one, sometimes the other.

You can also provide a `deinit` method that gets called just before the object is destroyed.

By the way, `class` isn't the only way to define an object in Swift. It also supports other types of objects such as `structs` and `enums`. You'll learn more about these later, so I won't give away the whole plot here – no spoilers!

Protocols

Besides objects, you can also define **protocols**. A protocol is simply a list of method names and possibly, properties:

```
protocol MyProtocol {
  func someMethod(value: Int)
  func anotherMethod() -> String
}
```

A protocol is like a job ad. It lists all the things that a candidate for a certain position in your company should be able to do.

But the ad itself doesn't do the job — it's just words printed in the careers section of the newspaper. So, you need to hire an actual employee who can get the job done. That would be an object.

Objects need to indicate that they conform to a protocol:

```
class MyObject: MyProtocol {
  . . .
}
```

This object now has to provide an implementation for the methods listed in the protocol - if not, it's fired!

From then on, you can refer to this object as a `MyObject` (because that is its class name) but also as a `MyProtocol` object:

```
var m1: MyObject = MyObject()
var m2: MyProtocol = MyObject()
```

To any part of the code using the `m2` variable, it doesn't matter that the object is really a `MyObject` under the hood. The type of `m2` is `MyProtocol`, not `MyObject`.

All your code sees is that `m2` is *some* object conforming to `MyProtocol`, but it's not important what sort of object that is.

In other words, you don't really care that your employee may also have another job on the side, as long as it doesn't interfere with the duties you've hired him, or her, for.

Protocols are often used to define **delegates**, but they come in handy for other uses as well, as you'll find out later on.


That ends the Swift language recap. It's time to write some code!

Chapter 22: Get Location Data

By Fahim Farook

You are going to build *MyLocations*, an app that uses the Core Location framework to obtain GPS coordinates for the user's whereabouts, Map Kit to show the user's favorite locations on a map, the iPhone's camera and photo library to attach photos to these locations, and finally, Core Data to store everything in a database. Phew, that's a lot of stuff!

The finished app looks like this:



The MyLocations app

MyLocations lets you keep a list of spots that you find interesting. Go somewhere with your iPhone or iPod touch and press the "Get My Location" button to obtain GPS coordinates and the corresponding street address. Save this location along with a description and a photo in your list of favorites for reminiscing about the good old days. Think of this app as a "location album" instead of a photo album.


To make the workload easier to handle, you'll split the project up into smaller chunks:

1. You will first figure out how to obtain GPS coordinates from the Core Location framework and how to convert these coordinates into an address, a process known as **reverse geocoding**. Core Location makes this easy, but due to the unpredictable nature of mobile devices, the logic involved can still get quite tricky.
2. Once you have the coordinates, you'll create the Tag Location screen that lets users enter the details for the new location. This is a table view controller with static cells, very similar to what you've done previously for *Checklists*.
3. You'll store the location data into a Core Data store. For the last app you saved app data into a .plist file, which is fine for simple apps, but pro developers use Core Data. It's not as scary as it sounds!
4. Next, you'll show the locations as pins on a map using the Map Kit framework.
5. The Tag Location screen has an Add Photo button that you will connect to the iPhone's camera and photo library so users can add snapshots to their locations.
6. Finally, you'll make the app look good using custom graphics. You will also add sound effects and some animations to the mix.

Of course, you are not going to do all of that at once :] In this chapter, you will do the following:

- **Get GPS Coordinates:** Create a tab bar-based app and set up the UI for the first tab.
- **CoreLocation:** Use the CoreLocation framework to get the user's current location.
- **Display coordinates:** Display location information on screen.

When you're done with this chapter, the app will look like this:




The first screen of the app

Get GPS coordinates

First, you'll create the *MyLocations* project in Xcode and then use the Core Location framework to find the latitude and longitude of the user's location.

Create project

➤ Fire up Xcode and make a new project. Choose the **App** template.



Choosing the App template

➤ Fill in the options as follows:

- Product Name: **MyLocations**
- Team: Select your team (if you have one), or leave at **None**.
- Organization Identifier: Your own identifier in reverse domain notation
- Interface: **Storyboard**
- Language: **Swift**
- Use Core Data: **checked** (you'll learn what this option does in Chapter 27)
- Host in CloudKit: **unchecked**
- Include Tests: **unchecked**

➤ Save the project.

If you run the app, you will get a blank white screen — just as you did with your previous two apps.

The Tabbed Interface


We are going to have a tabbed interface for *MyLocations*. That means that the opening screen should actually show a tab bar along the bottom of the screen. How do we go from the blank white screen to a tabbed interface?

➤ Open **Main.storyboard** and select the lone view controller on the storyboard.

➤ Use the Interface Builder toolbar along the bottom of the screen to switch to the **iPhone SE (2nd generation)** device as you've done before.

➤ Now select the lone view controller on the canvas and select **Editor ▸ Embed In ▸ Tab Bar Controller** from the Xcode menu.

Your storyboard should now look like this:




The storyboard with Tab Bar Controller

The view controller on the left, as the name indicates, is the Tab Bar Controller. It handles all the tasks related to displaying a tabbed interface on the screen. A Tab Bar Controller can have one or more child view controllers which display the contents for each tab.

Here, we have a single view controller and so, a single tab.

➤ **Run** the app. It should now look like this:



Single tab application


The app now has a tab bar along the bottom with a single tab named Item.

If you check the code files, you'll notice that no new code files have been added — the tab handling is done so far only using the storyboard.

The first tab

In this chapter, you'll be working with just the one tab. In future chapters you'll add two more tabs.

If you select the view controller on the right and check the **Identity Inspector** for the **Class** value, you'll notice that it says **ViewController**.




The tab class

This is the same basic ViewController which came with the App template. Let's give it a better name.

Remember the refactoring trick you learnt previously? That's what you'll use here since that renames both the file and any references to it anywhere in the project.➤ Open **ViewController.swift**, hover your mouse cursor over the word `ViewController` in the `class` line, right-click (or Control-click) and select **Refactor > Rename...** from the context menu.

➤ Change the name to **CurrentLocationViewController**. This changes the file name, the class name, and the reference to the class in the storyboard, all at once! Nifty, eh?

➤ Go to the **Project Settings** screen's **General** tab and select the Portrait setting under **Deployment Info - Device Orientation**. Now the app is portrait-only. You can enable **Upside Down** at the same time if you like, since this would enable both portrait modes on iPad.



The app only works in portrait


➤ Run the app again just to make sure everything still works.

Whenever I change how things are hooked up in the storyboard, I find it useful to run the app and verify that the change was successful — it's way too easy to forget a step and you want to catch such mistakes right away.

And if you are wondering where you changed things in the storyboard, remember how you renamed `ViewController`? That change modified the storyboard too :]

As you saw in *Checklists*, a view controller that sits inside a navigation controller has a Navigation Item object that allows it to configure the navigation bar. Tab bars work the same way. Each view controller that represents a tab has a Tab Bar Item object.

➤ Open the storyboard, select the **Tab Bar Item** (which is named **Item**) object from **Item Scene** (this is the Current Location View Controller) and go to the **Attributes inspector**. Change the **Title** to **Tag**.



Changing the title of the Tab Bar Item

Later on, you'll also set a new image for the Tab Bar Item as well; it currently shows a default image in the story board but the tab will show no image when the app is run.

First tab UI


You will now design the screen for this tab. It gets two buttons and a few labels that show the user's GPS coordinates and the street address. To save you some time, you'll add all the outlets in one go.

➤ Add the following to the class in **CurrentLocationViewController.swift**:

```
@IBOutlet weak var messageLabel: UILabel!
@IBOutlet weak var latitudeLabel: UILabel!
@IBOutlet weak var longitudeLabel: UILabel!
@IBOutlet weak var addressLabel: UILabel!
@IBOutlet weak var tagButton: UIButton!
@IBOutlet weak var getButton: UIButton!

// MARK: - Actions
@IBAction func getLocation() {
  // do nothing yet
}
```

Design the UI to look something like this — always make use of the positioning guides that Interface Builder provides to place controls since this gives you nice, even spacing:



The design of the Current Location screen

➤ The **(Message Label)** at the top should span the whole width of the screen. You'll use this label for status messages while the app is obtaining the GPS coordinates. Set the **Alignment** attribute to centered and connect the label to the `messageLabel` outlet.

➤ Once you've positioned the **(Message Label)**, set its Auto Layout constraints for **left**, **top**, and **right** so that it aligns with the Safe Area. In case you're wondering, you don't have to explicitly select the Safe Area — if you set up the constraints as below, most of the time the constraints should be set correctly for you.



The (Message Label) constraints

➤ Make the **(Latitude goes here)** and **(Longitude goes here)** labels right-aligned and connect them to the `latitudeLabel` and `longitudeLabel` outlets respectively.

➤ Set up **left**, **top**, **right**, and **bottom** Auto Layout constraints for the **Latitude:** label. You can use your judgement with regards to the top spacing — I used 24 points — or you can use the suggested spacing of 8 points. It's totally up to you, but I felt that there should be a bit more spacing between the message and the latitude, longitude grouping.

➤ Then, set up **left**, **right**, and **bottom** constraints for the **Longitude:** label — you don't need a top constraint since the bottom constraint of the **Latitude:** label acts as the top constraint for this one.

Again, you can use your judgement with regards to the bottom spacing since that determines how far away the **(Address goes here)** label is from the **Longitude:** label. I felt that it should have the same amount of spacing as there was at the top to the **(Message Label)** and so, went with 24 points.

➤ Add **top**, **right**, and **bottom** constraints for **(Latitude goes here)** and **right** and **bottom** constraints for **(Longitude goes here)**.

Do note that as you add constraints, the positions of some of the labels might shift. So you might need to adjust positioning again — for example, position the **(Longitude goes here)** label so that it stretches to the right edge of the screen — to set things up as they originally were.

➤ You will get some Auto Layout constraint issues at this point. This is due to none of the labels in the latitude and longitude grouping having specific widths or heights. It's hard for Xcode to determine what the actual sizes should be.

We know that the longer of the two left labels is **Longitude:**. So let's try setting both labels on the left to be the same size as the **Longitude:** label — Control-drag from the **Longitude:** label to the **Latitude:** label and select **Equal Widths** from the popup.

Hmm … that made things worse! Why?

Because you had an existing trailing space from the **Latitude:** label to the **(Latitude goes here)** label and that spacing is now incorrect. Select the **(Latitude goes here)** label, switch to the **Size inspector**, and remove the leading constraint to the **Latitude:** label.

➤ The **(Latitude goes here)** label will resize to fit its contents again. Add a leading constraint between it and the **Latitude:** label, but make the spacing greater than or equal to 8 points to match what's there for the longitude label set.

Why greater than or equal to when all the other constraints are set to equal to? Because if you set it to equal to, you'll get another set of red constraints :]

➤ The **(Address goes here)** label spans the whole width of the screen and should have an Auto Layout constraints where **height** is **50** so it can fit two lines of text. Set its **Lines** attribute to **0** — that means it can display a variable number of lines. Connect this label to the `addressLabel` outlet.

➤ Set **left**, **right**, and **bottom** constraints on the **(Address goes here)** label. Make the bottom constraint be 24 points to match the top spacing previously set, or, whatever value you set/like. It's your choice.

➤ The **Tag Location** button doesn't do anything yet, but should be connected to the `tagButton` outlet.

➤ Set **left** and **right** constraints of 16 points on the **Tag Location** button so that it stretches from side to side.

➤ Connect the **Get My Location** button to the `getButton` outlet, and its Touch Up Inside event to the `getLocation` action.

➤ Set **left**, **right**, and **bottom** constraints on the **Get My Location** button so that it stretches from side to side and is at least 16 points from the bottom of the screen — you can use your judgement as to the actual positioning you think is good.

➤ Run the app to see the new design in action.

If you think the positioning of some element is off, feel free to adjust the Auto Layout constraints till the layout looks right. There is no right or wrong here, it's all a matter of how it looks to you :]

So far, nothing special. With the exception of the tab bar, this is stuff you've seen and done before. Time to add something new: let's play with Core Location!

Core Location

Most iOS devices have a way to let you know exactly where you are on the globe, either through communication with GPS satellites, or Wi-Fi and cell tower triangulation. The Core Location framework puts that power in your own hands.

An app can ask Core Location for the user's current latitude and longitude. For devices with a compass, it can also give the heading — you won't be using that for this app. Core Location can also provide continuous location updates while you're on the move.

Get your current location

Getting a location from Core Location is pretty easy, but there are some pitfalls that you need to avoid. Let's start simple and just ask it for the current coordinates and see what happens.

➤ At the top of **CurrentLocationViewController.swift**, add an import statement:

```
import CoreLocation
```

That is all you have to do to add the Core Location framework to your project.

Core Location, like so many other parts of the iOS SDK, works via a delegate, so you should make the view controller conform to the `CLLocationManagerDelegate` protocol.

➤ Add `CLLocationManagerDelegate` to the view controller's `class` line:

```
class CurrentLocationViewController: UIViewController,
CLLocationManagerDelegate {
```

➤ Also add a new property:

```
let locationManager = CLLocationManager()
```

The `CLLocationManager` is the object that will give you GPS coordinates. You're putting the reference to this object in a constant — using `let`, not a variable (`var`). Once you have created the location manager object, the value of `locationManager` will never have to change.

The new `CLLocationManager` object doesn't give you GPS coordinates right away. To begin receiving coordinates, you have to call its `startUpdatingLocation()` method first.

Unless you're doing turn-by-turn navigation, you don't want your app to continuously receive GPS coordinates. That requires a lot of power and will quickly drain the battery. For this app, you only turn on the location manager when you want a location fix and turn it off again when you've received a usable location.

You'll implement that logic in a minute — it's more complex than you'd think. For now, you're only interested in receiving something from Core Location, just so you know that it works.

➤ Change the `getLocation()` action method to the following:

```
@IBAction func getLocation() {
  locationManager.delegate = self
  locationManager.desiredAccuracy =
kCLLocationAccuracyNearestTenMeters
  locationManager.startUpdatingLocation()
}
```

This method is hooked up to the **Get My Location** button. It tells the location manager that the view controller is its delegate and that you want to receive locations with an accuracy of up to ten meters. Then you start the location manager. From that moment on, the `CLLocationManager` object will send location updates to its delegate, i.e. the view controller.

➤ Speaking of the delegate, add the following code too:

```
// MARK: - CLLocationManagerDelegate
func locationManager(
  _ manager: CLLocationManager,
  didFailWithError error: Error
) {
  print("didFailWithError \(error.localizedDescription)")
}

func locationManager(
  _ manager: CLLocationManager,
  didUpdateLocations locations: [CLLocation]
) {
  let newLocation = locations.last!
  print("didUpdateLocations \(newLocation)")
}
```

These are the delegate methods for the location manager. For the time being, you'll simply output a `print()` message to the Console. Also, do note the `error.localizedDescription` bit which, instead of simply printing out the contents of the `error` variable, outputs a human understandable version of the error (if possible) based on the device's current locale, or language setting.

➤ Run the app in the Simulator and press the **Get My Location** button.

Hmm... nothing seems to happen. That's because you need to ask for permission before accessing location information.

Ask for permission

➤ Add the following lines to the top of `getLocation()`:


```
let authStatus = locationManager.authorizationStatus
if authStatus == .notDetermined {
  locationManager.requestWhenInUseAuthorization()
  return
}
```

This checks the current authorization status. If it is `.notDetermined` — meaning that this app has not asked for permission yet — then the app will request "When In Use" authorization. That allows the app to get location updates while it is open and the user is interacting with it.

There is also "Always" authorization, which permits the app to check the user's location even when it is not active. That's useful for a navigation app, for example. For most apps, including *MyLocations*, when-in-use is what you want to ask for.

Just adding these lines of code is not enough. You also have to add a special key to the app's Info tab.

➤ Go to the **Project Settings** screen's **Info** tab. Right-click somewhere inside list of items and choose **Add Row** from the menu.



Adding a new row to Info.plist

➤ For the key, type **NSLocationWhenInUseUsageDescription**, or, choose **Privacy - Location When In Use Usage Description** from the list. Note that there's also a "Privacy - Location Always and When In Use Usage Description" key – do not select that one since that's for Always-on location access.


➤ Type the following text in the Value column:

This app lets you keep track of interesting places. It needs access to the GPS coordinates for your location.

This description tells the user what the app wants to use the location data for. If this description is not there in your project settings, your app will either not work correctly (or, crash) when you check the location authorisation status.

➤ Run the app again and press the **Get My Location** button.

Core Location will pop up the following alert, asking the user for permission:



Users have to allow your app to use their location

If a user denies the request by selecting Don't Allow, then Core Location will never give your app location coordinates.

➤ Press the **Don't Allow** button. Now press Get My Location again.

Xcode's debug area should now show the following message, or something similar:

```
didFailWithError The operation couldn't be completed.
(kCLErrorDomain error 1.)
```

This comes from the `locationManager(_:didFailWithError:)` delegate method. It's telling you that the location manager wasn't able to obtain a location.

The reason why is described by an `Error` object, which is the standard object that the iOS SDK uses to convey error information. You'll see it in many other places in the SDK since there are plenty of places where things can go wrong!

This `Error` object has a *domain* and a *code*. The domain in this case is `kCLErrorDomain` meaning the error came from Core Location (CL). The code is 1, also identified by the symbolic name `CLError.denied`, which means the user did not allow the app to obtain location information.

> **Note:** The `k` prefix is often used by the iOS frameworks to signify that a name represents a constant value — I guess whoever came up with this prefix thought it was spelled "konstant". This is an old convention and you won't see it used much in new frameworks or in Swift code, but it still pops up here and there.

➤ Stop the app from within Xcode and run it again.

When you press the Get My Location button, the app does not ask for permission anymore but immediately gives you the same error message.

Let's make this a bit more user-friendly, because a normal user would never see that `print()` output.

Handle permission errors

➤ Add the following method to **CurrentLocationViewController.swift**:

```
// MARK: - Helper Methods
func showLocationServicesDeniedAlert() {
  let alert = UIAlertController(
    title: "Location Services Disabled",
    message: "Please enable location services for this app in
Settings.",
    preferredStyle: .alert)

  let okAction = UIAlertAction(
    title: "OK",
    style: .default,
    handler: nil)
  alert.addAction(okAction)

  present(alert, animated: true, completion: nil)
}
```

This pops up an alert with a helpful hint. This app is pretty useless without access to the user's location, so it should encourage the user to enable location services.


Do note that it's not necessarily the user of the app who has denied access to the location data; a systems administrator or parent could also have restricted location access.

➤ To show this alert, add the following lines to `getLocation()`, just before you set the `locationManager`'s delegate:

```
if authStatus == .denied || authStatus == .restricted {
  showLocationServicesDeniedAlert()
  return
}
```

This shows the alert if the authorization status is denied or restricted. Notice the use of `||` here, the "logical or" operator. `showLocationServicesDeniedAlert()` will be called if either of those two conditions is true.


➤ Try it out. Run the app and tap **Get My Location**. You should now get the Location Services Disabled alert:



The alert that pops up when location services are not available

Fortunately, users can change their minds and enable location services for your app again. This is done from the iPhone's Settings app.

➤ Open the **Settings** app in the Simulator and go to **Privacy ▸ Location Services**.



Location Services in the Settings app

➤ Click **MyLocations** and then **While Using the App** to enable location services again. If you select **Ask Next Time** instead, then you'll be prompted for permission again the next time you try to access location services instead of being explicitly granted location access.

Switch back to the app (or run it again from Xcode) and press the **Get My Location** button.

When I tried this, the following message appeared in Xcode's debug area:


```
didFailWithError The operation couldn't be completed.
(kCLErrorDomain error 0.)
```

Again there is an error message but with a different code, 0 — this is "location unknown" which means Core Location was unable to obtain a location for some reason.

That is not so strange, as you're running this from the Simulator, which obviously does not have a real GPS. Your Mac may have a way to obtain location information through Wi-Fi but this is not built into the Simulator. Fortunately, there is a way to fake it!

Fake location on the simulator

➤ With the app running and the simulator selected, from the Simulator's menu bar at the top of the screen, choose **Features ▸ Location ▸ Apple**.



The Simulator's Location menu

You should now see messages like these in the debug area:

```
didUpdateLocations <+37.33259552,-122.03031802> +/- 500.00m
(speed -1.00 mps / course -1.00) @ 8/11/20, 1:16:39 PM Eastern
Daylight Time
didUpdateLocations <+37.33240905,-122.03051211> +/- 65.00m
(speed -1.00 mps / course -1.00) @ 8/11/20, 1:16:41 PM Eastern
Daylight Time
didUpdateLocations <+37.33233141,-122.03121860> +/- 50.00m
(speed -1.00 mps / course -1.00) @ 8/11/20, 1:16:48 PM Eastern
Daylight Time
```

It keeps going on and on, giving the app a new location every second or so. After a short while, the latitude and longitude readings will not change anymore. These particular coordinates point at the Apple headquarters in Cupertino, California.

Look carefully at the coordinates the app is receiving. The first one says "+/- 500.00m", the second one "+/- 65.00m", a little further on "+/- 50.00m" etc. This number keeps getting smaller and smaller until it stops at about "+/- 5.00m".

This is the accuracy of the measurement, expressed in meters. What you see is the Simulator imitating what happens when you ask for a location on a real device.

If you go out with an iPhone and try to obtain location information, the iPhone uses three different ways to find your coordinates. It has onboard cellular, Wi-Fi, and GPS radios that each give it location information at different levels of detail:

- Cell tower triangulation will always work if there is a signal but it's not very precise.
- Wi-Fi positioning works better, but that is only available if there are known Wi-Fi routers nearby. This system uses a big database that contains the locations of wireless networking equipment.
- The very best results come from the GPS (**G**lobal **P**ositioning **S**ystem), but that needs satellite communication and is therefore the slowest of the three. It also won't work very well indoors.

So, your device has several ways of obtaining location data, ranging from fast but inaccurate (cell towers, Wi-Fi) to accurate but slow (GPS). And none of these are guaranteed to work. Some devices don't even have a GPS or cellular radio at all and have to rely on just Wi-Fi. Suddenly obtaining a location seems a lot trickier.

Fortunately for us, Core Location does all of the hard work of turning the location readings from its various sources into a useful number. Instead of making you wait for the definitive results from the GPS — which may never come — Core Location sends location data to the app as soon as it gets it, and then follows up with more and more accurate readings.

> **Exercise:** If you have an iPhone, iPod touch or iPad nearby, try the app on your device and see what kind of readings it gives you. If you have more than one device, try the app on all of them and note the differences.

★ ★ ★

Asynchronous operations

Obtaining a location is an example of an **asynchronous** process.

Sometimes apps need to do things that may take a while. After you start an operation, you have to wait until it gives you the results. If you're unlucky, those results may never come at all!

In the case of Core Location, it can take a second or two before you get the first location reading and then quite a few seconds more to get coordinates that are accurate enough for your app to use.

Asynchronous means that after you start such an operation, your app will continue on its merry way. The user interface is still responsive, new events are being sent and handled, and the user can still tap on things.

The asynchronous process is said to be operating "in the background". As soon as the operation is done, the app is notified through a delegate so that it can process the results.

The opposite is **synchronous** – without the a. If you start an operation that is synchronous, the app won't continue until that operation is done. In effect, the app freezes up.

In the case of `CLLocationManager` that would cause a big problem: your app would be totally unresponsive for the couple of seconds that it takes to get a location fix. Those kinds of "blocking" operations are often a bad experience for the user.

For example, *MyLocations* has a tab bar at the bottom. If the app blocked while getting the location, switching to another tab during that time would have no effect. The user expects to always be able to change tabs, but now it appears that the app is frozen, or worse, has crashed.

The designers of iOS decided that such behavior is unacceptable and therefore operations that take longer than a fraction of a second should be performed in an asynchronous manner.

In the next app, you'll see more asynchronous processing in action when we talk about network connections and downloading stuff from the Internet.

By the way, iOS has something called a *watchdog timer*. If your app is unresponsive for too long, then under certain circumstances, the watchdog timer will kill your app without mercy — so don't do anything that freezes your UI!

The take-away is this: any operation that takes long enough to be noticeable by the user should be done asynchronously, in the background.



Display coordinates

The `locationManager(_:didUpdateLocations:)` delegate method gives you an array of `CLLocation` objects that contain the current latitude and longitude coordinates of the user.

You'll take the last `CLLocation` object from the array — because that is the most recent update — and display its coordinates in the labels that you added to the screen earlier.

➤ Add a new instance variable to **CurrentLocationViewController.swift**:

```
var location: CLLocation?
```

You will store the user's current location in this variable.

This needs to be an optional, because it is possible to *not* have a location, for example, when you're stranded out in the Sahara desert somewhere and there are no cell towers or GPS satellites in sight – it happens.

But even when everything works as it should, the value of `location` will still be `nil` until Core Location reports back with a valid `CLLocation` object, which as you've seen, may take a few seconds. So an optional it is.

➤ Change `locationManager(_:didUpdateLocations:)` to:

```
func locationManager(
  _ manager: CLLocationManager,
  didUpdateLocations locations: [CLLocation]
) {
  . . .
  location = newLocation    // Add this
  updateLabels()            // Add this
}
```

You store the `CLLocation` object that you get from the location manager into the instance variable and call a new `updateLabels()` method.

Keep the `print()` you added earlier in there because it's handy for debugging.

➤ Add the `updateLabels()` method:

```
func updateLabels() {
  if let location = location {
    latitudeLabel.text = String(
      format: "%.8f",
      location.coordinate.latitude)
    longitudeLabel.text = String(
      format: "%.8f",
      location.coordinate.longitude)
    tagButton.isHidden = false
    messageLabel.text = ""
  } else {
    latitudeLabel.text = ""
    longitudeLabel.text = ""
    addressLabel.text = ""
    tagButton.isHidden = true
    messageLabel.text = "Tap 'Get My Location' to Start"
  }
}
```

Because the `location` instance variable is an optional, you use the `if let` syntax to unwrap it.

Note the *shadowing* of the original `location` variable by the unwrapped variable. Inside the `if` statement, `location` now refers to an actual `CLLocation` object that is not `nil`.

If there is a valid location object, you convert the latitude and longitude, which are values with type `Double`, into strings and put them into the labels.

You've seen *string interpolation* before to put values into strings, so why doesn't this code simply do the following?

```
latitudeLabel.text = "\(location.coordinate.latitude)"
```

That would certainly work, but it doesn't give you any control over how the latitude value appears. For this app, you want both latitude and longitude to be shown with 8 digits behind the decimal point.

For that sort of control, you need to use a *format string*.

Format strings

Like string interpolation, a format string uses placeholders that will be replaced by the actual value during runtime. These placeholders, or *format specifiers*, can be quite intricate.

To create the text for the latitude label you do this:

```
String(format: "%.8f", location.coordinate.latitude)
```


This creates a new `String` object using the format string `"%.8f"`, and the value to replace in that string, `location.coordinate.latitude`.

Placeholders always start with a percent (`%`) sign. Examples of common placeholders are: `%d` for integer values, `%f` for floating-point, and `%@` for objects.

Format strings are very common in Objective-C code, but less so in Swift because string interpolation is much simpler (but less powerful).

The `%.8f` format specifier does the same thing as `%f`: it takes a decimal number and puts it in the string. The `.8` means that there should always be 8 digits behind the decimal point.

➤ Run the app, select a location to simulate from the Simulator's **Features** menu and tap the **Get My Location** button. You'll now see the latitude and longitude appear on the screen.




The app shows the GPS coordinates

When the app starts up, it has no location object (`location` is still `nil`) and therefore ought to show the "Tap 'Get My Location' to Start" message at the top as a hint to the user. But it doesn't do that yet since the app doesn't call `updateLabels()` until it receives the first coordinates.

➤ To fix this, also call `updateLabels()` from `viewDidLoad()`:

```
override func viewDidLoad() {
  super.viewDidLoad()
  updateLabels()
}
```

➤ Run the app. Initially, the screen should now say, Tap 'Get My Location' to Start, and the latitude and longitude labels are empty.



What the app looks like when you start it

You can find the project files for this chapter under **22-Get-location-data** in the Source Code folder.

Chapter 23: Use Location Data

By Fahim Farook

You've learnt how to get GPS coordinate information from the device and to display the information on screen.

In this chapter, you will learn the following:

- **Handle GPS errors:** Receiving GPS information is an error-prone process. How do you handle the errors?
- **Improve GPS results:** How to improve the accuracy of the GPS results you receive.
- **Reverse geocoding:** Getting the address for a given set of GPS coordinates.
- **Testing on device:** Testing on device to ensure that your app handles real-world scenarios.
- **Support different screen sizes:** Setting up your UI to work on iOS devices with different screen sizes.

Handle GPS errors

Getting GPS coordinates is error-prone. You may be somewhere where there is no clear line-of-sight to the sky — such as inside or in an area with lots of tall buildings — blocking your GPS signal.

There may not be many Wi-Fi routers around you, or they haven't been catalogued yet, so the Wi-Fi radio isn't much help getting a location fix either. And of course your cellular signal might be so weak that triangulating your position doesn't offer particularly good results either.

All of that is assuming your device actually has a GPS or cellular radio. I just went out with my iPod touch to capture coordinates and get some pictures for this app. In the city center it was unable to obtain a location fix. My iPhone did better, but it still wasn't ideal.

The moral of this story is that your location-aware apps had better know how to deal with errors and bad readings. There are no guarantees that you'll be able to get a location fix, and if you do, then it might still take a few seconds.

This is where software meets the real world. You should add some error handling code to the app to let users know about problems getting those coordinates.

The error handling code

➤ Add these two instance variables to **CurrentLocationViewController.swift**:

```
var updatingLocation = false
var lastLocationError: Error?
```

➤ Change `locationManager(_:didFailWithError:)` to the following:

```
func locationManager(
  _ manager: CLLocationManager,
  didFailWithError error: Error
) {
  print("didFailWithError \(error.localizedDescription)")

  if (error as NSError).code == CLError.locationUnknown.rawValue
{
    return
  }
  lastLocationError = error
  stopLocationManager()
  updateLabels()
}
```

The location manager may report errors for a variety of scenarios. You can look at the `code` property of the `Error` object to find out what type of error you're dealing with. You do need to cast to `NSError` first since that is the subclass of `Error` that actually contains the `code` property.

Some of the possible Core Location errors:

- `CLError.locationUnknown` — the location is currently unknown, but Core Location will keep trying.
- `CLError.denied` — the user denied the app permission to use location services.
- `CLError.network` — there was a network-related error.

There are more, but you get the point. Lots of reasons for things to go wrong!

> **Note:** These error codes are defined in the `CLError` enumeration. Recall that an enumeration, or `enum`, is a list of values and names for these values.
>
> The error codes used by Core Location have simple integer values. Rather than using the values 0, 1, 2 and so on in your program, Core Location has given them symbolic names using the `CLError` enum. That makes these codes easier to understand and you're less likely to pick the wrong one.
>
> To convert these names back to an integer value you ask for the `rawValue`.

In your updated `locationManager(_:didFailWithError:)`, you do:

```
if (error as NSError).code == CLError.locationUnknown.rawValue {
  return
}
```

The `CLError.locationUnknown` error means the location manager was unable to obtain a location right now, but that doesn't mean all is lost. It might just need another second or so to get an uplink to the GPS satellite. In the mean time, it's letting you know that, for now, it could not get any location information.

When you get this error, you will simply keep trying until you do find a location or receive a more serious error.

In the case of a more serious error, you store the error object into the new instance variable, `lastLocationError`:

```
lastLocationError = error
```

That way, you can look up later what kind of error you were dealing with. This comes in useful in `updateLabels()`. You'll be modifying that method shortly to show the error to the user because you don't want to leave them in the dark about such things.

> **Exercise:** Can you explain why `lastLocationError` is an optional?

Answer: When there is no error, `lastLocationError` will not have a value. In other words, it can be `nil`, and variables that can be `nil` must be optionals in Swift.

Finally, the update to `locationManager(_:didFailWithError:)` adds a new method call:

```
stopLocationManager()
```

Stop location updates

If obtaining a location appears to be impossible for wherever the user currently is on the globe, then you need to tell the location manager to stop. To conserve battery power, the app should power down the iPhone's radios as soon as it doesn't need them anymore.

If this was a turn-by-turn navigation app, you'd keep the location manager running even in the case of a network error because who knows, a couple of meters ahead you might get a valid location.

For this app, the user will simply have to press the Get My Location button again if they want to try in another spot.

➤ Add the `stopLocationManager()` method:

```
func stopLocationManager() {
  if updatingLocation {
    locationManager.stopUpdatingLocation()
    locationManager.delegate = nil
    updatingLocation = false
  }
}
```

There's an `if` statement that checks whether the boolean instance variable `updatingLocation` is `true` or `false`. If it is `false`, then the location manager isn't currently active and there's no need to stop it.

The reason for having this `updatingLocation` variable is that you are going to change the appearance of the Get My Location button and the status message label when the app is trying to obtain a location fix, to let the user know the app is working on it.

➤ Put some extra code in `updateLabels()` to show the error message:

```
func updateLabels() {
  if let location = location {
    . . .
  } else {
    . . .
    // Remove the following line
    messageLabel.text = "Tap 'Get My Location' to Start"
    // The new code starts here:
    let statusMessage: String
    if let error = lastLocationError as NSError? {
      if error.domain == kCLErrorDomain && error.code ==
CLError.denied.rawValue {
        statusMessage = "Location Services Disabled"
      } else {
        statusMessage = "Error Getting Location"
      }
    } else if !CLLocationManager.locationServicesEnabled() {
      statusMessage = "Location Services Disabled"
    } else if updatingLocation {
      statusMessage = "Searching..."
    } else {
      statusMessage = "Tap 'Get My Location' to Start"
    }
    messageLabel.text = statusMessage
  }
}
```

The new code determines what to put in the `messageLabel` at the top of the screen. It uses a bunch of `if` statements to figure out what the current status of the app is.

If the location manager gave an error, the label will show an error message.

The first error it checks for is `CLError.denied` in the error domain `kCLErrorDomain`, which means Core Location errors. In that case, the user has not given this app permission to use the location services. That sort of defeats the purpose of this app but it can happen, and you have to check for it anyway. If the error code is something else, then you simply say "Error Getting Location" as this usually means there was no way of obtaining a location fix.

Even if there was no error, it might still be impossible to get location coordinates if the user disabled Location Services completely on their device, instead of just for this app. You check for that situation with the `locationServicesEnabled()` method of `CLLocationManager`.

Suppose there were no errors and everything works fine, then the status label will say "Searching..." before the first location object has been received.

If your device can obtain the location fix quickly, then this text will be visible only for a fraction of a second, but often, it might take a short while to get that first location fix. No one likes waiting, so it's nice to let the user know that the app is actively looking up their location. That is what you're using the `updatingLocation` boolean for.

> **Note:** You put all this logic into a single method because that makes it easy to change the screen when something has changed. Received a location? Simply call `updateLabels()` to refresh the contents of the screen. Received an error? Let `updateLabels()` sort it out...

Start location updates

➤ Also add a new `startLocationManager()` method — I suggest you put it right above `stopLocationManager()`, to keep related functionality together:

```
func startLocationManager() {
  if CLLocationManager.locationServicesEnabled() {
    locationManager.delegate = self
    locationManager.desiredAccuracy =
kCLLocationAccuracyNearestTenMeters
    locationManager.startUpdatingLocation()
    updatingLocation = true
  }
}
```

Starting the location manager used to happen in the `getLocation()` action method. However, because you now have a `stopLocationManager()` method, it makes sense to move the start code into a method of its own, just to keep things symmetrical.

The only difference from before is that this checks whether the location services are enabled and you set the variable `updatingLocation` to `true` if you did indeed start location updates.

➤ Change `getLocation()` to:

```
@IBAction func getLocation() {
  . . .
  if authStatus == .denied || authStatus == .restricted {
    . . .
  }
  // New code below, replacing existing code after this point
  startLocationManager()
  updateLabels()
}
```


There is one more tiny change. Suppose there was an error and no location could be obtained, but then you walk around for a bit and a valid location comes in. In that case, it's a good idea to remove the old error code.

➤ At the bottom of `locationManager(_:didUpdateLocations:)`, add the following line just before calling `updateLabels()`:

```
lastLocationError = nil
```

This clears out the old error state. After receiving a valid coordinate, any previous error you may have encountered is no longer applicable.

➤ Run the app and tap **Get My Location**. While the app is waiting for incoming coordinates, the label at the top should say "Searching..." until it finds a valid coordinate or encounters a fatal error.



The app is waiting to receive GPS coordinates

Play around with the Simulator's location settings for a while and see what happens when you choose different locations.

Note that changing the Simulator's location to None isn't an error anymore. This still returns the `.locationUnknown` error code but you ignore that because it's not a fatal error.

Ideally, you should not just test in the Simulator but also on your device, as you're more likely to encounter real errors that way.

Improve GPS results

Cool, you know how to obtain a `CLLocation` object from Core Location and you're able to handle errors. Now what?

Well, here's the thing: you saw in the Simulator that Core Location keeps giving you new location objects over and over, even though the coordinates may not have changed. That's because the user could be on the move, in which case their GPS coordinates *do* change.

However, you're not building a navigation app. So, for *MyLocations* you just want to get a location that is accurate enough and then you can tell the location manager to stop sending updates.

This is important because getting location updates costs a lot of battery power as the device needs to keep its GPS/Wi-Fi/cellular radios powered up for this. This app doesn't need to ask for GPS coordinates all the time, so it should stop when the location is accurate enough.

The problem is that you can't always get the accuracy you want, so you have to detect this. When the last couple of coordinates you received aren't increasing in accuracy then that is probably as good as it's going to get, and you should let the radio power down.

Get results for a specific accuracy level

➤ Change `locationManager(_:didUpdateLocations:)` to the following:

```
func locationManager(
  _ manager: CLLocationManager,
  didUpdateLocations locations: [CLLocation]
) {
  let newLocation = locations.last!
  print("didUpdateLocations \(newLocation)")

  // 1
  if newLocation.timestamp.timeIntervalSinceNow < -5 {
    return
  }

  // 2
  if newLocation.horizontalAccuracy < 0 {
    return
  }

  // 3
```

```
    if location == nil || location!.horizontalAccuracy >
  newLocation.horizontalAccuracy {

      // 4
      lastLocationError = nil
      location = newLocation

      // 5
      if newLocation.horizontalAccuracy <=
  locationManager.desiredAccuracy {
        print("*** We're done!")
        stopLocationManager()
      }
      updateLabels()
    }
  }
```

Let's take these changes one-by-one:

1. If the time at which the given location object was determined is too long ago — 5 seconds in this case —, then this is a *cached* result.

   Instead of returning a new location fix, the location manager may initially give you the most recently found location under the assumption that you might not have moved much in the last few seconds — obviously, this does not take into consideration people with jet packs.

   You'll simply ignore these cached locations if they are too old.

2. To determine whether new readings are more accurate than previous ones, you'll use the `horizontalAccuracy` property of the location object. However, sometimes locations may have a `horizontalAccuracy` that is less than 0. In which case, these measurements are invalid and you should ignore them.

3. This is where you determine if the new reading is more useful than the previous one. Generally speaking, Core Location starts out with a fairly inaccurate reading and then gives you more and more accurate ones as time passes. However, there are no guarantees — so, you cannot assume that the next reading truly is always more accurate.

   Note that a larger accuracy value means *less* accurate — after all, accurate up to 100 meters is worse than accurate up to 10 meters. That's why you check whether the previous reading, `location!.horizontalAccuracy`, is greater than the new reading, `newLocation.horizontalAccuracy`.

   You also check for `location == nil`.

Recall that `location` is an optional instance variable that stores the `CLLocation` object that you obtained in a previous call to `didUpdateLocations`. If `location` is `nil`, then this is the very first location update you're receiving and in that case you should continue.

So, if this is the very first location reading (`location` is `nil`) or the new location is more accurate than the previous reading, you continue to step 4. Otherwise you ignore this location update.

4. You've seen this part before. It clears out any previous error and stores the new `CLLocation` object into the `location` variable.

5. If the new location's accuracy is equal to or better than the desired accuracy, you can call it a day and stop asking the location manager for updates. When you started the location manager in `startLocationManager()`, you set the desired accuracy to 10 meters (`kCLLocationAccuracyNearestTenMeters`), which is good enough for this app.

Short circuiting

Because `location` is an optional object, you cannot access its properties directly — you first need to unwrap it. You could do that with `if let`, but if you're sure that the optional is not `nil` you can also *force unwrap* it with `!`.

That's what you are doing in this line:

```
if location == nil || location!.horizontalAccuracy >
newLocation.horizontalAccuracy {
```

You wrote `location!.horizontalAccuracy` with an exclamation point instead of just `location.horizontalAccuracy`.

But what if `location == nil`, won't the force unwrapping fail then? Not in this case, because the force unwrap is never performed.

The `||` operator (logical or) tests whether either of the two conditions is true. If the first one is true (`location` is `nil`), it will not evaluate the second condition. That's called *short circuiting*. There is no need for the app to check the second condition if the first one is already true.

So, the app will only look at `location!.horizontalAccuracy` when `location` is guaranteed to be non-`nil`. Blows your mind, eh?

➤ Run the app. First set the Simulator's location to None, then press Get My Location. The screen now says "Searching..."

➤ Switch the location to Apple but don't press Get My Location again. After a brief moment, the screen is updated with GPS coordinates as they come in.

If you check the Xcode Console, you'll get about 10 location updates before it says "*** We're done!" and the location updates stop.

> **Note:** It's possible the above steps won't work for you. If the screen does not say "Searching..." but shows an old set of coordinates instead, then the Simulator is holding on to old location data. This seems to happen when you pick a location from within Xcode using the arrow in the debug area instead of the Simulator's Features menu.
>
> The quickest way to fix this is to quit the Simulator and run the app again — this launches a new Simulator. If you can't get it to work, no worries, it's not that important. Just be aware that the Simulator can be finicky sometimes.

You, as the developer, can tell from the Console when the location updates stop, but obviously, the user won't see this.

The Tag Location button becomes visible as soon as the first location is received so the user can start saving this location to their library right away, but at this point the location may not be accurate enough yet.

So it's nice to show the user when the app has found the most accurate location.

Update the UI

To make this clearer, you are going to toggle the Get My Location button to say "Stop" when the location grabbing is active and switch it back to "Get My Location" when it's done. That gives a nice visual clue to the user. Later on, you'll also show an animated activity spinner that makes this even more obvious.

To change the state of the button, you'll add a `configureGetButton()` method.

➤ Add the following method to **CurrentLocationViewController.swift**:

```
func configureGetButton() {
  if updatingLocation {
    getButton.setTitle("Stop", for: .normal)
  } else {
```

```
      getButton.setTitle("Get My Location", for: .normal)
    }
  }
```

It's quite simple: if the app is currently updating the location, then the button's title becomes Stop, otherwise it is Get My Location.

You need to now call `configureGetButton()` from several different places in your code. If you look closely, you'll notice that wherever you call `updateLabels()`, you also need to call the new method. So might as well call the new method from within `updateLabels()`, right?

➤ Add a call to `configureGetButton()` at the end of `updateLabels()`:

```
func updateLabels() {
  . . .
  configureGetButton()
}
```

➤ Run the app again and perform the same test as before. The button changes to Stop when you press it. When there are no more location updates, it switches back.

When a button says "Stop", you naturally expect to be able to press it so you can interrupt the location updates. This is especially so when you're not getting any coordinates at all. Eventually Core Location may give an error, but as a user, you may not want to wait for that.

Currently, however, pressing Stop doesn't stop anything. You have to change `getLocation()` for this, as any taps on the button call this method.

➤ In `getLocation()`, replace the line with the call to `startLocationManager()` with the following:

```
if updatingLocation {
  stopLocationManager()
} else {
  location = nil
  lastLocationError = nil
  startLocationManager()
}
```

Again, you're using the `updatingLocation` flag to determine what state the app is in.

If the button is pressed while the app is already doing the location fetching, you stop the location manager.

Note that you also clear out the old location and error objects before you start looking for a new location.

➤ Run the app. Now pressing the Stop button will put an end to the location updates. You should see no more updates in the Console after you press Stop.

> **Note:** If the Stop button doesn't appear long enough for you to click it, set the location back to None first, tap Get My Location a few times, and then select the Apple location again.

Reverse geocoding

The GPS coordinates you've dealt with so far are just numbers. The coordinates 37.33240904, -122.03051218 don't really mean that much, but the address 1 Infinite Loop in Cupertino, California does.

Using a process known as **reverse geocoding**, you can turn a set of coordinates into a human-readable address. Regular or "forward" geocoding does the opposite: it turns an address into GPS coordinates. You can do both with the iOS SDK, but for *MyLocations* you'll only do the reverse one.

You'll use the `CLGeocoder` object to turn the location data into a human-readable address and then display that address on screen.

It's quite easy to do this but there are some rules. You're not supposed to send out a ton of these reverse geocoding requests at the same time. The process of reverse geocoding takes place on a server hosted by Apple and it costs them bandwidth and processor time to handle these requests. If you flood their servers with requests, Apple won't be happy.

MyLocations is only supposed to be used occasionally. So theoretically, its users won't be spamming the Apple servers, but you should still limit the geocoding requests to one at a time, and once for every unique location. After all, it makes no sense to reverse geocode the same set of coordinates over and over.

Reverse geocoding needs an active Internet connection and anything you can do to prevent unnecessary use of the iPhone's radios is a good thing for your users.

The implementation

➤ Add the following properties to **CurrentLocationViewController.swift**:

```
let geocoder = CLGeocoder()
var placemark: CLPlacemark?
var performingReverseGeocoding = false
var lastGeocodingError: Error?
```

These mirror what you did for the location manager. `CLGeocoder` is the object that will perform the geocoding and `CLPlacemark` is the object that contains the address results.

The `placemark` variable needs to be an optional because it will have no value when there is no location yet, or when the location doesn't correspond to a street address — I don't think it will respond with "Sahara desert, Africa", but to be fair, I haven't had the chance to try.

You set `performingReverseGeocoding` to `true` when a geocoding operation is taking place, and `lastGeocodingError` will contain an `Error` object if something went wrong, or, `nil` if there is no error.

➤ You'll put the geocoder to work in `locationManager(didUpdateLocations)`:

```
func locationManager(
  _ manager: CLLocationManager,
  didUpdateLocations locations: [CLLocation]
) {
  . . .
  if location == nil || location!.horizontalAccuracy >
newLocation.horizontalAccuracy {
    . . .
    if newLocation.horizontalAccuracy <=
locationManager.desiredAccuracy {
       . . .
    }
    updateLabels()
    // The new code begins here:
    if !performingReverseGeocoding {
      print("*** Going to geocode")

      performingReverseGeocoding = true

      geocoder.reverseGeocodeLocation(newLocation) {placemarks,
error in
        if let error = error {
          print("*** Reverse Geocoding error: \
(error.localizedDescription)")
          return
```

```
            }
            if let places = placemarks {
              print("*** Found places: \(places)")
            }
          }
        }
        // End of the new code
      }
    }
```

The app should only perform a single reverse geocoding request at a time. So, first you check whether it is busy by looking at the `performingReverseGeocoding` variable. Then you start the geocoder.

The code looks straightforward enough, right? Do note the closure at the end of the call to `reverseGeocodeLocation` — it's a *trailing closure*, similar to what you've seen before a few times.

Closures

Unlike the location manager, `CLGeocoder` does not use a delegate to return results from an operation. Instead, it uses a closure. Closures are an important Swift feature and you can expect to see them all over the place — for Objective-C programmers, a closure is similar to a "block".

Closures can have parameters too and here, the parameters for the closure are `placemarks` and `error`, both of which are optionals because either one or the other can be `nil` depending on the situation.

So, while all the code inside the closure does is print out either the list of places or the error, you do have to unwrap each optional before you do that to be sure that you have a value there.

Unlike the rest of the code in `locationManager(_:didUpdateLocations:)`, the code in the closure is not performed right away. After all, you can only print the geocoding results once the geocoding completes, and that may be several seconds later.

The closure is kept for later use by the `CLGeocoder` object and is only performed after `CLGeocoder` finds an address or encounters an error.

So why does `CLGeocoder` use a closure instead of a delegate?

The problem with using a delegate to provide feedback is that you need to write one or more separate methods. For example, for `CLLocationManager` there are the `locationManager(_:didUpdateLocations:)` and `locationManager(_:didFailWithError:)` methods.

By creating separate methods, you move the code that deals with the response away from the code that makes the request. With closures, on the other hand, you can put that handling code in the same place. That makes the code more compact and easier to read. Some APIs do both, and you have a choice between using a closure or becoming a delegate.

So when you write,

```
geocoder.reverseGeocodeLocation(newLocation) {placemarks, error
in
  // put your statements here
}
```

you're telling the `CLGeocoder` object that you want to reverse geocode the location, and that the code in the closure should be executed as soon as the geocoding is completed.

The closure itself is:

```
{ placemarks, error in
    // put your statements here
}
```

The items before the `in` keyword — `placemarks` and `error` — are the parameters for this closure and they work just like parameters for a method or a function.

When the geocoder finds a result for the location object that you gave it, it invokes the closure and executes the statements within. The `placemarks` parameter will contain an array of `CLPlacemark` objects that describe the address information, and the `error` variable contains an error message in case something went wrong.

Closures are basically the same principle as using delegate methods, except you're not putting the code into a separate method but in a closure.

It's OK if closures have got you scratching your head right now. You'll see them used many more times in the upcoming chapters.

➤ Run the app and pick a location. As soon as the first location is found, you can see in the Console that the reverse geocoder has kicked in after a second or two:

```
didUpdateLocations <+37.33233141,-122.03121860> +/- 5.00m (speed
0.00 mps / course -1.00) @ 7/24/21, 8:05:35 AM Eastern Daylight
Time
*** Going to geocode
*** Found places: [Apple Campus, Apple Campus, 1 Infinite Loop,
Cupertino, CA  95014, United States @
<+37.33233141,-122.03121860> +/- 100.00m, region
CLCircularRegion (identifier:'<+37.33213110,-122.02990105>
radius 279.38', center:<+37.33213110,-122.02990105>,
radius:279.38m)]
```

If you choose the Apple location, you'll see that some location readings are duplicates; the geocoder only does the first of those. Only when the accuracy of the reading improves does the app reverse geocode again. Nice!

> **Note:** Several readers have previously reported that if you are in China and are trying to reverse geocode an address that is outside of China, you may get an error and `placemarks` will be `nil`. If this happens to you, try a location inside China instead.

Handle reverse geocoding errors

➤ Replace the contents of the geocoding closure with the following:

```
self.lastGeocodingError = error
if error == nil, let places = placemarks, !places.isEmpty {
  self.placemark = places.last!
} else {
  self.placemark = nil
}

self.performingReverseGeocoding = false
self.updateLabels()
```

Just as with the location manager, you store the error object so you can refer to it later — you do use a different instance variable this time, `lastGeocodingError`.

The next line does something you haven't seen before:

```
if error == nil, let places = placemarks, !places.isEmpty {
```

You know that `if let` is used to unwrap optionals. Here, `placemarks` is an optional, so it needs be unwrapped before you can use it or you risk crashing the app when `placemarks` is `nil`. The unwrapped `placemarks` array gets the temporary name `places`.

The `!places.isEmpty` bit says that we should only enter this `if` statement if the array of placemark objects is not empty.

You should read this line as:

```
if there's no error and the unwrapped placemarks array is not
empty {
```

Of course, Swift doesn't speak English, so you have to express this in terms that Swift understands.

You could also have written this as three different, nested `if` statements:

```
if error == nil {
  if let places = placemarks {
    if !places.isEmpty {
```

But it's just as easy to combine all of these conditions into a single `if`.

You're doing a bit of **defensive programming** here: you specifically check first whether the array has any objects in it. If there is no error, then it should have at least one object, but you're not going to trust that it always will. Good developers are paranoid!

If all three conditions are met — there is no error, the `placemarks` array is not `nil`, and there is at least one `CLPlacemark` inside this array — then you take the last of those `CLPlacemark` objects:

```
    self.placemark = places.last!
```

The `last` property refers to the last item from an array. It's an optional because there is no last item if the array is empty. As an alternative, you can also write `places[places.count - 1]` but that's not as tidy.

Usually there will be only one `CLPlacemark` object in the array, but there is the odd situation where one location coordinate may refer to more than one address. This app can only handle one address at a time. So, you'll just pick the last one, which usually is the only one.

If there was an error during geocoding, you set `self.placemark` to `nil`.

Note that you did not do that for the locations. If there was an error there, you kept the previous location object because it may actually be correct, or good enough, and it's better than nothing.

But for the address that makes less sense. You don't want to show an old address, only the address that corresponds to the current location or no address at all.

In mobile development, nothing is guaranteed. You may get coordinates back or you may not, and if you do, they may not be very accurate. The reverse geocoding will probably succeed if there is some type of network connection available, but you also need to be prepared to handle the case where there is none.

And remember, not all GPS coordinates correspond to actual street addresses — there is no corner of 52nd and Broadway in the Sahara desert.

> **Note:** Did you notice that inside the closure you used `self` to refer to the view controller's properties and methods? This is a Swift requirement.
>
> Closures are said to *capture* all the variables they use and `self` is one of them. You can forget about that immediately, if you like; just know that Swift requires that all captured variables are explicitly mentioned.
>
> As you've seen, outside a closure, you can use `self` to refer to properties and methods, but it's not a requirement. However, you do get a compiler error if you leave out `self` inside a closure. So you don't have much choice there.

Display the address

Let's show the address to the user.

➤ Change `updateLabels()` to:

```
func updateLabels() {
  if let location = location {
    . . .
    // Add this block
    if let placemark = placemark {
      addressLabel.text = string(from: placemark)
    } else if performingReverseGeocoding {
      addressLabel.text = "Searching for Address..."
    } else if lastGeocodingError != nil {
      addressLabel.text = "Error Finding Address"
    } else {
      addressLabel.text = "No Address Found"
    }
```

```
      // End new code
    } else {
      . . .
    }
  }
```

Because you only do the address lookup after the app has a valid location, you just have to change the code inside the first `if` branch. If you've found an address, you show that to the user, otherwise you show a status message.

The code to format the `CLPlacemark` object into a string is placed in its own method, just to keep the code readable.

➤ Add the `string(from:)` method:

```
  func string(from placemark: CLPlacemark) -> String {
    // 1
    var line1 = ""
    // 2
    if let tmp = placemark.subThoroughfare {
      line1 += tmp + " "
    }
    // 3
    if let tmp = placemark.thoroughfare {
      line1 += tmp
    }
    // 4
    var line2 = ""
    if let tmp = placemark.locality {
      line2 += tmp + " "
    }
    if let tmp = placemark.administrativeArea {
      line2 += tmp + " "
    }
    if let tmp = placemark.postalCode {
      line2 += tmp
    }
    // 5
    return line1 + "\n" + line2
  }
```

Let's look at this in detail:


1. The address will be two lines of text — create a new string variable for the first line of text.
2. If the placemark has a `subThoroughfare`, add it to the string. This is an optional property, so you unwrap it with `if let` first. Just so you know, `subThoroughfare` is a fancy name for house number.

3. Adding the `thoroughfare`, or street name, is done similarly. Note that you put a space between it and `subThoroughfare` so they don't get glued together.
4. The same logic goes for the second line of text. This adds the locality (the city), administrative area (the state or province), and postal code (or zip code), with spaces between them where appropriate.
5. Finally, the two lines are concatenated, or added together, with a newline character in between. The `\n` adds the line break (or newline) to the string.

➤ In `getLocation()`, clear out the `placemark` and `lastGeocodingError` variables to start with a clean slate. Put this just above the call to `startLocationManager()`:

```
placemark = nil
lastGeocodingError = nil
```

➤ Run the app again. Seconds after a location is found, the address label should be filled in as well.



Reverse geocoding finds the address for the GPS coordinates

It's fairly common that street numbers or other details are missing from the address. The `CLPlacemark` object may contain incomplete information, which is why its properties are all optionals. Geocoding is not an exact science!

Exercise: If you pick the City Bicycle Ride or City Run locations from the Simulator's Features menu, you should see in the Console that the app jumps through a whole bunch of different coordinates — it simulates someone moving from one place to another. However, the coordinates on the screen and the address label don't change nearly as often. Why is that?

Answer: The logic for *MyLocations* was designed to find the most accurate set of coordinates for a stationary position. You only update the `location` variable when a new set of coordinates comes in that is more accurate than previous readings. Any new readings with a higher — or the same — `horizontalAccuracy` value are simply ignored, regardless of what the actual coordinates are.

With the City Bicycle Ride and City Run options, the app doesn't receive the same coordinates with increasing accuracy but a series of completely different coordinates. That means this app doesn't work very well when you're on the move, unless you press Stop and try again. On the other hand, the app was also not intended for capturing shifting locations.

> **Note:** If you're playing with different locations in the Simulator or from the Xcode debugger menu and you get stuck, then the quickest way to get unstuck is to reset the Simulator. Sometimes it just doesn't want to move to a new location even if you tell it to, and then you have to show it who's the boss!

Testing on device

When I first wrote this code, I had only tested it on the Simulator. It worked fine there. Then, I put it on my iPod touch and guess what? Not so good.

The problem with the iPod touch is that it doesn't have GPS, so it relies only on Wi-Fi to determine the location. But Wi-Fi might not be able to give you accuracy up to ten meters; I got +/- 100 meters at best.

Right now, you only stop the location updates when the accuracy of the reading falls within the `desiredAccuracy` setting — something that will never actually happen on my iPod touch.

That goes to show that you can't always rely on the Simulator to test your apps. You need to put them on your device and test them in the wild, especially when using device-dependent functionality like location-based APIs. If you have more than one device, then test on all of them!

In order to deal with this situation, you will improve upon the `didUpdateLocations` delegate method.

First fix

➤ Change `locationManager(_:didUpdateLocations:)` to:

```
func locationManager(
  _ manager: CLLocationManager,
  didUpdateLocations locations: [CLLocation]
) {
```

```
    . . .

    if newLocation.horizontalAccuracy < 0 {
      return
    }

    // New section #1
    var distance =
CLLocationDistance(Double.greatestFiniteMagnitude)
    if let location = location {
      distance = newLocation.distance(from: location)
    }
    // End of new section #1
    if location == nil || location!.horizontalAccuracy >
newLocation.horizontalAccuracy {
      . . .
      if newLocation.horizontalAccuracy <=
locationManager.desiredAccuracy {
        . . .
        // New section #2
        if distance > 0 {
          performingReverseGeocoding = false
        }
        // End of new section #2
      }
      if !performingReverseGeocoding {
        . . .
      }
          updateLabels()
    // New section #3
    } else if distance < 1 {
      let timeInterval =
newLocation.timestamp.timeIntervalSince(location!.timestamp)
      if timeInterval > 10 {
        print("*** Force done!")
        stopLocationManager()
        updateLabels()
      }
      // End of new sectiton #3
    }
  }
```

It's a pretty long method now, but only the three highlighted sections were added. This is the first one:

```
  var distance =
  CLLocationDistance(Double.greatestFiniteMagnitude)
  if let location = location {
    distance = newLocation.distance(from: location)
  }
```

This calculates the distance between the new reading and the previous reading, if there was one. We can use this `distance` to measure if our location updates are still improving.

If there was no previous reading, then the distance is `Double.greatestFiniteMagnitude`. That is a built-in constant that represents the maximum value that a `Double` value can have. This little trick gives it a gigantic distance if this is the very first reading. You're doing that so any of the following calculations still work even if you weren't able to calculate a true distance yet.

You also add an `if` statement later where you stop the location manager:

```
if distance > 0 {
  performingReverseGeocoding = false
}
```

This forces a reverse geocoding for the final location, even if the app is already currently performing another geocoding request.

You absolutely want the address for that final location, as that is the most accurate location you've found. But if some previous location was still being reverse geocoded, this step would normally be skipped. Simply by setting `performingReverseGeocoding` to `false`, you always force the geocoding to be done for this final coordinate.

Of course, if `distance` is 0, then this location is the same as the location from a previous reading, and you don't need to reverse geocode it anymore.

The real improvement is found in the final new section:

```
} else if distance < 1 {
  let timeInterval =
newLocation.timestamp.timeIntervalSince(location!.timestamp)
  if timeInterval > 10 {
    print("*** Force done!")
    stopLocationManager()
    updateLabels()
  }
}
```

If the coordinate from this reading is not significantly different from the previous reading and it has been more than 10 seconds since you've received that original reading, then it's a good point to hang up your hat and stop.

It's safe to assume you're not going to get a better coordinate than this and you can stop fetching the location.

This is the improvement that was necessary to make my iPod touch stop scanning after some time. It wouldn't give me a location with better accuracy than +/- 100 meters, but it kept repeating the same one over and over.

I picked a time limit of 10 seconds because that seemed to give good results.

Note that you don't just say:

```
} else if distance == 0 {
```

The distance between subsequent readings is never exactly 0. It may be something like 0.0017632. Rather than checking for equals to 0, it's better to check for less than a certain distance, in this case one meter.

By the way, did you notice how you used `location!` to unwrap it before accessing the timestamp property? When you are inside this `else-if`, the value of `location` is guaranteed to be non-`nil`, so its safe to force unwrap the optional.

➤ Run the app and test that everything still works. It may be hard to recreate this situation on the Simulator, but try it on your device inside the house and see what output you see in the Console.

Second fix

There is another improvement you can make to increase the robustness of this logic, and that is to set a time-out on the whole thing. You can tell iOS to perform a method one minute from now. If by that time the app hasn't found a location yet, you stop the location manager and show an error message.

➤ First add a new instance variable:

```
var timer: Timer?
```

➤ Then change `startLocationManager()` to:

```
func startLocationManager() {
  if CLLocationManager.locationServicesEnabled() {
    . . .
    timer = Timer.scheduledTimer(
      timeInterval: 60,
      target: self,
      selector: #selector(didTimeOut),
      userInfo: nil,
      repeats: false)
  }
}
```

The new lines set up a timer object that sends a `didTimeOut` message to `self` after 60 seconds; `didTimeOut` is the name of a method.

A *selector* is the term that Objective-C uses to describe the name of a method, and the `#selector()` syntax is how you create a selector in Swift.

➤ Change `stopLocationManager()` to:

```
func stopLocationManager() {
  if updatingLocation {
    . . .
    if let timer = timer {
      timer.invalidate()
    }
  }
}
```

You have to cancel the timer in case the location manager is stopped before the time-out fires. This happens when an accurate enough location is found within one minute after starting, or when the user taps the Stop button.

➤ Finally, add the `didTimeOut()` method:

```
@objc func didTimeOut() {
  print("*** Time out")
  if location == nil {
    stopLocationManager()
    lastLocationError = NSError(
      domain: "MyLocationsErrorDomain",
      code: 1,
      userInfo: nil)
    updateLabels()
  }
}
```

There's something new about this method — there's a new `@objc` attribute before `func` — whatever could it be?

Remember how how `#selector` is an Objective-C concept? (How could you forget, it was just a few paragraphs ago, right?) So, when you use `#selector` to identify a method to call, that method has to be accessible not only from Swift, but from Objective-C as well. The `@objc` attribute allows you to identify a method — or class, or property, or even enumeration — as being accessible from Objective-C.

So, that's what you've done for `didTimeOut` — declared it as being accessible from Objective-C.

`didTimeOut()` is always called after one minute, whether you've obtained a valid location or not — unless `stopLocationManager()` cancels the timer first.

If after that one minute there still is no valid location, you stop the location manager, create your own error code, and update the screen.

By creating your own `NSError` object and putting it into the `lastLocationError` instance variable, you don't have to change any of the logic in `updateLabels()`.


However, you do have to make sure that the error's domain is not `kCLErrorDomain` because this error object does not come from Core Location but from within your own app.

An error domain is simply a string, so `MyLocationsErrorDomain` will do. For the code I picked 1. The value of the code doesn't really matter at this point because you only have one custom error, but you can imagine that when your app becomes bigger, you might need multiple error codes.

Note that you don't always have to use an `NSError` object; there are other ways to let the rest of your code know that an error occurred. In this case `updateLabels()` was already using an `NSError` anyway, so having your own error object just made sense.

➤ Run the app. Set the Simulator location to None and press **Get My Location**.

After a minute, the debug area should say "*** Time out" and the Stop button reverts to Get My Location. There should also be an error message on the screen:



The error after a time out

Just getting a simple location from Core Location and finding the corresponding street address turned out to be a lot more complicated than it looked. There are many different situations to handle. Nothing is guaranteed, and everything can go wrong — iOS development sometimes requires nerves of steel!

To recap, the app can either:

- Find a location with the desired accuracy,
- Find a location that is not as accurate as you'd like and doesn't get any more accurate readings,

- Doesn't find a location at all,
- Or, takes too long finding a location.

The code now handles all these situations, but I'm sure it's not perfect yet. No doubt the logic could be tweaked more, but it will do for the purposes of this book.

I hope it's clear that if you're releasing a location-based app, you need to do a lot of field testing!

Required device capabilities


The **Info** tab can have a key, **Required device capabilities**, that lists the hardware that your app needs in order to run. This is the key that the App Store uses to determine whether a user can install your app on their device.

If your app requires additional features, such as Core Location to retrieve the user's location, you should list them here.

➤ Select the **Info** tab and add a new row and set the key as **Required device capabilities**.

The value for the new key is an array. If you expand the list of array items, you'll notice that there's a default item which is empty.

➤ Click the double headed arrow at the end of the value field for the empty array item to get a list of possible values. Select **Location Services** from the list:



Adding location-services to Info.plist


You could also add **GPS**, so that the app requires a GPS receiver. But if you did, users won't be able to install the app on an iPod touch or on certain iPads.

P.S. You can now take the `print()` statements out of the app, or simply comment them out. Personally, I like to keep them in there as they're handy for debugging. In an app that you plan to upload to the App Store, you'll definitely want to remove the `print()` statements when development is complete.

★ ★ ★

Attributes and properties

Most of the attributes in Interface Builder's inspectors correspond directly to properties on the selected object. For example, a `UILabel` has the following attributes:




These are directly related to the following properties:

```
Text          label.text
Color         label.textColor
Font          label.font
Alignment     label.textAlignment
Lines         label.numberOfLines
Enabled       label.isEnabled
Baseline      label.baselineAdjustment
Line Breaks   label.lineBreakMode
```

And so on... As you can see, the names may not always be exactly the same ("Lines" and `numberOfLines`) but you can easily figure out which property goes with which attribute.

You can find these properties in the documentation for `UILabel`. From the Xcode **Help** menu, select **Developer Documentation**. Type "uilabel" into the search field to bring up the class reference for `UILabel`:



The documentation for `UILabel` does not list properties for all of the attributes from the inspectors. For example, in the Attributes inspector there is a section named "View". The attributes in this section come from `UIView`, which is the base class of `UILabel`. So if you can't find a property in the `UILabel` class, you may need to check the documentation under the "Inherits From" section which is under the **Relationships** section of the `UILabel` documentation.

★ ★ ★

You can find the project files for this chapter under **23-Use-location-data** in the Source Code folder.

Chapter 24: Objects vs. Classes

By Fahim Farook

Time for something new. Up until now I've been calling almost everything an "object." That's not quite correct though. So, it's time for you to brush up on your programming theory a bit more.

In this chapter, you will learn the following:

- **Classes**: The difference between classes and objects.
- **Inheritance**: What class inheritance is and how it works.
- **Overriding methods**: Overriding methods in sub-classes to provide different functionality.
- **Casts**: Casting an object from a subclass to its superclass — how (and why) you do it.

Classes

If you want to use the proper object-oriented programming vernacular, you have to make a distinction between an object and its **class**.

When you do this,

```
class ChecklistItem: NSObject {
  . . .
}
```

You're really defining a class named `ChecklistItem`, not an object. An object is what you get when you **instantiate** a class:

```
let item = ChecklistItem()
```

The `item` variable now contains an object of the class `ChecklistItem`. You can also say: the `item` variable contains an **instance** of the class `ChecklistItem`. The terms object and instance mean the same thing.

In other words, "instance of class `ChecklistItem`" is the **type** of this `item` variable.

The Swift language and the iOS frameworks already come with a lot of types built-in, but you can also add types of your own by making new classes.

Let's use an example to illustrate the difference between a class and an instance / object.

You and I are both hungry, so we decide to eat some ice cream — my favorite subject next to programming!. Ice cream is the class of food that we're going to eat.

The ice cream class looks like this:

```
class IceCream: NSObject {
  var flavor: String
  var scoops: Int

  func eatIt() {
    // code goes in here
  }
}
```


You and I go on over to the ice cream stand and ask for two cones:

```
// one for you
let iceCreamForYou = IceCream()
iceCreamForYou.flavor = "Strawberry"
iceCreamForYou.scoops = 2

// and one for me
let iceCreamForMe = IceCream()
iceCreamForMe.flavor = "Pistachio"
iceCreamForMe.scoops = 3
```

Yep, I get more scoops, but that's because I'm hungry from all this explaining. ;-]

Now the app has two instances of `IceCream`, one for you and one for me. There is just one class that describes what sort of food we're eating — ice cream — but there are two distinct objects. Your object has strawberry flavor, mine pistachio.



The class is a template for making new instances

The `IceCream` class is like a template that declares: objects of this type have two properties, `flavor` and `scoops`, and a method named `eatIt()`.

Any new instance that is made from this template will have those instance variables and methods, but it lives in its own section of computer memory and therefore has its own values.

If you're more into architecture than food, you can also think of a class as a blueprint for a building. It is the design of the building but not the building itself. One blueprint can make many buildings, and you could paint each one — each instance — a different color if you wanted to.

Inheritance

Sorry, this is not where I tell you that you've inherited a fortune. We're talking about **class inheritance** here, one of the main principles of object-oriented programming.

Inheritance is a powerful feature that allows a class to be built on top of another class. The new class takes over all the data and functionality from that other class and adds its own specializations to it.

Take the `IceCream` class from the previous example. It is built on `NSObject`, the fundamental class for iOS frameworks. You can see that in the `class` line that defines `IceCream`:

```
class IceCream: NSObject {
```

This means that `IceCream` is actually the `NSObject` class with a few additions of its own, namely the `flavor` and `scoops` properties and the `eatIt()` method.

`NSObject` is the **base class** for almost all other classes in iOS frameworks. Most objects that you'll encounter are made from a class that either directly inherits from `NSObject`, or from another class that is ultimately based on `NSObject`. You can't escape it!


You've also seen class declarations that look like this:

```
class ChecklistViewController: UITableViewController
```

The `ChecklistViewController` class is really a `UITableViewController` class with your own additions. It does everything a `UITableViewController` does, plus whatever new data and functionality you've given it.

This inheritance thing is very handy because `UITableViewController` already does a lot of work for you behind the scenes. It has a table view, it knows how to deal with prototype cells and static cells, and it handles things like scrolling and a ton of other stuff. All you have to do is add your own customizations and you're ready to go.

`UITableViewController` itself is built on top of `UIViewController`, which is built on top of something called `UIResponder`, and ultimately that class is built on `NSObject`. This is called the *inheritance tree*.



All framework classes stand on the shoulders of NSObject

The big idea here is that each object that is higher up performs a more specialized task than the one below it.

`NSObject`, the base class, only provides a few basic functions that are needed by all objects. For example, it contains an `alloc` method that is used to reserve memory space for the object's instance variables, and a basic `init` method.

`UIViewController` is the base class for all view controllers. If you want to make your own view controller, you extend `UIViewController`. To **extend** means that you make a class that inherits from another one. Other commonly used terms are to **derive from** or **to base on** or **to subclass**. These phrases all mean the same thing.

`UIViewController` does way more than you'd think — you really don't want to write all your own screen and view handling code. If you'd had to program each screen totally from scratch, you'd still be working on lesson #1!

Thank goodness that stuff has been taken care of by very smart people working at Apple and they've bundled it all into `UIViewController`. You simply make a class that inherits from `UIViewController` and you get all that functionality for free. You just add your own data and logic to that class and off you go!


If your screen primarily deals with a table view, then you'd subclass `UITableViewController` instead. This class does everything `UIViewController` does — because it inherits from it — but is more specialized for dealing with table views.

You could write all that code by yourself, but why would you, when it's already available in a convenient package? Class inheritance lets you re-use existing code with minimal effort. It can save you a lot of time!

Superclasses and subclasses


When programmers talk about inheritance, they'll often throw around the terms **superclass** and **subclass**.

In the example above, `UITableViewController` is the immediate superclass of `ChecklistViewController`, and conversely `ChecklistViewController` is a subclass of `UITableViewController`. The superclass is the class you derived from (or extended), while a subclass derives from your class.



Superclass and subclass

A class in Swift can have many subclasses but only one immediate superclass. Of course, that superclass can have a superclass of its own. There are many different classes that inherit from `UIViewController`, for example:



A small portion of the UIKit inheritance tree

Because nearly all classes extend from `NSObject`, they form a big hierarchy. It is important that you understand this class hierarchy so you can make your own objects inherit from the proper superclasses.

As you'll see later on, there are many other types of hierarchies in programming. For some reason programmers seem to like hierarchies :]

Do note that in Objective-C, all your classes must at least inherit from the `NSObject` class. This is not the case with Swift. You could also have written the `IceCream` class as follows:

```
class IceCream {
  . . .
}
```

Now IceCream does not have a base class at all.

This is fine in pure Swift code, but you might run into troubled waters if you try to use `IceCream` instances in combination with iOS frameworks, which are generally written in Objective-C. So, sometimes you'll have to use the `NSObject` base class, even if you're writing the app in Swift only.

Inheriting properties (and methods)

Inheriting from a class means your new class gets to use the properties and methods from its superclass.

If you create a new base class `Snack`:

```
class Snack {
  var flavor: String
  func eatIt() {
    // code goes in here
  }
}
```

And make `IceCream` inherit from that class:

```
class IceCream: Snack {
  var scoops: Int
}
```

Then elsewhere in your code you can do:

```
let iceCreamForMe = IceCream()
iceCreamForMe.flavor = "Chocolate"
```

```
iceCreamForMe.scoops = 1
iceCreamForMe.eatIt()
```

This works even though `IceCream` did not explicitly declare an `eatIt()` method or `flavor` instance variable. But `Snack` did! Because `IceCream` inherits from `Snack`, it automatically gets the method and instance variable for free.

Overriding methods

In the previous example, `IceCream` could use the `eatIt()` method implementation from `Snack` for free. But that's not the full story :]

`IceCream` can also provide its own `eatIt()` method if it's important for your app that eating ice cream is different from eating any other kind of snack — for example, you may want to eat it faster, before it melts:

```
class IceCream: Snack {
  var scoops: Int

  override func eatIt() {
    // code goes in here
  }
}
```

Now, when someone calls `iceCreamForMe.eatIt()`, this new version of the method in the `IceCream` class is invoked. Note that Swift requires you to use the `override` keyword in front of any methods that you provide that already exist in the superclass.

A possible implementation of this overridden version of `eatIt()` could look like this:

```
class IceCream: Snack {
  var scoops: Int
  var isMelted: Bool

  override func eatIt() {
    if isMelted {
      throwAway()
    } else {
      super.eatIt()
    }
  }
}
```

If the ice cream has melted, you want to throw it in the trash. But if it's still edible, you'll call `Snack`'s version of `eatIt()` using `super`. Just like `self` refers to the current object, the `super` keyword refers to the object's superclass. That is the reason you've been calling `super` in various places in your code, to let any superclasses do their thing.

Something that happens often in iOS frameworks is that methods are used for communicating between a class and its subclasses, so that the subclass can perform specific behavior in certain circumstances. That is what methods such as `viewDidLoad()` and `viewWillAppear(_:)` are for.

These methods are defined and implemented by `UIViewController` but your own view controller subclass can override them.

For example, when its screen is about to become visible, the `UIViewController` class will call `viewWillAppear(true)`. Normally this will invoke the `viewWillAppear(_:)` method from `UIViewController` itself, but if you've provided your own version of this method in your subclass, then yours will be invoked instead.

By overriding `viewWillAppear(_:)`, you get a chance to handle this event before the superclass does:

```
class MyViewController: UIViewController {
  override func viewWillAppear(_ animated: Bool) {
    // do your own stuff before super

    // don't forget to call super!
    super.viewWillAppear(animated)

    // do your own stuff after super
  }
}
```

That's how you can tap into the power of your superclass. A well-designed superclass provides such "hooks" that allow you to react to certain events.

Don't forget to call `super`'s version of the method, though. If you neglect this, the superclass will not get its own notification and weird things may happen.

You've also seen `override` already in the table view data source methods:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  . . .
}
```

`UITableViewController`, the superclass, already implements these methods. So, if you want to provide your own implementation, you need to override the existing ones.

> **Note:** Inside those table view delegate and data source methods, it's usually not necessary to call `super`. The iOS API documentation can usually tell you whether you need to call `super` or not for an overridden method.

Subclass initialization

When making a subclass, the `init` methods require special care.

If you don't want to change any of the `init` methods from your superclass or add any new `init` methods, then it's easy: you don't have to do anything. The subclass will automatically take over the `init` methods from the superclass.

Most of the time, however, you will want to override an `init` method or add your own. For example, to put values into the subclass's new instance variables. In that case, you may have to override not just that one `init` method but all of them.

In the next app you'll create a class named `GradientView` that extends `UIView`. That app uses `init(frame:)` to create and initialize a `GradientView` object. `GradientView` overrides this method to set the background color:

```
class GradientView: UIView {
  override init(frame: CGRect) {
    super.init(frame: frame)
    backgroundColor = UIColor.black
  }
  required init?(coder aDecoder: NSCoder) {
    super.init(coder: aDecoder)
  }
  . . .
}
```

But because `UIView` also has another init method, `init?(coder:)`, `GradientView` needs to implement that method too even if it doesn't do anything but call `super`.

Also note that `init(frame:)` is marked as `override`, but `init?(coder:)` is `required`. The `required` keyword is used to enforce that every subclass always implements this particular `init` method.

Swift wants to make sure that subclasses don't forget to add their own stuff to such required `init` methods, even if the app doesn't actually use that particular `init` method, as in the case of `GradientView` — it can be a bit of an over-concerned parent, that Swift.

The rules for inheritance of `init` methods are somewhat complicated — the official Swift Programming Guide devotes many pages to it — but at least if you make a mistake, Xcode will tell you what's wrong and what you should do to fix it.

Private parts

So… does a subclass get to use all the methods from its superclass? Not quite.

`UIViewController` and other UIKit classes have a lot more methods hidden away than you have access to. Often, these secret methods do cool things and it is tempting to use them. But they are not part of the official API, making them off-limits for mere mortals such as you and I.

If you ever hear other developers speak of "private APIs" in hushed tones and down dark alleys, then this is what they are talking about.

It is, in theory, possible to call such hidden methods if you know their names, but this is not recommended. It may even get your app rejected from the App Store, as Apple is known to scan apps for usage of these private APIs.

You're not supposed to use private APIs for two reasons:

1. These APIs may have unexpected side effects and not be as robust as their publicly available relatives.
2. There is no guarantee these methods will exist from one version of iOS to the next. Using them is very risky, as your apps may suddenly stop working.

Sometimes, however, using a private API is the only way to access certain functionality on the device. If so, you're out of luck. Fortunately, for most apps, the official public APIs are more than enough and you won't need to resort to the private stuff.

So how do you mark your own methods as private, I hear you ask? This could get a bit complicated and is probably best left to a more detailed treatment of the subject.

But in simple terms, similar to the `@objc` attribute you used in the previous chapter, there are other attributes that you can use to modify the access control level of Swift classes, methods, or properties.

Some of the most common are `public`, `private`, and `internal`. Hopefully, the names of the first two alone give you an understanding as to their intent. As for `internal`, this indicates that the specified item can be accessed from within the current module but not from outside of that module.

Now I hear you ask, "But what's a module?". That is certainly a good question, but one which requires a lengthy explanation :] For the purposes of this book, the module can be taken to be the app — though that's not quite correct technically.

`internal` is the default access control level for any item for which you haven't explicitly specified the access control level. Which is why you have not had to prefix any of your classes or methods with an access control level till now.

`private` is what you need if you wanted to hide any of your classes, methods, or properties. But a discussion as to how `private` works in terms of what is hidden if you use the attribute and the advantages of doing so, might be a bit too broad a subject for now :]

Casts

Often, your code will refer to an instance not by its own class but by one of its superclasses. That probably sounds very weird, so let's look at an example.


MyLocations has a `UITabBarController` with three tabs, each of which is represented by a view controller. The view controller for the first tab is `CurrentLocationViewController`. Later on you'll add two others, `LocationsViewController` for the second tab, and `MapViewController` for the third.

The designers of iOS obviously didn't know anything about those three particular view controllers when they created `UITabBarController`. The only thing the tab bar controller can reliably depend on is that each tab has a view controller that inherits from `UIViewController`.


So, instead of talking to the `CurrentLocationViewController` class, the tab bar controller only sees its superclass part, `UIViewController`.

As far as the tab bar controller is concerned, it has three `UIViewController` instances and it doesn't know or care about the additions that you've made to each one.

The structure of the app:



What the tab bar controller sees:



The UITabBarController does not see your subclasses

The same thing goes for `UINavigationController`. To the navigation controller, any new view controllers that get pushed on the navigation stack are all instances of `UIViewController`, nothing more, nothing less.

Sometimes that can be a little annoying. When you ask the navigation controller for one of the view controllers on its stack, it returns a reference to a `UIViewController` instance, even though that is not the full type of that object.

If you want to treat that object as your own view controller subclass instead, you need to **cast** it to the proper type.

Previously you did the following in `prepare(for:sender:)`:

```
let controller = segue.destination as! ItemDetailViewController
controller.delegate = self
```

Here, you wanted to get the segue's destination view controller — which is an instance of `ItemDetailViewController` — and set its `delegate` property.

However, the segue's `destination` property won't give you an object of type `ItemDetailViewController`. The value it returns is of the plain `UIViewController` type, which naturally doesn't have your `delegate` property.

If you were write the above code without the `as! ItemDetailViewController` bit, like so:

```
let controller = segue.destination
```

Then, Xcode would show an error for the line below it. Swift now infers the type of `controller` to be `UIViewController`, but `UIViewController` does not have a `delegate` property. That property is something you added to the subclass, `ItemDetailViewController`.

You know that `destination` refers to an `ItemDetailViewController`, but Swift doesn't. Even though all `ItemDetailViewControllers` are `UIViewControllers`, not all `UIViewControllers` are `ItemDetailViewControllers`!

Just because your friend Chuck has no hair, that doesn't mean all bald guys are named Chuck. Or, that all guys named Chuck have no hair, either. :]

To solve this problem, you have to cast the object to the proper type. You, as the developer, know this particular object is an `ItemDetailViewController`, so you use the `as!` cast operator to tell the compiler, "I want to treat this object as an `ItemDetailViewController`."

With the cast, the code looks like this:

```
let controller = segue.destination as! ItemDetailViewController
```

Now, you can treat the value from `controller` as an `ItemDetailViewController` object. But... the compiler can't check whether the thing you're casting really is that kind of object. So, if you're wrong and it's not, your app will most likely crash.

Casts can fail for other reasons, too. For example, the value that you're trying to cast may actually be `nil`. If that's a possibility, it's a good idea to use the `as?` operator to make it an optional cast. You must also store the result of the cast into an optional value or use `if let` to safely unwrap it.

Note that a cast doesn't magically convert one type to another. You can't cast an `Int` to a `String`, for example. You only use a cast to make a type more specific, and the two types have to be compatible for this to work.

Casting is very common in Swift programs because of the Objective-C heritage of the iOS frameworks. You'll be doing a lot of it!

To summarize, there are three kinds of casts you can perform:

1. **as?** for casts that are allowed to fail. This would happen if the object is `nil` or doesn't have a type that is compatible with the one you're trying to cast to. It will try to cast to the new type and if it fails, then no biggie. This cast returns an optional that you can unwrap with `if let`.
2. **as!** for casts between a class and one of its subclasses. This is also known as a *downcast*. As with implicitly unwrapped optionals, this cast is potentially unsafe and you should only use `as!` when you are certain it cannot possibly go wrong. You often need to use this cast when dealing with objects coming from UIKit and other iOS frameworks. Better get used to all those exclamation marks!
3. **as** for casts that can never possibly fail. Swift can sometimes guarantee that a type cast will always work, for example between `NSString` and `String`. In that case you can leave off the `?` or the `!` and just write `as`.

It can sometimes be confusing to decide which of these three cast operators you need. If so, just type "as" and Xcode will suggest the correct variant. You can rely on Xcode. :]

Chapter 25: The Tag Location Screen

By Fahim Farook

There is a big button on the main screen of the app that says **Tag Location**. It only becomes active when GPS coordinates have been captured, and you use it to add a description and a photo to that location.

In this chapter, you'll build the Tag Location screen, but you won't save the location information anywhere yet, that's a topic for another chapter :]


This chapter covers the following:

- **The Screen**: What the finished screen looks like and what it will do.
- **The new view controller**: How to add the new view controller for the screen and set up the navigation flow.
- **Make the cells**: Create the table view cells for displaying information.
- **Display location info**: Display location info on screen via the new view.
- **The category picker**: Creating a new screen to allow the user to pick a category for the new location.

The screen

The Tag Location screen is a regular table view controller with static cells. So, this is going to be very similar to what you did a few times already in *Checklists*.

The finished Tag Location screen will look like this:



The Tag Location screen

The description cell — the empty area above the Category cell — at the top contains a `UITextView` for text. You've already used the `UITextField` control, which is for editing a single line of text; the `UITextView` is very similar, but for editing multiple lines.

Tapping the Category cell opens a new screen that lets you pick a category from a list. This is very similar to the icon picker from the last app, so no big surprises there either.

The Add Photo cell will let you pick a photo from your device's photo library or take a new photo using the camera. You'll skip this feature for now and build that later on. Let's not get ahead of ourselves and try to do too much at once!

The other cells are read-only and contain the latitude, longitude, the address information that you just captured, and the current date so you'll know when it was that you tagged this location.

> **Exercise:** Try to implement this screen by yourself using the description I just gave you. You don't have to make the Category and Add Photo buttons work yet. Yikes, that seems like a big job! It sure is, but you should be able to pull this off. This screen doesn't do anything you haven't done previously. So if you feel brave, go ahead!

The new view controller

➤ Add a new file to the project using the **Swift File** template. Name the file **LocationDetailsViewController**.

You know what's next: create a class, create outlets and connect them to the controls on the storyboard. In the interest of saving time, I'll just give you the code that you're going to end up with.

➤ Replace the contents of **LocationDetailsViewController.swift** with the following:

```
import UIKit

class LocationDetailsViewController: UITableViewController {
  @IBOutlet var descriptionTextView: UITextView!
  @IBOutlet var categoryLabel: UILabel!
  @IBOutlet var latitudeLabel: UILabel!
  @IBOutlet var longitudeLabel: UILabel!
  @IBOutlet var addressLabel: UILabel!
  @IBOutlet var dateLabel: UILabel!

  // MARK: - Actions
  @IBAction func done() {
    navigationController?.popViewController(animated: true)
  }

  @IBAction func cancel() {
    navigationController?.popViewController(animated: true)
  }
}
```

Nothing special here – just a bunch of outlet properties and a couple of action methods that go back to the previous view in the navigation stack.

➤ In the storyboard, select the Current Location View Controller (the Tag Scene), and choose **Editor ▸ Embed In ▸ Navigation Controller** from Xcode's menu bar to put the view controller inside a new navigation controller. This sets up all the views on that particular tab of the tab view controller to be part of a navigation stack.

➤ Drag a new **Table View Controller** on to the canvas and put it next to the Tag Scene.


➤ In the **Identity inspector**, change the **Class** attribute of the table view controller to **LocationDetailsViewController** to link it with the Swift file you just created.

➤ **Control-drag** from the **Tag Location** button on the Tag Scene to the new view controller and create a **Show** segue. Give the segue the identifier **TagLocation**.

➤ Change the title of the Navigation Item on the Location Details View Controller to **Tag Location**.

➤ Switch the table Content to **Static Cells** and its Style to **Grouped**.

The storyboard should now looks like this:



The Tag Location screen in the storyboard

Navigation bar hiding

You'll notice that the Tag Scene – the Current Location View Controller – now has a navigation bar with no title - it might not be easy to see but it's the white area at the top :] This is because it is now embedded in a Navigation Controller. You can either set the title and/or make it a large title. Or, you can hide the navigation bar altogether for the first view.

For this particular app design, I think having no titles would look the best. So, you now have to hide the navigation bar at runtime for only the Tag Scene. How do you do it?

Simple enough. It's just a code change :]

➤ Switch to **CurrentLocationViewController.swift** and add a new `viewWillAppear` implementation:

```
override func viewWillAppear(_ animated: Bool) {
  super.viewWillAppear(animated)
  navigationController?.isNavigationBarHidden = true
}
```

All you do is ask the navigation controller to hide the navigation bar when this particular view is about to appear. Simple as that :]

➤ Run the app and make sure the Tag Location button works.

Do you notice an issue when you switch to the Location Details View Controller via the Tag Location button?

The navigation bar on the new screen is hidden as well! Can you guess why this is?

Yep, it's because you hid the navigation controller's navigation bar in the previous screen :] That setting is not a per-screen setting. It affects the navigation bar for the navigation controller from that point onwards for all views displayed by the navigation controller.

So how do you fix it? Simple enough, ask the navigation controller to start showing the navigation bar as soon as you exit the view where you hide the navigation bar. And there is a handy `viewWillDisappear` method that you can override in `UIViewController` that's just the place for this kind of code.

➤ Add the following method to **CurrentLocationViewController.swift**:

```
override func viewWillDisappear(_ animated: Bool) {
  super.viewWillDisappear(animated)
  navigationController?.isNavigationBarHidden = false
}
```

You simply reverse what you did previously in `viewWillAppear` by asking the navigation controller to show the navigation bar each time the current view is about to disappear from view — usually, either because another view appeared on top of it, or because this view was dismissed in order to go back to a previous view.

➤ Run the app again and make sure that the navigation flow, and the showing/hiding of the navigation bar, works correctly.

Add navigation buttons

Of course, the new screen won't do anything useful yet. Let's add some buttons.

➤ Drag a **Bar Button Item** on to the left slot where the Back button currently is. Make it a **Cancel** button and connect it to the **cancel** action. If you're using the Connections inspector, the thing that you're supposed to connect is the Bar Button Item's **selector**, under Sent Actions.

> **Note:** A navigation bar usually has left and right navigation item positions where you can drag either bar button items or views on to. If you are unable to drag an item on to the left/right positions of a navigation bar and the scene has a navigation bar, it is possible that the scene is missing a Navigation Item. Then, you have to first drag a Navigation Item on to the scene.

➤ Also drag a **Bar Button Item** on to the right slot. Set both the **Style** and **System Item** attributes to **Done**, and connect it to the **done** action.

➤ Run the app again and make sure you can close the Tag Location screen from both buttons after you've opened it.

Make the cells

There will be three sections in this table view:

1. The description text view and the category cell. These can be changed by the user.
2. The photo. Initially this cell says Add Photo but once the user has picked a photo, you'll display the actual photo inside the cell. It's good to have that in a section of its own.
3. The latitude, longitude, address, and date rows. These are read-only values.


➤ Open the storyboard. Select the table view and go to the **Attributes inspector**. Change the **Sections** field from 1 to 3.

When you do this, the contents of the first section are automatically copied to the new sections. That isn't quite what you want. So, you'll have to remove some rows here and there. The first section will have 2 rows, the middle section will have just 1 row, and the last section will have 4 rows.

➤ Select one cell in the first section and delete it. If it won't delete, make sure you selected the whole Table View Cell and not its Content View. The Document Outline can be very useful here.

➤ Delete two cells from the middle section.

➤ Select the last Table View Section object — use the Document Outline for easy selection — and in the **Attributes inspector** set its **Rows** to 4.




Adding a row to a table view section

Alternatively, you can drag a new Table View Cell from the Object Library on to the section.

The right detail cells

The second row from the first section, and the first, second and fourth rows in the last section will all use a standard cell style.

➤ Select these cells — you can select multiple items via the Document Outline by Command-clicking — and set their **Style** attribute to **Right Detail**.



The cells with the Right Detail style

The labels in these standard cell styles are regular `UILabels`. So, you can select them and change their properties.

➤ Change the titles for the labels on the left, from top to bottom to: **Category**, **Latitude**, **Longitude**, and **Date**.

If Xcode moves the label when you type into it or cuts off the text, then change the cell style to Left Detail and back again to Right Detail. That seems to fix it.

➤ Drag a new **Label** into the cell in the middle section – the one that's still empty. You cannot use a standard cell style for this cell. So, you'll design it yourself. Name this label **Add Photo**.


Later on you'll also add an image view to this cell.

➤ You'll notice that the new label is much bigger than the labels from the Right Detail cell style. Set the font of the label to **System**, size **12**, so that the sizes match.

➤ Add a **left** Auto Layout Constraint — with a value of **0**, and have **Constrain to margins** checked — and also add a constraint to center **Vertically in Container**.

This will add some of the Auto Layout constraints you need to position the label, but not all of them. You will notice that you have a warning still at this point — this is due to the label not having a right constraint. Since we'll be adding an image to this cell later and that would require changes to the right constraint, we will live with the warning for the time being …

The table should now look like this:



The labels in the Tag Location screen

> **Note:** You're going to make a bunch of changes that are the same for each cell. For some of these, it is easier if you select all the cells at once and then change the setting. That will save you some time.
>
> Unfortunately, some menu items and options are grayed out when you have a multiple selection, so you'll still have to change some of the settings for each cell individually.

Tappable cells

Only the Category and Add Photo cells should handle taps, so you have to set the cell selection color to None on the other cells.

➤ Select all the cells except Category and Add Photo. In the **Attributes inspector**, set **Selection** to **None**.

➤ Select the Category and Add Photo cells and set **Accessory** to **Disclosure Indicator**.

The address cell

The empty cell in the last section is for the Address label. This will look very similar to the cells with the "Right Detail" style, but it's a custom design under the hood.

➤ Drag a new **Label** into that cell and set its title to **Address**.

➤ Add a **left** Auto Layout constraint (of **0**) to the label and also center **Vertically in Container**.

➤ Drag another **Label** into the same cell and title it **Detail**.

➤ Add a **right** Auto Layout constraint (of **0**) to the label and again, center **Vertically in Container**.

➤ Control-drag from the Address label to the Detail label and select **Horizontal Spacing** from the pop up. This will set up the current spacing between the two items as the default spacing. You don't want that since you want the Detail label to display an address and so it should have room to breath.


➤ Select the Address label, switch to the Size inspector, select the trailing space constraint and edit the constraint so that the **Constant** is **>= 8** (instead of =). Note that you have to change the operator as well as the numeric constant value.

➤ Make sure the font of both labels is **System**, size **12**.

➤ Change the **Alignment** of the Detail label to right-aligned.

The Detail label is special. Most likely the street address will be too long to fit in that small space. So, you'll configure this label to have a variable number of lines. This requires a bit of programming in the view controller to make it work, but you also have to set up this label's attributes properly.

➤ In the **Attributes inspector** for the Detail label, set **Lines** to **0** and **Line Break** to **Word Wrap**. When the number of lines is 0, the label will resize vertically to fit all the text that you put into it, which is exactly what you need.




The address detail label can have multiple lines

The description cell

So far, you've left the cell at the top empty. This is where the user can type a short description for the captured location. Currently, there is not much room to type anything. So first, you'll make the cell larger.

➤ Click on the top cell to select it, then go into the **Size inspector** and type **88** into the **Row Height** field.



Changing the height of a row

You can also drag the cell to this new height by using the sizing handle (the tiny white square) at its bottom, but I prefer to simply type in the new value.

The reason I chose 88 is that quite a few iOS screen elements have a size of 44 points. The navigation bar is 44 points high, regular table view cells are 44 points high, and so on. Choosing 44 or a multiple of it keeps the UI looking balanced.

➤ Drag a **Text View** (not a Text Field) into the cell and add Auto Layout constraints for **left**: 0, **top**: 0, **right**: 0, and **bottom**: 0, with **Constrain to margins** checked.


➤ By default, Interface Builder puts a whole bunch of Latin placeholder text (Lorem ipsum dolor, etc) into the text view. Replace that text with **(Description goes here)**. The user will never see that text, but it's handy to remind yourself what this view is for.

➤ Set the font to **System**, size **12**.

One more thing to do, and then the layout is complete. Because the top cell doesn't have a label to describe what it does — and the text view will initially be empty as well — the user may not know what it is for.

There really isn't any room to add a label in front of the text view, as you've done for the other rows. So, let's add a header to the section. Table view sections can have a header and footer, and these can either be text or complete views with controls of their own.


➤ Select the top-most Table View Section and in its **Attributes inspector** type **Description** into the **Header** field:



Giving the section a header

That's the layout done.

The Tag Location screen should look like this in the storyboard:



The finished design of the Tag Location screen


Now you can actually make the screen do stuff.

Connecting outlets

➤ Connect the Detail labels and the text view to their respective outlets. It should be obvious which one goes where.

Tip: Control-drag from the round yellow icon that represents the view controller to each of the labels. That's the quickest way.

If you look at the **Connections inspector** for this view controller, you should see the following:



The connections of the Location Details View Controller

➤ Run the app to test whether everything works.

Of course, the screen still says "Detail" in the labels instead of the location's actual coordinates and address because you haven't passed in any data yet. Time to fix that, you reckon?

Display location info

➤ Add two new properties to **LocationDetailsViewController.swift**:

```
var coordinate = CLLocationCoordinate2D(
  latitude: 0,
  longitude: 0)
var placemark: CLPlacemark?
```

You've seen the `CLPlacemark` class before. It contains the address information — street name, city name, and so on — that you've obtained through reverse geocoding. This is an optional because there is no guarantee that the geocoder finds an address for the given coordinates.

`CLLocationCoordinate2D` is new. This contains the latitude and longitude from the `CLLocation` object that you received from the location manager. You only need the latitude and longitude, so there's no point in sending along the entire `CLLocation` object. The `coordinate` is not an optional, so you must give it an initial value.

> **Exercise:** Why is coordinate not an optional?

Answer: You cannot tap the Tag Location button unless GPS coordinates have been found. So, you'll never open the `LocationDetailsViewController` without a valid set of coordinates.

During the segue from the Current Location screen to the Tag Location screen you will fill in these two properties, and then the Tag Location screen can put these values into its labels.

Xcode isn't happy with the two lines you just added. It complains about "Cannot find 'CLLocationCoordinate2D' in scope" and "CLPlacemark". That means Xcode does not know anything about these types yet.

That's because they are part of the Core Location framework – and before you can use anything from a framework, you first need to import it.

➤ Add the following import to the file:

```
import CoreLocation
```

Now Xcode's error messages should disappear after a second or two. If they don't, use ⌘+**B** to build the app again.

★ ★ ★

Structs

Unlike the objects you've seen before, `CLLocationCoordinate2D` is not a class, instead, it is a **struct** – short for structure. Structs are like classes, but a little less powerful. They can have properties and methods, but unlike classes, they cannot inherit from one another.

The definition for `CLLocationCoordinate2D` is as follows:

```
struct CLLocationCoordinate2D {
  var latitude: CLLocationDegrees
  var longitude: CLLocationDegrees
}
```

This struct has two fields, `latitude` and `longitude`. Both these fields have the data type `CLLocationDegrees`, which is a synonym for `Double`:

```
typealias CLLocationDegrees = Double
```

As you probably remember from before, the `Double` type is one of the primitive types built into Swift. It's like a `Float` but with higher precision.

Don't let these synonyms confuse you; `CLLocationCoordinate2D` is basically this:

```
struct CLLocationCoordinate2D {
  var latitude: Double
  var longitude: Double
}
```

The reason the designers of Core Location used `CLLocationDegrees` instead of `Double` is that "CL Location Degrees" tells you what this type is intended for: it stores the degrees of a location from the Core Location framework.

Underneath the hood it's a `Double`, but as a user of Core Location all you need to care about when you want to store latitude or longitude is that you can use the `CLLocationDegrees` type. The name of the type adds meaning.

UIKit and other iOS frameworks also use structs regularly. Common examples are `CGPoint` and `CGRect`. In fact, `Array` and `Dictionary` are also structs.

Structs are more lightweight than classes. If you just need to pass around a set of values, it's often easier to bundle them into a struct and pass that struct around — and that is exactly what Core Location does with coordinates.

★ ★ ★

Pass data to the details view

Back to the new properties that you just added to `LocationDetailsViewController`. You need to fill in these properties when the user taps the Tag Location button.

➤ Switch to **CurrentLocationViewController.swift** and add the following code:

```
// MARK: - Navigation
override func prepare(for segue: UIStoryboardSegue, sender:
Any?) {
  if segue.identifier == "TagLocation" {
    let controller = segue.destination as!
LocationDetailsViewController
    controller.coordinate = location!.coordinate
    controller.placemark = placemark
  }
}
```

You've seen how this works before. You use some casting magic to obtain the proper destination view controller and then set its properties. Now when the segue is performed, the coordinate and address are passed on to the Tag Location screen.

Because `location` is an optional, you need to unwrap it before you can access its `coordinate` property. It's perfectly safe to force unwrap at this point because the Tag Location button that triggers the segue won't be visible unless a location is found. At this point, `location` will never be `nil`.

The `placemark` variable is also an optional, but so is the `placemark` property on `LocationDetailsViewController`, so you don't need to do anything special here. You can always assign the value of one optional to another optional without problems.

Now that you have the values, you need to display them in the Tag Location screen.

Display information on the Tag Location screen

`viewDidLoad()` is a good place to display the passed in values on screen.

➤ Add the following code to **LocationDetailsViewController.swift**:

```
override func viewDidLoad() {
  super.viewDidLoad()

  descriptionTextView.text = ""
  categoryLabel.text = ""

  latitudeLabel.text = String(
    format: "%.8f",
    coordinate.latitude)
  longitudeLabel.text = String(
    format: "%.8f",
    coordinate.longitude)
  if let placemark = placemark {
    addressLabel.text = string(from: placemark)
  } else {
    addressLabel.text = "No Address Found"
  }

  dateLabel.text = format(date: Date())
}
```

This simply sets a value for every label. It uses two helper methods that you haven't defined yet: `string(from:)` to format the `CLPlacemark` object into a string, and `format(date:)` to do the same for a `Date` object.

➤ Add the `string(from:)` method:

```
// MARK: - Helper Methods
func string(from placemark: CLPlacemark) -> String {
  var text = ""
  if let tmp = placemark.subThoroughfare {
    text += tmp + " "
  }
  if let tmp = placemark.thoroughfare {
    text += tmp + ", "
  }
  if let tmp = placemark.locality {
    text += tmp + ", "
  }
  if let tmp = placemark.administrativeArea {
    text += tmp + " "
  }
  if let tmp = placemark.postalCode {
    text += tmp + ", "
```

```
    }
    if let tmp = placemark.country {
      text += tmp
    }
    return text
  }
```

This is fairly straightforward. It is similar to how you formatted the placemark on the main screen, except that you also include the country here.

> **Note:** You might have noticed the `// MARK` comments all over the previous sections of code in this chapter. You already know what the `// MARK` comment does. So, I'm not going to explain that again.
>
> You can feel free to leave the comments out when you type in your own code, but personally, I like to organize my code into identifiable sections as I've done here so that I can navigate my code easily. It's totally up to you whether you follow what I do, create an organization style of your own, or use no organization at all :]

Date formatting

To format the date, you'll use a `DateFormatter` object. You've seen this class at work in the previous app. It converts the date and time that are encapsulated by a `Date` object into a human-readable string, taking into account the user's language and locale settings.

For *Checklists* you created a new instance of `DateFormatter` every time you wanted to convert a `Date` to a string. However, `DateFormatter` is a relatively expensive object to create. In other words, it takes a while to initialize this object. If you do that many times over, then it may slow down your app and drain the phone's battery faster.

It is better to create `DateFormatter` just once and then re-use that same object over and over. The trick is that you won't create the `DateFormatter` object until the app actually needs it. This principle is called **lazy loading** and it's a very important pattern for iOS apps — the work that you don't do won't cost any battery power.

In addition, you'll only ever create one instance of `DateFormatter`. The next time you need to use `DateFormatter`, you'll re-use the existing one.

To pull this off you'll use a *private global* constant. That's a constant that lives outside of the `LocationDetailsViewController` class (global) but it is only visible inside the **LocationDetailsViewController.swift** file (private).

➤ Add the following to the top of **LocationDetailsViewController.swift**, in between the `import` and `class` lines:

```
private let dateFormatter: DateFormatter = {
  let formatter = DateFormatter()
  formatter.dateStyle = .medium
  formatter.timeStyle = .short
  return formatter
}()
```

What is going on here? You're creating a new constant named `dateFormatter` of type `DateFormatter`, that much should be obvious. This constant is `private` so it cannot be used outside of this Swift file — remember the discussion about `private` and `public` attributes in the previous chapter?

You're also giving `dateFormatter` an initial value, but what follows the = is not an ordinary value — it looks like a bunch of source code in between `{ }` brackets. That looks like a closure, doesn't it? That's because it *is* a closure.

Normally, you'd create a new object like this:

```
private let dateFormatter = DateFormatter()
```

But to initialize the date formatter it's not enough to just make an instance of `DateFormatter`, you also want to set the `dateStyle` and `timeStyle` properties of this instance.

To create the object and set its properties in one go, you can use a closure:

```
private let dateFormatter: DateFormatter = {
  // the code that sets up the DateFormatter object
  return formatter
}()
```

The closure contains the code that creates and initializes the new `DateFormatter` object, and then returns it. This returned value is what gets put into `dateFormatter`.

The trick to making this work is the `()` at the end. Closures are like functions, and to perform the code inside the closure you call it just like you'd call a function.

> **Note:** If you leave out the `()`, Swift thinks you're assigning the closure itself to `dateFormatter` — in other words, `dateFormatter` will contain a block of code, not an actual `DateFormatter` object. That's not what you want.
>
> Instead, you want to assign the *result* of that closure to `dateFormatter`. To make that happen, you use the `()` to perform or **evaluate** the closure — this runs the code inside the closure and returns a `DateFormatter` object.

Using a closure to create and configure an object all at once is a nifty trick; you can expect to see this often in Swift programs.

In Swift, globals are always created in a lazy fashion, which means the code that creates and sets up this `DateFormatter` object isn't performed until the very first time the `dateFormatter` global is used in the app.

That happens inside the new `format(date:)` method.

➤ Add the new method — this code goes inside the `class` and I would generally put it in the helper methods section created by my previous `// MARK` comment, for organizational purposes:

```
func format(date: Date) -> String {
  return dateFormatter.string(from: date)
}
```


How simple is that? It just asks the `DateFormatter` to turn the `Date` into a `String` and returns that.

> **Exercise:** How can you verify that the date formatter is really only created once?

Answer: Add a `print()` just before the `return formatter` line in the closure. This `print()` text should appear only once in the Xcode Console.

➤ Run the app. Choose the Apple location from the Simulator's Features menu. Wait until the street address is visible and then press the Tag Location button.

The coordinates, address and date are all filled in:



The Address label doesn't fit well

Sometimes, depending on the length of the address and the width of the screen, you might run into a situation like the above, where the address seems to be having some trouble fitting in :]

Content Compression Resistance

You earlier configured the label to fit multiple lines of text, but the problem is that the two labels in the address row don't know how to get along with each other — the detail label is too full of itself and encroaches on the space of the Address label.

The solution is simple enough — Content Compression Resistance. Quite a mouthful, and not very illuminating, right?

Let me try to shed some light.


➤ Select the **Address** label, switch to the **Size inspector** and scroll to the bottom. You should see a section named **Content Compression Resistance Priority**.

This section determines how easily the selected control allows other controls to push it (and its content) out of the way to present their own content. The higher the priority, the less likely this control is to be pushed out of the way.

All controls have a horizontal and vertical content compression resistance value set and this is by default set to 750. All we need to do is increase the Address label's vertical content resistance priority so that it doesn't get pushed around.

➤ Change the **Horizontal** value to **751**.


➤ Run the app. Now the reverse geocoded address should display correctly without cutting off the Address label. Try it out with a few different locations.



The label is not cut off by the address

The category picker

When the user taps the Category cell, the app should show a list of category names:



The category picker

The view controller class

This is a new screen, so you need a new view controller. The way this works is very similar to the icon picker from *Checklists*. I'm just going to give you the source code and tell you how to hook it up.

➤ Add a new file to the project named **CategoryPickerViewController.swift**.

➤ Replace the contents of **CategoryPickerViewController.swift** with:

```
import UIKit

class CategoryPickerViewController: UITableViewController {
  var selectedCategoryName = ""

  let categories = [
    "No Category",
    "Apple Store",
    "Bar",
    "Bookstore",
    "Club",
    "Grocery Store",
    "Historic Building",
    "House",
    "Icecream Vendor",
    "Landmark",
```

```
    "Park"
  ]

  var selectedIndexPath = IndexPath()

  override func viewDidLoad() {
    super.viewDidLoad()

    for i in 0..<categories.count {
      if categories[i] == selectedCategoryName {
        selectedIndexPath = IndexPath(row: i, section: 0)
        break
      }
    }
  }

  // MARK: - Table View Delegates
  override func tableView(
    _ tableView: UITableView,
    numberOfRowsInSection section: Int
  ) -> Int {
    return categories.count
  }

  override func tableView(
    _ tableView: UITableView,
    cellForRowAt indexPath: IndexPath
  ) -> UITableViewCell {
    let cell = tableView.dequeueReusableCell(
      withIdentifier: "Cell",
      for: indexPath)

    let categoryName = categories[indexPath.row]
    cell.textLabel!.text = categoryName

    if categoryName == selectedCategoryName {
      cell.accessoryType = .checkmark
    } else {
      cell.accessoryType = .none
    }
    return cell
  }

  override func tableView(
    _ tableView: UITableView,
    didSelectRowAt indexPath: IndexPath
  ) {
    if indexPath.row != selectedIndexPath.row {
      if let newCell = tableView.cellForRow(at: indexPath) {
        newCell.accessoryType = .checkmark
      }
      if let oldCell = tableView.cellForRow(
        at: selectedIndexPath) {
```

```
          oldCell.accessoryType = .none
        }
        selectedIndexPath = indexPath
      }
    }
  }
```

There's nothing special going on here. This is a table view controller that shows a list of category names. The table gets its rows from the `categories` array.

The only thing worth noting is the `selectedIndexPath` instance variable. When the screen opens, it shows a checkmark next to the currently selected category. This comes from the `selectedCategoryName` property, which is filled in when you segue to this screen.

When the user taps a row, you want to remove the checkmark from the previously selected row and put it in the new row.

In order to be able to do that, you need to know which row is the currently selected one. You can't use `selectedCategoryName` for this because that is a string, not a row number. Therefore, you first need to find the row number — or index-path — for the selected category name.

That happens in `viewDidLoad()`. You loop through the array of categories and compare the name of each category to `selectedCategoryName`. If they match, you create an index-path object and store it in the `selectedIndexPath` variable. Once a match is found, you can `break` out of the loop because there's no point in looping through the rest of the categories.

Now that you know the row number, you can remove the checkmark for this row in `tableView(_:didSelectRowAt:)` when another row gets tapped.

It's a bit of work for such a small feature, but in a good app it's the details that matter.

There are several different ways of looping through the contents of an array.

You've already seen `for...in`, which is used as follows:

```
  for category in categories {
```

This puts the name of each category into a temporary constant named `category`.

However, in order to make the index-path object, you don't want the name of the category but the index of that category in the array. So you'll have to loop in a slightly different fashion:

```
for i in 0..<categories.count {
  let category = categories[i]
  . . .
}
```

Thanks to the half-open range operator `..<`, `i` is a number that increments from 0 to `categories.count - 1`. This is a very common pattern for looping through an array if you want to have the index as well.

Another way to do this is to use the `enumerated()` method, for which you'll see an example when you get to the next app. As a quick preview, this is how you'd use it:

```
for (i, category) in categories.enumerated() {
  . . .
}
```

The storyboard scene

➤ Open the storyboard and drag a new **Table View Controller** on to the canvas. Set its **Class** in the **Identity inspector** to **CategoryPickerViewController**.


➤ Change the **Style** of the prototype cell to **Basic**, and give it the re-use identifier **Cell**.

➤ **Control-drag** from the Category cell on the Location Details View Controller to this new view controller and choose **Selection Segue - Show**.

➤ Give the segue the identifier **PickCategory**.

The Category Picker View controller now has a navigation bar at the top. You could change its title to "Choose Category", but Apple recommends that you do not give view controllers a title if their purpose is obvious.

This helps to keep the navigation bar uncluttered.



The category picker in the storyboard

That's enough for the storyboard. Now all that remains is to handle the segue.

The Segue

➤ Switch back to **LocationDetailsViewController.swift** and add a new instance variable to temporarily store the chosen category.

```
var categoryName = "No Category"
```

Initially you set the category name to "No Category", which is the category at the top of the list in the category picker.

➤ Change `viewDidLoad()` to put `categoryName` into the label:


```
override func viewDidLoad() {
  . . .
  categoryLabel.text = categoryName      // change this line
  . . .
```

➤ Finally, add the segue handling code:

```
// MARK: - Navigation
override func prepare(for segue: UIStoryboardSegue, sender:
Any?) {
  if segue.identifier == "PickCategory" {
    let controller = segue.destination as!
CategoryPickerViewController
    controller.selectedCategoryName = categoryName
  }
}
```

This simply sets the `selectedCategoryName` property of the category picker. And with that, the app has categories.

➤ Run the app and play with the category picker.



Selecting a new category

Hmm, it doesn't seem to work very well. You can choose a category, but the screen doesn't close when you tap a row. When you press the back button, the category you picked isn't shown on the parent screen.

Exercise: Which piece of the puzzle is missing?


Answer: The `CategoryPickerViewController` currently does not have a way to communicate back to the `LocationDetailsViewController` about the user selection.

I hope that at this point you're thinking, "Of course, dummy! You forgot to give the category picker a delegate protocol. That's why it cannot send any messages to the other view controller."

If so, awesome! You're getting the hang of this. A delegate protocol is a fine solution indeed, but I want to show you a handy storyboarding feature that can accomplish the same thing with less work: **unwind segues**.

The unwind segue

In case you were wondering what the orange "Exit" icons in the storyboard are for, you now have your answer: unwind segues.



The Exit icon

Where a regular segue is used to open a new screen, an unwind segue closes the active screen. Sounds simple enough. However, making unwind segues is not very intuitive.

The orange Exit icons don't appear to do anything. Try Control-dragging from the prototype cell to the Exit icon, for example. It won't let you make a connection.

First, you have to add a special type of action method to the *destination* of the unwind segue.

➤ In **LocationDetailsViewController.swift**, add the following method:

```
@IBAction func categoryPickerDidPickCategory(
  _ segue: UIStoryboardSegue
) {
  let controller = segue.source as! CategoryPickerViewController
  categoryName = controller.selectedCategoryName
  categoryLabel.text = categoryName
}
```


You can see that this is an action method because it has the `@IBAction` annotation. What's different from a regular action method is the parameter, a `UIStoryboardSegue` object.

Normally, if an action method has a parameter, it points to the control that triggered the action, such as a button or slider. But in order to make an unwind segue, you need to define an action method that takes a `UIStoryboardSegue` parameter.

What happens inside the method is pretty straightforward. You look at the view controller that sent the segue (the `source`), which of course is the `CategoryPickerViewController`, and then read the value of its `selectedCategoryName` property. That property contains the category that the user picked.


Now, to use this new method in the storyboard...

➤ Open the storyboard. **Control-drag** from the prototype cell in the Category Picker scene to the Exit button. This time it allows you to make a connection:



Control-dragging to the Exit icon to make an unwind segue

From the popup choose **Selection Segue - categoryPickerDidPickCategory:**, the name of the unwind action method you just added.



The popup lists the unwind action methods

If Interface Builder doesn't let you make a connection, then make sure you're really Control-dragging from the Cell, not from its Content View or the label.

Now when you tap a cell in the category picker, the screen closes and this new method is called.

➤ Run the app to try it out.

That was easy! Well, not quite. Unfortunately, the chosen category is ignored...

That's because `categoryPickerDidPickCategory()` looks at the `selectedCategoryName` property, but that property isn't set anywhere in your code yet.

You need some kind of mechanism that is invoked when the unwind segue is triggered, at which point you can fill in the `selectedCategoryName` based on the row that was tapped.

What might such a mechanism be called? `prepare(for:sender:)`, of course! This works for segues in both directions.


➤ Add the following method to **CategoryPickerViewController.swift**:

```
// MARK: - Navigation
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
  if segue.identifier == "PickedCategory" {
    let cell = sender as! UITableViewCell
    if let indexPath = tableView.indexPath(for: cell) {
      selectedCategoryName = categories[indexPath.row]
    }
  }
}
```

This looks at the selected index-path and puts the corresponding category name into the `selectedCategoryName` property.

This logic assumes the unwind segue is named "PickedCategory", so you still have to set an identifier on the unwind segue.

Unfortunately, there is no visual representation of that unwind segue in the storyboard. There is no nice, big arrow that you can click on. To select the unwind segue you have to locate it in the Document Outline:



You can find unwind segues in the Document Outline

➤ Select the unwind segue and go to the **Attributes inspector**. Give it the identifier **PickedCategory**.

➤ Run the app. Now the category picker should work properly. As soon as you tap the name of a category, the screen closes and the new category name is displayed.

Unwind segues are pretty cool and are often easier than using a delegate protocol, especially for simple picker screens such as this one.

You can find the project files for this chapter under **25-Tag-location-screen** in the Source Code folder.

Chapter 26: Adding Polish

By Fahim Farook

Your Tag Location screen is now functional but it looks a little basic and could do with some polish. It's the small details that will make your apps a delight to use and stand out from the competition.

In this chapter, you will learn the following:

- **Improve the user experience**: How to improve the user experience by adding tiny tweaks to your app which gives it some polish.
- **Add a HUD**: How to add a HUD (**H**eads **U**p **D**isplay) to your app to provide a quick, animated status update.
- **Handle the navigation**: How to continue the navigation flow after displaying the HUD.

Improve the user experience

Take a look at the design of the cell with the Description text view:



There is a margin between the text view and the cell border

There is a margin between the text view and the cell border, but because the background of both the cell and the text view are white, the user cannot see where the text view begins or ends.

It is possible to tap on the cell but be just outside the text view area. That is annoying when you want to start typing: you think that you're tapping in the text view, but the keyboard doesn't appear.

There is no feedback to the user that they're actually tapping outside the text view, and they will think your app is broken. In my opinion, deservedly so.

Keyboard activation for cells

You'll have to make the app a little more forgiving. When the user taps anywhere inside that first cell, the text view should activate, even if the tap wasn't on the text view itself.

➤ Add the following table view delegate methods to **LocationDetailsViewController.swift**:

```
// MARK: - Table View Delegates
override func tableView(
  _ tableView: UITableView,
  willSelectRowAt indexPath: IndexPath
) -> IndexPath? {
  if indexPath.section == 0 || indexPath.section == 1 {
    return indexPath
  } else {
    return nil
  }
}

override func tableView(
```

```
    _ tableView: UITableView,
    didSelectRowAt indexPath: IndexPath
  ) {
    if indexPath.section == 0 && indexPath.row == 0 {
      descriptionTextView.becomeFirstResponder()
    }
  }
```

The `tableView(_:willSelectRowAt:)` method limits taps to just the cells from the first two sections. Recall that `||` means *or*. So, if the section number equals 0 *or* when it equals 1, you accept the tap on the cell. The third section only has read-only labels — it doesn't need to allow taps.

The `tableView(_:didSelectRowAt:)` method handles the actual taps on the rows. You don't need to respond to taps on the Category or Add Photo rows as these cells are connected to segues.

But if the user taps on the first row of the first section — the row with the description text view — then you will give the input focus to the text view. Here you use &&, meaning *and*, to make sure the tap is in the first section *and* also on the first row of that section.

➤ Try it out. Run the app and click or tap somewhere along the edges of the first cell. Any tap inside that first cell should now make the text view active and bring up the keyboard — remember that on the Simulator you may need to press **⌘+K** to make the keyboard visible.

Anything you can do to make screens less frustrating to use, is worth putting in the effort!

Speaking of the text view, once you've activated it, there's no way to get rid of the keyboard! And because the keyboard takes up half of the screen, that can be a bit annoying.

Deactivate the keyboard

It would be nice if the keyboard disappeared after you tapped anywhere else on the screen. As it happens, that is not so hard to implement.

➤ Add the following to the end of `viewDidLoad()` in **LocationDetailsViewController.swift**:

```
  // Hide keyboard
  let gestureRecognizer = UITapGestureRecognizer(
    target: self,
```

```
    action: #selector(hideKeyboard))
  gestureRecognizer.cancelsTouchesInView = false
  tableView.addGestureRecognizer(gestureRecognizer)
```

A **gesture recognizer** is a very handy object that can recognize touch-based actions like taps, swipes, pans and pinches. You simply create the gesture recognizer object, give it a method to call when that particular gesture has been observed to take place, and add the recognizer object to a view.

You're using a `UITapGestureRecognizer`, which as the name implies, recognizes simple taps. Notice the `#selector()` keyword again:

```
. . . action: #selector(hideKeyboard)) . . .
```

You use this syntax to tell the `UITapGestureRecognizer` that it should call the method named by `#selector()` whenever the gesture happens.

This pattern is known as **target-action** and you've already used it whenever you've connected `UIButtons`, `UIBarButtonItems`, and other controls to action methods.

The "target" is the object receiving the message, which is often `self`, and "action" is the message to send.

Here you've chosen the message **hideKeyboard** to be sent when a tap is recognized anywhere in the table view — so, you have to implement the method and respond to that message. Also, remember that selectors have their root in Objective-C and so, any method which is called via a selector has to be accessible from Objective-C.)

➤ Add the `hideKeyboard()` method to **LocationDetailsViewController.swift**:

```
  @objc func hideKeyboard(
    _ gestureRecognizer: UIGestureRecognizer
  ) {
    let point = gestureRecognizer.location(in: tableView)
    let indexPath = tableView.indexPathForRow(at: point)

    if indexPath != nil && indexPath!.section == 0 &&
    indexPath!.row == 0 {
      return
    }
    descriptionTextView.resignFirstResponder()
  }
```

Whenever the user taps somewhere in the table view, the gesture recognizer calls this method. Conveniently, it also passes a reference to itself as a parameter, which lets you ask `gestureRecognizer` where the tap happened.

The `gestureRecognizer.location(in:)` method returns a `CGPoint` value indicating the tap position. `CGPoint` is a common struct that you see all the time in UIKit. It contains two fields, `x` and `y`, that describe a position on screen.

Using this `CGPoint`, you ask the table view which index-path is currently displayed at that position. This is important because you obviously don't want to hide the keyboard if the user tapped in the row with the text view! If the user tapped anywhere else, you hide the keyboard.

> **Exercise**. Does the logic in the `if` statement make sense to you? Explain how this works.

Answer: It is possible that the user tapped inside the table view, but not on a cell — for example, somewhere in between two sections or on the section header. In that case, `indexPath` will be `nil`, making this an optional (of type `IndexPath?`). And to use an optional, you need to unwrap it somehow, either with `if let` or with `!`.

You only want to hide the keyboard if the index-path for the tap is not section 0, row 0, which is the cell with the text view. If the user did tap that particular cell, you bail out of `hideKeyboard()` with the `return` statement before the code reaches the call to `resignFirstResponder()`.

> **Note:** You don't want to force unwrap an optional if there's a chance it might be `nil` or you risk crashing the app. Force unwrapping `indexPath!.section` and `indexPath!.row` may look dangerous here, but it is guaranteed to work thanks to the **short-circuiting** behavior of the && operator.
>
> If `indexPath` equals `nil`, then everything after the first && is simply ignored. The condition can never become true anymore if one of the terms is false. So when the app gets to look at `indexPath!.section`, you know that the value of `indexPath` is not `nil` at that point.

An alternative way to write this logic is:

```
if indexPath == nil || !(indexPath!.section == 0 &&
  indexPath!.row == 0) {
  descriptionTextView.resignFirstResponder()
}
```

Can you wrap your head around that? Here, the `if` statement checks for the exact opposite. The `&&` and `||` operators are each other's opposite in Boolean logic and you can often flip the meaning of a condition around by turning `&&` into `||` by introducing the `!` not operator.

You don't need to worry about this so early on in your programming career, but at some point you'll have to learn these Boolean logic rules. They can be mind-benders!

Of course, you can also use `if let` to safely unwrap `indexPath`. So a third (but more verbose) way to write the `if` statement is as follows:

```
if let indexPath = indexPath {
  if indexPath.section != 0 && indexPath.row != 0 {
    descriptionTextView.resignFirstResponder()
  }
} else {
  descriptionTextView.resignFirstResponder()
}
```

I just wanted to give you a brief glimpse of the various ways you can write the conditions in `if` statements. There's often more than one way to do something in Swift. So, choose whatever approach you find easiest to understand.

➤ Run the app. Tap in the text view to bring up the keyboard — if the keyboard doesn't come up, press **⌘+K**. Tap anywhere else in the table view to hide the keyboard again.

The table view can also automatically dismiss the keyboard when the user starts scrolling. You can enable this in the storyboard.


➤ Open the storyboard and select the table view in the Tag Location scene. In the **Attributes inspector** change the **Keyboard** option to **Dismiss on drag**. Now scrolling should also hide the keyboard.

If this doesn't work for you on the simulator, try it on a real device. The keyboard in the Simulator can be a bit wonky.

➤ Also try the **Dismiss interactively** option. Which one do you like best?

The HUD

There is one more improvement I wish to make to this screen, just to add a little spice. When you tap the Done button to close the screen, the app will show a quick animation to let you know it successfully saved the location:



Before you close the screen it shows an animated checkmark

This type of overlay graphic is often called a HUD, for **H**eads-**U**p **D**isplay. Apps aren't quite fighter jets, but HUDs are often used to display a progress bar or spinner while files are downloading or another long-lasting task is taking place.

You'll show your own HUD view for a brief second before the screen closes. It adds an extra bit of liveliness to the app.

If you're wondering how you can display anything on top of a table, this HUD is simply a `UIView` subclass. You can add views on top of other views. That's what you've been doing all along, in fact. The labels are views that are added on top of the cells, which are also views. The cells themselves are added on top of the table view, and the table view in turn is added on top of the navigation controller's content view.

So far, when you've made your own objects, they have always been view controllers or data model objects, but it's also possible to make your own views.

Often, using the standard buttons and labels is sufficient. But when you want to do something that is not available as a standard view, you can always make your own. You either subclass `UIView` or `UIControl` and do your own drawing. That's what you're going to do for the HUD view as well.

Create the HUD view

➤ Add a new file to the project using the **Swift File** template. Name it **HudView**.

Let's build a minimal version of this class just so that you can get something on the screen. When that works, you'll make it look fancy.

➤ Replace the contents of **HudView.swift** with the following:

```
import UIKit

class HudView: UIView {
  var text = ""

  class func hud(
    inView view: UIView,
    animated: Bool
  ) -> HudView {
    let hudView = HudView(frame: view.bounds)
    hudView.isOpaque = false

    view.addSubview(hudView)
    view.isUserInteractionEnabled = false

    hudView.backgroundColor = UIColor(
      red: 1,
      green: 0,
      blue: 0,
      alpha: 0.5)
    return hudView
  }
}
```

The `hud(inView, animated)` method is known as a **convenience constructor**. It creates and returns a new `HudView` instance.

Normally you would create a new `HudView` object by writing:

```
let hudView = HudView()
```

But using the convenience constructor you'd write:

```
let hudView = HudView.hud(inView: parentView, animated: true)
```

A convenience constructor is generally a **class method**, i.e. a method that works on the class as a whole and not on any particular instance. You can tell because its declaration begins with `class func` instead of just `func`.

When you call `HudView.hud(inView: parentView, animated: true)` you don't have an instance of `HudView` yet. The whole purpose of this method is to create an instance of the HUD view for you, so you don't have to do that yourself, and to place it on top of another view.

You can see that making an instance is actually the first thing this method does:

```
class func hud(inView view: UIView, animated: Bool) -> HudView {
  let hudView = HudView(frame: view.bounds)
  . . .
  return hudView
}
```

It calls `HudView()`, or actually `HudView(frame:)` which is an `init` method inherited from `UIView`. At the end of the method, the new instance is returned to the caller.

So why use this convenience constructor? As the name implies, for convenience.

Since there are several steps to setting up the view, putting them in the convenience constructor frees you from having to worry about any of that.

One of these additional steps is that this method adds the new `HudView` object as a subview on top of the "parent" view object. This is the navigation controller's view, so the HUD will cover the entire screen.

It also sets the parent view's `isUserInteractionEnabled` property to `false`. While the HUD is showing, you don't want the user to interact with the screen anymore. The user has already pressed the Done button and the screen is in the process of closing.

Most users will leave the screen alone at this point, but there's always some joker who wants to try and break things. By setting `isUserInteractionEnabled` to `false`, the view swallows any touches and all the underlying views become unresponsive.

Just for testing, you set the background color of the HUD to 50% transparent red. That way you can see if it covers the entire screen.

Use the HUD view

Let's add the code to call this funky new HUD, so that you can see it in action.

➤ Change the `done()` method in **LocationDetailsViewController.swift** to:

```
@IBAction func done() {
  guard let mainView = navigationController?.parent?.view
    else { return }
  let hudView = HudView.hud(inView: mainView, animated: true)
  hudView.text = "Tagged"
}
```

The first thing you notice might be the `guard let` part. That's new. What does it do?

This is some syntactic sugar to allow you to check for optionals and handle `nil` conditions easily. You could have written the first line of code like this instead:

```
var mainView: UIView
if let view = navigationController?.parent?.view {
  mainView = view
} else {
  return
}
```

But that took 6 lines instead of the one-liner that we had above! Basically though, both bits of code do the same thing – they check to see if the navigation controller's parent — which could be `nil` if the navigation controller does not have a parent — has a view. If it does, then that view is assigned to the `mainView` variable. Otherwise, code execution finishes and returns control to the caller of the method.

Also do note that with the longer code, you had to declare the `mainView` variable first because it couldn't be just assigned via the `if let` statement because then, `mainView` would have only existed with the scope of the `if` statement.


So `guard let` does all of that work in just one line of code – sweet!

The next line of code creates a `HudView` object and adds it to the navigation controller's view with an animation.

Finally, you set the `text` property on the new object.

Previously, `done()` sent you back to the previous view controller. For testing purposes, you're not going to do that anymore. You want to have enough time to see what the `HudView` looks like as you build it step-by-step; if you immediately close the screen after showing the HUD, it will be hard to see what's going on — unless you have the ability to slow down time somehow... You'll put back the code that closes the screen later.

➤ Run the app. When you press the Done button, the screen will look like this:



The HUD view covers the whole screen

The app is now totally unresponsive because user interaction is disabled.

When you're working with views, it's a good idea to set the background color to a bright color such as red or blue, so you can see exactly how big a given view is.


Did you, upon looking at the HUD activation code think, "Hey, how come we are using the navigation' controller's parent's view instead of the view from `LocationDetailsViewController`?" If you did, good on you! It shows that you are starting to understand the composition of view controllers and views and thinking about how they work.

The answer is simple enough to figure out :] Just try it and see what happens. Change the `HudView` creation line in `done()` to the following:

```
let hudView = HudView.hud(inView: view, animated: true)
```

Here, instead of the navigation controller's parent's content view, you use the current view controller's view as the parent for the HUD.

➤ Run the app and try the Done button. You should get a screen like this:



The HUD view does not cover the full screen

Do you see what happened? Or do you think it still looks the same?

If you think it still looks the same, look a bit closer :] Do you notice that the title and the navigation buttons look clearer now?

In previous versions of iOS, the HUD would now have covered the screen area for the `LocationDetailsViewController`'s view — it wouldn't cover the navigation bar or the tab bar. So the effect would have been clearer. However, in iOS 15, the `LocationDetailsViewController`'s view extends under the navigation bar and the tab bar and the navigation bar and the tab bar are translucent - so you see the view underneath. But, the navigation bar and the tab bar are now actually *above* the HUD in terms of positioning.

And you know what that means, right? The user can tap on the Cancel or Done buttons — or the tab bar button, since that will take you back to the root view of the tab — and have them respond even if the rest of the screen has user interactions disabled. That can be a problem in certain situations.

That's why you use the view from the navigation controller's parent – the parent for the navigation controller is the tab bar controller. That way, the view area for both the navigation controller *and* the tab bar controller are covered by the HUD. Check your storyboard if you want to make sure :]

Note that all `UIViewController` instances have a `parent` property which points to the parent view controller of the current view controller, if one exists. But if the current view controller has no parent, then the `parent` property would be `nil`.

Revert your code back to using the navigation controller's parent's view before you forget.

Let's get the HUD view to actually display something on screen instead of the red background.

Draw the HUD view

➤ Remove the `backgroundColor` line from the `hud(inView:animated:)` method.

➤ Add the following method to **HudView.swift**:

```
override func draw(_ rect: CGRect) {
  let boxWidth: CGFloat = 96
  let boxHeight: CGFloat = 96

  let boxRect = CGRect(
    x: round((bounds.size.width - boxWidth) / 2),
    y: round((bounds.size.height - boxHeight) / 2),
    width: boxWidth,
    height: boxHeight)

  let roundedRect = UIBezierPath(
    roundedRect: boxRect,
    cornerRadius: 10)
  UIColor(white: 0.3, alpha: 0.8).setFill()
  roundedRect.fill()
}
```

The `draw()` method is invoked whenever UIKit wants your view to redraw itself.

Recall that everything in iOS is event-driven. The view doesn't draw anything on screen unless UIKit asks it to draw itself. That means you should never call `draw()` yourself.

Instead, if you want a view to redraw, you should send it the `setNeedsDisplay()` message. UIKit will then trigger a `draw()` when it is ready to perform the drawing. This may seem strange if you're coming from another platform. You may be used to redrawing the screen whenever you feel like it, but on iOS, UIKit is in charge of who gets to draw when.

The previous code draws a filled rectangle with rounded corners in the center of the screen. The rectangle is 96 by 96 points – so I suppose it's really a square:

```
let boxWidth: CGFloat = 96
let boxHeight: CGFloat = 96
```

This declares two constants you'll be using in the calculations that follow. You're using constants because it's clearer to refer to the symbolic name `boxWidth` than the number 96. That number doesn't mean much by itself, but "box width" is a pretty clear description of its purpose.

Additionally, if you were to later decide to change the size of the HUD box, you only have one place in your code where you need to change the width or the height, instead of going through all your code trying to figure out where else you had the width or the height value.

Note that you force the type of these constants to be `CGFloat`, which is the type used by UIKit to represent decimal numbers. When working with UIKit or **C**ore **G**raphics (CG, get it?) you use `CGFloat` instead of the regular `Float` or `Double`.

```
let boxRect = CGRect(
  x: round((bounds.size.width - boxWidth) / 2),
  y: round((bounds.size.height - boxHeight) / 2),
  width: boxWidth,
  height: boxHeight)
```

There's `CGRect` again, the struct that represents a rectangle. You use it to calculate the position for the HUD. The HUD rectangle should be centered horizontally and vertically on the screen. The size of the screen is given by `bounds.size` – this is the size of `HudView` itself, which spans the entire screen.

The above calculation uses the `round()` function to make sure the rectangle doesn't end up on fractional pixel boundaries because that makes the image look fuzzy.

```
let roundedRect = UIBezierPath(roundedRect: boxRect,
cornerRadius: 10)
UIColor(white: 0.3, alpha: 0.8).setFill()
roundedRect.fill()
```

`UIBezierPath` is a very handy object for drawing rectangles with rounded corners. You just tell it how large the rectangle is and how round the corners should be. Then you fill the rectangle with an 80% opaque dark gray color.

➤ Run the app. The result should look like this:



The HUD view has a partially transparent background

There are two more things to add to the HUD, a checkmark and a text label. The checkmark is an image.

Display the HUD checkmark

➤ The Resources folder for the book has two files in the **Hud Images** folder, **Checkmark@2x.png** and **Checkmark@3x.png**. Add these files to the asset catalog, **Assets.xcassets**.

You can do this with the **Import...** option under the + button or simply drag them from Finder on to the Xcode window with the asset catalog open.

➤ Add the following code to the end of `draw()`:

```
// Draw checkmark
if let image = UIImage(named: "Checkmark") {
  let imagePoint = CGPoint(
    x: center.x - round(image.size.width / 2),
    y: center.y - round(image.size.height / 2) - boxHeight / 8)
  image.draw(at: imagePoint)
}
```

This loads the checkmark image into a `UIImage` object. Then it calculates the position for that image based on the center coordinate of the HUD view (`center`) and the dimensions of the image (`image.size`).

Finally, it draws the image at that position.

➤ Run the app to see the HUD view with the image:



The HUD view with the checkmark image

Note: If you don't see the checkmark when you run the app, and if you did change the `done()` method to use the view controller's view instead of the navigation controller's content view earlier, make sure that you reverted the code back.

The position calculations are based on the HUD view stretching up to the navigation bar, and if the view size is different, the checkmark will be placed a little above the rounded square. Since the background is mostly white outside the square, and the checkmark is white too, you might not even notice it when it is drawn outside the rounded square :]

Failable initializers

To create the `UIImage` you used `if let` to unwrap the resulting object. That's because `UIImage(named:)` is a *failable* initializer.

It is possible that loading the image fails. This could be for one of many different reasons such as there being no image with the specified name, or the file not containing a valid image. You can't fool `UIImage` into loading something that isn't an image!

That's why `UIImage`'s `init(named:)` method is really defined as `init?(named:)`. The question mark indicates that this method returns an optional. If there was a problem loading the image, it returns `nil` instead of a brand spanking new `UIImage` object.

You'll see these failable initializers throughout the iOS frameworks. Whenever it is possible that creating a new object will fail, the responsible `init` method will return an optional that you need to unwrap before you can use it.

Also note that you could have written the failable initializer with a `guard let` instead of an `if let` like this:

```
guard let image = UIImage(named: "Checkmark") else { return }
let imagePoint = CGPoint(
  x: center.x - round(image.size.width / 2),
  y: center.y - round(image.size.height / 2) - boxHeight / 8)
image.draw(at: imagePoint)
```

Personally, I like the `guard let` version better since it feels a little cleaner :] But feel free to use what you feel most comfortable with – there's almost always many different ways to code the same thing in Swift.

Display the HUD text

Usually, to display text in your own view, you'd add a `UILabel` object as a subview and let `UILabel` do all the hard work. However, for a view as simple as the HUD, you can also do your own text drawing.

➤ Add the following code to the end of `draw()` to complete the method:

```
// Draw the text
let attribs = [
    NSAttributedString.Key.font: UIFont.systemFont(ofSize: 16),
    NSAttributedString.Key.foregroundColor: UIColor.white
]

let textSize = text.size(withAttributes: attribs)

let textPoint = CGPoint(
  x: center.x - round(textSize.width / 2),
  y: center.y - round(textSize.height / 2) + boxHeight / 4)

text.draw(at: textPoint, withAttributes: attribs)
```

When drawing text, you first need to know how big the text is so you can figure out where to position it. `String` has a bunch of handy methods for doing both.


First, you set up a dictionary of attributes for the text that you want to draw, such as the font to be used, the text color etc. Here, you'll use a white system font of size 16.

You use these attributes and the string from the `text` property to calculate how wide and tall the text will be. The result ends up in the `textSize` constant, which is of type `CGSize`.

As you'll notice, `CGPoint`, `CGSize`, and `CGRect` are types you use a lot when making your own views.

Finally, you calculate where to draw the text (`textPoint`), and then draw it. Quite simple, really.

➤ Run the app to try it out. Lookin' good!



The HUD view with the checkmark and the text

➤ Make sure to test the HUD on different Simulators. No matter the device dimensions, the HUD should always appear centered in the screen.

Add some animation

OK, you've now got a rounded box with a checkmark, but it's still far from spectacular. Time to liven it up a little with some animation!

You've already seen a bit about animations before — they're really easy to add.

➤ Add the following method to **HudView.swift**:

```
// MARK: - Helper methods
func show(animated: Bool) {
  if animated {
    // 1
    alpha = 0
    transform = CGAffineTransform(scaleX: 1.3, y: 1.3)
    // 2
    UIView.animate(withDuration: 0.3) {
      // 3
      self.alpha = 1
      self.transform = CGAffineTransform.identity
    }
  }
}
```

For the *Bull's Eye* app, you made a crossfade animation using the Core Animation framework. `UIView`, however, has its own animation mechanism. It still uses Core Animation under the hood, but it's a little more convenient to use.

The standard steps for doing `UIView`-based animations are as follows:

1. Set up the initial state of the view before the animation starts. Here you set `alpha` to 0, making the view fully transparent. You also set the `transform` to a scale factor of 1.3. We're not going to go into depth on transforms here, but basically, this means the view is initially scaled up to be larger than it normally would be.

2. Call `UIView.animate(withDuration:animations:)` to set up an animation. You pass the method a closure that describes what happens as part the animation. Recall that a closure is a piece of inline code that is not executed right away. UIKit will animate the properties that you change inside the closure from their initial state to the final state.

   Also note that you don't actually see the `animations` parameter label in the code above because that parameter is written as a trailing closure.

3. Inside the closure, set up the state of the view as it should be after the animation completes. You set `alpha` to 1, which means the `HudView` is now fully opaque. You also set the `transform` to the "identity" transform, restoring the scale back to normal. Because this code is part of a closure, you need to use `self` to refer to the `HudView` instance and its properties. That's the rule for closures.

The HUD view will quickly fade in as it goes from fully transparent to fully opaque, and it will scale down from 1.3 times its original size to its regular width and height.

This is only a simple animation but it looks quite smart.

➤ Change the `hud(inView:animated:)` method to call `show(animated:)` just before it returns:

```
class func hud(inView view: UIView, animated: Bool) -> HudView {
  . . .
  hudView.show(animated: animated)    // Add this
  return hudView
}
```

➤ Run the app and marvel at the magic of `UIView` animation.

Improve the animation

You can actually do one better. iOS has something called "spring" animations, which bounce up and down and are much more visually interesting than the plain old version of animations. Using them is very simple.

➤ Replace the `UIView.animate(withDuration:animations:)` code in `show(animated:)` with the following:

```
UIView.animate(
  withDuration: 0.3,
  delay: 0,
  usingSpringWithDamping: 0.7,
  initialSpringVelocity: 0.5,
  options: [],
  animations: {
    self.alpha = 1
    self.transform = CGAffineTransform.identity
  }, completion: nil)
```

The code in the closure is still the same — it sets alpha to 1 and restores the identity transform — but this new animation method has a lot more options. Feel free to play with these options to see what they do.

Also note that we don't have a trailing closure here. Swift 5.3 introduced multiple trailing closures and so, we could have had trailing closures for both the final parameters – `animations` and `completion`. But, since `completion` has no code, it isn't possible to use the non-trailing closure syntax here — unless you pass in an empty closure to `completion`.

➤ Run the app and watch it bounce. Actually, the effect is very subtle, but subtle is good when it comes to user interfaces. You don't want your users to get seasick from using the app!

Handle the navigation

Back to **LocationDetailsViewController**... You still need to close the screen when the user taps Done.

There's a challenge here: you don't want to dismiss the screen right away. It won't look very good if the screen closes before the HUD is finished animating. You didn't spend all that time writing `HudView` for nothing — you want to give your users a chance to see it.

You are going to use the **G**rand **C**entral **D**ispatch framework, or GCD, here. GCD is a very handy but somewhat low-level library for handling asynchronous tasks. Telling the app to wait a few seconds before executing some code is a perfect example of an async task.

➤ Add these lines to the bottom of the `done()` action method:

```
let delayInSeconds = 0.6
DispatchQueue.main.asyncAfter(deadline: .now() + delayInSeconds)
{
  self.navigationController?.popViewController(animated: true)
}
```

Believe it or not, these mysterious incantations tell the app to close the Tag Location screen after 0.6 seconds :]

The magic happens in `DispatchQueue.main.asyncAfter()`. This function takes a closure as its final parameter. Inside that closure, you tell the navigation controller to go back to the previous view controller in the navigation stack. This doesn't happen right away, though. That's the exciting thing about closures: even though this code sits side-by-side with all the other code in the method, everything inside the closure is ignored for now and kept for a later time.

`DispatchQueue.main.asyncAfter()` uses the time given by `.now() + delayInSeconds` to schedule the closure for some point in the future. Until then, the app just sits there twiddling its thumbs.

By the way, `.now()` is a shortcut for `DispatchTime.now()`. Swift's type inference already knows that the type of the `when:` parameter is always a `DispatchTime` object, so you don't have to mention `DispatchTime` explicitly.

After 0.6 seconds, the code from the closure runs and the screen closes.

> **Note:** I spent some time tweaking that number. The HUD view takes 0.3 seconds to fully fade in and then you wait another 0.3 seconds before the screen disappears. That felt right to me. You don't want to close the screen too quickly or the effect from showing the HUD is lost, but it shouldn't take too long either, or it will annoy the user. Animations are cool, but they shouldn't make the app more frustrating to use!

➤ Run the app. Press the Done button and watch how the screen disappears. This looks pretty smooth, if I do say so myself.

But wait ... the HUD never goes away after the Tag Location screen closes! It still is there after you navigate back to the parent view. This is not good ...

> **Exercise:** Can you explain why this happens?

The reason is simple. You added the HUD to the tab bar controller's content view, not the Tag Location screen's view. So, even though you've dismissed the Tag Location screen, you still have the HUD displaying because the tab bar controller itself is still in existence.

So what do you think you should do to hide the HUD? Remove it from view, of course!

➤ Add the following method to **HudView.swift**:

```
func hide() {
  superview?.isUserInteractionEnabled = true
  removeFromSuperview()
}
```

This method is rather simple. Remember how you disabled user-interactions when showing the HUD? You first re-enable user-interactions and then remove the `HudView` instance from it's parent view. The only new thing might be `superview` and that's a reference to a view's parent view — all `UIView` objects (and sub-classes of `UIVew` too) have a `superview` property which identifies the view's parent.

Of course, if you wanted, you could have made the method a bit more complex and interesting by adding some animation to the removal of the HUD. Basically, you'd set up the animation to reverse what you did when you showed the view. But I leave that to you as an exercise :]

Now, you need to call this new method to hide the HUD before you exit the Tag Location screen.

➤ Modify the `DispatchQueue.main.asyncAfter` closure for `done()` in **LocationDetailsViewController.swift**:

```
DispatchQueue.main.asyncAfter(deadline: .now() + delayInSeconds)
{
  hudView.hide()   // Add this line
  self.navigationController?.popViewController(animated: true)
}
```

➤ Run the app. Press the Done button and check if the HUD disappears when the Tag Location screen goes away.

Clean up the code

I don't know about you, but I find this GCD stuff to be a bit messy. So let's clean up the code and make it easier to understand.

➤ Add a new file to the project using the **Swift File** template. Name the file **Functions.swift**.

➤ Replace the contents of the new file with:

```
import Foundation

func afterDelay(_ seconds: Double, run: @escaping () -> Void) {
  DispatchQueue.main.asyncAfter(
    deadline: .now() + seconds,
    execute: run)
}
```

That looks very much like the code you just added to `done()`, except it now lives in its own function, `afterDelay()`. This is a **free function**, not a method inside an object. So, it can be used from anywhere in your code.

Take a good look at `afterDelay()`'s second parameter, the one named `run`. Its type is `() -> Void`. That's not some weird emoticon; it is Swift notation for a parameter that takes a closure with no arguments and no return value.

The type for a closure generally looks like this:

```
(parameter list) -> return type
```

In this case, both the parameter list and the return value are empty, `()` and `Void`. This can also be written as `Void -> Void`, or even `() -> ()`, but I like the `() -> Void` better because it looks like a function declaration.

So, whenever you see a -> in the type annotation for a parameter, you know that parameter is a closure.

`afterDelay()` simply passes this closure along to `DispatchQueue.main.asyncAfter()`.

The annotation `@escaping` is necessary for closures that are not performed immediately. This is so that Swift knows that it should hold on to this closure for a while.

You may be wondering why you're going through all this trouble. No fear! The reason will become apparent after you've made the following change...

➤ Go back to **LocationDetailsViewController.swift** and change `done()` as follows:

```
@IBAction func done() {
  ...
  hudView.text = "Tagged"
  afterDelay(0.6) {
    hudView.hide()
    self.navigationController?.popViewController(animated: true)
  }
}
```

Now that's the power of Swift! It only takes one look at this code to immediately understand what it does. After a delay, some code is executed.

By moving the nasty GCD stuff into a new function, `afterDelay()`, you have added a new level of **abstraction** to your code that makes it much easier to follow. Writing good programs is all about finding the right abstractions.

> **Note:** Because the code referring to the navigation controller sits in a closure, it needs to use `self` . Inside closures you always need to use `self` explicitly. But, you didn't need to use `self` for the line referring to the `hudView` since it is a local variable which would be in existence only within the scope of the `done()` method.

➤ Run the app again to make sure the timing still works. Boo-yah!

You can find the project files for this chapter under **26-Adding-polish** in the Source Code folder.

Chapter 27: Saving Locations

By Fahim Farook

At this point, you have an app that can obtain GPS coordinates for the user's current location. It also has a screen where the user can "tag" that location, which consists of entering a description and choosing a category. Later on, you'll also allow the user to pick a photo.

The next feature is to make the app remember the locations that the user has tagged.

This chapter covers the following:

- **Core Data overview:** A brief overview of what Core Data is and how it works.
- **Add Core Data:** Add the Core Data framework to the app and use it.
- **The data store:** Initializing the data store used by Core Data.
- **Pass the context:** How to pass the context object used to access Core Data between view controllers.
- **Browse the data:** Looking through the saved data.
- **Save the locations:** Saving entered location information using Core Data.
- **Handle Core Data errors:** Handling Core Data errors when there's an issue with saving.

Core Data overview

You have to persist the data for these captured locations somehow — they need to be remembered even when the app terminates.

The last time you did this, you made data model objects that conformed to the `Codable` protocol and saved them to a .plist file. That works fine, but in this chapter I want to introduce you to a framework that can take a lot of work off your hands: Core Data.

Core Data is an object persistence framework for iOS apps. If you've looked at Core Data before, you may have found the official documentation a little daunting, but the principle is quite simple.

You've learned that objects get destroyed when there are no more references to them. In addition, all objects get destroyed when the app terminates.

With Core Data, you can designate some objects as being persistent so they will always be saved to a **data store**. Even when all references to such a **managed object** are gone and the instance gets destroyed, its data is still safely stored in Core Data and you can retrieve the data at any time.

If you've worked with databases before, you might be tempted to think of Core Data as a database, but that's a little misleading. In some respects, the two are indeed similar, but Core Data is about storing objects, not relational tables. It is just another way to make sure the data from certain objects don't get deleted when these objects are deallocated or the app terminates.

Using Core Data

Core Data requires the use of a data model. This is a special file that you add to your project to describe the objects that you want to persist. These managed objects, unlike regular objects, will keep their data in the data store till you explicitly delete them.


The data model

Back in Chapter 22, when you first created the *MyLocations* project, the project settings had an option named **Use Core Data**. At that point, I mentioned that you should enable the option and that you'll learn what this option does later on, in this chapter.

What that option did was to let Xcode know that you would be using Core Data in your project and that it should create a data model and add the necessary set up code as part of the initial project. If you check the Project Navigator, you will see the data model file, **MyLocations.xcdatamodeld**, listed.

If you forgot to enable the option when creating the project — or, you want to know how to add a Core Data model to an existing project — simply select **New File...** from the Xcode context menu and then select the **Data Model** option under **Core Data** in the template chooser under **iOS**, give the new data model a name and save it. It's as simple as that!

➤ Click **MyLocations.xcdatamodeld** in the Project navigator to open the Data Model editor:



The empty data model

For each object that you want Core Data to manage, you have to add an **entity**.


An entity describes which data fields your objects will have. In a sense, it serves the same purpose as a class, but specifically for Core Data's data store — if you've worked with SQL databases before, you can think of an entity as a table.

This app will have one entity, Location, which stores all the properties for a location that the user tagged. Each Location will keep track of the following data:

- Latitude and longitude
- Placemark – the street address
- The date when the location was tagged
- The user's description
- Category

These are the items from the Tag Location screen, except for the photo. Photos can potentially be very big and can take up several megabytes of storage space. Even though the Core Data store can handle big "blobs" of data, it is usually better to store photos as separate files in the app's Documents directory. More about that later.

➤ Click the **Add Entity** button at the bottom of the data model editor. This adds a new entity under the ENTITIES heading. Name it **Location** — you can rename the entity by clicking its name, or from the Data Model inspector pane on the right.




The new Location entity

The entity detail pane in the center shows three sections: Attributes, Relationships and Fetched Properties. The Attributes are the entity's data fields.

This app only has one entity, but generally, apps will have many entities that are all related to each other somehow. With Relationships and Fetched Properties, you can tell Core Data how your objects depend on each other.

For this app, you will only use the Attributes section only.

➤ Click the **Add Attribute** button at the bottom of the editor, or the small + button below the Attributes section. Name the new attribute **latitude** and set its **Type** to **Double**:



Choosing the attribute type


Attributes are basically the same as properties, and therefore they have a type. You've seen earlier that the latitude and longitude coordinates really have the data type `Double`. So, that's what you're choosing for the attribute as well.

> **Note:** Don't let the change in terminology scare you. Just think:
>
> entity = object (or class)
>
> attribute = property
>
> If you're wondering where you'll define methods in Core Data, then the answer is: you don't. Core Data is only for storing the data portion of objects. That is what an entity describes: the data of an object, and optionally, how that object relates to other objects if you use Relationships and Fetched Properties.
>
> In a short while, you're going to define your own `Location` class by creating a Swift file, just as you've been doing all along. Because it describes a managed object, this class will be associated with the Location entity in the data model. But it's still a regular class, so you can add your own methods to it.

➤ Add the rest of the attributes for the Location entity:

- **longitude** – Type: **Double**
- **date** – Type: **Date**
- **locationDescription** – Type: **String**
- **category** – Type: **String**
- **placemark** – Type: **Transformable**

The data model should look like this when you're done:



All the attributes of the Location entity

Why didn't you just call the description value "description" instead of "locationDescription"? As it turns out, `description` is the name of a method from `NSObject`.

If you try to name an attribute "description", then it will cause a naming conflict with the `NSObject` method since Core Data managed objects are derived from `NSObject`. Xcode will give you an error message if you try to do this.


The type of the placemark attribute is Transformable. Core Data only supports a limited number of data types out of the box, such as `String`, `Double`, and `Date`. The placemark is a `CLPlacemark` object and is not in the list of supported data types.

Fortunately, Core Data has a provision for handling arbitrary data types. Any class that conforms to the `NSCoding` protocol can be stored in a Transformable attribute without additional work. Fortunately for us, `CLPlacemark` does conform to `NSCoding`, so you can store it in Core Data with no trouble.

And in case you are wondering, `NSCoding` is the Objective-C equivalent of the Swift `Codable` protocol — it allows classes to encode and decode themselves if they support it.

By default, entity attributes are optional, meaning they can be `nil`. In our app, the only thing that can be `nil` is the placemark, in case reverse geocoding failed. It's a good idea to embed this constraint in the data model.

➤ Select the **category** attribute. In the inspectors panel, switch to the **Data Model inspector** and uncheck the **Optional** setting:



Making the category attribute non-optional

➤ Repeat this for the other attributes, except for placemark.


Tip: you can select multiple attributes at the same time, either by Command+clicking to select individually, or Shift+Clicking to select a range.

➤ Press **⌘+S** to save your changes. Xcode is supposed to do this automatically, but I've found the data model editor to be a little unreliable at times. Better safe than sorry!

You're done with the data model, but there's one more thing to do.

Generate the code

➤ Click on the **Location** entity to select it and go to the **Data Model inspector**.



The Data Model inspector

The **Class > Name** field says "Location". When you retrieve a Location entity from Core Data, it gives you an instance of the `Location` class which is derived from `NSManagedObject`. `NSManagedObject` is the base class for all objects that are managed by Core Data. Regular objects inherit from `NSObject`, but Core Data objects extend `NSManagedObject`.

Because using `NSManagedObject` directly is a bit limiting, Xcode helpfully sets you up to use your own `Location` class instead. You're not required to make your own classes for your entities, but it does make Core Data easier to use. So now when you retrieve a Location entity from the data store, Core Data doesn't give you an `NSManagedObject` but an instance of your own `Location` class.

Note also that the **Class > Codegen** dropdown is set to "Class Definition". Xcode will automatically generate the code for your entity's class with this setting so that you don't have to do any extra work. However, it is useful to understand how to make your own `NSManagedObject` subclass rather than relying on Xcode magic. So, for this app, you'll write the code yourself.

➤ In the inspector, change **Codegen** to **Manual/None**.

Even though you won't be using automatic class generation, Xcode can still lend a helping hand.

➤ From the menu bar, choose **Editor ▸ Create NSManagedObject Subclass...**.

The assistant will now ask you for the data models and entities you wish to create classes for.

➤ Select **MyLocations** (which is the name of your data model) and click **Next**. In the next step, make sure **Location** is selected and click **Next** again.

➤ Choose a location to save the source files — in your case, the folder for your project. Press **Create** to finish.

This adds two new files to the project. The first one is named **Location+CoreDataClass.swift** and looks something like this:

```
import Foundation
import CoreData

@objc(Location)
public class Location: NSManagedObject {

}
```

As you can see in the `class` line, the `Location` class extends `NSManagedObject` instead of the regular `NSObject`.

You already know what the `public` and `@objc` attributes are for since you've encountered them before, but what does the `(Location)` bit do?

That is actually a part of the `@objc` attribute. The Swift compiler uses a mechanism called *name mangling* to rename methods internally so that they can be identified uniquely. After all, if you have two methods named `copyFiles` in the same project, how does the compiler know which one a particular bit of code refers to? It has to have a way to identify each method uniquely so that all method calls are resolved correctly.

Name mangling works fine if your project has only Swift code. But since you can combine Swift and Objective-C code in the same project, sometimes you run into trouble in such "hybrid" projects because Objective-C is not able to identify a Swift class correctly due to name mangling. This happens often when working with archived data since the archived data saves the class name and you run into issues when Objective-C can't reconcile the name it receives with a known class.

This is where the `@objc(Location)` (or similar) notation comes into play. The part inside the brackets, in this case `Location`, tells the compiler that that is the name Objective-C code will use to refer to this particular class.

You shouldn't have to worry about the above notation at all in this book since you'll be working with Swift code only. However, it's always a good idea to know things such as this for when you are a full-blown developer since you most likely will encounter a "hybrid" project at some point.

The second file that got created is **Location+CoreDataProperties.swift**:

```
import Foundation
import CoreData

extension Location {
```

```
    @nonobjc public class func fetchRequest() ->
NSFetchRequest<Location> {
        return NSFetchRequest<Location>(entityName: "Location")
    }

    @NSManaged public var latitude: Double
    @NSManaged public var longitude: Double
    @NSManaged public var date: Date?
    @NSManaged public var locationDescription: String?
    @NSManaged public var category: String?
    @NSManaged public var placemark: NSObject?
}

extension Location : Identifiable {

}
```

In this file, Xcode has created properties for the attributes that you specified in the Data Model editor. But what is this `extension` thing?

With an *extension* you can add additional functionality to an existing object without having to change the original source code for that object. This even works when you don't actually have the source code for those objects. Later on you'll see an example of how you can use an extension to add new methods to objects from iOS frameworks.

Here, the extension is used for another purpose. If you change your Core Data model at some later time and you want to automatically update the code to match those changes, then you can choose **Create NSManagedObject Subclass** again and Xcode will only overwrite what is in **Location+CoreDataProperties.swift** but not anything you added to **Location+CoreDataClass.swift**. So, it's not a good idea to make changes to **Location+CoreDataProperties.swift** if you plan on overwriting this file later.

The second extension simply indicates that the `Location` class conforms to the `Identifiable` protocol – which basically means that all `Location` items can be uniquely identified by means of a few methods provided by the protocol.

Fix the code

Unfortunately, Xcode made a few small boo-boos in the types of the properties, so you'll have to make some changes to **Location+CoreDataProperties.swift**.

The first thing to fix is the `placemark` variable. Because you made placemark a Transformable attribute, Xcode doesn't really know what kind of object this will be. So, it chose the generic type `NSObject`.

But you know it's going to be a `CLPlacemark` object. So, you can make things easier for yourself by changing it.

➤ First, import Core Location into **Location+CoreDataProperties.swift**:

```
import CoreLocation
```

➤ Then change the `placemark` property to:

```
@NSManaged public var placemark: CLPlacemark?
```

➤ Finally, remove the question marks behind the `date`, `category` and `locationDescription` properties. Earlier you told Core Data these attributes were not optionals. So, they don't need the question mark.

Because this is a *managed* object, and the data lives inside a data store, Swift will handle `Location`'s variables in a special way. The `@NSManaged` keyword tells the compiler that these properties will be resolved at runtime by Core Data. When you put a new value into one of these properties, Core Data will place that value into the data store for safekeeping, instead of in a regular instance variable.

And if you are wondering, the `@nonobjc` attribute is the reverse of the `@objc` attribute — it makes a class, method, or property not available to Objective-C. Since this came by way of generated boilerplate code, don't worry too much about why you'd want to do that in this particular case :]

This concludes the definition of the data model for *MyLocations*. Now you have to hook it up to a data store.

The data store

On iOS, Core Data stores all of its data into an SQLite — pronounced "SQL light" — database. It's OK if you have no idea what SQLite is. You'll take a peek into that database later, but you don't really need to know what goes on inside the data store in order to use Core Data.

However, you do need to initialize this data store when the app starts. The code for that is the same for just about any app that uses Core Data and it goes in the app delegate class.

As you learnt previously, the *app delegate* is the object that gets notifications that concern the application as a whole and the *scene delegate* is the object which gets notified about changes to the main application window. Just a couple of years ago, the scene delegate did not exist and the main application window was also handled by the app delegate.

If you had enabled the **Use Core Data** option when you created the *MyLocations* project, then most of the necessary code will already be there in your `AppDelegate`. Unfortunately, due to the addition of scene delegate, and how we'll be passing on Core Data references to the rest of your app, this code really needs to be in scene delegate instead :]

So, let's move the code piece by piece over to scene delegate and I'll explain what each bit does.

➤ First, move the Core Data import at the very top of **AppDelegate.swift** over to **SceneDelegate.swift**:

```
import CoreData
```

➤ Then, move the following code for the `persistentContainer` variable over to the `SceneDelegate` class — the existing code might look slightly different to this and will also have a lot of comments but essentially, it's the same:

```
lazy var persistentContainer: NSPersistentContainer = {
  let container = NSPersistentContainer(name: "MyLocations")
  container.loadPersistentStores {_, error in
    if let error = error {
      fatalError("Could not load data store: \(error)")
    }
  }
  return container
}()
```

This is the code you need to load the data model that you've defined earlier, and to connect it to an SQLite data store.

The goal here is to create an `NSManagedObjectContext` object. That is the object you'll use to talk to Core Data. To get that `NSManagedObjectContext` object, the app needs to do several things:

1. Create an `NSManagedObjectModel` from the Core Data model you created earlier. This object represents the data model during runtime. You can ask it what sort of entities it has, what attributes these entities have, and so on. In most apps, you don't need to use the `NSManagedObjectModel` object directly.

2. Create an `NSPersistentStoreCoordinator` object. This object is in charge of the SQLite database.

3. Finally, create the `NSManagedObjectContext` object and connect it to the persistent store coordinator.

Together, these objects are also known as the "Core Data stack".

Previously, you had to perform the above steps one-by-one in code, which could get a little messy. But now, there is a new object, the `NSPersistentContainer`, that takes care of everything.

That doesn't mean you should immediately forget what you just learned about the `NSManagedObjectModel` and the `NSPersistentStoreCoordinator`, but it does save you from writing a bunch of code.

The code that you just added creates an instance variable `persistentContainer` of type `NSPersistentContainer`. To get the `NSManagedObjectContext` that we're after, you can simply ask the `persistentContainer` for its `viewContext` property.

➤ For convenience, add another property to get the `NSManagedObjectContext` from the persistent container — this code would not have been added by Xcode, so you need to add this yourself to **SceneDelegate.swift**:

```
lazy var managedObjectContext = persistentContainer.viewContext
```

➤ There should be a `saveContext()` method in **AppDelegate.swift** – move that to **SceneDelegate.swift** as well.

➤ Finally, in `sceneDidEnterBackground(_:)` in **SceneDelegate.swift**, there's a line calling the `saveContext()` method like this:

```
(UIApplication.shared.delegate as? AppDelegate)?.saveContext()
```

Change it to:

```
saveContext()
```

Since you moved the `saveContext` method to the scene delegate, instead of calling the `saveContext` method from `AppDelegate` you change the method call to indicate that it is now an internal scene delegate method. That's it.

Now we're ready to start using Core Data!

➤ Build the app to make sure it compiles without errors. If you run it, you won't notice any difference because you're not actually using Core Data anywhere yet.

Pass the context

When the user presses the Done button in the Tag Location screen, the app currently just closes the screen. Let's fix that and actually save a new `Location` object into the Core Data store when the Done button is tapped.

I mentioned the `NSManagedObjectContext` object. This is the object that you use to talk to Core Data. It is often described as a "scratchpad". You first make your changes to the context and then you call its `save()` method to store those changes permanently in the data store.

This means that every object that needs to do something with Core Data needs to have a reference to the `NSManagedObjectContext` object.

Get the context

➤ Switch to **LocationDetailsViewController.swift**. First, import Core Data at the top, and then add a new instance variable:

```
var managedObjectContext: NSManagedObjectContext!
```

The problem is: how do you put the `NSManagedObjectContext` object from the scene delegate into this property?

The context object is created by `SceneDelegate`, but `SceneDelegate` has no reference to the `LocationDetailsViewController`.

That's not so strange since the Location Details view controller doesn't exist until the user taps the Tag Location button. Prior to that, there simply is no `LocationDetailsViewController` object in existence.

The answer is to pass along the `NSManagedObjectContext` object during the segue that presents the `LocationDetailsViewController`. The obvious place for that is `prepare(for:sender:)` in `CurrentLocationViewController`.

But then you need to find a way to get the `NSManagedObjectContext` object into the `CurrentLocationViewController` in the first place. And this means `CurrentLocationViewController` needs its own property for the `NSManagedObject` context.

➤ Add the following property to **CurrentLocationViewController.swift** (and don't forget to add the Core Data import):

```
var managedObjectContext: NSManagedObjectContext!
```

➤ Add the following to `prepare(for:sender:)`, so that it passes on the context to the Tag Location screen:

```
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
  if segue.identifier == "TagLocation" {
    . . .
    // New code
    controller.managedObjectContext = managedObjectContext
  }
}
```

This should also explain why the `managedObjectContext` variable is declared as an implicitly unwrapped optional with the type `NSManagedObjectContext!`.

You should know by now that variables in Swift must always have a value. If they can be `nil` — which means "no value" —, then the variable must be made optional.

If you were to declare `managedObjectContext` without the exclamation point, like this:

```
var managedObjectContext: NSManagedObjectContext
```

Then Swift demands you give it a value in an `init` method — for objects loaded from a storyboard, such as view controllers, that method is `init?(coder:)`.

However, `prepare(for:sender:)` happens *after* the new view controller is instantiated, long after the call to `init?(coder:)`. As a result, inside `init?(coder:)` you can't know what the value for `managedObjectContext` will be.

You have no choice but to leave the `managedObjectContext` variable `nil` for a short while until the segue happens, and therefore it must be an optional.

You could also have declared it like this:

```
var managedObjectContext: NSManagedObjectContext?
```

The difference between `?` and `!` is that the former requires you to manually unwrap the value with `if let` every time you want to use it.

That gets annoying really fast, especially when you know that `managedObjectContext` will get a proper value during the segue and that it will never become `nil` afterwards again. In that case, the exclamation mark is the best type of optional to use.

These rules for optionals may seem very strict — and possibly confusing — when you're coming from another language such as Objective-C. But they are there for a good reason — by only allowing certain variables to have no value, Swift can make your programs safer and reduce the number of programming mistakes.

The fewer optionals you use, the better, but sometimes you can't avoid them — as in this case with `managedObjectContext`.

Pass the context from SceneDelegate

SceneDelegate.swift now needs some way to pass the `NSManagedObjectContext` object to `CurrentLocationViewController`.

Unfortunately, Interface Builder does not allow you to make outlets for your view controllers on the Scene Delegate. Instead, you have to look up these view controllers by digging through the view hierarchy.

➤ Change the `scene(_:willConnectTo:options:)` method to:

```
func scene(
  _ scene: UIScene,
  willConnectTo session: UISceneSession,
  options connectionOptions: UIScene.ConnectionOptions
) {
  let tabController = window!.rootViewController as!
UITabBarController
  if let tabViewControllers = tabController.viewControllers {
    let navController = tabViewControllers[0] as!
UINavigationController
    let controller = navController.viewControllers.first as!
CurrentLocationViewController
    controller.managedObjectContext = managedObjectContext
  }
}
```

In order to get a reference to the `CurrentLocationViewController`, you first have to find the `UITabBarController` and then look at its `viewControllers` array.

And since the first controller for the first tab is a navigation controller, then you have to go through the navigation controller's list of controllers to finally get at the `CurrentLocationViewController`.

Once you have a reference to the `CurrentLocationViewController` object, you pass it the `managedObjectContext`. It may not be immediately obvious from looking at the code, but something special happens at this point…

Remember the code for `persistentContainer` you added to the scene delegate earlier? You probably recognized it as a lazy loading variable since you've encountered something similar before. This is the point at which the closure for the variable is actually executed and a new `NSPersistentContainer` instance is created.

What actually happens inside the closure is fairly straightforward:

```
let container = NSPersistentContainer(name: "MyLocations")
container.loadPersistentStores {_, error in
  if let error = error {
    fatalError("Could not load data store: \(error)")
  }
}
return container
```

You instantiate a new `NSPersistentContainer` object with the name of the data model you created earlier, `MyLocations`. Then you tell it to `loadPersistentStores()`, which loads the data from the database into memory and sets up the Core Data stack.

There is another closure here, the trailing closure for `loadPersistentStores`. The code in this closure gets invoked when the persistent container is done loading the data. If something went wrong, you print an error message — useful for debugging! — and terminate the app using the function `fatalError()`.

Now that you know what it does, you may be wondering why you didn't just put all of this code into a regular method like this:

```
var persistentContainer: NSPersistentContainer

init() {
  persistentContainer = createPersistentContainer()
}

func createPersistentContainer() -> NSPersistentContainer {
  // all the initialization code here
  return container
}
```

That would certainly work, but now the initialization of `persistentContainer` is spread over three different parts of the code: the declaration of the variable, the method that performs all the initialization logic, and the `init` method to tie it all together.

Isn't it nicer to keep all this stuff in one place, rather than in three different places? Swift lets you perform complex initialization right where you declare the variable. I think that's pretty nifty!

There's another thing going on here:

```
lazy var persistentContainer: NSPersistentContainer = { ... }()
```

Notice the `lazy` keyword? That means the entire block of code in the `{ ... }()` closure isn't actually performed right away. The context object won't be created until you ask for it. This is another example of *lazy loading*, Similar to how you handled `DateFormatter` earlier.

The `managedObjectContext` property is also declared `lazy`:

```
lazy var managedObjectContext = persistentContainer.viewContext
```

This is necessary because its initial value comes from `persistentContainer`.

➤ Run the app. Everything should still be the way it was, but behind the scenes a new database has been created for Core Data.

Browse the data

Core Data stores the data in an SQLite database. That file is named **MyLocations.sqlite** and it lives in the app's Library folder. That's similar to the Documents folder that you saw previously.

Core Data data store location

➤ The easiest way to find the location of the Core Data folder is to add the following to **Functions.swift**:

```
let applicationDocumentsDirectory: URL = {
  let paths = FileManager.default.urls(
    for: .documentDirectory,
    in: .userDomainMask)
  return paths[0]
}()
```

This creates a new global constant, `applicationDocumentsDirectory`, containing the path to the app's Documents directory. It's a global because you're not putting this inside a class. This constant will exist for the duration of the app; it never goes out of scope. You could have made a method for this as you did for *Checklists*, but using a global constant works just as well.

As before, you're using a closure to provide the code that initializes this constant. Like all globals, this is evaluated lazily the very first time it is used.

> **Note:** Globals have a bad reputation. Many programmers avoid them at all costs. The problem with globals is that they create hidden dependencies between the various parts of your program. And dependencies make the program hard to change and hard to debug.
>
> But used well, globals can be very handy. It's feasible that your app will need to know the path to the Documents directory in several different places. Putting it in a global constant is a great way to solve that design problem.

➤ Add the following line to `application(_:didFinishLaunchingWithOptions:)` — a good place would be just before the final `return` statement:


```
print(applicationDocumentsDirectory)
```

On my computer this prints out:

```
file:///Users/fahim/Library/Developer/CoreSimulator/Devices/
31DCE39D-CEC6-4228-B6DF-98FA08E5544F/data/Containers/Data/
Application/D21A7746-093C-4431-82CF-917A86AB7186/Documents/
```

➤ Open a new Finder window and press **Shift+⌘+G**. Then copy-paste the path without the `file://` bit — note that you leave out only two slashes out of the three... — to go to the Documents folder.

The database is not actually in the Documents folder, so go back up one level and enter the **Library** folder, and then **Application Support**:



The new database in the app's Documents directory


The **MyLocations.sqlite-shm** and **-wal** files are also part of the data store.

This database is still empty because you haven't stored any objects in it yet, but just for the fun of it, you'll take a peek inside. There are several handy — and free! — tools that give you a graphical interface for interacting with your SQLite databases.

Browse the Core Data store using a GUI app

You will use **Liya** to examine the data store file. Download it from the Mac App Store or cutedgesystems.com/software/liya/.

➤ Start Liya. It asks you for a database connection. Under **Database Type** choose **SQLite**.



Liya opens with this dialog box


➤ On the right of the Database Type field is a small icon. Click this to open a file picker.

You can navigate to the **CoreSimulator/.../Library/Application Support** folder, but that's a lot of work – it's a very deeply nested folder.

If you have the Finder window still open, it's easier to drag the **MyLocations.sqlite** file from Finder directly on to the open file picker. Click **Choose** when you're done.

> **Tip:** You can also right-click the MyLocations.sqlite file in Finder and choose **Open With ▸ Liya** from the popup menu.


The **Database URL** field should now point to the correct folder and **Database Name** should say MyLocations.sqlite:



Connecting to the SQLite database

➤ Click **Login** to proceed.

The screen should look something like this:



The empty MyLocations.sqlite database in Liya

The ZLOCATION table is where your Location objects will be stored. It's currently empty, but on the right you can already see the column names that correspond to your fields: ZDATE, ZLATITUDE, and so on. Core Data also adds its own internal columns and tables with the Z_ prefix.

You're not really supposed to change anything in this database by hand, but sometimes using a visual tool like this is handy to see what's going on. You'll come back to Liya once you've inserted new Location objects.

> **Note:** An alternative to Liya is SQLiteStudio, sqlitestudio.pl. You can find more tools, paid and free, on the Mac App Store by searching for "sqlite".


Troubleshoot Core Data issues

There is another handy tool for troubleshooting Core Data. By setting a special flag on the app, you can see the SQL statements that Core Data uses under the hood to talk to the data store.

Even if you have no experience with SQL, this is still valuable information. At least you can use it to tell whether Core Data is doing something or not. To enable this tool, you have to edit the project's *scheme*.


Schemes are how Xcode lets you configure your projects. A scheme is a bunch of settings for building and running your app. Standard projects have just one scheme, but you can add additional schemes, which is handy when your project becomes bigger.

➤ Click on the left part of the **MyLocations > iPhone** bar at the top of the screen and choose **Edit Scheme...** from the menu.



The Edit Scheme... option

The following panel should pop up:




The scheme editor

➤ Choose the **Run** option on the left-hand side.

➤ Select the **Arguments** tab.

➤ In the **Arguments Passed On Launch** section, add the following:

```
-com.apple.CoreData.SQLDebug 1
-com.apple.CoreData.Logging.stderr 1
```



Adding the SQLDebug launch argument

➤ Press **Close** to close this dialog, and run the app.

You should see something like this in the Xcode Console:

```
CoreData: annotation: Connecting to sqlite database file at "/
Users/fahim/Library/Developer/CoreSimulator/Devices/31DCE39D-
CEC6-4228-B6DF-98FA08E5544F/data/Containers/Data/Application/
2BB1CA6C-E43C-4D48-B744-90206ECD3667/Library/Application
Support/MyLocations.sqlite"
CoreData: sql: SELECT TBL_NAME FROM SQLITE_MASTER WHERE TBL_NAME
= 'Z_METADATA'
CoreData: sql: pragma recursive_triggers=1
CoreData: sql: pragma journal_mode=wal
CoreData: sql: SELECT Z_VERSION, Z_UUID, Z_PLIST FROM Z_METADATA
CoreData: sql: SELECT TBL_NAME FROM SQLITE_MASTER WHERE TBL_NAME
= 'Z_METADATA'
CoreData: sql: SELECT TBL_NAME FROM SQLITE_MASTER WHERE TBL_NAME
= 'Z_MODELCACHE'
CoreData: sql: SELECT TBL_NAME FROM SQLITE_MASTER WHERE TBL_NAME
= 'ACHANGE'
CoreData: sql: SELECT TBL_NAME FROM SQLITE_MASTER WHERE TBL_NAME
= 'ATRANSACTIONSTRING'
```

This is the debug output from Core Data. If you understand SQL, some of this will look familiar. The specifics don't matter, but it's clear that Core Data is connecting to the data store at this point. Excellent!

Save the locations

You've successfully initialized Core Data and passed the `NSManagedObjectContext` to the Tag Location screen. Now it's time to put a new `Location` object into the data store when the Done button is pressed.

➤ Add the following instance variable to **LocationDetailsViewController.swift**:

```
var date = Date()
```

You're adding this variable because you need to store the current date in the new `Location` object. You only want to make that `Date` object once.

➤ In `viewDidLoad()`, change the line that sets the `dateLabel`'s text to:

```
dateLabel.text = format(date: date)
```

This now uses the new property instead of creating the date on the fly.

➤ Change the `done()` method to the following:

```
@IBAction func done() {
  guard let mainView = navigationController?.parent?.view
  else { return }
  let hudView = HudView.hud(inView: mainView, animated: true)
  hudView.text = "Tagged"
  // 1
  let location = Location(context: managedObjectContext)
  // 2
  location.locationDescription = descriptionTextView.text
  location.category = categoryName
  location.latitude = coordinate.latitude
  location.longitude = coordinate.longitude
  location.date = date
  location.placemark = placemark
  // 3
  do {
    try managedObjectContext.save()
    afterDelay(0.6) {
      hudView.hide()
      self.navigationController?.popViewController(
        animated: true)
    }
  } catch {
    // 4
    fatalError("Error: \(error)")
  }
}
```

This is where you do all the work:

1. First, you create a new `Location` instance. Because this is a managed object, you have to use its `init(context:)` method. You can't just write `Location()` because then the `managedObjectContext` won't know about the new object.

2. Once you have created the `Location` instance, you can use it like any other object. Here you set its properties to whatever the user entered in the screen.

3. You now have a new `Location` object whose properties are all filled in, but if you were to look in the data store at this point, you'd still see no objects there. That won't happen until you `save()` the context.

   Saving takes any objects that were added to the context, or any managed objects that had their contents changed, and permanently writes these changes to the data store. That's why they call the context a "scratchpad"; its changes aren't persisted until you save them. The `save()` method can fail for a variety of reasons and therefore you need to catch any potential errors. That's done using Swift error handling, which you've encountered before.

4. Output the error and then terminate the application via the system method `fatalError`. But where does the `error` variable that you output come from? This is a local constant that Swift automatically populates with the error that it caught — handy, huh?


➤ Run the app and tag a location. Enter a description and press the Done button.

If everything went well, Core Data will dump a whole bunch of debug information into the debug area:

```
CoreData: sql: BEGIN EXCLUSIVE
. . .
CoreData: sql: INSERT INTO ZLOCATION(Z_PK, Z_ENT, Z_OPT,
ZCATEGORY, ZDATE, ZLATITUDE, ZLOCATIONDESCRIPTION, ZLONGITUDE,
ZPLACEMARK) VALUES(?, ?, ?, ?, ?, ?, ?, ?, ?)
. . .
CoreData: sql: COMMIT
```

These are the SQL statements that Core Data performs to store the new Location object in the database.

➤ In Liya, refresh the contents of the ZLOCATION table by pressing the Go button below the Tables list. There should now be one row in that table:




A new row was added to the table

> **Note:** If you don't see any rows in the table, press the Stop button in Xcode first to exit the app. You can also try closing the Liya window and opening a new connection to the database. Sometimes, the Simulator data folder locations might change between app runs. So, you might need to set up a new database connection in Liya if this happens.

As you can see, the columns in this table contain the property values from the `Location` object. The only column that is not readable is ZPLACEMARK. Its contents have been encoded as a binary "blob" of data. That is because it's a Transformable attribute and the `NSCoding` protocol has converted its fields into a binary chunk of data.

If you don't have Liya or are a command line junkie, then there is another way to examine the contents of the database. You can use the Terminal app and the `sqlite3` tool, but you'd better know your SQL's from your ABC's if you want to go that route:



Examining the database from the Terminal

Handle Core Data errors

To save the contents of the context to the data store, you did:

```
do {
  try managedObjectContext.save()
  . . .
} catch {
  fatalError("Error: \(error)")
}
```

What if something goes wrong with the save? In that case, code execution jumps to the `catch` branch and you call the `fatalError()` function. That will immediately kill the app and return the user to the iPhone's Springboard. That's a nasty surprise for the user, and therefore, not recommended.

The good news is that Core Data only gives an error if you're trying to save something that is not valid. In other words, when there is some bug in your app.

Of course, you'll get all the bugs out during development so users will never experience any, right? The sad truth is that you'll never catch all your bugs. Some always manage to slip through.

Unfortunately, there isn't much else to do but crash when Core Data does give an error. Something went horribly wrong somewhere and now you're stuck with invalid data. If the app were allowed to continue, things would likely only get worse, as there is no telling what state the app is in. The last thing you want to do is to corrupt the user's data.


However, instead of making the app crash hard with `fatalError()`, it might be nice to tell the user about the issue first so at least they know what is happening. The crash is still inevitable, but now your users will know why the app suddenly stopped working.

In this section, you'll add a popup alert for handling such situations. Again, these errors should happen only during development, but just in case they do occur to an actual user, you'll try to handle it with at least a little bit of grace.

Fake errors for testing purposes

Here's a way to fake such a fatal error, just to illustrate what happens.

➤ Open the data model **MyLocations.xcdatamodeld** and select the **placemark** attribute. In the Data Model inspector, uncheck the **Optional** flag.



Making the placemark attribute non-optional

That means `location.placemark` can never be `nil`. This is a constraint that Core Data will enforce. When you try to save a `Location` object to the data store whose `placemark` property is `nil`, Core Data will throw a tantrum. So that's exactly what you're going to do here, just to test your error handling code and to make sure the app fails gracefully.

➤ Run the app. It is possible that the app crashes right away…

What happens is that you have just changed the data model by making changes to the `placemark` attribute. When you launch the app, the `NSPersistentContainer` notices this and tries to perform a "migration" of the SQLite database to the new, updated data model.

The migration may succeed… or not… depending on what is currently in your data store. If you previously tagged a location that did not have a valid address — i.e. whose `placemark` is `nil` — then the migration to the new data model fails. After all, the new data model does not allow for `placemarks` that are `nil`.

If the app crashed for you, then the debug area says why:

```
reason=Validation error missing attribute values on mandatory
destination attribute, . . .
```

The MyLocations.sqlite file is out of date with respect to the changed data model, and Core Data can't automatically resolve this issue.There are two ways to fix this:

1. Simply throw away the MyLocations.sqlite file from the Library directory.
2. Remove the entire app from the Simulator.

➤ Remove the MyLocations.sqlite file, as well as the –shm and –wal files, and run the app again.

That wasn't actually the crash I wanted to show you, but it's important to know that changing the data model may require you to throw away the database file or Core Data cannot be initialized properly.


> **Note:** Not all is lost if `NSPersistentContainer`'s migration fails. Core Data allows you to perform your own migrations when you release an update to your app with a new data model. Instead of crashing, this mechanism allows you to convert the contents of the user's existing data store to the new model. However, during development, it is just as easy to toss out the old database.

➤ Now here's the trick. Tap the Get My Location button and then tap immediately on Tag Location. If you do that quickly enough, you can beat the reverse geocoder to it and the Tag Location screen will say: "No Address Found". It only says that when `placemark` is `nil`.

If geocoding happens too fast, you can fake this by temporarily commenting out the line `self.placemark = p.last!` in `locationManager(_:didUpdateLocations:)` inside **CurrentLocationViewController.swift**. This will make it seem as if no address was found and the value of `placemark` stays `nil`.

➤ Tap the Done button to save the new `Location` object.

The app will crash:



The app crashes after a Core Data error

At the very end of that error message — the above doesn't show the full error message, but the Xcode console will —, you can see that it says:

```
NSValidationErrorKey=placemark
```

This means the `placemark` attribute did not validate properly. Because you set it to non-optional, Core Data does not accept a placemark value that is `nil`.

Of course, what you've just seen only happens when you run the app from Xcode — when it crashes, the debugger takes over and points at the line with the error. But that's not what the user sees.

➤ Stop the app. Now tap the app's icon in the Simulator to launch the app outside of Xcode. Repeat the same procedure to make the app crash. The app will simply cease functioning and disappear from the screen.

Imagine this happening to a user who just paid 99 cents (or more) for your app. They'll be horribly confused, "What just happened?!" They may even ask for their money back.

It's better to show an alert when this happens. After the user dismisses that alert, you'll still make the app crash, but at least the user knows the reason why.

The alert message should probably ask them to contact you and explain what they did, so you can fix that bug in the next version of your app.

Alert the user about crashes

➤ Add the following code to **Functions.swift**:

```
let dataSaveFailedNotification = Notification.Name(
  rawValue: "DataSaveFailedNotification")

func fatalCoreDataError(_ error: Error) {
```

```
    print("*** Fatal error: \(error)")
    NotificationCenter.default.post(
      name: dataSaveFailedNotification,
      object: nil)
  }
```

This defines a new global function for handling fatal Core Data errors.

➤ Replace the error handling code in the `done()` action in **LocationDetailsViewController.swift** with:

```
  . . .
  } catch {
    fatalCoreDataError(error)
  }
```

The call to `fatalCoreDataError()` has taken the place of `fatalError()`. So what does that new function do, actually?

It first outputs the error message to the Console using `print()` because it's always useful to log such errors. After dumping the debug info, the function does the following:

```
  NotificationCenter.default.post(name:
  dataSaveFailedNotification, object: nil)
```

I've been using the term "notification" to mean any generic event or message being delivered, but the iOS SDK also has an object called the `NotificationCenter` — not to be confused with Notification Center on your iOS device.

The code above uses `NotificationCenter` to post a notification. Any object in your app can subscribe to such notifications and when these occur, `NotificationCenter` will call a certain method in those listener objects.

Using this official notification system is yet another way that your objects can communicate with each other. The handy thing is that the object that sends the notification and the object that receives the notification don't need to know anything about each other. The sender just broadcasts the notification to all and doesn't really care what happens to it. If anyone is listening, great. If not, then that's cool too.

UIKit defines a lot of standard notifications that you can subscribe to. For example, there is a notification that lets you know that the app is about to be suspended after the user taps the Home button.

You can also define your own notifications, and that is what you've done here. The new notification is called `dataSaveFailedNotification`.

The idea is that there is one place in the app that listens for this notification, pops up an alert view, and terminates. The great thing about using `NotificationCenter` is that your Core Data code does not need to care about any of this.

Whenever a saving error occurs, no matter at which point in the app, the `fatalCoreDataError(_:)` function sends out this notification, safe in the belief that some other object is listening for the notification and will handle the error.

So who will actually handle the error? The scene delegate is a good place for this. It's the top-level object in the app and it's always guaranteed to exist.

➤ Add the following method to **SceneDelegate.swift**:

```
// MARK: - Helper methods
func listenForFatalCoreDataNotifications() {
  // 1
  NotificationCenter.default.addObserver(
    forName: dataSaveFailedNotification,
    object: nil,
    queue: OperationQueue.main
  ) { _ in
      // 2
      let message = """
      There was a fatal error in the app and it cannot continue.

      Press OK to terminate the app. Sorry for the
inconvenience.
      """
      // 3
      let alert = UIAlertController(
        title: "Internal Error",
        message: message,
        preferredStyle: .alert)

      // 4
      let action = UIAlertAction(title: "OK", style: .default) {
_ in
        let exception = NSException(
          name: NSExceptionName.internalInconsistencyException,
          reason: "Fatal Core Data error",
          userInfo: nil)
        exception.raise()
      }
      alert.addAction(action)

      // 5
      let tabController = self.window!.rootViewController!
```

```
        tabController.present(
          alert,
          animated: true,
          completion: nil)
    }
  }
```

Here's how this works step-by-step:

1. Tell `NotificationCenter` that you want to be notified whenever a `dataSaveFailedNotification` is posted. The actual code that is performed when that happens sits in a trailing closure.

2. Set up the error message to display. This could have been done using a normal string by inserting new lines (`\n`) as you've seen done before, but this shows another way to do this — using multiline strings.

   Note that the multiline string starts and ends with a triple quote (`"""`) and that the first line of the string has to start on a new line and the closing triple quotes have to be on a new line as well. You can include new lines and other special characters like quotes within the string. So it can be really handy, even if it looks a little weird :]

3. Create a `UIAlertController` to show the error message and use the multiline string from earlier as the message.

4. Add an action for the alert's OK button. The code for handling the button press is again a closure — these things are everywhere! Instead of calling `fatalError()`, the closure creates an `NSException` object to terminate the app. That's a bit nicer and it provides more information to the crash log.


5. To show the alert with `present(animated:completion:)` you need a view controller that is currently visible. You simply use the window's `rootViewController` — in this app that is the tab bar controller — since it will be visible at all times as per the current navigation flow of the app.

All that remains is calling this new method so that the notification handler is registered with `NotificationCenter`.

➤ Add the following to the end of `scene(_:willConnectTo:options:)`:

```
  listenForFatalCoreDataNotifications()
```

➤ Run the app again and try to tag a location before the street address has been obtained. Even though the app still crashes when you tap the OK button on the alert, at least now it tells the user what's going on:



The app crashes with a message

Again, I should stress that you test your app thoroughly to make sure you're not giving Core Data any objects that do not validate. You want to avoid these save errors at all costs!

Ideally, users should never have to see that alert view, but it's good to have it in place because there are no guarantees your app won't have bugs.

> **Note:** You can legitimately use `managedObjectContext.save()` to let Core Data validate user input. There is no requirement that you make your app crash after an unsuccessful save, only if the error was unexpected and definitely shouldn't have happened!
>
> Besides the "optional" flag, there are many more validation settings you can set for your entities. If you let users enter data that needs to go into these attributes, then it's perfectly acceptable to use `save()` to validate input. If it throws an error, then a user input is invalid and you need to handle it.

➤ In the data model, set the **placemark** attribute back to optional (and uncomment the code in **CurrentLocationViewController.swift**, if you did comment out the `placemark` line).

Run the app just to make sure everything works as it should.


You can find the project files for this chapter under **27-Saving-locations** in the Source Code folder.

Chapter 28: The Locations Tab

By Fahim Farook

You've set up the data model and given the app the ability to save new locations to the data store. Next, you'll show these saved locations in a table view in the second tab.

The completed Locations screen will look like this:



The Locations screen

This chapter covers the following:

- **The locations tab:** Set up the second tab to display a list of saved locations.
- **Create a custom table view cell subclass:** Create a custom table view cell subclass to handle displaying location information.
- **Edit locations:** Add functionality to allow editing of items in the locations list.
- **Use NSFetchedResultsController:** How do you use `NSFetchedResultsController` to fetch data from your Core Data store?
- **Delete Locations:** Add the ability to the UI to delete locations, thus removing them from the Core Data store as well.
- **Table view sections:** Use built-in Core Data functionality to add the ability to display separate sections based on the location category.

The Locations tab


➤ Open the storyboard and drag a new **Navigation Controller** on to the canvas — it has a table view controller attached to it, which is fine. You'll use that in a second.

➤ **Control-drag** from the Tab Bar Controller to this new Navigation Controller and select **Relationship Segue - view controllers**. This adds the navigation controller to the tab bar.

➤ The Navigation Controller now has a **Tab Bar Item** that is named "Item". Rename it to **Locations**.


➤ Change the navigation bar of the new table view controller so that the title is set to **Locations**.

The storyboard now looks like this:



The storyboard after adding the Locations screen

➤ Run the app and activate the Locations tab. It doesn't show anything useful yet:



The Locations screen in the second tab

Design the table view cell

Before you can show any data in the table, you have to design the prototype cell.

➤ Set the prototype cell's Reuse Identifier to **LocationCell**.

➤ In the **Size inspector**, change **Row Height** to 65.

➤ Drag two Labels on to the cell. Give the top one the text **Description** and the bottom one the text **Address**. This is just so you know what they are for.

➤ Set the font of the Description label to **System Bold**, size **17**. Give this label a tag of **100**.

➤ Set the font of the Address label to **System**, size **14**. Set the text color to **black with 50% opacity** (so its looks like a medium gray). Give it a tag of **101**.

The cell will look something like this:



The prototype cell

Drag the labels handles so that they are wide enough to span the entire cell, position them vertically to suit your taste, and then set up AutoLayout constraints for the **left**, **top**, **right**, and **bottom** so that the labels stay in place even if the screen dimensions changed.

The basic table view controller

Let's write the code for the view controller. You've seen table view controllers several times now, so this should be easy.

You're going to fake the content first, because it's a good idea to make sure that the prototype cell works before you have to deal with Core Data.

➤ Add a new file to the project and name it **LocationsViewController.swift**.

> **Tip:** If you want to keep your list of source files neatly sorted by name in the project navigator, then right-click the MyLocations group (the yellow folder icon) and choose **Sort by Name** from the menu.

➤ Change the contents of **LocationsViewController.swift** to:

```
import UIKit
import CoreData
import CoreLocation

class LocationsViewController: UITableViewController {
  var managedObjectContext: NSManagedObjectContext!

  // MARK: - Table View Delegates
  override func tableView(
    _ tableView: UITableView,
    numberOfRowsInSection section: Int
  ) -> Int {
    return 1
  }

  override func tableView(
    _ tableView: UITableView,
    cellForRowAt indexPath: IndexPath
  ) -> UITableViewCell {
    let cell = tableView.dequeueReusableCell(
      withIdentifier: "LocationCell",
      for: indexPath)

    let descriptionLabel = cell.viewWithTag(100) as! UILabel
    descriptionLabel.text = "If you can see this"


    let addressLabel = cell.viewWithTag(101) as! UILabel
    addressLabel.text = "Then it works!"

    return cell
  }
}
```

You've faked a single row with some placeholder text in the labels. You've also given this class an `NSManagedObjectContext` property even though you won't be using it yet.

➤ Switch to the storyboard, select the Locations scene, and in the **Identity inspector**, change the **Class** of the table view controller to **LocationsViewController** — be careful with the auto completion when you're doing this since you also have a LocationsDetailViewController and that might get auto added if you are not careful...

➤ Run the app to make sure the table view works.



The table view with fake data

Great! Now it's time to fill the table with the Location objects from the data store.

Get Locations from data store

➤ Run the app and tag a handful of locations. If there is no data in the data store, then the app doesn't have much to show...

This new part of the app doesn't know anything yet about the `Location` objects that you have added to the data store. In order to display them in the table view, you need to obtain references to these objects somehow. You can do that by asking the data store. This is called *fetching*.

➤ First, add a new instance variable to **LocationsViewController.swift**:

```
var locations = [Location]()
```

This array will hold the list of `Location` objects.

➤ Add a `viewDidLoad()` implementation:

```
override func viewDidLoad() {
  super.viewDidLoad()
  // 1
  let fetchRequest = NSFetchRequest<Location>()
  // 2
  let entity = Location.entity()
  fetchRequest.entity = entity
  // 3
  let sortDescriptor = NSSortDescriptor(
    key: "date",
    ascending: true)
  fetchRequest.sortDescriptors = [sortDescriptor]
  do {
    // 4
    locations = try managedObjectContext.fetch(fetchRequest)
  } catch {
    fatalCoreDataError(error)
  }
}
```

This may look daunting but it's actually quite simple. You're going to ask the managed object context for a list of all `Location` objects in the data store, sorted by date.

1. The `NSFetchRequest` is the object that describes which objects you're going to fetch from the data store. To retrieve an object that you previously saved to the data store, you create a fetch request that describes the search parameters of the object — or objects — that you're looking for.
2. Here you tell the fetch request you're looking for `Location` entities.
3. The `NSSortDescriptor` tells the fetch request to sort on the `date` attribute, in ascending order so that the `Location` objects that the user added first will be at the top of the list. You can sort on any attribute here — later on, you'll sort on the `Location`'s category as well.

   That completes the fetch request. It took a few lines of code, but basically you said: "Get all `Location` objects from the data store and sort them by date."
4. Now that you have a fetch request, you can tell the context to execute it. The `fetch()` method returns an array with the sorted objects, or throws an error in case something went wrong. That's why this happens inside a `do-try-catch` block.

   If everything goes well, you assign the results of the fetch to the `locations` instance variable.

> **Note:** To create the fetch request you wrote `NSFetchRequest<Location>`.
>
> The `< >` mean that `NSFetchRequest` is a *generic*. Recall that arrays are also generics — to create an array you specify the type of objects that go into the array, either using the shorthand notation `[Location]`, or the longer `Array<Location>`.
>
> To use an `NSFetchRequest`, you need to tell it what type of object you're going to be fetching. Here, you create an `NSFetchRequest<Location>` so that the result of `fetch()` is an array of `Location` objects.

You could have simplified the code above by combining sections 1 and 2 as follows:

```
let fetchRequest = NSFetchRequest<Location>(entityName:
"Location")
```

This does the same thing as the previous code by specifying the entity name in the `NSFetchRequest` initializer. However, this code is a bit more error prone since you are relying on a string name for the entity. If you misspelt something — for example, you said "Locations" instead of "Location" — your code would crash when you ran it because Core Data can't find the entity.

Using the actual `Location` object to return the underlying entity prevents that kind of mistake. So our code might be a bit more verbose, but it's also safer.

Display the fetched Locations

Now that you've loaded the list of `Location` objects into an instance variable, you can change the table view's data source methods.

➤ Change the data source methods to:

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return locations.count
}
```

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "LocationCell",
    for: indexPath)

  let location = locations[indexPath.row]

  let descriptionLabel = cell.viewWithTag(100) as! UILabel
  descriptionLabel.text = location.locationDescription

  let addressLabel = cell.viewWithTag(101) as! UILabel
  if let placemark = location.placemark {
    var text = ""
    if let tmp = placemark.subThoroughfare {
      text += tmp + " "
    }
    if let tmp = placemark.thoroughfare {
      text += tmp + ", "
    }
    if let tmp = placemark.locality {
      text += tmp
    }
```

```
      addressLabel.text = text
    } else {
      addressLabel.text = ""
    }
    return cell
  }
```

This should have no surprises for you. You get the `Location` object for the row from the array and then use its properties to fill the labels. Because `placemark` is an optional, you use `if let` to unwrap it.

➤ Run the app. Now switch to the Locations tab and... crap! It crashes.

The error message should say something like:

```
Fatal error: Unexpectedly found nil while implicitly unwrapping
an Optional value
```

Exercise: What did you forget?

Answer: You added a `managedObjectContext` property to `LocationsViewController`, but never gave this property a value. Therefore, there is nothing to fetch `Location` objects from.

If you already noticed this and were like, "How come we are not passing the value from SceneDelegate?", good job! You are really getting the hang of this.


➤ Switch to **SceneDelegate.swift**. In `scene(_:WillConnectTo:options:)`, change the `if let tabBarViewControllers` block, as follows:

```
  if let tabViewControllers = tabController.viewControllers {
    // First tab
    var navController = tabViewControllers[0] as!
  UINavigationController
    let controller1 = navController.viewControllers.first
                      as! CurrentLocationViewController
    controller1.managedObjectContext = managedObjectContext
    // Second tab
    navController = tabViewControllers[1] as!
  UINavigationController
    let controller2 = navController.viewControllers.first
                      as! LocationsViewController
    controller2.managedObjectContext = managedObjectContext
  }
```

There are a couple of minor changes to the existing code — one is to make `navController` a variable so that it can be re-used for the second tab, and the second is to rename the `controller` constant to `controller1` to separate it from the the second view controller which would be of a different type.

The code for the second tab looks up the `LocationsViewController` in the storyboard and gives it a reference to the managed object context, similar to what you did for the first tab.

➤ Run the app again and switch to the Locations tab. Core Data properly fetches the objects and displays them:



The list of Locations

Note that the list doesn't update yet if you tag a new location. You have to restart the app to see the new `Location` object appear. You'll solve this later on.

Create a custom table view cell subclass

Using `viewWithTag(_:)` to find the labels from the table view cell works, but it doesn't look very object-oriented to me.

It would be much nicer if you could make your own `UITableViewCell` subclass and give it outlets for the labels. Fortunately, you can, and it's pretty easy!

➤ Add a new file to the project using the **Cocoa Touch Class** template. Name it **LocationCell** and make it a subclass of **UITableViewCell**. Make sure that the class name does not change when you set the subclass — that can be a little annoying.

➤ Add the following outlets to **LocationCell.swift**, inside the class definition:

```
@IBOutlet var descriptionLabel: UILabel!
@IBOutlet var addressLabel: UILabel!
```

➤ Open the storyboard and select the prototype cell that you made earlier. In the **Identity inspector**, set **Class** to **LocationCell**.

➤ Now you can connect the two labels to the two outlets. This time the outlets are not on the view controller but on the cell, so use the `LocationCell`'s Connections inspector to connect the `descriptionLabel` and `addressLabel` outlets.

That is all you need to do to make the table view use your own table view cell class. But, you do need to update `LocationsViewController` to make use of it.

➤ In **LocationsViewController.swift**, replace `tableView(cellForRowAt)` with the following:

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "LocationCell",
    for: indexPath) as! LocationCell

  let location = locations[indexPath.row]
  cell.configure(for: location)

  return cell
}
```

As before, this asks for a cell using `dequeueReusableCell(withIdentifier:for:)`, but now this will be a `LocationCell` object instead of a regular `UITableViewCell`. That's why you've added the type cast.

Note that the string `LocationCell` is the re-use identifier from the placeholder cell, but `LocationCell` is the class of the actual cell object that you're getting.

They have the same name but one is a `String` and the other is a `UITableViewCell` subclass with extra properties. I hope that's not too confusing.

Once you have the cell reference, you call a new method, `configure(for:)` to put the `Location` object into the table view cell.

➤ Add this new method to **LocationCell.swift**:

```
// MARK: - Helper Method
func configure(for location: Location) {
  if location.locationDescription.isEmpty {
    descriptionLabel.text = "(No Description)"
  } else {
    descriptionLabel.text = location.locationDescription
  }

  if let placemark = location.placemark {
    var text = ""
```

```
      if let tmp = placemark.subThoroughfare {
        text += tmp + " "
      }
      if let tmp = placemark.thoroughfare {
        text += tmp + ", "
      }
      if let tmp = placemark.locality {
        text += tmp
      }
      addressLabel.text = text
    } else {
      addressLabel.text = String(
        format: "Lat: %.8f, Long: %.8f",
        location.latitude,
        location.longitude)
    }
  }
```

Instead of using `viewWithTag(_:)` to find the description and address labels, you now simply use the `descriptionLabel` and `addressLabel` properties of the cell.

➤ Run the app to make sure everything still works. If you have a location without a description, the table cell will now say "(No Description)". If there is no placemark, the address label contains the GPS coordinates.

When using a custom subclass for your table view cells there is no limit to how complex the cell functionality can be.

Edit locations


You will now connect the `LocationsViewController` to the Location Details screen, so that when you tap a row in the table, it lets you edit that location's description and category.

You'll be re-using the `LocationDetailsViewController` but have it edit an existing `Location` object rather than add a new one.

Create edit segue

➤ Go to the storyboard. Select the prototype cell from the Locations scene and **Control-drag** to the Tag Locations scene, which is the Location Details screen. Add a **Show** selection segue and set its **Identifier** to **EditLocation**.

At this point the storyboard should look like this:



The Location Details screen is now also connected to the Locations screen

There are now two segues from two different screens going to the same view controller.

This is the reason why you should build your view controllers to be as independent of their "calling" controllers as possible. You can then easily re-use them somewhere else in your app.

Soon, you will be calling this same screen from yet another place. In total there will be three segues to it.

➤ Go to **LocationsViewController.swift** and add the following code:

```
// MARK: - Navigation
override func prepare(for segue: UIStoryboardSegue, sender:
Any?) {
  if segue.identifier == "EditLocation" {
    let controller = segue.destination  as!
LocationDetailsViewController
    controller.managedObjectContext = managedObjectContext

    if let indexPath = tableView.indexPath(
      for: sender as! UITableViewCell) {
      let location = locations[indexPath.row]
      controller.locationToEdit = location
    }
  }
}
```

This method is invoked when the user taps a row in the Locations screen. It figures out which `Location` object belongs to the row and puts it in the new `locationToEdit` property of `LocationDetailsViewController`. This property doesn't exist yet, but you'll add it in a moment.

★ ★ ★

The Any type

The type of the `sender` parameter is `Any`. You have seen this type in a few places before. What is it?

Objective-C has a special type, `id`, that means "any object". It's similar to `NSObject` except that it doesn't make any assumptions at all about the underlying type of the object. `id` doesn't have any methods, properties or instance variables, it's a completely naked object reference.

All objects in an Objective-C program can be treated as having type `id`. As a result, a lot of the APIs from iOS frameworks depend on this special `id` type. This is a powerful feature of Objective-C, but unfortunately, a dynamic type like `id` doesn't really fit in a *strongly typed* language such as Swift.

Still, we can't avoid `id` completely because it's so prevalent in iOS frameworks. The Swift equivalent of `id` is the `Any` type.

The `sender` parameter from `prepare(for:sender:)` can be any kind of object, and so has type `Any` – and thanks to the question mark it can also be `nil`.

If the segue is triggered from a table view, `sender` is of type `UITableViewCell`. If triggered from a `button`, sender is of type `UIButton` (or `UIBarButtonItem`), and so on.

Objects that appear as type `Any` are not very useful in that form, and you'll have to tell Swift what sort of object it really is. In the code that you just wrote, `indexPath(for:)` expects a `UITableViewCell` object, not an `Any` object.

You and I both know that `sender` in this case really is a `UITableViewCell` because the only way to trigger this segue is to tap a table view cell. With the `as!` type cast you're giving Swift your word (scout's honor!) that it can safely interpret `sender` as a `UITableViewCell`.

Of course, if you were to hook up this segue to something else, such as a button, then this assumption is no longer valid and the app will crash.

Set up the edit view controller

When editing an existing `Location` object, you have to do a few things differently in the `LocationDetailsViewController`. The title of the screen shouldn't be "Tag Location" but "Edit Location". You also must put the values from the existing `Location` object into the various cells.

The value of the new `locationToEdit` property determines whether the screen operates in "add" mode or in "edit" mode.

➤ Add these properties to **LocationDetailsViewController.swift**:

```
var locationToEdit: Location?
var descriptionText = ""
```

`locationToEdit` needs to be an optional because in "add" mode it will be `nil`.

➤ Update `viewDidLoad()` to check whether `locationToEdit` is set:

```
override func viewDidLoad() {
  super.viewDidLoad()
  if let location = locationToEdit {
    title = "Edit Location"
  }
  . . .
}
```

If `locationToEdit` is not `nil`, you're editing an existing `Location` object. In that case, the title of the screen becomes "Edit Location".

> **Note:** Xcode gives a warning on the line `if let location = locationToEdit` because you're not using the value of `location` anywhere. If you click the yellow icon, Xcode suggests that you replace it with `if locationToEdit != nil`. You *will* use `location` in a bit, so ignore Xcode's suggestion.

➤ Also change this line in `viewDidLoad()`:

```
descriptionTextView.text = descriptionText
```

You load the value of the new `descriptionText` variable into the text view.

Now how do you get the values from the `locationToEdit` object into the text view and labels of this view controller? Swift has a really cool **property observer** feature that is perfect for this.

➤ Change the declaration of the `locationToEdit` property to the following:


```
var locationToEdit: Location? {
  didSet {
    if let location = locationToEdit {
      descriptionText = location.locationDescription
      categoryName = location.category
      date = location.date
      coordinate = CLLocationCoordinate2DMake(
        location.latitude,
        location.longitude)
      placemark = location.placemark
    }
  }
}
```

If a variable has a `didSet` block, then the code in this block is performed whenever you put a new value into that variable — very handy!

Here, you take the opportunity to fill in the view controller's instance variables with the `Location` object's values.

Because `prepare(for:sender:)` — and therefore `locationToEdit`'s `didSet` — is called before `viewDidLoad()`, this puts the right values on the screen before it becomes visible.

➤ Run the app, go to the Locations tab and tap on a row. The Edit Location screen should now appear with the data from the selected location:



Editing an existing location

➤ Change the description of the location and press Done.

Nothing happened?! Well, that's not quite true. Stop the app and run it again. You will see that a new location has been added with the changed description, but the old one is still there as well.

Fix the edit screen

There are two problems to solve:

1. When editing an existing location you must save changes to that location instead of creating a new entry.
2. The Locations screen doesn't update to reflect any changes to the data.

The first fix is easy.

➤ Still in **LocationDetailsViewController.swift**, change the top part of `done()`:

```
@IBAction func done() {
  guard let mainView = . . .
  let hudView = HudView.hud(inView: . . .)

  let location: Location
  if let temp = locationToEdit {
    hudView.text = "Updated"
    location = temp
  } else {
    hudView.text = "Tagged"
    location = Location(context: managedObjectContext)
  }

  location.locationDescription = descriptionTextView.text
  . . .
```

The change is straightforward: you only ask Core Data for a new `Location` object if you don't already have one. You also make the text in the HUD say "Updated" when the user is editing an existing `Location`.

> **Note:** I've been harping on about the fact that Swift requires all non-optional variables and constants to always have a value. But here you declare `let location` without giving it an initial value. What gives?
>
> Well, the `if` statement that follows this declaration always puts a value into `location`, either the unwrapped value of `locationToEdit`, or a new `Location` object obtained from Core Data. After the `if` statement, `location` is guaranteed to have a value. Swift is cool with that.

➤ Run the app again and edit a location. Now the HUD should say "Updated".

➤ Stop the app and run it again to verify that the object was indeed properly changed. You can also look at the data directly in the SQLite database, of course.

> **Exercise:** Why do you think the table view isn't being updated after you change a `Location` object? Recall that the table view also doesn't update when you tag new locations.

Answer: You fetch the `Location` objects in `viewDidLoad()`. But `viewDidLoad()` is only performed once, when the app starts. After the initial load of the `Locations` screen, its contents are never refreshed.

In *Checklists*, you solved this by using a delegate and that would be a valid solution here too. The `LocationDetailsViewController` could tell you through delegate methods that a location has been added or changed.

However, since you're using Core Data, there is a better way to do this.

Use NSFetchedResultsController

As you are no doubt aware by now, table views are everywhere in iOS apps. A lot of the time when you're working with Core Data, you want to fetch objects from the data store and show them in a table view. And when those objects change, you want to do a live update of the table view in response, to show the changes to the user.

So far, you've filled the table view by manually fetching the results, but then you also need to manually check for changes and perform the fetch again to update the table. With `NSFetchedResultsController`, all that manual work is no longer needed.

It works like this: you give `NSFetchedResultsController` a fetch request, just like the `NSFetchRequest` you made earlier, and tell it to go fetch the objects. So far nothing new.

But, you don't put the results from that fetch into your own array. Instead, you read them straight from the fetched results controller. In addition, you make the view controller the delegate for the `NSFetchedResultsController`. Through this delegate, the view controller is informed that objects have been changed, added or deleted so that it can update the table in response.

➤ In **LocationsViewController.swift**, replace the `locations` instance variable with a new `fetchedResultsController` variable:

```
lazy var fetchedResultsController:
NSFetchedResultsController<Location> = {
  let fetchRequest = NSFetchRequest<Location>()

  let entity = Location.entity()
  fetchRequest.entity = entity

  let sortDescriptor = NSSortDescriptor(
    key: "date",
    ascending: true)
  fetchRequest.sortDescriptors = [sortDescriptor]

  fetchRequest.fetchBatchSize = 20

  let fetchedResultsController = NSFetchedResultsController(
    fetchRequest: fetchRequest,
    managedObjectContext: self.managedObjectContext,
    sectionNameKeyPath: nil,
    cacheName: "Locations")

  fetchedResultsController.delegate = self
  return fetchedResultsController
}()
```

This again uses the lazy initialization pattern with a closure to set everything up. It's good to get into the habit of lazily loading objects. You don't allocate them until you first use them. This makes your apps quicker to start and it saves memory.

The code in the closure does the same thing that you used to do in `viewDidLoad()`: it makes an `NSFetchRequest` and gives it an entity and a sort descriptor.

> **Note:** Note that the new variable is not just `NSFetchedResultsController` but `NSFetchedResultsController<Location>`, since it's a generic. You need to tell the fetched results controller what type of objects to fetch.

But this line is new:

```
fetchRequest.fetchBatchSize = 20
```

If you have a huge table with hundreds of objects, then it requires a lot of memory to keep all of these objects around, even though you can only see a handful of them at a time.

The NSFetchedResultsController is pretty smart about this and will only fetch the objects that you can actually see, which cuts down on memory usage. This is all done in the background without you having to worry about it. The fetch batch size setting allows you to tweak how many objects will be fetched at a time.

Once the fetch request is set up, you create the star of the show:

```
let fetchedResultsController = NSFetchedResultsController(
  fetchRequest: fetchRequest,
  managedObjectContext: self.managedObjectContext,
  sectionNameKeyPath: nil,
  cacheName: "Locations")
```

The cacheName needs to be a unique name that NSFetchedResultsController uses to cache the search results. It keeps this cache around even after your app quits, so the next time the fetch request is lightning fast, as the NSFetchedResultsController doesn't have to make a round-trip to the database but can simply read from the cache.

We'll talk about the sectionNameKeyPath parameter shortly.

The line that sets fetchedResultsController.delegate to self currently gives an error message because LocationsViewController does not conform to the right delegate protocol yet. You'll fix that in minute.

Now that you have a fetched results controller, you clean up viewDidLoad().

➤ Change viewDidLoad() like this:

```
override func viewDidLoad() {
  super.viewDidLoad()
  performFetch()
}

// MARK: - Helper methods
func performFetch() {
  do {
    try fetchedResultsController.performFetch()
  } catch {
    fatalCoreDataError(error)
  }
}
```

You still perform the initial fetch in viewDidLoad(), using the new performFetch() helper method. However, if any Location objects change after that initial fetch, the NSFetchedResultsController's delegate methods are called to let you know about these changes. I'll show you how in a second.

It's always a good idea to explicitly set the delegate to `nil` when you no longer need the `NSFetchedResultsController`, just so you don't get any more notifications that were still pending.

➤ For that reason, add a `deinit` method:

```
deinit {
  fetchedResultsController.delegate = nil
}
```

The `deinit` method is invoked when this view controller is destroyed. It may not be strictly necessary to `nil` out the delegate here, but it's a bit of defensive programming that won't hurt.

Note that in this app the `LocationsViewController` will never actually be deallocated because it's one of the top-level view controllers in the tab bar. Still, it's good to get into the habit of writing `deinit` methods.

Because you removed the `locations` array, you should also change the table's data source methods.

➤ Change `tableView(_:numberOfRowsInSection:)` to:

```
override func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  let sectionInfo = fetchedResultsController.sections![section]
  return sectionInfo.numberOfObjects
}
```

The fetched results controller's `sections` property returns an array of `NSFetchedResultsSectionInfo` objects that describe each section of the table view. The number of rows is found in the section info's `numberOfObjects` property.

Currently there is only one section in your app, but later you'll split up the locations by category and then each category will get its own section.

➤ Change `tableView(_:cellForRowAt:)` to:

```
override func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cell = tableView.dequeueReusableCell(
    withIdentifier: "LocationCell",
    for: indexPath) as! LocationCell
```

```
    let location = fetchedResultsController.object(at: indexPath)
    cell.configure(for: location)

    return cell
  }
```

Instead of looking into the `locations` array like you did before, you now ask the `fetchedResultsController` for the object at the requested index-path. Because it is designed to work closely with table views, `NSFetchedResultsController` knows how to deal with index-paths, so that's very convenient.

➤ Make the same change in `prepare(for:sender:)` to get the correct `Location` object.

There is still one piece of the puzzle missing. You need to implement the delegate methods for `NSFetchedResultsController` in `LocationsViewController`. Let's use an *extension* for that, to keep the code organized.

Organize the code using extensions

An extension lets you add code to an existing class without having to modify the original class source code. When you make an extension you say, "here are a bunch of extra methods that also need to go into that class", and you can do that even if you didn't write the original class to begin with.

You've seen an extension used in Location+CoreDataProperties.swift. That was done to make it easier for Xcode to regenerate this file without overwriting the contents of Location+CoreDataClass.swift.

You can also use extensions to organize your source code. Here you'll use an extension just for the `NSFetchedResultsControllerDelegate` methods, so they are not all tangled up with `LocationsViewController`'s other code. By putting this code in a separate unit, you keep the responsibilities separate.

This makes it easy to spot which part of `LocationsViewController` plays the role of the delegate. All the fetched results controller delegate stuff happens just in this extension, not in the main body of the class — you could even place this extension in a separate Swift file if you wanted.

➤ Add the following code to the bottom of **LocationsViewController.swift**, outside of the class implementation:

```
// MARK: - NSFetchedResultsController Delegate Extension
extension LocationsViewController:
NSFetchedResultsControllerDelegate {
```

```
  func controllerWillChangeContent(
    _ controller:
NSFetchedResultsController<NSFetchRequestResult>
  ) {
    print("*** controllerWillChangeContent")
    tableView.beginUpdates()
  }

  func controller(
    _ controller:
NSFetchedResultsController<NSFetchRequestResult>,
    didChange anObject: Any,
    at indexPath: IndexPath?,
    for type: NSFetchedResultsChangeType,
    newIndexPath: IndexPath?
  ) {
    switch type {
    case .insert:
      print("*** NSFetchedResultsChangeInsert (object)")
      tableView.insertRows(at: [newIndexPath!], with: .fade)

    case .delete:
      print("*** NSFetchedResultsChangeDelete (object)")
      tableView.deleteRows(at: [indexPath!], with: .fade)

    case .update:
      print("*** NSFetchedResultsChangeUpdate (object)")
      if let cell = tableView.cellForRow(
        at: indexPath!) as? LocationCell {
        let location = controller.object(
          at: indexPath!) as! Location
        cell.configure(for: location)
      }

    case .move:
      print("*** NSFetchedResultsChangeMove (object)")
      tableView.deleteRows(at: [indexPath!], with: .fade)
      tableView.insertRows(at: [newIndexPath!], with: .fade)

    @unknown default:
      print("*** NSFetchedResults unknown type")
    }
  }

  func controller(
    _ controller:
NSFetchedResultsController<NSFetchRequestResult>,
    didChange sectionInfo: NSFetchedResultsSectionInfo,
    atSectionIndex sectionIndex: Int,
    for type: NSFetchedResultsChangeType
  ) {
    switch type {
    case .insert:
```

```
        print("*** NSFetchedResultsChangeInsert (section)")
        tableView.insertSections(
          IndexSet(integer: sectionIndex), with: .fade)
      case .delete:
        print("*** NSFetchedResultsChangeDelete (section)")
        tableView.deleteSections(
          IndexSet(integer: sectionIndex), with: .fade)
      case .update:
        print("*** NSFetchedResultsChangeUpdate (section)")
      case .move:
        print("*** NSFetchedResultsChangeMove (section)")
      @unknown default:
        print("*** NSFetchedResults unknown type")
      }
    }

    func controllerDidChangeContent(
      _ controller:
  NSFetchedResultsController<NSFetchRequestResult>
    ) {
      print("*** controllerDidChangeContent")
      tableView.endUpdates()
    }
  }
```

Yowza, that's a lot of code. Don't let this freak you out! This is the standard way of implementing these delegate methods. For many apps, this exact code will suffice and you can simply copy it over. Look it over for a few minutes to see if this code makes sense to you. You've made it this far, so I'm sure it won't be too hard.

`NSFetchedResultsController` will invoke these methods to let you know that certain objects were inserted, removed, or just updated. In response, you call the corresponding methods on the `UITableView` to insert, remove or update rows. That's all there is to it.

I put `print()` statements in these methods so you can follow along in the Console as to what is happening. Also note that you're using the `switch` statement here. A series of `if`'s would have worked just as well but `switch` reads better.

➤ Run the app. Edit an existing location and press the Done button.

The debug area now shows:

```
*** controllerWillChangeContent
*** NSFetchedResultsChangeUpdate (object)
*** controllerDidChangeContent
```

`NSFetchedResultsController` noticed that an existing object was updated and, through updating the table, called your `cell.configure(for:)` method to redraw the contents of the cell. By the time the Edit Location screen disappears from sight, the table view is updated and your change is visible.

This also works for adding new locations.

➤ Tag a new location and press the Done button.

The debug area says:

```
*** controllerWillChangeContent
*** NSFetchedResultsChangeInsert (object)
*** controllerDidChangeContent
```

This time it's an "insert" notification. The delegate methods tell the table view to do `insertRows(at:with:)` in response and the new `Location` object is inserted in the table.

That's how easy it is. You make a new `NSFetchedResultsController` object with a fetch request and implement the delegate methods.

The fetched results controller keeps an eye on any changes that you make to the data store and notifies its delegate in response.

It doesn't matter where in the app you make these changes, they can happen on any screen. When that screen saves the changes to the managed object context, the fetched results controller picks up on it right away.

Delete locations

Everyone makes mistakes. So, it's likely that users will want to delete locations from their list at some point. This is a very easy feature to add: you just have to remove the `Location` object from the data store and the `NSFetchedResultsController` will make sure it gets dropped from the table — again, through its delegate methods.

➤ Add the following method to **LocationsViewController.swift** under the table view delegate section:


```
override func tableView(
  _ tableView: UITableView,
  commit editingStyle: UITableViewCell.EditingStyle,
  forRowAt indexPath: IndexPath
) {
```

```
    if editingStyle == .delete {
      let location = fetchedResultsController.object(
        at: indexPath)
      managedObjectContext.delete(location)
      do {
        try managedObjectContext.save()
      } catch {
        fatalCoreDataError(error)
      }
    }
  }
```

You've seen `tableView(_:commit:forRowAt:)` before. It's part of the table view's data source protocol. As soon as you implement this method in your view controller, it enables swipe-to-delete.

This method gets the `Location` object from the selected row and then tells the context to delete that object. This will trigger the `NSFetchedResultsController` to send a notification to the delegate, which then removes the corresponding row from the table. That's all you need to do!

➤ Run the app and remove a location using swipe-to-delete. The `Location` object is dropped from the database and its row disappears from the screen with a brief animation.



Swipe to delete rows from the table


Mass editing

Many apps have an Edit button in the navigation bar that triggers a mode that also lets you delete — and sometimes move — rows. This is extremely easy to add.

➤ Add the following line to `viewDidLoad()` in **LocationsViewController.swift**:

```
  navigationItem.rightBarButtonItem = editButtonItem
```

That's all there is to it. Every view controller has a built-in Edit button that can be accessed through the `editButtonItem` property. Tapping that button puts the table in editing mode:



The table view in edit mode

➤ Run the app and verify that you can now also delete rows by pressing the Edit button.

Pretty sweet, huh? There's more cool stuff that `NSFetchedResultsController` makes really easy, such as splitting up the rows into sections.

Table view sections

The `Location` objects have a `category` field. It would be nice to group the locations by category in the table. The table view supports organizing rows into sections and each of these sections can have its own header.

Putting your rows into sections is a lot of work if you're doing it by hand, but `NSFetchedResultsController` practically gives you section support for free.

➤ Change the creation of the sort descriptors in the `fetchedResultsController` initialization block:

```
lazy var fetchedResultsController: . . . = {
  . . .
  let sort1 = NSSortDescriptor(key: "category", ascending: true)
  let sort2 = NSSortDescriptor(key: "date", ascending: true)
  fetchRequest.sortDescriptors = [sort1, sort2]
  . . .
```

Instead of one sort descriptor object, you now have two. First you sort the `Location` objects by `category` and inside each of the category groups you sort by `date`.

➤ Also change the initialization of the `NSFetchedResultsController` object:

```
    let fetchedResultsController = NSFetchedResultsController(
      fetchRequest: fetchRequest,
      managedObjectContext: self.managedObjectContext,
      sectionNameKeyPath: "category",              // change this
      cacheName: "Locations")
```

The only difference here is that the `sectionNameKeyPath` parameter is set to "category", which means the fetched results controller will group the search results based on the value of the category attribute.

You're not done yet — the table view's data source also has methods for sections. So far you've only used the methods for rows, but now that you're adding sections to the table, you need to implement a few additional methods.

➤ Add the following methods to the table view delegate section:

```
  override func numberOfSections(
    in tableView: UITableView
  ) -> Int {
    return fetchedResultsController.sections!.count
  }


  override func tableView(
    _ tableView: UITableView,
    titleForHeaderInSection section: Int
  ) -> String? {
    let sectionInfo = fetchedResultsController.sections![section]
    return sectionInfo.name
  }
```

Because you let `NSFetchedResultsController` do all the work already, the implementation of these methods is very simple. You ask the fetcher object for a list of the sections, which is an array of `NSFetchedResultsSectionInfo` objects, and then look inside that array to find out how many sections there are and what their names are.

Exercise: Why do you need to write `sections!` with an exclamation point?

Answer: the `sections` property is an optional, so it needs to be unwrapped before you can use it. Here you know for sure that `sections` will never be `nil` — after all, you just told `NSFetchedResultsController` to group the search results based on the value of their "category" field — so you can safely force unwrap it using the exclamation mark. Are you starting to get the hang of these optionals already?

➤ Run the app. Play with the categories on the Locations tab and notice how the table view automatically updates. All thanks to `NSFetchedResultsController`!



The locations are now grouped in sections


You can find the project files for this chapter under **28-Locations-tab** in the Source Code folder.

Chapter 29: Maps

By Fahim Farook

Showing the locations in a table view is useful, but not very visually appealing. Given that the iOS SDK comes with an awesome map view control, it would be a shame not to use it :]

In this chapter, you will add a third tab to the app that will look like this when you are finished:



The completed Map screen

This is what you'll do in this chapter:

- **Add a map view:** Learn how to add a map view to your app and get it to show the current user location or pins for a given set of locations.
- **Make your own pins:** Learn to create custom pins to display information about points on a map.

Add a map view

First visit: the storyboard.

➤ From the Objects Library, drag a **View Controller** on to the canvas.


➤ Control-drag from the Tab Bar Controller to this new View Controller to add it to the tabs – choose **Relationship segue – view controllers**.

➤ The new view controller now has a **Tab Bar Item**. Change its title to **Map** via the **Attributes inspector**.

➤ Drag a **Map Kit View** into the view controller. Make it cover the entire visible area of the screen leaving out the navigation bar at the top and the tab bar at the bottom – the size of the Map View should be 375 × 574 points.

➤ Add **left**, **top**, **right**, and **bottom** Auto Layout constraints to the Map View via the **Add New Constraints** menu, pinning it to the main view.

➤ In the **Attributes inspector** for the Map View, enable **Shows: User Location**. That will put a blue dot on the map at the user's current coordinates.




Enable show user location for the Map View

➤ Select the new view controller and select **Editor ▸ Embed In ▸ Navigation Controller**. This wraps your view controller in a navigation controller, and makes the new navigation controller the view controller displayed by the Tab Bar Controller.

➤ Change the view controller's — not the new navigation controller, but its root view controller — Navigation Item title to **Map**.

➤ Drag a **Bar Button Item** into the left-hand slot of the navigation bar and set the title to **Locations**. Drag another into the right-hand slot and set its title to **User**. Later on you'll use nice icons for these buttons, but for now these labels will do.

This part of the storyboard should look like this:



The design of the Map screen

➤ Run the app. Choose a location in the Simulator's Features menu and switch to the Map. The screen should look something like this — the blue dot shows the current location:



The map shows the user's location

Sometimes, the map might show a different location than the current user location and you might not see the blue dot. If that happens, you can pan the map by clicking the mouse and dragging it across the Simulator window. Also, to zoom in or out, hold down the Alt/Option key while dragging the mouse.

Zoom in

Next, you're going to show the user's location in a little more detail because that blue dot could be almost anywhere in California!

➤ Add a new Swift source file to the project and name it **MapViewController**.

➤ Replace the contents of **MapViewController.swift** with the following:

```
import UIKit
import MapKit
import CoreData

class MapViewController: UIViewController {
  @IBOutlet var mapView: MKMapView!

  var managedObjectContext: NSManagedObjectContext!

  // MARK: - Actions
  @IBAction func showUser() {
    let region = MKCoordinateRegion(
      center: mapView.userLocation.coordinate,
      latitudinalMeters: 1000,
      longitudinalMeters: 1000)
    mapView.setRegion(
      mapView.regionThatFits(region),
      animated: true)
  }

  @IBAction func showLocations() {
  }
}

extension MapViewController: MKMapViewDelegate {
}
```

This is a standard view controller — not one of the specialized types like a table view controller. It has an outlet for the map view and two action methods that will be connected to the buttons in the navigation bar. The view controller is also the delegate of the map view, courtesy of the extension.


➤ In the storyboard, select the Map scene — the one with the view controller, not the one with the navigation controller — and in the **Identity inspector** set its **Class** to **MapViewController**.

➤ Connect the Locations button to the `showLocations` action and the User button to the `showUser` action. In case you forgot how, Control-drag from each button to the yellow circle for the view controller.

➤ Connect the Map View with the `mapView` outlet — Control-drag from the view controller to the Map View —, and its delegate with the view controller — Control-drag the other way around.

Currently the view controller only implements the `showUser()` action method. When you press the **User** button, it zooms in the map to a region that is 1000 by 1000 meters, a little more than half a mile in both directions, around the user's position.

Try it out:



Pressing the User button zooms in to the user's location

Show pins for locations

The other button, Locations, is going to show the region that contains all the user's saved locations. Before you can do that, you first have to fetch those locations from the data store.

Even though this screen doesn't have a table view, you could still use an `NSFetchedResultsController` object to handle all the fetching and automatic change detection. But this time, we're going to do this the hard way — you'll do the fetching by hand.

➤ Add a new array to **MapViewController.swift**:

```
var locations = [Location]()
```

➤ Also add this new method:

```
// MARK: - Helper methods
func updateLocations() {
  mapView.removeAnnotations(locations)

  let entity = Location.entity()

  let fetchRequest = NSFetchRequest<Location>()
  fetchRequest.entity = entity

  locations = try! managedObjectContext.fetch(fetchRequest)
  mapView.addAnnotations(locations)
}
```

The fetch request is nothing new, except this time you're not sorting the `Location` objects. The order of the `Location` objects in the array doesn't really matter to the map view — only their latitude and longitude coordinates.

You've already seen how to handle errors with a `do-try-catch` block. But if you're certain that a particular method call will never fail, you can dispense with the `do` and `catch` and just write `try!` with an exclamation point. As with other things in Swift that have exclamation points, if it turns out that you were wrong, the app will crash without mercy. But in this case there isn't much that can go wrong. So, you can choose to live a little more dangerously.

Once you've obtained the `Location` objects, you call `mapView.addAnnotations()` to add a pin for each location on the map.

The idea is that `updateLocations()` will be executed every time there is a change in the data store. How you'll do that is of later concern, but the point is that when this happens, the `locations` array may already exist and may contain `Location` objects. If so, you first remove the pins for these old objects with `removeAnnotations()`.

Xcode says the lines with `mapView.addAnnotations()` and `removeAnnotations()` have errors. This is to be expected and you'll fix it in a minute.

➤ First, add the `viewDidLoad()` method:

```
override func viewDidLoad() {
  super.viewDidLoad()
  updateLocations()
}
```

This fetches the `Location` objects and shows them on the map when the view loads. Nothing special here.

Before this class can use the `managedObjectContext`, you have to give it a reference to that object first. As before, that happens in `SceneDelegate`.

➤ In **SceneDelegate.swift**, extend `scene(_:willConnectTo:options:)` to pass the context object to the `MapViewController` as well. This goes inside the `if let` statement:

```
// Third tab
navController = tabViewControllers[2] as! UINavigationController
let controller3 = navController.viewControllers.first as!
MapViewController
controller3.managedObjectContext = managedObjectContext
```

You're not quite done yet. In `updateLocations()` you told the map view to add the `Location` objects as annotations — an annotation is a pin on the map — but `MKMapView` expects an array of `MKAnnotation` objects, not your own `Location` class.

Luckily, `MKAnnotation` is a protocol. So, you can turn the `Location` objects into map annotations by making the class conform to that protocol.

➤ Change the `class` line from **Location+CoreDataClass.swift** to:

```
public class Location: NSManagedObject, MKAnnotation {
```

Just because `Location` is an object that is managed by Core Data doesn't mean you can't add your own stuff to it. It's still an object!

> **Exercise:** Xcode now says "Cannot find type 'MKAnnotation' in scope". Why is that?

Answer: You still need to `import MapKit`. Add that line at the top of the file.

> **Exercise:** Xcode still shows an error about the class not conforming to the MKAnnotation protocol. What is wrong now?

Answer: You said `Location` conforms to the `MKAnnotation` protocol — you have to provide all the required features from that protocol in the `Location` class. Xcode makes this easy since it provides a "Fix" option to add protocol stubs.

> **Note:** If you use the "Fix" option, you'll still get errors since the stubs are just that — empty placeholders. So you still have to actually do some work to flesh things out.

The `MKAnnotation` protocol requires the class to implement the `coordinate` property. There are two other properties — `title` and `subtitle` — which are optional, but we'll implement those as well.

The annotation needs to know the coordinate in order to place the pin in the correct place on the map. The title and subtitle are used to display additional information about the location for each pin.

➤ Add the following code to **Location+CoreDataClass.swift**:

```
public var coordinate: CLLocationCoordinate2D {
  return CLLocationCoordinate2DMake(latitude, longitude)
}

public var title: String? {
  if locationDescription.isEmpty {
    return "(No Description)"
  } else {
    return locationDescription
  }
}

public var subtitle: String? {
  return category
}
```

Do you notice anything special here? All three items are instance variables — because of `var` — but they also have a block of source code associated with them.

These variables are **read-only computed properties**. That means they don't actually store a value in a memory location. Whenever you access the `coordinate`, `title`, or `subtitle` variables, they perform the logic from their code blocks. That's why they are *computed* properties: they compute something.

These properties are read-only because they only return a value — you can't assign them a new value using the assignment operator.

The following is OK because it reads the value of the property:

```
let s = location.title
```

But you cannot do this:

```
location.title = "Time for a change"
```

The only way the `title` property can change is if the `locationDescription` value changes. You could also have written this as a method:

```
func title() -> String? {
  if locationDescription.isEmpty {
    return "(No Description)"
  } else {
    return locationDescription
  }
}
```

This is equivalent to using the computed property. Whether to use a method or a computed property is often a matter of taste and you'll see both ways used throughout the iOS frameworks.

By the way, it is also possible to make *read-write* computed properties that *can* be changed, but the `MKAnnotation` protocol doesn't use those.

One more thing that you might have noticed about the variables above is the fact that they all have a `public` attribute. Except for the generated code in **Location+CoreDataProperties.swift**, you've never used a `public` attribute for variables before. So why here?

That's because the `MKAnnotation` protocol declares all three properties as `public`. You have to match the protocol declaration exactly and so your properties must have the `public` attribute as well. If you don't, Xcode will start whining :] Try removing the `public` attribute from one variable and see what happens ...

➤ Run the app and switch to the Map screen. It should now show pins for all the saved locations. Below each pin you should see the value of the `title` property from the `MKAnnotation` protocol.



The map shows pins for the saved locations

If you tap on a pin, the category for the location — which comes from the `subtitle` property — would be added below the title while the pin itself would scale up to indicate that it is currently selected.

> **Note:** So far, all the protocols you've seen were used for making delegates. But that's not the case here — `Location` is not a delegate of anything.
>
> The `MKAnnotation` protocol simply lets you pretend that `Location` is an annotation that can be placed on a map view. You can use this trick with any object you want; as long as the object implements the `MKAnnotation` protocol, it can be shown on a map.
>
> Protocols let objects wear different hats.

Show a region

Tapping the User button makes the map zoom to the user's current coordinates, but the same thing doesn't happen yet for the location pins.

By looking at the highest and lowest values for the latitude and longitude of all the `Location` objects, you can calculate a region and then tell the map view to zoom to that region.

➤ In **MapViewController.swift**, add the following new method:

```
func region(for annotations: [MKAnnotation]) ->
MKCoordinateRegion {
  let region: MKCoordinateRegion

  switch annotations.count {
  case 0:
    region = MKCoordinateRegion(
      center: mapView.userLocation.coordinate,
      latitudinalMeters: 1000,
      longitudinalMeters: 1000)

  case 1:
    let annotation = annotations[annotations.count - 1]
    region = MKCoordinateRegion(
      center: annotation.coordinate,
      latitudinalMeters: 1000,
      longitudinalMeters: 1000)

  default:
    var topLeft = CLLocationCoordinate2D(
      latitude: -90,
      longitude: 180)
    var bottomRight = CLLocationCoordinate2D(
      latitude: 90,
      longitude: -180)

    for annotation in annotations {
      topLeft.latitude = max(topLeft.latitude,
                             annotation.coordinate.latitude)
      topLeft.longitude = min(topLeft.longitude,
                              annotation.coordinate.longitude)
      bottomRight.latitude = min(bottomRight.latitude,
                                 annotation.coordinate.latitude)
      bottomRight.longitude = max(
        bottomRight.longitude,
        annotation.coordinate.longitude)
    }

    let center = CLLocationCoordinate2D(
      latitude: topLeft.latitude - (topLeft.latitude -
bottomRight.latitude) / 2,
      longitude: topLeft.longitude - (topLeft.longitude -
bottomRight.longitude) / 2)

    let extraSpace = 1.1
    let span = MKCoordinateSpan(
      latitudeDelta: abs(topLeft.latitude -
bottomRight.latitude) * extraSpace,
      longitudeDelta: abs(topLeft.longitude -
bottomRight.longitude) * extraSpace)
```

```
      region = MKCoordinateRegion(center: center, span: span)
    }

    return mapView.regionThatFits(region)
  }
```

`region(for:)` has three situations to handle. It uses a `switch` statement to look at the number of annotations and then chooses the corresponding case:

1. There are no annotations. You center the map on the user's current position.
2. There is only one annotation. You center the map on that one annotation.
3. There are two or more annotations. You calculate the extent of their reach and add a little padding. See if you can make sense of those calculations. The `max()` function looks at two values and returns the larger of the two; `min()` returns the smaller; `abs()` always makes a number positive — absolute value.

Note that this method does not use `Location` objects for anything. It assumes that all the objects in the array conform to the `MKAnnotation` protocol and it only looks at that part of the object. As far as `region(for:)` is concerned, what it deals with are annotations. It just so happens that these annotations are represented by your `Location` objects.

That is the power of using protocols. It also allows you to use this method in any app that uses Map Kit, without modifications. Pretty neat.

➤ Add the following code to `showLocations()`:

```
  @IBAction func showLocations() {
    let theRegion = region(for: locations)
    mapView.setRegion(theRegion, animated: true)
  }
```


This calls `region(for:)` to calculate a reasonable region that fits all the `Location` objects and then sets that region on the map view.

➤ Finally, change `viewDidLoad()`:

```
  override func viewDidLoad() {
    . . .
    if !locations.isEmpty {
      showLocations()
    }
  }
```

It's a good idea to show the user's locations the first time you switch to the Map tab. So `viewDidLoad()` calls `showLocations()` if the user has any saved locations.

➤ Run the app and switch to the Map tab, the map view should be zoomed in on your saved locations — because you have the code in `viewDidLoad`, remember? This only works well if the locations aren't too far apart, of course.



The map view zooms in to fit all your saved locations

Make your own pins

You made the `MapViewController` conform to the `MKMapViewDelegate` protocol, but so far, you haven't done anything with that.

This delegate is useful for creating your own annotation views. Currently, a default pin is displayed with a title below it, but you can change this to anything you like.

Create custom annotations

➤ Add the following code to the extension at the bottom of **MapViewController.swift**:

```
func mapView(
  _ mapView: MKMapView,
  viewFor annotation: MKAnnotation
) -> MKAnnotationView? {
  // 1
  guard annotation is Location else {
    return nil
  }
```

```
    // 2
    let identifier = "Location"
    var annotationView = mapView.dequeueReusableAnnotationView(
      withIdentifier: identifier)
    if annotationView == nil {
      let pinView = MKPinAnnotationView(
        annotation: annotation,
        reuseIdentifier: identifier)
      // 3
      pinView.isEnabled = true
      pinView.canShowCallout = true
      pinView.animatesDrop = false
      pinView.pinTintColor = UIColor(
        red: 0.32,
        green: 0.82,
        blue: 0.4,
        alpha: 1)

      // 4
      let rightButton = UIButton(type: .detailDisclosure)
      rightButton.addTarget(
        self,
        action: #selector(showLocationDetails(_:)),
        for: .touchUpInside)
      pinView.rightCalloutAccessoryView = rightButton

      annotationView = pinView
    }

    if let annotationView = annotationView {
      annotationView.annotation = annotation

      // 5
      let button = annotationView.rightCalloutAccessoryView as!
  UIButton
      if let index = locations.firstIndex(of: annotation as!
  Location) {
        button.tag = index
      }
    }

    return annotationView
  }
```

This is very similar to what a table view data source does in `cellForRowAt`, except that you're not dealing with table view cells here but with `MKAnnotationView` objects.

This is what happens step-by-step :

1. Because `MKAnnotation` is a protocol, there may be other objects apart from the `Location` object that want to be annotations on the map. An example is the blue dot that represents the user's current location.

   You should leave such annotations alone. So, you use the special `is` type check operator to determine whether the annotation is really a `Location` object. If it isn't, you return `nil` to signal that you're not making an annotation for this other kind of object.

2. This is similar to creating a table view cell. You ask the map view to re-use an annotation view object. If it cannot find a recyclable annotation view, then you create a new one.

   Note that you're not limited to using `MKPinAnnotationView` for your annotations. This is the standard annotation view class, but you can also create your own `MKAnnotationView` subclass and make it look like anything you want. Pins are only one option.

3. This sets some properties to configure the look and feel of the annotation view. Previously the pins were red, but you make them green here.

4. This is where it gets interesting. You create a new `UIButton` object that looks like a detail disclosure button — ⓘ. You use the target-action pattern to hook up the

   button's "Touch Up Inside" event with a new method `showLocationDetails()`, and add the button to the annotation view's accessory view.

5. Once the annotation view is constructed and configured, you obtain a reference to that detail disclosure button again and set its `tag` to the index of the `Location` object in the `locations` array. That way, you can find the `Location` object later in `showLocationDetails()` when the button is pressed.

➤ Add the `showLocationDetails()` method but leave it empty for now. Put it in the main class, not the extension.

```
@objc func showLocationDetails(_ sender: UIButton) {
}
```

Because you've told the button its `#selector` is `showLocationDetails`, the app won't compile unless you add at least an empty version of this method.

This method takes one parameter, `sender`, that refers to the control that sent the action message. In this case, the sender will be the ⓘ button. That's why the type of the `sender` parameter is `UIButton`.

➤ Run the app. The pins don't look the same as the standard pins from before, and are green. There's no title below each pin, but there's a callout when you tap a pin, and the callout has a custom button.

If the pins don't change, then make sure you connected the view controller as the delegate of the map view in the storyboard.



The annotations use your own view

★ ★ ★

Guard

In the map view delegate method, you wrote the following:

```
guard annotation is Location else {
  return nil
}
```

As you've seen before, the `guard` statement lets you try something. If the result is `nil` or `false`, the code from the `else` block is performed.

If everything works like it's supposed to, the code simply skips the `else` block and continues.

You could also have written it as follows:

```
if annotation is Location {
  // do all the other things
  . . .
} else {
  return nil
}
```

This uses the familiar `if` statement. But notice how the code that handles the situation when `annotation` is *not* a `Location` is now all the way at the bottom of the method. If you have several of these `if` statements, your code ends up looking like this:

```
if condition1 {
  if condition2 {
    if condition3 {
      . . .
    } else {
      return nil  // condition3 is false
    }
  } else {
    return nil    // condition2 is false
  }
} else {
  return nil      // condition1 is false
}
```

This kind of structure is known as the "Pyramid of Doom". There's nothing wrong with it per se, but it can make the program flow harder to decipher. With `guard` you can write this as:

```
guard condition1 else {
  return nil             // condition1 is false
}
guard condition2 else {
  return nil             // condition2 is false
}
guard condition3 else {
  return nil             // condition3 is false
}
. . .
```

Now all the conditions are checked first and any errors or unexpected situations are handled straight away. Many programmers find this easier to read.

★ ★ ★

Add annotation actions


Tapping a pin on the map now brings up a callout with a blue ⓘ button. What should this button do? Show the Edit Location screen, of course!

➤ Open the storyboard. Find the Map View Controller, and **Control-drag** from the yellow circle at the top to the Tag Location scene, which is the Location Details View Controller.

Make this a new **Show** segue and set its **Identifier** to **EditLocation**.

Tip: If making this connection gives you problems because the storyboard won't fit on your screen, then try Control-dragging from (or to) the Document Outline. You can also zoom out to show more of the storyboard.

The storyboard should now look something like this:



The Location Details screen is connected to all three screens

I had to zoom out the Storyboard in order to make the screen capture. Not sure if you can see very clearly at this level, but you should see that there are now three segues going to the Tag Location scene.

➤ Back in **MapViewController.swift**, change `showLocationDetails(_:)` to trigger the segue:

```
func showLocationDetails(sender: UIButton) {
  performSegue(withIdentifier: "EditLocation", sender: sender)
}
```

Because the segue isn't connected to any particular control in the view controller, you have to perform the segue manually. You pass along the button object as the `sender`, so you can read its `tag` property later.

➤ Add the `prepare(for:sender:)` method:

```
// MARK: - Navigation
override func prepare(
  for segue: UIStoryboardSegue,
  sender: Any?
) {
  if segue.identifier == "EditLocation" {
    let controller = segue.destination as!
LocationDetailsViewController
    controller.managedObjectContext = managedObjectContext

    let button = sender as! UIButton
    let location = locations[button.tag]
    controller.locationToEdit = location
  }
}
```

This is very similar to what you did in the Locations screen, except that now you get the `Location` object to edit from the `locations` array, using the `tag` property of the `sender` button as the index in that array.

➤ Run the app, tap on a pin and edit the location.

It works, except ... the annotation's callout doesn't change until you tap the pin again. Likewise, changes on the other screens, such as adding or deleting a location, have no effect on the map.

This is the same problem you had earlier with the Locations screen. Because the list of `Location` objects is only fetched once in `viewDidLoad()`, any changes that happen afterwards are overlooked.

Live-updating annotations

The way you're going to fix this for the Map screen is by using notifications. Recall that you have already put `NotificationCenter` to use for dealing with Core Data save errors.

As it happens, Core Data also sends out a bunch of notifications when changes are made to the data store. You can subscribe to these notifications and update the map view when you receive them.

➤ In **MapViewController.swift**, change the `managedObjectContext` property declaration to:

```
var managedObjectContext: NSManagedObjectContext! {
  didSet {
    NotificationCenter.default.addObserver(
      forName:
Notification.Name.NSManagedObjectContextObjectsDidChange,
      object: managedObjectContext,
      queue: OperationQueue.main
    ) { _ in
      if self.isViewLoaded {
        self.updateLocations()
      }
    }
  }
}
```

This is another example of a property observer put to good use. As soon as `managedObjectContext` is given a value — which happens in `AppDelegate` during app startup — the `didSet` block tells the `NotificationCenter` to add an observer for the `NSManagedObjectContextObjectsDidChange` notification.

This notification with the very long name is sent out by the `managedObjectContext` whenever the data store changes. In response, call a closure which executes this code:

```
if self.isViewLoaded {
 self.updateLocations()
}
```

This couldn't be simpler: you just call `updateLocations()` to fetch all the `Location` objects again. This throws away all the old pins and it makes new pins for all the newly fetched `Location` objects. Granted, it's not a very efficient method if there are hundreds of annotation objects, but for now it gets the job done.

> **Note:** You use `isViewLoaded` to make sure `updateLocations()` only gets called when the map view is loaded. Because this screen sits in a tab, the view from `MapViewController` does not actually get loaded from the storyboard until the user switches to the Map tab. So the view may not be loaded yet when the user tags a new location. In that case, it makes no sense to call `updateLocations()` — it could even crash the app since the `MKMapView` object doesn't exist at that point!

➤ Run the app. First go to the Map screen to see your existing location pins. Then tag a new location. The map should have added a new pin for it, although you may have to press the Locations bar button to make the new pin appear if it's outside the visible range.

★ ★ ★

Wildcard

Have another look at that closure. The `_ in` bit is the parameter list for the closure. Like functions and methods, closures can take parameters.

Because this particular closure gets called by `NotificationCenter`, you're given a `Notification` object as the parameter. Since you're not using this `notification` object anywhere in the closure, you use the _ to stand in for the parameter name.

You've already seen the _ underscore used in a few places in the code. This symbol is called the *wildcard* and you can use it whenever a name is expected but you don't really care about it.

Here, the _ tells Swift you're not interested in the closure's parameter. It also helps to reduce visual clutter in the source code; it's obvious at a glance that this parameter — whatever it may be — isn't being used in the closure.

So whenever you see the _ used in Swift source code it just means, "there's something here but the programmer has chosen to ignore it".



Exercise: The `Notification` object that we ignored above has a `userInfo` dictionary. From that dictionary it is possible to figure out which objects were inserted/deleted/updated. For example, use the following `print()`s to examine this dictionary:

```
if let dictionary = notification.userInfo {
  print(dictionary[NSInsertedObjectsKey])
  print(dictionary[NSUpdatedObjectsKey])
  print(dictionary[NSDeletedObjectsKey])
}
```

This will print out an (optional) collection of `Location` objects or `nil` if there were no changes. Your mission, should you choose to accept it: try to make the reloading of the locations more efficient by only inserting or deleting the items that have changed. Good luck! If you get stuck, you can find the solutions from other readers on the raywenderlich.com forums.

That's it for the Map screen.

You can find the project files for this chapter under **29-Maps** in the Source Code folder.


Chapter 30: Image Picker

By Fahim Farook

Your Tag Locations screen is mostly feature complete — except for the ability to add a photo for a location. Time to fix that!

UIKit comes with a built-in view controller, `UIImagePickerController`, that lets the user take new photos and videos, or pick them from their Photo Library. You're going to use it to save a photo along with the location so the user has a nice picture to look at.

This is what your screen will look like when you're done:



A photo in the Tag Location screen

In this chapter, you will do the following:

- **Add an image picker:** Add an image picker to your app to allow you to take photos with the camera or to select existing images from your photo library.
- **Show the image:** Show the picked image in a table view cell.
- **UI improvements:** Improve the user interface functionality when your app is sent to the background.
- **Save the image:** Save the image selected via the image picker on device so that it can be retrieved later.
- **Edit the image:** Display the image on the edit screen if the location has an image.
- **Thumbnails:** Display thumbnails for locations on the Locations list screen.

Add an image picker

Just as you need to ask the user for permission before you can get GPS information from the device, you need to ask for permission to access the user's photo library.

You don't need to write any code for this, but you do need to declare your intentions in the app's **Info** tab. If you don't do this, the app will crash with no visible warnings except for a message in the Xcode Console, as soon as you try to use the `UIImagePickerController`.

Info tab changes

➤ Go to the project's **Info** tab and add a new row — either use the plus (+) button on existing rows, or right-click and select **Add Row**.

For the key, choose **Privacy - Photo Library Usage Description** from the dropdown list.

For the value, type: **Add photos to your locations.**



Adding a usage description to Info tab

➤ Also add the key **Privacy - Camera Usage Description** and give it the same description.

Now when the app opens the photo picker or the camera for the first time, iOS will tell the user what the app intends to use the photos for, using the description you just added to Info.plist.

Use camera to add image

➤ In **LocationDetailsViewController.swift**, add the following extension to the end of the source file:

```
extension LocationDetailsViewController:
UIImagePickerControllerDelegate,
  UINavigationControllerDelegate {
  // MARK: - Image Helper Methods
  func takePhotoWithCamera() {
    let imagePicker = UIImagePickerController()
    imagePicker.sourceType = .camera
    imagePicker.delegate = self
    imagePicker.allowsEditing = true
    present(imagePicker, animated: true, completion: nil)
  }
}
```

The `UIImagePickerController` is a view controller like any other, but it is built into UIKit and it takes care of the entire process of taking new photos or picking them from the user's photo library.

All you need to do is create a `UIImagePickerController` instance, set its properties to configure the picker, set its `delegate`, and then present it. When the user closes the image picker screen, the delegate methods will let you know the result of the operation.

That's exactly how you've been designing your own view controllers — except that you don't need to add the `UIImagePickerController` to the storyboard.

> **Note:** You're doing this in an extension because it allows you to group all the photo-picking related functionality together.
>
> If you wanted to, you could put these methods in the main class body. That would work fine too, but view controllers tend to become very big with many methods that all do different things.

As a way to preserve your sanity, it's nice to extract conceptually related methods — such as everything that has to do with picking photos — and place them together in their own extension.

You could even move each of these extensions to their own source file, for example "LocationDetailsViewController+PhotoPicking.swift", but personally, I find having less files to manage to be a good thing :]

➤ Add the following methods to the extension:

```
// MARK: - Image Picker Delegates
func imagePickerController(
  _ picker: UIImagePickerController,
  didFinishPickingMediaWithInfo info:
[UIImagePickerController.InfoKey: Any]
) {
  dismiss(animated: true, completion: nil)
}

func imagePickerControllerDidCancel(
  _ picker: UIImagePickerController
) {
  dismiss(animated: true, completion: nil)
}
```

Currently these delegate methods simply remove the image picker from the screen. Soon, you'll take the image the user picked and add it to the `Location` object, but for now, you just want to make sure the image picker shows up.

Note that the view controller — in this case the extension — must conform to both `UIImagePickerControllerDelegate` and `UINavigationControllerDelegate` for this to work, but you don't have to implement any of the `UINavigationControllerDelegate` methods.

➤ Now change `tableView(_:didSelectRowAt:)` in the class as follows:

```
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  if indexPath.section == 0 && indexPath.row == 0 {
    . . .
  } else if indexPath.section == 1 && indexPath.row == 0 {
    takePhotoWithCamera()
  }
}
```

Add Photo is the first row in the second section. When it's tapped, you call the `takePhotoWithCamera()` method that you just added.

➤ Run the app, tag a new location or edit an existing one, and tap **Add Photo**.

If you're running the app in the Simulator, bam! It crashes. The error message is this:

```
*** Terminating app due to uncaught exception
'NSInvalidArgumentException', reason: 'Source type 1 not
available'
```

The culprit for the crash is the line:

```
imagePicker.sourceType = .camera
```

Not all devices have a camera, and the Simulator does not. If you try to use the `UIImagePickerController` with a `sourceType` that is not supported by the device or the Simulator, the app crashes.

If you run the app on your device — and if it has a camera, which it probably does if it's a recent model — then you should see something like this:



The camera interface

That is very similar to what you see when you take pictures using the iPhone's Camera app. *MyLocations* doesn't let you record video, but you can certainly enable this feature in your own apps, if you wanted to.

Use photo library to add image

You can still test the image picker on the Simulator, but instead of using the camera, you have to use the photo library.

➤ Add another method to the extension:


```
func choosePhotoFromLibrary() {
  let imagePicker = UIImagePickerController()
  imagePicker.sourceType = .photoLibrary
  imagePicker.delegate = self
  imagePicker.allowsEditing = true
  present(imagePicker, animated: true, completion: nil)
}
```

This method does essentially the same thing as `takePhotoWithCamera`, except now you set the `sourceType` to `.photoLibrary`.

➤ Change `didSelectRowAt` to call `choosePhotoFromLibrary()` instead of `takePhotoWithCamera()`.

➤ Run the app in the Simulator and tap **Add Photo**.

At this point you should see a handful of stock images like this:



The iOS photos library on the simulator

> **Note:** If you don't see any images for some reason, stop the app and click on the built-in **Photos** app in the Simulator. This should display a handful of sample photos. Run the app again and try picking a photo.

Adding photos to the simulator

There are several ways you can add new photos to the Simulator. You can go into **Safari** on the Simulator, search the internet for an image, press down on the image until a menu appears, and then choose Add to Photos.

Or, instead of surfing the internet for images, you can simply drag and drop an image file on to the Simulator window. This adds the picture to your library in the Photos app.

Finally, you can use the Terminal and the `simctl` command. Type the following, all on one line — the last part, `~/Desktop/MyPhoto.JPG`, should be replaced with an actual path to an image you want to add:

```
/Applications/Xcode.app/Contents/Developer/usr/bin/simctl
addmedia booted ~/Desktop/MyPhoto.JPG
```

The `simctl` tool can be used to manage your Simulators — type `simctl help` for a list of options. The command `addmedia booted` adds the specified media file to the active Simulator.

★ ★ ★

➤ Choose one of the photos. The screen now changes to:



The user can tweak the photo

This happens because you set the image picker's `allowsEditing` property to `true`. With this setting enabled, the user can do some quick editing of the photo before making their final choice — in the Simulator you can hold down Alt/Option while dragging to zoom the photo.

So, there are two types of image pickers you can use: the camera and the Photo Library. But the camera won't work everywhere. It's a bit limiting to restrict the app to just picking photos from the library, though.

You'll have to make the app a little smarter and allow the user to choose the camera when it is present.

Choose between camera and photo library

First, you check whether the camera is available. When it is, you show an **action sheet** to let the user choose between the camera and the Photo Library.

➤ Add the following methods to **LocationDetailsViewController.swift**, in the photo extension:

```
func pickPhoto() {
  if UIImagePickerController.isSourceTypeAvailable(.camera) {
    showPhotoMenu()
  } else {
    choosePhotoFromLibrary()
  }
}

func showPhotoMenu() {
  let alert = UIAlertController(
    title: nil,
    message: nil,
    preferredStyle: .actionSheet)

  let actCancel = UIAlertAction(
    title: "Cancel",
    style: .cancel,
    handler: nil)
  alert.addAction(actCancel)

  let actPhoto = UIAlertAction(
    title: "Take Photo",
    style: .default,
    handler: nil)
  alert.addAction(actPhoto)

  let actLibrary = UIAlertAction(
    title: "Choose From Library",
```

```
      style: .default,
      handler: nil)
    alert.addAction(actLibrary)


    present(alert, animated: true, completion: nil)
  }
```

You use `UIImagePickerController`'s `isSourceTypeAvailable()` method to check whether there's a camera present. If not, you call `choosePhotoFromLibrary()` as that is your only option. But when the device does have a camera, you show a `UIAlertController` on the screen.

Unlike the alert controllers you've used before, this one has the `.actionSheet` style. An action sheet works very much like an alert view, except that it slides in from the bottom of the screen and offers the user one of several choices.

➤ In `didSelectRowAt`, change the call to `choosePhotoFromLibrary()` to `pickPhoto()` instead. This is the last time you'll change this line, honest.

➤ Run the app on your device to see the action sheet in action:



The action sheet that lets you choose between camera and photo library

Tapping any of the buttons in the action sheet simply dismisses the action sheet but doesn't do anything else yet.

By the way, if you want to test this action sheet in the Simulator, then you can fake the availability of the camera by writing the following in `pickPhoto()`:

```
  if true ||
  UIImagePickerController.isSourceTypeAvailable(.camera) {
```

That will always show the action sheet because the condition is now always true.

The choices in the action sheet are provided by `UIAlertAction` objects. The `handler:` parameter is a closure which determines what happens when you press the corresponding button in the action sheet.

Right now the handlers for all three choices — Take Photo, Choose From Library, Cancel — are `nil`, so nothing will happen.

➤ Change these lines to the following:

```
let actPhoto = UIAlertAction(
  title: "Take Photo",
  style: .default) { _ in
    self.takePhotoWithCamera()
  }
```

```
let actLibrary = UIAlertAction(
  title: "Choose From Library",
  style: .default) { _ in
    self.choosePhotoFromLibrary()
  }
```

This turns `handler:` into a trailing closure that calls the corresponding method from the extension. You use the _ wildcard to ignore the parameter that is passed to this closure — a reference to the `UIAlertAction` itself.

➤ Run the app and make sure the buttons from the action sheet work properly.

There may be a small delay between pressing any of these buttons before the image picker appears, but that's because it's a big component and iOS needs a few seconds to load it up.

Notice that the Add Photo cell remains selected, showing a dark gray background, when you cancel the action sheet. That doesn't look so good.

➤ In `tableView(_:didSelectRowAt)`, add the following line before the call to `pickPhoto()`:

```
tableView.deselectRow(at: indexPath, animated: true)
```

This first deselects the Add Photo row. Try it out, it looks better this way. The cell background quickly fades from gray back to white as the action sheet slides into the screen.

Show the image

Now that the user can pick a photo, you should display it somewhere — what's the point otherwise, right? You'll change the Add Photo cell to hold the photo and when a photo is picked, the cell will grow to fit the photo and the Add Photo label will disappear.

➤ Add two new outlets to the class in **LocationDetailsViewController.swift**:

```
@IBOutlet var imageView: UIImageView!
@IBOutlet var addPhotoLabel: UILabel!
```

➤ In the storyboard, drag an Image View into the Add Photo cell. It doesn't really matter how big it is or where you put it. You'll programmatically move it to the proper place later.

This is the reason you made this a custom cell way back when, so you could add this image view to it.



Adding an Image View to the Add Photo cell

➤ Connect the Image View to the view controller's `imageView` outlet. Also connect the Add Photo label to the `addPhotoLabel` outlet.

➤ Select the Image View. In the **Attributes inspector**, check its **Hidden** attribute from the **Drawing** section. This makes the image view initially invisible, until you have a photo to give it.

➤ Add **left**, **top**, **right**, **bottom**, and **height** Auto Layout constraints to the Image View:




Image View Auto Layout constraints

We will use some of these Auto Layout constraints to move things out of the way, or to expand the image view to fill the cell when we are displaying an image. But first, we need a variable to hold the picked image.

➤ Add a new instance variable to **LocationDetailsViewController.swift**:

```
var image: UIImage?
```

If no photo is picked yet, `image` will be `nil`, so the variable has to be an optional.

➤ Add a new method to the class:

```
func show(image: UIImage) {
  imageView.image = image
  imageView.isHidden = false
  addPhotoLabel.text = ""
}
```

This puts the image from the parameter into the image view, makes the image view visible, and removes the title from the Add Photo label so that the Auto Layout constraints would move the image over into the space occupied by the label.

➤ Change the `imagePickerController(_:didFinishPickingMediaWithInfo:)` method from the photo picking extension to the following:

```
func imagePickerController(
  _ picker: UIImagePickerController,
  didFinishPickingMediaWithInfo info:
[UIImagePickerController.InfoKey: Any]
) {
  image = info[UIImagePickerController.InfoKey.editedImage] as?
UIImage
  if let theImage = image {
    show(image: theImage)
  }
  dismiss(animated: true, completion: nil)
}
```

This is the method that gets called when the user has selected a photo in the image picker.

You can tell by the notation `[UIImagePickerController.InfoKey: Any]` that the `info` parameter is a dictionary. Whenever you see `[ A : B ]` you're dealing with a dictionary that has keys of type "A" and values of type "B".

The `info` dictionary contains data describing the image that the user picked. You use the `UIImagePickerController.InfoKey.editedImage` key to retrieve a `UIImage` object that contains the final image after the user moved and/or scaled it — you can also get the original image if you wish, using a different key.

Once you have the photo, you store it in the `image` instance variable so you can use it later.

Dictionaries always return optionals, because there is a theoretical possibility that the key you asked for — `UIImagePickerController.InfoKey.editedImage` in this case — doesn't actually exist in the dictionary.

Since the `image` instance variable is an optional, you simply assign the value from the dictionary.

If `info[UIImagePickerController.InfoKey.editedImage]` is `nil`, then `image` will be `nil` too. You do need to cast the value from the meaningless `Any` to `UIImage` using the `as?` operator. In this case you need to use the optional cast, `as?` instead of `as!`, because `image` is an optional instance variable.

Once you have the image and it is not `nil`, the call to `show(image:)` puts it in the Add Photo cell.

> **Exercise:** See if you can rewrite the above logic to use a `didSet` property observer on the `image` instance variable. If you succeed, then placing the photo into image will automatically update the `UIImageView`, without needing to call `show(image:)`.

➤ Run the app and choose a photo. Whoops, it looks like you have a "small" problem here:



The photo is tiny

If you recall, we set the height for the Image View to 24 points when we set the Auto Layout constraints earlier because that's how tall the image needed to be to fit the original row. However, when we're displaying the image, we need a larger value — something like 260 points.

But of course, if we set the Image View height to 260 at the outset, the image picker cell would start out too tall. So how do we fix this?


Simple enough — you can actually set up connections for Auto Layout constraints too and change the constraint values via code during runtime!

Resize table view cell to show image

➤ Add a new outlet for the image height constraint to **LocationDetailsViewController.swift**:

```
@IBOutlet var imageHeight: NSLayoutConstraint!
```

➤ Switch to the storyboard and then connect the new outlet to the height constraint for the image — the easiest way to do this is via the Document Outline since you can pick the exact constraint you want from there. Simply Control-drag from the circle for the view controller to the correct constraint in the Document Outline and then pick the outlet name, **imageHeight**, from the popup menu:



Connect the outlet for the constraint

Now, all you have to do is change the Image View's height constraint to 260 when you display an image!

➤ Change the `show(image:)` method:

```
func show(image: UIImage) {
  ...
  // Add the following lines
  imageHeight.constant = 260
  tableView.reloadData()
}
```

You simply change the height of the image to 260 points and then refresh the table view to set the photo row to the proper height.

➤ Try it out. The cell now resizes and is big enough for the whole photo.



The photo displays correctly

There's one small issue – there is too much space around the image. This is due to the Content Mode for the image. You learnt about Content Mode in Chapter 8 and how the default Content Mode for images fits the image to the available space so that the longest side fills the available space fully.

Here, the longest side is the width and so the width takes up the available space but that might mean that there is a bit more space above and below the image.

> **Exercise:** Make the height of the photo table view cell dynamic, depending on the aspect ratio of the image. This is a tough one! You can keep the width of the image view at 260 points. This should correspond to the width of the `UIImage` object. You get the aspect ratio by doing `image.size.width / image.size.height`. With this ratio you can calculate what the height of the image view and the cell should be. Good luck! You can find solutions from other readers at forums.raywenderlich.com

UI improvements

The user can take a photo — or pick one — now but the app doesn't save it to the data store yet. Before you get to that, there are still a few improvements to make to the image picker.

Apple recommends that apps remove any alert or action sheet from the screen when the user presses the Home button to move the app to the background.

The user may return to the app hours or days later and they will have forgotten what they were going to do. The presence of the alert or action sheet is confusing and the user might think, "What's that thing doing here?!"

To prevent this from happening, you'll make the Tag Location screen a little more attentive. When the app goes to the background, it will dismiss the action sheet if that is currently showing. You'll do the same for the image picker.

Handle background mode

You saw in the *Checklists* app that the `SceneDelegate` is notified by the operating system when the app is about to go to the background through its `sceneDidEnterBackground(_:)` method.

View controllers don't have such a method, but fortunately, iOS sends out "going to the background" notifications through `NotificationCenter` that you can configure the view controller to listen to.

Earlier you used the notification center to observe notifications from Core Data. This time you'll listen for the `UIScene.didEnterBackgroundNotification` notification.

➤ In **LocationDetailsViewController.swift**, add a new method:

```
func listenForBackgroundNotification() {
  NotificationCenter.default.addObserver(
    forName: UIScene.didEnterBackgroundNotification,
    object: nil,
    queue: OperationQueue.main) { _ in
    if self.presentedViewController != nil {
      self.dismiss(animated: false, completion: nil)
    }
    self.descriptionTextView.resignFirstResponder()
  }
}
```

This adds an observer for `UIScene.didEnterBackgroundNotification`. When this notification is received, `NotificationCenter` will call the closure.

If there is an active image picker or action sheet, you dismiss it. You also hide the keyboard if the text view is active.

The image picker and action sheet are both presented as modal view controllers that appear above everything else. If such a modal view controller is active, `UIViewController`'s `presentedViewController` property has a reference to that modal view controller.

So, if `presentedViewController` is not `nil` you call `dismiss()` to close the modal screen. By the way, this has no effect on the category picker; that does not use a modal segue but a push segue.

➤ Call the `listenForBackgroundNotification()` method from within `viewDidLoad()`.

➤ Try it out. Open the image picker, or the action sheet if you're on a device that has a camera, and exit to the home screen to put the app to sleep.

Then tap the app's icon to activate the app again. You should now be back on the Tag Location screen, or Edit Location screen if you opted to edit an existing one. The image picker, or action sheet, has automatically closed.

That seems to work, cool!

Remove notification observers

Now that you've add a notification to the `NotificationCenter`, prior to iOS 9.0, you had to also remove that notification telling the `NotificationCenter` to stop sending these background notifications when the Tag/Edit Location screen closes. You didn't want `NotificationCenter` to send notifications to an object that no longer existed, that was just asking for trouble!

However, as of iOS 9.0, this is no longer necessary since the system handles all of this for you. But, we'll go ahead and unregister the observer just so that you can see how that works — and also to illustrate another issue that we'll get to soon :]

The `deinit` method is a good place to unregister observers.

➤ First, add a new instance variable:

```
var observer: Any!
```

This will hold a reference to the observer, which is necessary to unregister it later.

The type of this variable is `Any!`, meaning that you don't really care what sort of object this is.

➤ In `listenForBackgroundNotification()`, change the first line so that it stores the return value of the call to `addObserver()` into this new instance variable:

```
func listenForBackgroundNotification() {
  observer = NotificationCenter.default.addObserver(forName: . .
.
```

➤ Finally, add the `deinit` method:

```
deinit {
  print("*** deinit \(self)")
  NotificationCenter.default.removeObserver(observer!)
}
```

You add a `print()` here so you have proof that the view controller really does get destroyed when you close the Tag/Edit Location screen.

➤ Run the app, edit an existing location, and tap Done to close the screen.

I don't know about you, but I don't see the `*** deinit` message anywhere in the Xcode Console. Guess what? The `LocationDetailsViewController` doesn't get destroyed for some reason. That means the app is leaking memory... Of course, this was all a big setup on my part so I can tell you about closures and capturing :]

Closures and capturing

Remember how in closures you always have to specify `self` when you want to access an instance variable or call a method? That is because closures capture any variables that are used inside the closure.

When it captures a variable, the closure simply stores a reference to that variable. This allows it to use the variable at some later point when the closure is actually performed.

Why is this important? If the code inside the closure uses a local variable, the method that created this variable may no longer be active by the time the closure is performed. After all, when a method ends all locals are destroyed. But when such a local is captured by a closure, it stays alive until the closure is also done with it.


Because the closure needs to keep the objects from those captured variables alive in the time between capturing and actually performing the closure, it stores a *strong* reference to those objects. In other words, capturing means the closure becomes a shared owner of the captured objects.

What may not be immediately obvious is that `self` is also one of those variables and therefore gets captured by the closure. Sneaky! That's why Swift requires you to explicitly write out `self` inside closures, so you won't forget this value is being captured.

In the context of `LocationDetailsViewController`, `self` refers to the view controller itself. So, as the closure captures `self`, it creates a strong reference to the `LocationDetailsViewController` object, and the closure becomes a co-owner of this view controller. I bet you didn't expect that!

Remember, as long as an object has owners, it is kept alive. So this closure is keeping the view controller alive, even after you closed it!

This is known as an *ownership cycle*, because the view controller itself has a strong reference back to the closure through the `observer` variable.



The relationship between the view controller and the closure

In case you're wondering, the view controller's other owner is UIKit. The observer is also being kept alive by `NotificationCenter`.

This sounds like a classic catch-22 problem! Fortunately, there is a way to break the ownership cycle. You can give the closure a *capture list*. What's *that* you ask? All will be explained soon!

➤ Change `listenForBackgroundNotification()` to the following:

```
func listenForBackgroundNotification() {
  observer = NotificationCenter.default.addObserver(
    forName: UIApplication.didEnterBackgroundNotification,
    object: nil,
    queue: OperationQueue.main) { [weak self] _ in

    if let weakSelf = self {
      if weakSelf.presentedViewController != nil {
        weakSelf.dismiss(animated: false, completion: nil)
      }
      weakSelf.descriptionTextView.resignFirstResponder()
    }
  }
}
```

There are a couple of new things here. Let's look at the first part of the closure:

```
{ [weak self] _ in
  . . .
}
```

The `[weak self]` bit is the capture list for the closure. It tells the closure that the variable `self` will still be captured, but as a weak reference. As a result, the closure no longer keeps the view controller alive.

Weak references are allowed to become `nil`, which means the captured `self` is now an optional inside the closure. You need to unwrap it with `if let` before you can send messages to the view controller.

Other than that, the closure still does the exact same things as before.

➤ Try it out. Open the Tag/Edit Location screen and close it again. You should now see the `print()` from `deinit` in the Xcode Console.

That means the view controller gets destroyed properly and the notification observer is removed from `NotificationCenter`. Good riddance!

Do note that as of iOS 9.0 and above, even if you do not remove the observer explicitly, the system would handle this for you and automatically remove the observer when the view controller is deallocated. So you don't have to worry about any side effects from an errant observer any longer.

But it's always a good idea to clean up after yourself. Use `print()`'s to make sure your objects really get deallocated! Xcode also comes with Instruments, a handy tool that you can use to detect such issues.

Save the image

The ability to pick photos is rather useless if the app doesn't also save them. So, that's what you'll do here.

It is possible to store images in the Core Data store as BLOBs (**B**inary **L**arge **OB**jects), but that is not recommended. Large blocks of data are better off stored as regular files in the app's Documents directory.

> **Note:** Core Data has an "Allows external storage" feature that is designed to make this process completely transparent for the developer. In theory, you can put data of any size into your entities and Core Data automatically decides whether to put the data into the SQLite database or store it as an external file.
>
> Unfortunately, this feature doesn't work very well in practice. Last time I checked, it had too many bugs to be useful. So, until this part of Core Data becomes rock solid, we'll be doing it by hand.

When the image picker gives you a `UIImage` object for a photo, that image only lives in the iPhone's working memory.

The image may also be stored as a file somewhere if the user picked it from the photo library, but that's not the case if they just snapped a new picture. Besides, the user may have resized or cropped the image.

So you have to save that `UIImage` to a file of your own if you want to keep it. The photos in *MyLocations* will be saved in JPEG format.

You need a way to associate that JPEG file with your `Location` object. The obvious solution is to store the filename in the `Location` object. You won't store the entire filename, just an ID, which is a positive number. The image file itself will be named **Photo-XXX.jpg**, where XXX is the numeric ID.

Data model changes

➤ Open the Data Model editor. Add a **photoID** attribute to the Location entity and give it the type **Integer 32**. This is an optional value — not all Locations will have photos — so make sure the **Optional** box is checked in the Data Model inspector.

➤ Add a property for this new attribute to **Location+CoreDataProperties.swift**:

```
@NSManaged public var photoID: NSNumber?
```

Remember that for an object that is managed by Core Data, you have to declare the property as `@NSManaged`.

You may be wondering why you're declaring the type of `photoID` as `NSNumber` and not as `Int` or, more precisely, `Int32`. Remember that Core Data is an Objective-C framework, so you're limited by the possibilities of that language. `NSNumber` is how number objects are handled in Objective-C.

For various reasons, you can't represent an `Int` value as an optional in Objective-C. Instead, you'll use the `NSNumber` class. Swift will automatically convert between `Int` values and this `NSNumber`, so it's no big deal.

You'll now add some other properties to the `Location` object to make working with photos a little easier.

➤ Add the `hasPhoto` computed property to **Location+CoreDataClass.swift**:

```
var hasPhoto: Bool {
  return photoID != nil
}
```

This determines whether the `Location` object has a photo associated with it or not. Swift's optionals make this easy.

➤ Also add the `photoURL` property:

```
var photoURL: URL {
  assert(photoID != nil, "No photo ID set")
  let filename = "Photo-\(photoID!.intValue).jpg"
  return
applicationDocumentsDirectory.appendingPathComponent(filename)
}
```

This property computes the full URL for the JPEG file for the photo. Note that iOS uses URLs to refer to files, even those saved on the local device.

You'll save these JPEG files in the app's Documents directory. To get the URL to that directory, you use the global variable `applicationDocumentsDirectory` that you added to Functions.swift earlier.

Notice the use of `assert()` to make sure the `photoID` is not `nil`. An *assertion* is a special debugging tool that is used to check that your code always does something valid. If not, the app will crash with a helpful error message. You'll see more of this later when we talk about finding bugs — and squashing them.

Assertions are a form of defensive programming. Most of the crashes you've seen so far were actually caused by assertions in UIKit. They allow the app to crash in a controlled manner. Without these assertions, programming mistakes could crash the app at random moments, making it very hard to find out what went wrong.

If the app were to ask a `Location` object for its `photoURL` without having given it a valid `photoID` earlier, the app will crash with the message "No photo ID set". If so, there is a bug in the code somewhere because this is not supposed to happen. Internal consistency checks like this can be very useful.

Assertions are usually enabled only while you're developing and testing your app and disabled when you upload the final build of your app to the App Store. By then, there should be no more bugs in your app — or so you would hope! It's a good idea to use `assert()` in strategic places to catch yourself making programming errors.

➤ Add a `photoImage` property:

```
var photoImage: UIImage? {
  return UIImage(contentsOfFile: photoURL.path)
}
```

This returns a `UIImage` object by loading the image file. You'll need this later to show the photos for existing `Location` objects.

Note that this property has the optional type `UIImage?` — that's because loading the image may fail if the file is damaged or removed. Of course, that *shouldn't* happen, but no doubt you've heard of Murphy's Law... As I've repeatedly said, it's good to get into the habit of defensive programming.

There is one more thing to add, a `nextPhotoID()` method. This is a class method, meaning that you don't need to have a `Location` instance to call it. You can call this method anytime from anywhere.

➤ Add the method:

```
class func nextPhotoID() -> Int {
  let userDefaults = UserDefaults.standard
  let currentID = userDefaults.integer(forKey: "PhotoID") + 1
  userDefaults.set(currentID, forKey: "PhotoID")
  return currentID
}
```

You need to have some way to generate a unique ID for each `Location` object. All `NSManagedObjects` have an `objectID` method, but that returns something unreadable such as:

```
<x-coredata://C26CC559-959C-49F6-BEF0-F221D6F3F04A/Location/p1>
```

You can't really use that in a filename. So instead, you're going to put a simple integer in `UserDefaults` and update it every time the app asks for a new ID — this is similar to what you did in the last app to make `ChecklistItem` IDs for use with local notifications.

It may seem a little silly to use `UserDefaults` for this when you're already using Core Data as the data store, but with `UserDefaults`, the `nextPhotoID()` method is only five lines. You've seen how verbose the code is for fetching something from Core Data and then saving it again. This is just as easy. Of course, if you wanted to, as an exercise, you could try to implement these IDs using Core Data…

That does it for `Location`. Now you have to save the image and fill in the `Location` object's `photoID` field. This happens in the Location Details View Controller's `done()` action.

Save the image to a file

➤ In **LocationDetailsViewController.swift**, in the `done()` method, add the following in between where you set the properties of the `Location` object and where you save the managed object context:


```
// Save image
if let image = image {
  // 1
  if !location.hasPhoto {
    location.photoID = Location.nextPhotoID() as NSNumber
  }
  // 2
  if let data = image.jpegData(compressionQuality: 0.5) {
    // 3
    do {
```

```
        try data.write(to: location.photoURL, options: .atomic)
      } catch {
        print("Error writing file: \(error)")
      }
    }
  }
```

This code is only performed if `image` is not `nil` — in other words, when the user has picked a photo.

1. You need to get a new ID and assign it to the `Location`'s `photoID` property, but only if you're adding a photo to a `Location` that didn't already have one. If a photo existed, you simply keep the same ID and overwrite the existing JPEG file.
2. The `image.jpegData(compressionQuality: 0.5)` call converts the `UIImage` to JPEG format and returns a `Data` object. `Data` is an object that represents a blob of binary data, usually the contents of a file.
3. You save the `Data` object to the path given by the `photoURL` property. Also notice the use of a `do-try-catch` block again.

➤ Run the app, tag a location, choose a photo, and press Done to exit the screen. Now the photo you picked should be saved in the app's Documents directory as a regular JPEG file.



The photo is saved in the app's Documents folder

Note: The first time you run the app after adding a new attribute to the data model (photoID), the `NSPersistentContainer` performs a migration of the data store behind the scenes to make sure the data store is in sync again with the data model. If this doesn't work for you for some reason, then remove the old MyLocations.sqlite file from the Library/Application Support folder and try again — or, simply reset the Simulator or remove the app from your test device.

➤ Tag another location and add a photo to it. Hmm... if you look into the app's Documents directory, this seems to have overwritten the previous photo.

> **Exercise:** Try to debug this one on your own. What is going wrong here? This is a tough one!

Answer: When you create a new `Location` object, its `photoID` property gets a default value of 0. That means each `Location` initially has a `photoID` of 0. That should really be `nil`, which means "no photo".

➤ In **LocationDetailsViewController.swift**, add the following line near the top of `done()`:


```
@IBAction func done() {
  . . .
  if let temp = locationToEdit {
    . . .
  } else {
    . . .
    location.photoID = nil           // add this
  }
  . . .
```

You now set the `photoID` of a new `Location` object to `nil` so that the `hasPhoto` property correctly recognizes that these `Locations` as not having a photo yet.

➤ Run the app again, delete your existing data — or create a few new tags — and tag multiple locations with photos. Verify that now each photo is saved individually.

Verify photoID in SQLite

If you have Liya or another SQLite inspection tool, you can verify that each Location object has been given a unique photoID value (in the ZPHOTOID column):



The Location objects with unique photoId values in Liya

Edit the image

So far, all the changes you've made were for the Tag Location screen and adding new locations. Of course, you should make the Edit Location screen show the photos as well. The change to `LocationDetailsViewController` is quite simple.

➤ Change `viewDidLoad()` in **LocationDetailsViewController.swift** to:

```
override func viewDidLoad() {
  super.viewDidLoad()

  if let location = locationToEdit {
    title = "Edit Location"
    // New code block
    if location.hasPhoto {
      if let theImage = location.photoImage {
        show(image: theImage)
      }
    }
    // End of new code
  }
  . . .
```

If the `Location` that you're editing has a photo, this calls `show(image:)` to display it in the photo cell. Recall that the `photoImage` property returns an optional, `UIImage?`, so you use `if let` to unwrap it. This is another bit of defensive programming. Sure, if `hasPhoto` is `true` there should always be a valid image file present. But it's possible to imagine a scenario where there isn't — the JPEG file could have been erased or corrupted — even though that "should" never happen. I'm sure you've had your own share of computer gremlins eating important files.

Note also what you **don't** do here: the `Location`'s image is *not* assigned to the `image` instance variable. If the user doesn't change the photo, then you don't need to write it out to a file again — it's already in that file and doing perfectly fine, thank you.

If you were to put the photo in the `image` variable, then `done()` would overwrite the existing file with the exact same data, which is a little silly. Therefore, the `image` instance variable will only be set when the user picks a new photo.

➤ Run the app and take a peek at the existing locations from the Locations or Map tabs. The Edit Location screen should now show the photos for the locations you're editing.

➤ Verify that you can also change the photo and that the JPEG file in the app's Documents directory gets overwritten when you press the Done button.

Clean up on location deletion

There's another editing operation the user can perform on a location: deletion. What happens to the image file when a location is deleted? At the moment nothing. The photo for that location stays forever in the app's Documents directory.

Let's add some code to remove the photo file, if it exists, when a `Location` object is deleted.

➤ First add a new method to **Location+CoreDataClass.swift**:

```
func removePhotoFile() {
  if hasPhoto {
    do {
      try FileManager.default.removeItem(at: photoURL)
    } catch {
      print("Error removing file: \(error)")
    }
  }
}
```

This code snippet can be used to remove any file or folder. The `FileManager` class has all kinds of useful methods for dealing with the file system.

➤ Deleting locations happens in **LocationsViewController.swift**. Add the following line to `tableView(_:commit:forRowAt:)`:

```
override func tableView(
  _ tableView: UITableView,
  commit editingStyle: UITableViewCell.EditingStyle,
  forRowAt indexPath: IndexPath
) {
  if editingStyle == .delete {
    let location = fetchedResultsController.object(at:
indexPath)

    location.removePhotoFile()              // add this line
    managedObjectContext.delete(location)
    . . .
```

The new line calls `removePhotoFile()` on the `Location` object just before it is deleted from the Core Data context.

➤ Try it out. Add a new location and give it a photo. You should see the JPEG file in the Documents directory.

From the Locations screen, delete the location you just added and look in the Documents directory to make sure the JPEG file truly is a goner.


Thumbnails

Now that locations can have photos, it's a good idea to show thumbnails for these photos in the Locations tab. That will liven up this screen a little... a plain table view with just a bunch of text isn't particularly exciting.

Storyboard changes

➤ Go to the storyboard editor. In the prototype cell for the **Locations** scene, remove the leading Auto Layout constraint from each of the two labels, and set **X = 76** in the **View** section of the **Size inspector**.

➤ Drag a new **Image View** into the cell. Place it at the top-left corner of the cell. Give it the following position: X = 16, Y = 6. Make it 52 by 52 points big.



The table view cell has an image view

➤ Add **top**, **left**, **height**, and **width** Auto Layout constraints for the currently set values for the new Image View.

➤ Select each of the labels and set their left constraint again so that each one is positioned relative to the image view — the spacing should be 8 points (or standard spacing) if you set all the positions and sizes above correctly.

➤ Connect the image view to a new `UIImageView` outlet on `LocationCell`, named **photoImageView**.

> **Exercise:** Make this connection with the Assistant editor. Tip: you should connect the image view to the cell, not to the view controller.

Now you can put any image into the table view cell simply by passing it to the `LocationCell`'s `photoImageView` property.

Code changes

➤ Go to **LocationCell.swift** and add the following method:

```
func thumbnail(for location: Location) -> UIImage {
  if location.hasPhoto, let image = location.photoImage {
    return image
  }
  return UIImage()
}
```

This returns either the image from the `Location` or an empty placeholder image.

You should read this `if` statement as, "if the location has a photo, and I can unwrap `location.photoImage`, then return the unwrapped image."

You have previously seen the && (logical and) used to combine two conditions, but you cannot write the above like this:


```
if location.hasPhoto && let image = location.photoImage
```

The && only works if both conditions are booleans, but here you're unwrapping an optional as well. In that case you must combine the two conditions with a comma.

➤ Call this new method from the end of `configure(for:)`:

```
photoImageView.image = thumbnail(for: location)
```

➤ Try it out. The Locations tab should now look something like this:



Images in the Locations table view

You've got thumbnails, all right!

There's a tiny — or rather, literally huge — problem here. These photos are potentially big — 2592 by 1936 pixels or more — even though the image view is only 52 pixels square. To make them fit, the image view needs to scale down the images by a lot — which is why they might look a little "gritty".

What if you have tens or even hundreds of locations? That is going to require a ton of memory and processing speed just to display these tiny thumbnails. A better solution is to scale down the images before you put them into the table view cell.

And what better way to do that than using an extension?

★ ★ ★

Extensions

So far you've used extensions on your view controllers to group related functionality together, such as delegate methods. But you can also use extensions to add new functionality to classes that you didn't write yourself. That includes classes such as `UIImage` from the iOS frameworks.

If you ever catch yourself thinking, "Gee, I wish object X had such-and-such a method", then you can probably add that method by using an extension.

Extensions are pretty cool because they make it simple to add new functionality to an existing class. In other programming languages you would have to make a subclass and put your new methods in there, but extensions are often a cleaner solution.

Besides new methods, you can also add new computed properties, but you can't add regular instance variables. You can also use extensions on types that don't even allow inheritance, such as `structs` and `enums`.

★ ★ ★

Thumbnails via UIImage extension

You are going to add an extension to `UIImage` that lets you resize the image. You'll use it as follows:

```
return image.resized(withBounds: CGSize(width: 52, height: 52))
```

The `resized(withBounds:)` method is new. The "bounds" is the size of the rectangle, or square in this case, that encloses the image. If the image itself is not square, then the resized image may actually be smaller than the bounds.

Let's write the extension.

➤ Add a new file to the project and choose the **Swift File** template. Name the file **UIImage+Resize.swift**.

➤ Replace the contents of this new file with:

```
import UIKit

extension UIImage {
  func resized(withBounds bounds: CGSize) -> UIImage {
    let horizontalRatio = bounds.width / size.width
    let verticalRatio = bounds.height / size.height
    let ratio = min(horizontalRatio, verticalRatio)
    let newSize = CGSize(
      width: size.width * ratio,
      height: size.height * ratio)
    UIGraphicsBeginImageContextWithOptions(newSize, true, 0)
    draw(in: CGRect(origin: CGPoint.zero, size: newSize))
    let newImage = UIGraphicsGetImageFromCurrentImageContext()
    UIGraphicsEndImageContext()

    return newImage!
  }
}
```

This method first calculates how big the image should be in order to fit inside the bounds rectangle. It uses the "aspect fit" approach to keep the aspect ratio intact.


Then it creates a new image context and draws the image into that. We haven't really dealt with graphics contexts before, but they are an important concept in Core Graphics — in case you're wondering, it has nothing to do with the managed object context from Core Data, even though they both use the term "context".

Let's put this extension to work.

➤ Switch to **LocationCell.swift**. Update the `thumbnail(for:)` method:

```
func thumbnail(for location: Location) -> UIImage {
  if location.hasPhoto, let image = location.photoImage {
    return image.resized(
      withBounds: CGSize(width: 52, height: 52))
  }
  return UIImage()
}
```

➤ Run the app. The thumbnails should look A-OK:



The thumbnails now look great

Exercise: Change the resizing function in the `UIImage` extension to resize using the "Aspect Fill" rules instead of the "Aspect Fit" rules. Both keep the aspect ratio intact but Aspect Fit keeps the entire image visible while Aspect Fill fills up the entire rectangle and may cut off parts on the sides. In other words, Aspect Fit scales to the longest side but Aspect Fill scales to the shortest side.



Aspect Fit vs. Aspect Fill

★ ★ ★

Handling low-memory situations

The `UIImagePickerController` is very memory-hungry. Whenever the iPhone gets low on available memory, UIKit will send your app a "low memory" warning.

When that happens, you should reclaim as much memory as possible, or iOS might be forced to terminate the app. And that's something to avoid — users generally don't like apps that suddenly quit on them!

Chances are that your app gets one or more low-memory warnings while the image picker is open, especially when you run it on a device that has other apps suspended in the background. Photos take up a lot of space — especially when your camera is 5 or more megapixels — so it's no wonder that memory fills up quickly.

You can respond to memory warnings by overriding the `didReceiveMemoryWarning()` method in your view controllers to free up any memory you no longer need. This is often done for things that can easily be recalculated or recreated later, such as thumbnails or other cached objects.

UIKit is already pretty smart about low memory situations and it will do everything it can to release memory, including the thumbnail images of rows that are not (or no longer) visible in your table view.

For *MyLocations* there's not much that you need to do to free up additional memory, you can rely on UIKit to automatically take care of it. But in your own apps you might want to take extra measures, depending on the sort of cached data that you have.

By the way, on the Simulator you can trigger a low memory warning using the **Debug ▸ Simulate Memory Warning** menu item. It's smart to test your apps under low memory conditions, because they are likely to encounter such situations out in the wild once they're running on user devices.

★ ★ ★

Great! That concludes all the functionality for this app. Now it's time to fine-tune its looks.


You can find the project files for this chapter under **30-Image-picker** in the Source Code folder.

Chapter 31: Polishing the App


By Fahim Farook

Apps with appealing visuals sell better than ugly ones. Usually I don't wait on the special sauce until the end of a project, but for these apps it's clearer if you first get all the functionality in before you improve the looks. Now that the app works as it should, let's make it look good!

You're going to go from this:



To this:



The main screen gets the biggest makeover, but you'll also tweak the others a little.

You'll do the following in this chapter:

- **Convert placemarks to strings:** Refactor the code to display placemarks as text values so that the code is centralized and easier to use.
- **Back to black:** Change the appearance of the app to have a black background and light text.
- **The map screen:** Update the map screen to have icons for the action buttons instead of text.
- **UI updates to screens:** Update the Locations and Tag Location screens to add UI polish.
- **Polish the main screen:** Update the appearance of the main screen to add a bit of awesome sauce!
- **Make some noise:** Add sound effects to the app.
- **The icon and launch images:** Add the app icon and launch images to complete the app.

Convert placemarks to strings

Let's begin by improving the code. I'm not really happy with the way the reverse geocoded street address gets converted from a `CLPlacemark` object into a string. It works, but the code is unwieldy and repetitive.

There are three places where this happens:

- `CurrentLocationViewController`, the main screen.
- `LocationDetailsViewController`, the Tag/Edit Location screen.
- `LocationsViewController`, the list of saved locations.

Let's start with the main screen. **CurrentLocationViewController.swift** has a method named `string(from:)` where this conversion happens. It's supposed to return a string that looks like this:

```
subThoroughfare thoroughfare
locality administrativeArea postalCode
```

This string goes into a `UILabel` that has room for two lines, so you use the `\n` character sequence to create a line-break between the thoroughfare and locality.

The problem is that any of these properties may be `nil`. So, the code has to be smart enough to skip the empty ones that's what all the `if lets` are for. What I don't like is that there's a lot of repetition going on in this method. You can refactor this.

> **Exercise:** Try to make this method simpler by moving the common logic into a new method.

Answer: Here is how I did it. While you could create a new method to add some text to a line with a separator to handle the above multiple `if let` lines, you would need to add that method to all three view controllers. Of course, you could add the method to the Functions.swift file to centralize the method too…

But better still, what if you created a new `String` extension since this functionality is for adding some text to an existing string? Sounds like a plan?

➤ Add a new file to the project using the **Swift File** template. Name it **String+AddText**.

➤ Add the following to **String+AddText.swift**:

```
extension String {
  mutating func add(
    text: String?,
    separatedBy separator: String
  ) {
    if let text = text {
      if !isEmpty {
        self += separator
      }
      self += text
    }
  }
}
```

Most of the code should be pretty self-explanatory. You ask the string to add some text to itself, and if the string is currently not empty, you add the specified separator first before adding the new text.

Mutating

Notice the `mutating` keyword. You haven't seen this before. Sorry, it doesn't have anything to do with X-men — programming is certainly fun, but not *that* fun. When a method changes the value of a `struct`, it must be marked as `mutating`. Recall that `String` is a `struct`, which is a value type, and therefore cannot be modified when declared with `let`. The `mutating` keyword tells Swift that the `add(text:separatedBy:)` method can only be used on strings that are made with `var`, but not on strings made with `let`.

If you try to modify `self` in a method on a `struct` that is not marked as `mutating`, Swift considers this an error.

You don't need to use the `mutating` keyword on methods inside a `class` because classes are reference types and can always be mutated, even if they are declared with `let`.

➤ Switch over to **CurrentLocationViewController.swift** and replace `string(from:)` with the following:

```
func string(from placemark: CLPlacemark) -> String {
  var line1 = ""
  line1.add(text: placemark.subThoroughfare, separatedBy: "")
  line1.add(text: placemark.thoroughfare, separatedBy: " ")

  var line2 = ""
  line2.add(text: placemark.locality, separatedBy: "")
  line2.add(text: placemark.administrativeArea, separatedBy: "
")
  line2.add(text: placemark.postalCode, separatedBy: " ")

  line1.add(text: line2, separatedBy: "\n")
  return line1
}
```

That looks a lot cleaner. The logic that decides whether or not to add a `CLPlacemark` property to the string now lives in your new `String` extension, so you no longer need all those `if let` statements. You also use `add(text:separatedBy:)` to add `line2` to `line1` with a newline character in between.

➤ Run the app to see if it works.

There's still a small thing you can do to improve the new `add(text:separatedBy:)` method. Remember default parameter values? You can use them here.

➤ In **String+AddText.swift**, change the line that defines the method to:

```
mutating func add(text: String?, separatedBy separator: String =
"") {
```

Now, instead of:

```
line1.add(text: placemark.subThoroughfare, separatedBy: "")
```

You can write:

```
line1.add(text: placemark.subThoroughfare)
```

The default value for `separator` is an empty string. If the `separatedBy` parameter is left out, `separator` will be set to "".

➤ Make these changes in **CurrentLocationViewController.swift**:

```
func string(from placemark: CLPlacemark) -> String {
  . . .
  line1.add(text: placemark.subThoroughfare)
  . . .
  line2.add(text: placemark.locality)
  . . .
```

Where the separator is an empty string, you leave out the `separatedBy: ""` part of the method call. Note that the other instances of `add(text:separatedBy:)` in the method don't have empty strings as the separator but instead, have a space.

Now you have a pretty clean solution that you can re-use in the other two view controllers.

➤ In **LocationDetailsViewController.swift**, replace the `string(from:)` code with:

```
func string(from placemark: CLPlacemark) -> String {
  var line = ""
  line.add(text: placemark.subThoroughfare)
  line.add(text: placemark.thoroughfare, separatedBy: " ")
  line.add(text: placemark.locality, separatedBy: ", ")
  line.add(text: placemark.administrativeArea, separatedBy: ",
")
  line.add(text: placemark.postalCode, separatedBy: " ")
  line.add(text: placemark.country, separatedBy: ", ")
  return line
}
```

It's slightly different from how the main screen does it. There are no newline characters and some of the elements are separated by commas instead of just spaces. Newlines aren't necessary here because the label will wrap.

The final place where placemarks are shown is `LocationsViewController`. However, this class doesn't have a `string(from:)` method. Instead, the logic for formatting the address lives in `LocationCell`.

➤ Go to **LocationCell.swift**. Change the relevant part of `configure(for:)`:

```
func configure(for location: Location) {
  . . .
  if let placemark = location.placemark {
    var text = ""
    text.add(text: placemark.subThoroughfare)
    text.add(text: placemark.thoroughfare, separatedBy: " ")
    text.add(text: placemark.locality, separatedBy: ", ")
    addressLabel.text = text
  } else {
    . . .
```

You only show the street and the city, so the conversion is simpler.

And that's it for placemarks.

Back to black

Right now the app looks like a typical iOS app: lots of white, gray tab bar, blue tint color. Let's go for a radically different look and paint the whole thing black.

Back in the day, changing the interface black would have required a lot of manual work. You would have had to change the background for the views, change the text color of the labels, and then do some additional work to change table views and so on.


But as of iOS 13, there's a new way to have a dark interface on — dark mode.

Dark mode is really supposed to be used in conjunction with the operating system itself so that when the user switches the device to dark mode — for example, at night — the interface of your app changes to match the device mode.

However, you can also enable dark mode to be always on in your app and it's as simple as — mostly — changing one setting :]

➤ Go to the **Info** tab and add a new row. Set its key to **Appearance** — you can select this from the available list of keys. The value for this key is a string – set it to **Dark**.

➤ Build and run your app and voila! Your app now has a fully dark theme!



The app now has a dark theme

➤ Check each of the screens in the app — note the instances where everything works correctly, and where things don't work so well.

Here's what I noticed:

1. The blue tint for buttons and actions doesn't look so hot against the black background
2. The second line of text on the Locations tab's list of items does not show up at all against the black background.
3. The main screen items might need something to make the "pop".

Let's fix those.

The tint color

➤ Open the asset catalog and select **AccentColor**.

You are used to using images from the Asset Catalog, but this is a color value. The special AccentColor value defines the tint color for the whole app.


By default, the AccentColor has no color value set and can be configured for a universal setting so that the color value you specify is used for any appearance – Dark or Light. You can change it to define custom colors based on appearance — dark mode vs. light mode — by changing the **Appearance** dropdown under the Attributes Inspector.

But since we only have one appearance mode all the time, we won't do that.

➤ Select **AccentColor**, click on **Universal**, and then in the **Attributes Inspector**, click **Show Color Panel** under the **Color** section. Set the color to **Red: 255, Green: 238, Blue: 136**. That will make the buttons and other interactive elements yellow, which stands out nicely against the black background.

➤ Build and run the app.

Now the blue tint is gone and the buttons and action items look much better with the yellow against the black background.



The new yellow tinted design


And that fixes all of the tint color issues in one fell swoop!

Tab bar icons

While we're at it, let's also add some icons for the tab bar items. Tab bar images should be basic grayscale images of up to 30 × 30 points — that is 60 × 60 pixels for Retina and 90 × 90 pixels for Retina HD. You don't have to tint the images; iOS will automatically draw them in the proper color.

➤ The resources for this tutorial include an **Images** directory. Add the files from this folder to the asset catalog.

➤ Go to the storyboard. Select the **Tab Bar Item** of the navigation controller embedding the Current Location screen. In the **Attributes inspector**, under **Image** choose **Tag** — this is the name of one of the images you've just added.



Choosing an image for a Tab Bar Item

➤ For the Tab Bar Item of the navigation controller attached to the Locations screen, choose the **Locations** image.

➤ For the Tab Bar Item of the navigation controller embedding the Map View Controller, choose the **Map** image.

Now the tab bar looks a lot more appealing:




The tab bar with proper icons

Storyboard dark mode

Now that you are using dark mode for your user interface, it would be helpful if you could see all your storyboard items in dark mode, wouldn't it? It's really easy to do.

➤ Open the storyboard.

➤ Tap the **Appearance** button on the Interface Builder toolbar once to set the storyboard to use **Dark Appearance** – if you tap the button again, it toggle the appearance.



Select dark mode appearance for the storyboard

Your screens now appear as they would under dark mode. There's one issue – the storyboard does not show the yellow tint color that we set via the Asset Catalog. But, there's a very easy fix.

Select the File Inspector while the storyboard is open and set the **Global Tint** to the yellow color you set in the Asset Catalog earlier – you can even select the AccentColor value straight from the color dropdown.

The Address label

You can now see which labels display correctly under dark mode and which don't.

The Address label in the Location scene's prototype cell does not display correctly. This is because we set a custom text color for this label.

Here's the secret – for dark mode to work correctly, you need the correct colors set on your interface elements. By default, labels have their text color set to **Default (Label Color)**. This is a special setting that iOS understands and which is required for dark mode to work.

When the device (and subsequently the app) is in light mode, the Default (Label Color) is black and so labels display black color against a white background. When the device switches to dark mode, then the system automatically switches the label color to white so that the label will still display correctly.

However, if you change the label color to a custom value, then iOS does not know what the dark or light mode variants for your custom color should be. So it will display your label with just the value you set.

So let's say you want to have your own custom color which switches between dark mode and light mode. How do you do that?

Remember how you set the tint color using the special AccentColor? Similar to that, you can create your own colors that you can add to the Asset Catalog. And since colors in the Asset Catalog can have dark and light variants, if you set up a color with these variants and then assign that color to any of your UI elements, they'll switch colors depending on the appearance.

We aren't going to do all that though. *MyLocations* will permanently be displaying in dark mode. So we don't need a light mode variant for the Address label.

➤ Select the Address label on the Locations scene. and set its **Label - Color** and **Label - Highlighted** color to **white with 60% Opacity**.

That's it :]

Make the main screen pop


➤ In the Current Location scene, change the **Font** of the **(Latitude/Longitude goes here)** labels to **System Bold 17**.

➤ Select the two buttons and change their **Style** to **Default**.

➤ Then, change their **Font** to **System Bold 20**, to make them slightly larger.

➤ Select the Get My Location button and change its **Text Color** to **White Color**. This provides some contrast between the two buttons.

The storyboard should now look like this:



The updated main screen


When you run the app, there is one minor issue that you might notice. The splash screen for the app, which used to be just a blank white screen, is now a blank black screen. But for the second that the splash screen displays, you don't see the status bar on the screen because it is black text on a black background.

The status bar

When the app starts up, iOS looks in the project configuration to determine whether it should show a status bar while the app launches, and if so, what color that status bar should be.

Right now, it's set to Default, which is the black status bar.

➤ Go to the **Project Settings** screen. In the **General** tab, under **Deployment Info** is a **Status Bar Style** option. Change this to **Light Content**.




Changing the status bar style for app startup

And now the status bar displays correctly even on start up!

The map screen

The Map screen currently has a somewhat busy navigation bar with three pieces of text in it: the title and the two buttons.



The bar button items have text labels

The design advice that Apple gives is to prefer text to icons because icons tend to be harder to understand. The disadvantage of using text is that it makes your navigation bar more crowded.

There are two possible solutions:


1. Remove the title. If the purpose of the screen is obvious, which it is in this case, then the title "Map" is superfluous. You might as well remove it.
2. Keep the title but replace the button labels with icons.

For this app, you'll choose the second option.

➤ Go to the Map scene in the storyboard and select the **Locations** bar button item. In the **Attributes inspector**, under **Image** choose **Pin**. This will remove the text from the button.

➤ For the User bar button item, choose the **User** image.

The Map screen now looks like this:



Map screen with the button icons

Notice that the dot for the user's current location is drawn in the yellow tint color – it was a blue dot before.

UI updates to screens

The app is starting to shape up, but there are still some details to take care of for the following screens:

1. Locations screen
2. Tag Location screen

The Locations screen

The section headers on the Locations screen are a bit on the heavy side. There is no easy way to customize the existing headers, but you can replace them with a view of your own.

➤ Go to **LocationsViewController.swift** and add the following table view delegate method:

```
override func tableView(
  _ tableView: UITableView,
  viewForHeaderInSection section: Int
) -> UIView? {
  let labelRect = CGRect(
    x: 15,
    y: tableView.sectionHeaderHeight - 14,
    width: 300,
    height: 14)
  let label = UILabel(frame: labelRect)
  label.font = UIFont.boldSystemFont(ofSize: 11)

  label.text = tableView.dataSource!.tableView!(
    tableView,
    titleForHeaderInSection: section)
```


```
    label.textColor = UIColor(white: 1.0, alpha: 0.6)
    label.backgroundColor = UIColor.clear

    let separatorRect = CGRect(
      x: 15, y: tableView.sectionHeaderHeight - 0.5,
      width: tableView.bounds.size.width - 15,
      height: 0.5)
    let separator = UIView(frame: separatorRect)
    separator.backgroundColor = tableView.separatorColor

    let viewRect = CGRect(
      x: 0, y: 0,
      width: tableView.bounds.size.width,
      height: tableView.sectionHeaderHeight)
    let view = UIView(frame: viewRect)
    view.backgroundColor = UIColor(white: 0, alpha: 0.85)
    view.addSubview(label)
    view.addSubview(separator)
    return view
  }
```

This method gets called once for each section in the table view. Here, you create a label for the section name, a 1-pixel high view that functions as a separator line, and a container view to hold these two subviews.

It looks like this:



The section headers now draw much less attention to themselves

Note: Did you notice anything special about the following line?

```
label.text = tableView.dataSource!.tableView!(tableView,
titleForHeaderInSection: section)
```

This asks the table view's data source for the text to put in the header. The `dataSource` property is an optional so you're using `!` to unwrap it. But that's not the only `!` in this line...

You're calling the `tableView(_:titleForHeaderInSection:)` method on the table view's data source, which is of course the `LocationsViewController` itself.

But this method is an optional method — not all data sources need to implement it. Because of that you have to *unwrap the method* with the exclamation mark in order to use it. Unwrapping methods... does it get any crazier than that?

By the way, you can also write this as:

```
label.text = self.tableView(tableView, titleForHeaderInSection:
section)
```


Here you use `self` to directly access that method on `LocationsViewController`. Both ways achieve exactly the same thing, since the view controller happens to be the table view's data source.

Another small improvement you can make is to always put the section headers in uppercase.

➤ Change `tableView(_:titleForHeaderInSection:)` to:

```
override func tableView(
  _ tableView: UITableView,
  titleForHeaderInSection section: Int
) -> String? {
  let sectionInfo = fetchedResultsController.sections![section]
  return sectionInfo.name.uppercased()
}
```

Now the section headers look even better:



The section header text is in uppercase


Currently, if a location does not have a photo, there is a black gap where the thumbnail is supposed to be. That doesn't look very professional. It's better to show a placeholder image. You already added one to the asset catalog when you imported the Images folder.

➤ In **LocationCell.swift**'s `thumbnail(for:)`, replace the last line that returns an empty `UIImage` with:

```
return UIImage(named: "No Photo")!
```

Recall that `UIImage(named:)` is a failable initializer, so it returns an optional. Don't forget the exclamation point at the end to unwrap the optional.

Now locations without photos appear like so:



A location using the placeholder image

That makes it a lot clearer to the user that the photo is missing – as opposed to, say, being a photo of a black hole. The placeholder image is round.

That's the fashion for thumbnail images on iOS these days, and it's pretty easy to make the other thumbnails rounded too.


➤ Still in **LocationCell.swift**, add the following lines to the end of `awakeFromNib()`:

```
// Rounded corners for images
photoImageView.layer.cornerRadius =
photoImageView.bounds.size.width / 2
photoImageView.clipsToBounds = true
separatorInset = UIEdgeInsets(top: 0, left: 82, bottom: 0,
right: 0)
```

This gives the image view rounded corners with a radius that is equal to half the width of the image, which makes it a perfect circle.

The `clipsToBounds` setting makes sure that the image view respects these rounded corners and does not draw outside them.

The `separatorInset` moves the separator lines between the cells a bit to the right so there are no lines between the thumbnail images.



The thumbnails are now circular

> **Note:** As you'll notice from the above image, the rounded thumbnails don't look very good if the original photo isn't square. You may want to change the Mode of the image view to Aspect Fill or Scale to Fill so that the thumbnail always fills up the entire image view.


The Tag Location screen

➤ Open the storyboard and go to the **Tag Location scene**.

➤ Select the detail label from all the cells with the Right Detail style and set their **Label - Color** and **Label - Highlighted** color to **white with 60% Opacity**.

➤ Select the Address detail label and set its **Label - Color** and **Label - Highlighted** color to **white with 60% Opacity**.

➤ Run the app. The Tag Location screen should now look like this:



The Tag Location screen with styling applied

Polish the main screen

I'm pretty happy with all the other screens, but the main screen needs a bit more work to be presentable.

Here's what you'll do:

- Show a logo when the app starts up. Normally, such splash screens are bad for the user experience, but here I think we can get away with it.
- Make the logo disappear with an animation when the user taps Get My Location.
- While the app is fetching the coordinates, show an animated activity spinner to make it even clearer to the user that something is going on.
- Hide the Latitude: and Longitude: labels until the app has found coordinates.

You will first hide the text labels from the screen until the app actually has some coordinates to display. The only label that will be visible until then is the one at the top and it will say "Searching..." or give some kind of error message.

In order to do this, you must have outlets for the labels.

➤ Add the following properties to **CurrentLocationViewController.swift**:

```
@IBOutlet weak var latitudeTextLabel: UILabel!
@IBOutlet weak var longitudeTextLabel: UILabel!
```

You'll put the logic for updating these labels in a single place, `updateLabels()`, so that hiding and showing them is pretty straightforward.

➤ Change `updateLabels()` in **CurrentLocationViewController.swift**:


```
func updateLabels() {
  if let location = location {
    . . .
    latitudeTextLabel.isHidden = false
    longitudeTextLabel.isHidden = false
  } else {
    . . .
    latitudeTextLabel.isHidden = true
    longitudeTextLabel.isHidden = true
  }
}
```

➤ Connect the **Latitude:** and **Longitude:** labels in the storyboard to the `latitudeTextLabel` and `longitudeTextLabel` outlets.

➤ Run the app and verify that the **Latitude:** and **Longitude:** labels only appear when you have obtained GPS coordinates.

The first impression

The main screen looks decent and is completely functional, but it could do with more pizzazz. It lacks the "Wow!" factor. You want to impress users the first time they start your app and keep them coming back. To pull this off, you'll add a logo and a cool animation. When the user hasn't yet pressed the Get My Location button, there are no GPS coordinates and the Tag Location button is hidden. Instead of showing a completely blank upper panel, you can show a large version of the app's icon.



The welcome screen of MyLocations

When the user taps the Get My Location button, the icon rolls out of the screen — it's round so that kinda makes sense — while a panel with the GPS status will slide in.

This is pretty easy to program thanks to the power of Core Animation and it makes the app a whole lot more impressive for first-time users.

First, you need to move the labels into a new container subview.


➤ Open the storyboard and go to the **Current Location View Controller**. In the Document Outline, select the six labels and the Tag Location button. With these seven views selected, choose **Editor ▸ Embed In ▸ View Without Inset** from the Xcode menu bar.

This creates a new `UIView` and puts these labels and the button inside that new view.

The layout of the screen hasn't changed; you have simply reorganized the view hierarchy so that you can easily manipulate and animate this group of views as a whole. Grouping views in a container view is a common technique for building complex layouts.

➤ To avoid problems on smaller screens, make sure that the Get My Location button sits higher up in the view hierarchy than the container view. If the button sits under another view you cannot tap it anymore.

Non-intuitively, in the Document Outline, the button must sit below the container view. If it doesn't, drag to rearrange:



Get My Location must sit below the container view in the Document Outline

> **Note:** When you drag the Get My Location button, make sure you're not dropping it into the container view. The view you just added and the Get My Location button should sit at the same level in the view hierarchy.

When you embedded the six labels and the button in the container view, the Auto Layout constraints that those seven controls had to the main view were broken. Makes sense, right? Because those controls are now inside a different view.

We have to fix a few Auto Layout constraints so that the controls are laid out correctly within the container view.

➤ Select the Container View and set its Auto Layout constraints as follows: **left=16**, **top=16**, and **right=16**.

➤ Select the **(Message Label)** at the top and set its Auto Layout Constraints to: **left=0**, **top=0**, and **right=0**.

➤ Select the **Latitude:**, **Longitude:**, and **(Address goes here)** labels and set their Auto Layout Constraints to: **left=0**.

➤ Select the **(Latitude goes here)**, **(Longitude goes here)**, and **(Address goes here)** labels and set their Auto Layout Constraints to: **right=0**.

➤ Finally, set the Tag Location button's Auto Layout Constraints to: **left=0**, **bottom=0**, and **right=0**.

➤ Add the following outlet to **CurrentLocationViewController.swift**:

```
@IBOutlet weak var containerView: UIView!
```

➤ In the storyboard, connect the new container `UIView` to the `containerView` outlet.

Now on to the good stuff!

➤ Add the following instance variables to **CurrentLocationViewController.swift**:

```
var logoVisible = false

lazy var logoButton: UIButton = {
  let button = UIButton(type: .custom)
  button.setBackgroundImage(
    UIImage(named: "Logo"), for: .normal)
  button.sizeToFit()
  button.addTarget(
    self, action: #selector(getLocation), for: .touchUpInside)
  button.center.x = self.view.bounds.midX
  button.center.y = 220
  return button
}()
```

The logo image is actually a button, so that you can tap the logo to get started. The app will show this button when it starts up, and when it doesn't have anything better to display — for example, after you press Stop and there are no coordinates and no error. To orchestrate this, you'll use the boolean `logoVisible`.

The button is a "custom" type `UIButton`, meaning that it has no title text or other frills. It draws the **Logo.png** image and calls the `getLocation()` method when tapped.

This is another one of those lazily loaded properties; I did that because it's nice to keep all the initialization logic inline with the declaration of the property.

➤ Add the following method:

```
func showLogoView() {
  if !logoVisible {
    logoVisible = true
    containerView.isHidden = true
    view.addSubview(logoButton)
  }
}
```

This hides the container view so the labels disappear, and puts the `logoButton` object on the screen. This is the first time `logoButton` is accessed, so at this point the lazy loading kicks in.

➤ In `updateLabels()`, change the line that says,

```
statusMessage = "Tap 'Get My Location' to Start"
```

to:

```
statusMessage = ""
showLogoView()
```

This new logic makes the logo appear when there are no coordinates or error messages to display. That's also the state at startup time, so when you run the app now, you should be greeted by the logo.

➤ Run the app to check it out.

When you tap the logo (or Get My Location), the logo should disappear and the panel with the labels ought to show up. That doesn't happen yet, so let's add some more code to do that.

➤ Add the following method:

```
func hideLogoView() {
  logoVisible = false
  containerView.isHidden = false
  logoButton.removeFromSuperview()
}
```

This is the counterpart to `showLogoView()`. For now, it simply removes the button with the logo and un-hides the container view with the GPS coordinates.

➤ Add the following to `getLocation()`, right after the authorization status checks:

```
if logoVisible {
  hideLogoView()
}
```

Before it starts/stops the location manager, this first removes the logo from the screen if it was visible.

Currently, there is no animation code to be seen. When doing complicated layout stuff such as this, I always first want to make sure the basics work. If they do, you can make it look fancy with an animation afterwards.

➤ Run the app. You should see the screen with the logo. Press the Get My Location button and the logo is replaced by the coordinate labels.

Great! *Now* you can add the animation. The only method you have to change is `hideLogoView()`.

➤ First, give `CurrentLocationViewController` the ability to handle animation events by making it a `CAAnimationDelegate`:

```
class CurrentLocationViewController: UIViewController,
CLLocationManagerDelegate, CAAnimationDelegate {
```

➤ Then replace `hideLogoView()` with:

```
func hideLogoView() {
  if !logoVisible { return }

  logoVisible = false
  containerView.isHidden = false
  containerView.center.x = view.bounds.size.width * 2
  containerView.center.y = 40 + containerView.bounds.size.height
/ 2

  let centerX = view.bounds.midX

  let panelMover = CABasicAnimation(keyPath: "position")
  panelMover.isRemovedOnCompletion = false
  panelMover.fillMode = CAMediaTimingFillMode.forwards
  panelMover.duration = 0.6
  panelMover.fromValue = NSValue(cgPoint: containerView.center)
  panelMover.toValue = NSValue(
    cgPoint: CGPoint(x: centerX, y: containerView.center.y))
  panelMover.timingFunction = CAMediaTimingFunction(
    name: CAMediaTimingFunctionName.easeOut)
  panelMover.delegate = self
  containerView.layer.add(panelMover, forKey: "panelMover")
```

```
    let logoMover = CABasicAnimation(keyPath: "position")
    logoMover.isRemovedOnCompletion = false
    logoMover.fillMode = CAMediaTimingFillMode.forwards
    logoMover.duration = 0.5
    logoMover.fromValue = NSValue(cgPoint: logoButton.center)
    logoMover.toValue = NSValue(
      cgPoint: CGPoint(x: -centerX, y: logoButton.center.y))
    logoMover.timingFunction = CAMediaTimingFunction(
      name: CAMediaTimingFunctionName.easeIn)
    logoButton.layer.add(logoMover, forKey: "logoMover")

    let logoRotator = CABasicAnimation(
      keyPath: "transform.rotation.z")
    logoRotator.isRemovedOnCompletion = false
    logoRotator.fillMode = CAMediaTimingFillMode.forwards
    logoRotator.duration = 0.5
    logoRotator.fromValue = 0.0
    logoRotator.toValue = -2 * Double.pi
    logoRotator.timingFunction = CAMediaTimingFunction(
      name: CAMediaTimingFunctionName.easeIn)
    logoButton.layer.add(logoRotator, forKey: "logoRotator")
  }
```

This creates three animations that are played at the same time:

1. The `containerView` is placed outside the screen (somewhere on the right) and moved to the center.
2. The logo image view slides out of the screen.
3. The logo image also rotates around its center, giving the impression that it's rolling away.

Because the "panelMover" animation takes longest, you set a delegate on it so that you will be notified when the entire animation is over.

➤ Now add the necessary `CAAnimationDelegate` method:

```
  // MARK: - Animation Delegate Methods
  func animationDidStop(_ anim: CAAnimation, finished flag: Bool)
  {
    containerView.layer.removeAllAnimations()
    containerView.center.x = view.bounds.size.width / 2
    containerView.center.y = 40 + containerView.bounds.size.height
  / 2
    logoButton.layer.removeAllAnimations()
    logoButton.removeFromSuperview()
  }
```

This cleans up after the animations and removes the logo button, as you no longer need it.


➤ Run the app. Tap on Get My Location to make the logo disappear. I think the animation looks pretty cool.

Tip: To get the logo back so you can try again, first choose **Location ▸ None** from the Simulator's **Features** menu. Then tap Get My Location followed by Stop to make the logo reappear. Apple says that good apps should "surprise and delight", and modest animations such as these really make your apps more interesting to use — as long as you don't overdo it!

Add an activity indicator

When the user taps the Get My Location button, you currently change the button's text to say Stop to indicate the change of state. You can make it even clearer to the user that something is going on by adding an animated activity "spinner".

It will look like this:



The animated activity spinner shows that the app is busy

UIKit comes with a standard control for this, `UIActivityIndicatorView`. You could add the spinner to the storyboard — and that's the way I generally prefer to do things. However, it's good to learn different techniques and so you'll create the spinner in code this time. The code to change the appearance of the Get My Location button sits in the `configureGetButton()` method. That's also a good place to show and hide the spinner.

➤ Replace `configureGetButton()` with the following:

```
func configureGetButton() {
  let spinnerTag = 1000

  if updatingLocation {
    getButton.setTitle("Stop", for: .normal)

    if view.viewWithTag(spinnerTag) == nil {
      let spinner = UIActivityIndicatorView(style: .medium)
      spinner.center = messageLabel.center
      spinner.center.y += spinner.bounds.size.height / 2 + 25
      spinner.startAnimating()
```

```
        spinner.tag = spinnerTag
        containerView.addSubview(spinner)
      }
    } else {
      getButton.setTitle("Get My Location", for: .normal)

      if let spinner = view.viewWithTag(spinnerTag) {
        spinner.removeFromSuperview()
      }
    }
  }
```

In addition to changing the button text to "Stop", you create a new instance of `UIActivityIndicatorView`. Then you do some calculations to position the spinner view below the message label at the top of the screen. The call to `addSubview()` actually adds the spinner to the container view and makes it visible.

To keep track of this spinner view, you give it a tag of 1000. You could use an instance variable but this is just as easy and it keeps everything local to the `configureGetButton()` method. It's nice to have everything in one place.

When it's time to revert the button to its old state, you call `removeFromSuperview()` to remove the activity indicator view from the screen.

And that's all you need to do.

➤ Run the app. There should now be a cool little animation while the app is busy talking to the GPS satellites.

Make some noise

Visual feedback is important, but you can't expect users to keep their eyes glued to the screen all the time, especially if an operation might take a few seconds or more.

Emitting an unobtrusive sound is a good way to alert the user that a task is complete — for example, when your iPhone sends an email, you hear a soft "whoosh" sound.

You're going to add a sound effect to the app too, which is to be played when the first reverse geocoding successfully completes. That seems like a reasonable moment to alert the user that GPS and address information has been captured.

There are many ways to play sounds on iOS, but you're going to use one of the simplest: system sounds. The System Sound API is intended for short beeps and other notification sounds, which is exactly the type of sound that you want to play here.

➤ Add an import for AudioToolbox, the framework for playing system sounds, to the top of **CurrentLocationViewController.swift**:

```
import AudioToolbox
```

➤ Add a `soundID` instance variable:

```
var soundID: SystemSoundID = 0
```

Because writing just 0 would normally give you a variable of type `Int`, you explicitly mention the type that you want it to be: `SystemSoundID`. This is a numeric identifier — sometimes called a "handle" — that refers to a system sound object. 0 means no sound has been loaded yet.

➤ Add the following methods to the class:

```
// MARK: - Sound effects
func loadSoundEffect(_ name: String) {
  if let path = Bundle.main.path(forResource: name, ofType: nil)
{
    let fileURL = URL(fileURLWithPath: path, isDirectory: false)
    let error = AudioServicesCreateSystemSoundID(fileURL as
CFURL, &soundID)
    if error != kAudioServicesNoError {
      print("Error code \(error) loading sound: \(path)")
    }
  }
}

func unloadSoundEffect() {
  AudioServicesDisposeSystemSoundID(soundID)
  soundID = 0
}

func playSoundEffect() {
  AudioServicesPlaySystemSound(soundID)
}
```

The `loadSoundEffect()` method loads the sound file and puts it into a new sound object. The specifics don't really matter, but you end up with a reference to that object in the `soundID` instance variable.

➤ Call `loadSoundEffect()` from `viewDidLoad()`:

```
loadSoundEffect("Sound.caf")
```

➤ In `locationManager(_:didUpdateLocations:)`, in the geocoder's completion closure, change the following code:

```
if error == nil, let places = placemarks, !places.isEmpty {
  // New code block
  if self.placemark == nil {
    print("FIRST TIME!")
    self.playSoundEffect()
  }
  // End new code
  self.placemark = places.last!
} else {
  . . .
```

The new `if` statement simply checks whether the `self.placemark` instance variable is `nil`, in which case this is the first time you've reverse geocoded an address. It then plays a sound using the `playSoundEffect()` method. Of course, you shouldn't forget to add the actual sound effect to the project!

➤ Add the **Sound** folder from this app's Resources to the project. Make sure **Copy items if needed** is selected — click the Options button in the file open panel to reveal this option.

➤ Run the app and see if it makes some noise. The sound should only be played for the first address it finds — when you see the FIRST TIME! log message — even if more precise locations keep coming in afterwards.

Note: If you don't hear the sound on the Simulator, try the app on a device. Sometimes system sounds will not play on the simulators.

CAF audio files

The Sound folder contains a single file, **Sound.caf**. The **caf** extension stands for Core Audio Format, and it's the preferred file format for these kinds of short audio files on iOS.

If you want to use your own sound file but it is in a different format than CAF and your audio software can't save CAF files, then you can use the `afconvert` utility to convert the audio file. You need to run it from the Terminal:

```
$ /usr/bin/afconvert -f caff -d LEI16 Sound.wav Sound.caf
```


This converts the Sound.wav file into Sound.caf. You don't need to do this for the audio file from this app's Sound folder because that file is already in the correct format. But if you want to experiment with your own audio files, then knowing how to use `afconvert` might be useful.

By the way, iOS can play .wav files just fine, but .caf is more optimal.

The icon and launch images

The Resources folder for this app contains an **Icon** folder with the app icons.

➤ Import the icon images into the asset catalog — you can simply drag them from Finder into the **AppIcon** group. It's best to drag them one-by-one into their respective slots — if you drag the whole set of icons into the group at once, Xcode can get confused.



The icons in the asset catalog

The app currently also has a launch file, **LaunchScreen.storyboard**, that provides the splash image for when the app is still loading. We'll modify it quickly to fit in with the look and feel of the rest of the app.

➤ Open **LaunchScreen.storyboard** and change the **Appearance** to **Dark Appearance**.

➤ Also switch the view to **iPhone SE (2nd Generation)** since that's what we've been designing the other screens for.

➤ Add an **Image View** from the Library and set its **Image** property in the **Attributes Inspector** to **Logo**. This puts the logo image from the main screen on the splash screen as well.

➤ Set the new image view to align **Horizontally in Container** in its parent view using the Auto Layout **Align** menu.

➤ Set the image view's **top** alignment to be **100** points.


➤ The Resources folder for this app contains a **Launch Images** folder. Add the **tabbar@2x.png** image it contains to the **Asset Catalog**.

➤ Add another **Image View** from the Library and set its **Image** property in the **Attributes Inspector** to **tabbar**. This adds an image of the app's tab bar.

➤ With the new image view selected, use **Editor ▸ Size to Fit Content** to size the image view to fit the image.

➤ Set the Auto Layout constraints for the new image as: **left=0**, **right=0**, **bottom=0**.

Your LaunchScreen.storyboard should now look like this:



The launch screen for the app

The launch screen only shows the tab bar and the logo button, but no status bar or any buttons. The reason it has no "Get My Location" button is that you don't want users to try and tap it while the app is still loading since it's not really a button!

There's one tiny issue that might not be evident at this point.

➤ Switch to an **iPhone 11 Pro Max** via the IB toolbar.

You will see that the tab bar image does not cover the width of the screen – it might be easier to see if you toggle the Appearance to Light Mode.60%](images/31-Polishing-the-app/Tab-does-not-cover-screen.png "The tab image does not cover width of screen") This is due to our old friend, the Content Mode setting for the image.

➤ Change the **Content Mode** for the image in the **Attributes Inspector** to **Aspect Fill**.


Done. That was easy. :] And with that, *MyLocations* is complete! Woohoo!

You can find the final project files for the app under **31-Polishing-the-app** in the Source Code folder.

The end

Congrats on making it this far! It has been a long and winding road with a lot of theory to boot. I hope you learned a lot of useful stuff.

The final storyboard for *MyLocations* looks like this:



In this section you took a more detailed look at Swift, but there's still plenty to discover. To learn more about the Swift programming language, I recommend that you read the following books:

- **The Swift Programming Language** by Apple. This is a free download on the iBooks Store. If you don't want to read the whole thing, at least take the Swift tour. It's a great introduction to the language.
- **Swift Apprentice** by the raywenderlich.com tutorial Team. This is a book that teaches you everything you need to know about Swift, from beginning to advanced topics. This is a sister book to the UIKit Apprentice; the UIKit Apprentice focuses more on making apps, while the Swift Apprentice focuses more on the Swift language itself. https://www.raywenderlich.com/books/swift-apprentice.

There are several good Core Data beginner books on the market. Here are two recommendations:

- **Core Data by Tutorials** by the raywenderlich.com tutorial Team. One of the few Core Data books that is completely up-to-date with the latest iOS and Swift versions. This book is for intermediate iOS developers who already know the basics of iOS and Swift development, but want to learn how to use Core Data to save data in their apps. https://www.raywenderlich.com/books/core-data-by-tutorials.
- **Core Data Programming Guide** by Apple. If you want to get into the nitty gritty, then Apple's official guide is a must-read. You can learn a ton from this guide. apple.co/2wNgiRu.

Credits for this tutorial:

- Sound effect based on a flute sample by elmomo, downloaded from The Freesound Project (freesound.org).
- Image resizing category is based on code by Trevor Harmon (bit.ly/2wNGRX3).
- HudView code is based on MBProgressHud by Matej Bukovinski (github.com/matej/MBProgressHUD).

Are you ready for the final app? Then continue on to the next chapter, where you'll make an app that communicates with a web service over the network!

Section 4: Store Search

The final section of the book covers building an app which supports both Light and Dark appearances from scratch via the *StoreSearch* app. *StoreSearch* shows you how to have separate custom assets and colors for each type of iOS appearance.

But that's not all! The app also shows you how to do custom screens both for specific orientations (landscape vs. portrait) as well as for specific platforms (iPhone vs. iPad). This section covers networking, working with remote API endpoints to fetch data needed by your app, and how to parse the fetched data, how to work with Stack Views, and how to add iPad support to your app.

If that wasn't enough, this section also takes you through the full application life cycle – from developing the code, testing it, and all the way to submitting to Apple. So don't skip this section thinking that you know all about iOS development after the last few sections!

Chapter 32: Search Bar

By Fahim Farook


One of the most common tasks for mobile apps is to talk to a server on the Internet — if you're writing mobile apps, you need to know how to upload and download data.

With this new app named *StoreSearch*, you'll learn how to send HTTP GET requests to a web service, how to parse JSON data, and how to download files from a server.

You're going to build an app that lets you search the iTunes store. Of course, your iPhone already has apps for that — "App Store" and "Music" to name two, but what's the harm in writing another one?

Apple has made a web service available for searching the entire iTunes store and you'll be using that to learn about networking.

The finished app will look like this:




The finished StoreSearch app

You will add search capability to your old friend, the table view. There is an animated pop-up with extra information when you tap an item in the table. And when you flip the iPhone over to landscape, the layout of the app completely changes to show the search results in a different way.

With the last app, you dipped your toe in the dark mode pool. Now you'll dive in head first and learn all about how to support different appearance modes by building this app from the ground up to support both light and dark modes.

There will also be an iPad version of the app with a custom UI for the iPad:



The app on the iPad

StoreSearch fills in the missing pieces and rounds off the knowledge you have gained from developing the previous apps. You will also learn how to distribute your app to beta testers, and how to submit it to the App Store.

In this chapter, you will do the following:

- **Create the project:** Create a new project for your new app. Set up version control using Git.
- **Create the UI:** Create the user interface for *StoreSearch*.
- **Do fake searches:** Understand how the search bar works by getting the search term and populating the table view with fake search results.
- **Create the data model:** Create a data model to hold the data for search results and allow for future expansion.
- **No data found:** Handle "no data" situations when doing a search.


There's a lot of work ahead, so let's get started!

Create the project

Fire up Xcode and make a new project. Choose the **App** template and fill in the options as follows:

- Product Name: **StoreSearch**
- Team: **Default value**
- Organization Identifier: **com.yourname**
- Interface: **Storyboard**
- Language: **Swift**
- Use Core Data, Include Tests: leave these **unchecked**

When you save the project Xcode gives you the option to create a **Git repository**. You've ignored this option thus far, but now you should make sure it is enabled:



Creating a Git repository for the project

If you don't see this option, click the Options button at the bottom-left of the dialog.

★ ★ ★

Git and version control

Git is a **version control system** — it allows you to make snapshots of your work so you can always go back later and see a history of the changes made to the project. Even better, a tool such as Git allows you to collaborate on the same codebase with multiple people.

Imagine the chaos if two programmers changed the same source file at the same time. It's possible that your changes could accidentally be overwritten by a colleague's. I once had a job where I had to shout down the hall to another programmer, "Are you using file X?" just so we wouldn't be destroying each other's work.

With a version control system such as Git, each programmer can work independently on the same files, without fear of undoing the work of another. Git is smart enough to automatically merge in all of the changes, and if there are any conflicting edits, it will let you resolve them manually.

Git is not the only version control system out there, but it's the most popular one for iOS. A lot of iOS developers share their source code on GitHub (github.com), a free collaboration site that uses Git as its engine. Xcode has built-in support for Git.

For *StoreSearch*, you will use some basic Git functionality. Even if you work alone and don't have to worry about other programmers messing up your code, it still makes sense to use it. After all, you might be the one messing up your own code, and with Git, you'll always have a way to go back to your old — and working! — version of the code.

★ ★ ★

The first screen

The first screen in *StoreSearch* will have a table view with a search bar — let's create the view controller for that screen.

➤ In the Project navigator, select **ViewController.swift**, move your cursor over the `ViewController` class name and right-click to show the context menu. Select **Refactor ▸ Rename...** from the menu and rename the class (and associated files and storyboard references) to `SearchViewController`.

➤ Run the app to make sure everything works. You should see a white screen with the status bar at the top.

Test dark mode


Since we are building the app for both appearance modes from the ground up, we should test each screen for both appearance modes each time we do any testing.

➤ Select **Features ▸ Toggle Appearance** from the Simulator menu to switch your simulator to dark mode. You should now see a black screen with white status bar text. It's looking good.

You can use the Toggle Appearance menu option again to switch your simulator back to light mode.

Since we'll be doing a lot of dark mode testing, there's another way to switch the app's appearance, as well as some other settings, via Xcode directly.

When you have the app running via Xcode, click on the **Environment Overrides** button in the debug toolbar at the bottom of the Xcode editor window.



The Xcode environment overrides


Initially, each section in the menu that pops up will be disabled, but you can use the relevant switch to enable the section.

Once enabled, you can change the settings in that particular section to change how your app looks on-the-fly. So, for example, you can enable the switch for the Appearance section and then click on either the Light or Dark options to switch your app between dark and light modes.

It's good to know different ways to test your app under different environment conditions and to actually test for all these conditions. You never know what particular set of conditions surfaces a hard to replicate bug.

Git version control

Notice that the project navigator now shows **M** and **R** icons next to some of the filenames in the list:



Xcode shows the files that are modified

If you don't see these icons, then choose the **Source Control ▸ Refresh File Status** option from the Xcode menu bar. If that gives an error message or still doesn't work, simply restart Xcode. That's a good tip in general: if Xcode is acting weird, restart it.


An **M** means the file has been modified since the last *commit* and an **R** means this is a file that has been renamed.

So what is a *commit*?

When you use a version control system such as Git, you're supposed to make a snapshot every so often. Usually you'll do that after you've added a new feature to your app or when you've fixed a bug, or whenever you feel like you've made changes that you want to keep. That is called a commit.

When you created the project, Xcode made the initial commit. You can see that in the Project History window.

➤ Select the **Source Control navigator** from the Navigator pane and switch to the **Repositories** tab to see the project history:




The history of commits for this project

> **Note:** Your Git history might not always look the same as mine in the screenshots since mine might have additional commits than what I tell you to make in the book. Don't worry about that. You can always make your own commits – once you learn how — at any point and not rely solely on the instructions in the book.

➤ Let's commit the change you just made. From the Xcode menu select **Source Control ▸ Commit...**

This opens a new window that shows in detail what changes you made. This a good time to quickly review the code changes, just to make sure you're not committing anything you didn't intend to:



Xcode shows the changes you've made since the last commit

The text view at the bottom of the window — the one which says "Enter commit message here" — is where you mention what changed in this particular commit. It's always a good idea to write a short but clear reason for the commit here. Having a good description will help you later to find specific commits in your project's history.

➤ Write: **Rename ViewController to SearchViewController** as the commit message.

➤ Press the **Commit 5 Files** button – the number will vary, in your case it'll probably be 3 files. You'll see that in the Project navigator the M and R icons are gone – at least until you make your next change.

The Source Control navigator should now show two commits.




Your commit is listed in the project history

If you double-click a particular commit, Xcode will show you the changes for that commit. You'll be doing commits on a regular basis and by the end of the book you'll be a pro at it :]

Create the UI

StoreSearch still doesn't do much yet. In this section, you'll build the UI to look like this — a search bar on top of a table view:



The app with a search bar and table view

Even though this screen uses the familiar table view, it is not a *table* view controller but a regular `UIViewController` — check the class definition in SearchViewController.swift, if you are not sure.

You are not required to use a `UITableViewController` as the base class for your view controller just because you have a table view in your UI. For this app I will show you how to do that.



UITableViewController vs. UIViewController

So what exactly is the difference between a *table* view controller and a regular view controller?

First off, `UITableViewController` is a subclass of `UIViewController` — it can do everything that a regular view controller can. However, it is optimized for use with table views and has some cool extra features.

For example, when a table cell contains a text field, tapping that text field will bring up the on-screen keyboard. `UITableViewController` automatically scrolls the cells out of the way of the keyboard so you can always see what you're typing.

You don't get that behavior for free with a plain `UIViewController` — if you want that feature, you'll have to program it yourself.

`UITableViewController` does have a big restriction: its main view must be a `UITableView` that takes up the entire screen space, except for a possible navigation bar at the top, and a toolbar or tab bar at the bottom.

If your screen consists of just a `UITableView`, then it makes sense to make it a `UITableViewController`. But if you want to have other views (or controls) as well, the more basic `UIViewController` is the option to go with.

That's the reason you're not using a `UITableViewController` in this app. Beside the table view, the app has another view, a `UISearchBar`. It is possible to put the search bar *inside* the table view as a special header view, or have the search bar appear as part of the navigation bar, but for this app you will have it sitting above the table view.

★ ★ ★

Set up the storyboard


➤ Open the storyboard and use the Interface Builder toolbar to switch to the **iPhone SE (2nd generation)**. It doesn't really matter which iPhone model you choose here, but the iPhone SE makes it easiest to follow along with this book.

➤ Also set the **Appearance** to **Dark Appearance**. Again, it doesn't really matter which appearance you use, but you know from the past few apps that light mode (which is the default) works fine generally. So, using dark mode allows you to immediately see any visual/color issues that might be there for specifically for dark mode.

➤ Drag a new **Table View** — *not* a Table View Controller — into the existing view controller.

➤ Make the Table View as big as the main view (375 by 667 points) and then use the **Add New Constraints menu** at the bottom to attach the Table View to the edges of the screen so that **left=0**, **top=0**, **right=0**, **bottom=0**.

Remember to uncheck **Constrain to margins**, if it is checked. Each screen has 16-point margins on the left and right, but you can change their size. When "Constrain to margins" is enabled you're pinning to these margins. That's no good here; you want to pin the Table View to the edge of the screen instead.




Creating constraints to pin the Table View

This pins the Table View to the edges of its superview. Now the table will always fill up the entire screen, regardless of the size of the device screen.

➤ From the Objects Library, drag a **Search Bar** on to the Document Outline so that it is placed just below the Table View.

The reason you drag the Search Bar on to the Document Outline is that if you drop the Search Bar on to the main view, it is likely to be placed inside the Table View rather than outside.


You want the Search Bar to sit on the same level as the Table View in the Document Outline:



Search Bar must be below of Table View (left), not inside (right)

If you did put the Search Bar inside the Table View, you can pick it up in the Document Outline and drag it below the Table View.

➤ Pin the Search Bar so that **top=0**, **left=0**, and **right=0** — 3 constraints in total.




The constraints for the Search Bar

You don't need to pin the bottom of the Search Bar or give it a height constraint. Search Bars have an *intrinsic* height of 51 points.

➤ In the **Attributes inspector** for the Search Bar, change the **Placeholder** text to **App name, artist, song, album, e-book**.

At this point, the view controller's design should look like this:



The search view controller with Search Bar and Table View

Connect to outlets

You know what's coming next — connecting the Search Bar and the Table View to outlets on the view controller.

➤ Add the following outlets to **SearchViewController.swift**:

```
@IBOutlet weak var searchBar: UISearchBar!
@IBOutlet weak var tableView: UITableView!
```

➤ Switch back to the storyboard and connect the Search Bar and the Table View to their respective outlets — Control-drag from the view controller to the object that you want to connect.

➤ Run the app to make sure that everything works correctly.

> **Note:** You might have noticed that when you ran the app, the appearance is Light — unless you'd already switched the appearance on the simulator, of course. If this confuses you, note that though you have the appearance set to Dark on Interface Builder, that does not mean that the app will run in Dark mode. Instead, the app will show whichever Appearance that is set on your device or simulator.
>
> So if you want to see the app in dark mode when you run it, you'd have to switch the device or simulator to dark mode explicitly.

Do fake searches

Before you implement the iTunes store searching, it's good to understand how the `UISearchBar` component works.

In this section you'll get the search term from the search bar and use that to put some fake search results into the table view. Once you've got that working, you can build in the web service. Baby steps!

➤ Run the app. If you tap the search bar, the on-screen keyboard will appear — if you're on the simulator, you may need to press **⌘K** to bring up the keyboard, and **Shift+⌘K** to allow typing from your Mac keyboard.

However, it won't do anything when you type in a search term and tap the Search button.

Listening to the search bar is done — how else? — with a delegate. Let's put this delegate code into an extension.

Add a search bar delegate

➤ Add the following to the bottom of **SearchViewController.swift**, after the final closing bracket:

```
// MARK: - Search Bar Delegate
extension SearchViewController: UISearchBarDelegate {
  func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
    print("The search text is: '\(searchBar.text!)'")
  }
}
```

Recall that you can use extensions to organize your source code. By putting all the `UISearchBarDelegate` stuff into its own extension, you keep it together in one place and out of the way of the rest of the code.

The `UISearchBarDelegate` protocol has a method `searchBarSearchButtonClicked(_:)` that is invoked when the user taps the Search button on the keyboard. You will implement this method to put some fake data into the table. Later, you'll make this method send a network request to the iTunes store to find songs, movies and e-books that match the search text that the user typed, but let's not do too many new things at once!

At the moment, all the new code does is to output the search term from the search bar to the Xcode Console.

> **Tip:** I always put strings between single quotes when I use `print()`. That way you can easily see whether there are any trailing or leading spaces in the string. Also note that `searchBar.text` is an optional, so we need to unwrap it. It will never actually return `nil`, so a `!` will do just fine.

➤ In the storyboard, **Control-drag** from the Search Bar to Search View Controller, or the yellow circle at the top. Connect to **delegate**.

➤ Run the app, type something in the search bar and press the Search button. The Xcode Debug pane should now print the text you typed.

Show fake results

➤ Add the following new (and empty) extension to **SearchViewController.swift**:

```
// MARK: - Table View Delegate
extension SearchViewController: UITableViewDelegate,
UITableViewDataSource {
}
```

The above extension will handle all the table view related delegate methods. You could certainly have added them as two separate extensions if you liked, but I prefer to keep all the table view delegate related code in one place.

Adding the `UITableViewDataSource` and `UITableViewDelegate` protocols wasn't necessary for the previous apps because you used a `UITableViewController` in each case. `UITableViewController` already conforms to these protocols under the hood.

`SearchViewController` however, is a regular view controller and therefore you have to hook up the data source and delegate protocols yourself.

➤ Xcode should complain at this point that your code does not conform to the `UITableViewDataSource` protocol. Modify the extension as follows to add the minimum code you need for the moment:

```
extension SearchViewController: UITableViewDelegate,
UITableViewDataSource {
  func tableView(
    _ tableView: UITableView,
    numberOfRowsInSection section: Int
  ) -> Int {
    return 0
  }
```


```
    func tableView(
      _ tableView: UITableView,
      cellForRowAt indexPath: IndexPath
    ) -> UITableViewCell {
      return UITableViewCell()
    }
  }
```

This simply tells the table view that it has no rows yet. Soon you'll give it some fake data to display, but for now you just want to be able to compile the code without errors.

Often you can declare as conforming to a protocol without implementing any of its methods — for example, this works fine for `UISearchBarDelegate`. A protocol can have optional and required methods. If you forget a required method, you'll generally see Xcode complain, like you did above.

➤ In the storyboard, **Control-drag** from the Table View to Search View Controller. Connect to **dataSource**. Repeat to connect to **delegate**.

In case you're wondering how you connected something to a `delegate` property in Search View Controller twice — first the Search Bar, and then the Table View — the way Interface Builder presents this is a little misleading: the delegate outlet is not from `SearchViewController`, but belongs to the thing that you Control-dragged from. So you connected the `SearchViewController` to the `delegate` outlet on the Search Bar and also to the `delegate` (and `dataSource`) outlets on the Table View:



The connections from Search View Controller to the other objects

➤ Build and run the app to make sure everything still works.

> **Note:** Did you notice a difference between these data source methods and the ones from the previous apps? Look closely...

Answer: They don't have the `override` keyword.

In the previous apps, `override` was necessary because you were dealing with a subclass of `UITableViewController`, which already provides its own version of the `tableView(_:numberOfRowsInSection:)` and `tableView(_:cellForRowAt:)` methods.

In those apps, you were "overriding" or replacing those methods with your own versions, hence the need for the `override` keyword.

Here, however, your base class is not a table view controller but a regular `UIViewController`. Such a view controller doesn't have any table view methods yet, so you're not overriding anything here.

As you know by now, a table view needs some kind of data model. Let's start with a simple `Array`.

➤ Add an instance variable for the array — this goes inside the `class` brackets, not in any of the extensions:

```
var searchResults = [String]()
```

The search bar delegate method will put some fake data into this array and then display it using the table.

➤ Replace the `searchBarSearchButtonClicked(_:)` method with:

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  searchResults = []
  for i in 0...2 {
    searchResults.append(
      String(
        format: "Fake Result %d for '%@'", i, searchBar.text!
      )
    )
  }
  tableView.reloadData()
}
```

Here the notation `[]` means you instantiate a new `String` array and replace the contents of `searchResults` property with it. This is done each time the user performs a search. If there was already a previous array of results, then that is thrown away and deallocated. You could also have written `searchResults = [String]()` to do the same thing.

You add a string with some text into the array. Just for fun, that is repeated 3 times so your data model will have three rows in it.

When you write `for i in 0...2`, it creates a loop that repeats three times because the *closed range* `0...2` contains the numbers 0, 1, and 2. Note that this is different from the *half-open range* `0..<2`, which only contains 0 and 1. You could also have written `1...3` but as you've discovered by now, programmers like to start counting at 0 :]

You've seen format strings before. The format specifier `%d` is a placeholder for integer numbers. Likewise, `%f` is for floating-point numbers. The placeholder `%@`is for all other kinds of objects, such as strings.

The last statement in the method reloads the table view to make the new rows visible, which means you have to adapt the data source methods to read from this array as well.

➤ Replace the methods in the table view delegate extension with the following:

```
func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  return searchResults.count
}


func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cellIdentifier = "SearchResultCell"

  var cell = tableView.dequeueReusableCell(
    withIdentifier: cellIdentifier)
  if cell == nil {
    cell = UITableViewCell(
      style: .default, reuseIdentifier: cellIdentifier)
  }
  cell.textLabel!.text = searchResults[indexPath.row]
  return cell
}
```

All of the above code should be pretty familiar to you by now. You simply return the number of rows to display based on the contents of the `searchResults` array and you create a `UITableViewCell` by hand to display the table rows.

➤ Run the app. If you search for anything, a few fake results get added to the data model and are shown in the table.

Search for something else and the table view updates with new fake results.



The app shows fake results when you search

UI Improvements

There are some issues with the current implementation of the app though – some are immediately evident, while others are a bit more subtle.

Table view content insets

The first thing you might have noticed: the first row of the Table View is hidden beneath the Search Bar.

That's not so strange because you put the Search Bar on top of the table, obscuring part of the table view below.

You could fix this in several different ways:

1. Change the table view's top layout constraint to match the search bar's bottom edge.
2. Make the Search Bar partially translucent to let the contents of the table cells shine through.
3. Use the table view's **content inset** attribute to allow for the area covered by the search bar.

You will go with option #3. Unfortunately, the content inset attribute is unavailable via Interface Builder. So, this has to be done from code.

➤ Add the following line to the end of `viewDidLoad()` in **SearchViewController.swift**:

```
tableView.contentInset = UIEdgeInsets(top: 51, left: 0, bottom:
0, right: 0)
```

This tells the table view to add a 51-point margin at the top to account for the Search Bar.

Now the first row will always be visible, and when you scroll the table view, the cells still go under the search bar. Nice.

Don't forget to switch appearance from Light to Dark (or vice versa) to make sure that your UI changes work correctly for both appearance modes.

Dismiss keyboard on search

It's not very nice that the keyboard stays on screen after you press the Search button. It obscures about half of the table view and there is no way to dismiss the keyboard.

➤ Add the following line to the top of `searchBarSearchButtonClicked(_:)`:

```
searchBar.resignFirstResponder()
```

This tells the `UISearchBar` that it should no longer listen for keyboard input. As a result, the keyboard will hide itself until you tap on the search bar again.

You can also configure the table view to dismiss the keyboard with a gesture.

➤ In the storyboard, select the Table View. Go to the **Attributes inspector** and set **Scroll View - Keyboard** to **Dismiss interactively**.

Extend search bar to status area


The search bar has a slightly jarring line above it to separate it from the status area. Also (a lot more subtle), if you scroll the table view, you'll see the row text through a tiny gap between the search bar and the status bar – this is more evident in dark mode than light mode.

It would look a lot better if the status bar area was unified with the search bar. There's a delegate method for `UINavigationBar` and `UISearchBar` items which allows the item to indicate its top position.

➤ Add the following method to the `SearchBarDelegate` extension:

```
func position(for bar: UIBarPositioning) -> UIBarPosition {
  return .topAttached
}
```

Now the app looks way better:



The search bar is "attached" to the top of the screen

★ ★ ★

Since you've made a UI change, don't forget to check for Dark appearance as well. In this particular case, there isn't anything you need to handle.

If you are keen-eyed, you might notice that there's now slightly more space above the first row of the table view and the search bar — this is due to the merging of the status bar and the search bar and the elimination of the separator line between the two. That additional space is about 4 points.

If you want, you can adjust the table view content inset by that amount to make things look just right again. I leave that to you as an exercise :]

The API documentation

If you were to look in the API documentation for `UISearchBarDelegate` you wouldn't find the `position(for:)` method that you used above.

Instead, it is part of the `UIBarPositioningDelegate` protocol, which the `UISearchBarDelegate` protocol extends — like classes, protocols can inherit from other protocols.


Xcode comes with a big library of documentation for developing iOS apps. Basically everything you need to know is in here. Learn to use the Xcode documentation browser — it will become your best friend!

There are a few ways to get to the documentation for an item in Xcode. There is **Quick Help**, which shows info about the item under the text cursor:




Simply have the **Quick Help inspector** open and it will show context-sensitive help. Put the text cursor on the item you want to know more about and the inspector will provide a summary. You can click any of the blue text links in the summary to jump to the full documentation.

You can also get pop-up help. Hold down the **Option** (Alt) key and hover over the item that you want to learn more about. Then click the mouse:



And of course, there is the full-fledged documentation window. You can access it from the **Help** menu, under **Developer Documentation**. Use the bar at the top to search for the item that you want to know more about:



★ ★ ★

Create the data model

So far you've added `String` objects to the `searchResults` array, but that's a bit limited. The search results that you'll get back from the iTunes store include the product name, the name of the artist, a link to an image, the purchase price, and much more.

You can't fit all of that in a single string, so let's create a new class to hold this data.

The SearchResult class

➤ Add a new file to the project using the **Swift File** template. Name the new class **SearchResult**.

➤ Add the following to **SearchResult.swift**:

```
class SearchResult {
  var name = ""
  var artistName = ""
}
```

This adds two properties to the new `SearchResult` class. You'll add several others in a bit.

In `SearchViewController` you need to modify the `searchResults` array to hold instances of `SearchResult`.

➤ In **SearchViewController.swift**, change the declaration of the property:

```
var searchResults = [SearchResult]()
```

➤ Next, change the `for in` loop in the search bar delegate method to:

```
for i in 0...2 {
  let searchResult = SearchResult()
  searchResult.name = String(format: "Fake Result %d for", i)
  searchResult.artistName = searchBar.text!
  searchResults.append(searchResult)
}
```

This creates an instance of the `SearchResult` object and simply puts some fake text into its `name` and `artistName` properties. Again, you do this in a loop because just having one search result by itself is a bit sad.


➤ At this point, `tableView(_:cellForRowAt:)` still expects the array to contain strings. So, update that method:

```
func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  . . .
  if cell == nil {
    cell = UITableViewCell(style: .subtitle,          // change
                           reuseIdentifier: cellIdentifier)
  }
```

```
    // Replace all the code below this point
    let searchResult = searchResults[indexPath.row]
    cell.textLabel!.text = searchResult.name
    cell.detailTextLabel!.text = searchResult.artistName
    return cell
  }
```

Instead of a regular table view cell, the code now uses a "subtitle" cell style. You put the contents of the `artistName` property into the subtitle text label.

➤ Run the app; it should look like this:



Fake results in a subtitle cell

No results found

When you add search functionality to your apps, you have to handle the following situations:

1. The user did not perform a search yet.
2. The user performed the search and received one or more results. That's what happens in the current version of the app: for every search you'll get back a handful of `SearchResult` objects.
3. The user performed the search and there were no results. It's usually a good idea to explicitly tell the user there were no results. If you display nothing at all, the user may wonder whether the search was actually performed or not.

Even though the app doesn't do any actual searching yet, there is no reason why you cannot fake the last scenario as well.

Handle not getting any results

In defense of good taste, the app will return 0 results when a user searches for "justin bieber", just so you know the app can handle this kind of situation.

➤ In `searchBarSearchButtonClicked(_:)`, put the following `if` statement around the `for in` loop:

```
. . .
if searchBar.text! != "justin bieber" {
  for i in 0...2 {
    . . .
  }
}
. . .
```

The change here is pretty simple — you've added an `if` statement that prevents the creation of any `SearchResult` objects if the text is equal to `"justin bieber"`.

➤ Run the app and do a search for "justin bieber" — note the all lowercase. The table should remain empty.

At this point, you don't know if the search failed, or if there were no results. You can improve the user experience by showing the text "(Nothing found)" instead, so the user knows beyond a shadow of a doubt that there were no search results.

➤ Change the last part of `tableView(_:cellForRowAt:)` to:

```
if cell == nil {
  . . .
}
// New code
if searchResults.count == 0 {
  cell.textLabel!.text = "(Nothing found)"
  cell.detailTextLabel!.text = ""
} else {
  let searchResult = searchResults[indexPath.row]
  cell.textLabel!.text = searchResult.name
  cell.detailTextLabel!.text = searchResult.artistName
}
// End of new code
return cell
```

That alone is not enough. When there is nothing in the array, `searchResults.count` is 0, right? But that also means that `numberOfRowsInSection` will return 0 and the table view will stay empty — this "Nothing found" row will never show up.


➤ Change `tableView(_:numberOfRowsInSection:)` to:

```
func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  if searchResults.count == 0 {
```

```
      return 1
    } else {
      return searchResults.count
    }
  }
```

Now, if there are no results, the method returns 1, for the row with the text "(Nothing Found)". This works because both `numberOfRowsInSection` and `cellForRowAt` check for this special situation.

➤ Try it out:



One can hope...

Handle no results when app starts

Unfortunately, the text "Nothing found" also appears initially when the user has not searched for anything yet. That's just silly.

The problem is that you have no way to distinguish between "not searched yet" and "nothing found". Right now, you can only tell whether the `searchResults` array is empty, but not what caused this.

> **Exercise:** How would you solve this little problem?

There are two obvious solutions that come to mind:

- Change `searchResults` to an optional. If it is `nil`, i.e. it has no value, then the user hasn't searched yet. That's different from the case where the user did search and no matches were found.
- Use a separate boolean variable to keep track of whether a search has been done yet or not.

It may be tempting to choose the optional, but it's best to avoid optionals if you can. They complicate the logic, they can cause the app to crash if you don't unwrap them properly, and they require `if let` statements everywhere. Optionals certainly have their uses, but here they are not really necessary.

So, we'll opt for the boolean. But do feel free to come back and try the optional on your own, and compare the differences. It'll be a great exercise!

➤ Still in **SearchViewController.swift**, add a new instance variable:

```
var hasSearched = false
```

➤ In the search bar delegate method, set this variable to `true`. It doesn't really matter where you do this, as long as it happens before the table view is reloaded.

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  . . .
  hasSearched = true      // Add this line
  tableView.reloadData()
}
```

➤ And finally, change `tableView(_:numberOfRowsInSection:)` to look at the value of this new variable:

```
func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  if !hasSearched {
    return 0
  } else if searchResults.count == 0 {
    return 1
  } else {
    return searchResults.count
  }
}
```

Now, the table view remains empty until you first search for something. Try it out! Later on, you'll see a much better way to handle this using an `enum` and it will blow your mind!

Selection handling

One more thing, if you currently tap on a row it will become selected and stay selected.

➤ To fix that, add the following methods to the table view delegate extension:

```
func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
```

```
    tableView.deselectRow(at: indexPath, animated: true)
  }

  func tableView(
    _ tableView: UITableView,
    willSelectRowAt indexPath: IndexPath
  ) -> IndexPath? {
    if searchResults.count == 0 {
      return nil
    } else {
      return indexPath
    }
  }
```

The `tableView(_:didSelectRowAt:)` method will simply deselect the row with an animation, while `willSelectRowAt` makes sure that you can only select rows when you have actual search results.

If you tap on the **(Nothing Found)** row now, you will notice that it is not selected at all. Actually, the row may still turn gray if you press down on it for a short while. That happens because you did not change the `selectionStyle` property of the cell. You'll fix that in a bit.

➤ This is a good time to commit your changes. Go to **Source Control ▸ Commit…** — or press the ⌘+**Option**+**C** keyboard shortcut.

Make sure all the modified files are selected/checked in the list on the left, review your changes, and type a good commit message — something like "Add a search bar and table view. The search puts fake results in the table for now". Press the **Commit** button to finish.

> **Note:** It is customary to write commit messages in the present tense. That's why I wrote "Add a search bar" instead of "Added a search bar".

The app isn't very impressive yet, but you've laid the foundation for what is to come. You have a search bar and know how to take action when the user presses the Search button. The app also has a simple data model that consists of an array with `SearchResult` objects, and it can display these search results in a table view for both Light and Dark appearances.


You can find the project files for this chapter under **32-Search-bar** in the Source Code folder.

Chapter 33: Custom Table Cells

By Fahim Farook

Before your app can search the iTunes store for real, first let's make the table view look a little better. Appearance does matter when it comes to apps!

Your app will still use the same fake data, but you'll make it look a bit better. This is what you'll have by the end of this chapter:



The app with better looks

In the process, you will learn the following:

- **Custom table cells and nibs:** How to create, configure and use a custom table cell via nib file.
- **Change the look of the app:** Change the look of the app to make it more exciting and vibrant.

- **Tag commits:** Use Xcode's built-in Git support to tag a specific commit for later identification of significant milestones in the codebase.
- **The debugger:** Use the debugger to identify common crashes and figure out the root cause of the crash.

Custom table cells and nibs


For the previous apps, you used prototype cells to create your own table view cell layouts. That works great, but there's another way. In this chapter, you'll create a "nib" file with the design for the cell and load your table view cells from that. The principle is very similar to prototype cells.

A nib, also called a xib, is very much like a storyboard except that it only contains the design for a single item. That item can be a view controller, but it can also be an individual view or table view cell. A nib is really nothing more than a container for a "freeze dried" object that you can edit in Interface Builder.

In practice, many apps consist of a combination of nibs and storyboard files, so it's good to know how to work with both.

Add a nib file

➤ Add a new file to the project. Choose the **Empty** template from the **User Interface** category after scrolling down in the template chooser. This will create a new empty nib.



Adding an empty nib to the project

➤ Click **Next** and save the new file as **SearchResultCell**.

Open **SearchResultCell.xib** and you will see an empty canvas.

★ ★ ★

Xib or nib?

I've been calling it a nib but the file extension is **.xib**. So what is the difference? In practice, these terms are used interchangeably. Technically speaking, a xib file is compiled into a nib file that is put into your application bundle. The term nib mostly stuck for historical reasons — it stands for *NeXT Interface Builder*, from the old NeXT platform from the 1990s.

You can consider the terms "xib file" and "nib file" to be equivalent. The preferred term seems to be nib, so that is what I will be using from now on. This won't be the last time computer terminology is confusing, ambiguous or inconsistent. The world of programming is full of jargon.

★ ★ ★

➤ Use the IB toolbar to switch to **iPhone SE (2n Generation)** and **Dark** appearance. As usual, we'll design for the smaller device but use Auto Layout to make the user interface adapt to larger devices/screens.

➤ From the Objects Library, drag a new **Table View Cell** on to the canvas.

➤ Select the new Table View Cell and go to the **Size inspector**. Type **80** in the **Height** field (not Row Height). Make sure **Width** is **375**, the width of the iPhone SE screen.

➤ Drag an **Image View** and two **Labels** into the cell so that the cell now looks like this:



The design of the cell

Note: If you get blue rectangles around each item like above — or would like to get the rectangles to see the full bounds of each item — then use the **Editor ▸ Canvas ▸ Bounds Rectangles** menu item to toggle the bounds rectangles on/off.

➤ Position the Image View at **X**:16, **Y**:10, **Width**:60, **Height**:60.

➤ Set the **Text** of the first label to **Name**, **Font** to **System 18**, **X**:84, **Y**:16, **Width**:275, **Height**:22.

➤ Set the **Text** for the second label to **Artist Name**, **Font** to **System 15**, **X**:84, **Y**:44, **Width**:275, **Height**:18.

➤ The Table View Cell itself needs to have a reuse identifier. You can set this in the **Attributes inspector** to **SearchResultCell**.

As you can see, editing a nib is just like editing a storyboard. The difference is that the canvas is a lot smaller because you're only editing a single table view cell, not an entire view controller.

Set up Auto Layout constraints

The design for the cell is only 375 points wide but there are iOS devices with screens wider than that. The cell itself will resize to accommodate those larger screens, but the labels won't, potentially causing their text to be cut off. You'll have to add some Auto Layout constraints to make the labels resize along with the cell.

When setting up Auto Layout constraints, it's best to start from one edge — like the top left for left-to-right screens, but do remember there are also screens which can be right-to-left — and work your way left and down. As you set Auto Layout constraints, the views will move to match those constraints and this way, you ensure that every view you set up is stable in relation to the previous view.

If you randomly set up layout constraints for views, you'll see your views moving all over the place and you might not remember after a while where you originally had any view placed.

➤ Select the **Image View** and open the **Add New Constraints** menu. Uncheck **Constrain to margins** (if checked) and pin the Image View so that **top=10** and **left=16**. Also set **Width=60** and **Height=60** so that the image is always fixed at 60 by 60 points.

➤ Select the **Name** label and again use the **Add New Constraints** menu. Uncheck **Constrain to margins** and set **top=16**, **left=8**, and **right=16**.

➤ Pin the **Artist Name** label so that **left=8**, **top=8**, **right=16** and **bottom=16** — again without constraining to margins.

➤ Finally, select the **Name** label and set its **Vertical Compression Resistance Priority** to **751** in the **Size Inspector**.


The last setting is to let Auto Layout figure out which label has priority in displaying its content if both Name and Artist Name labels had too much content to fit within the available space. Here, we declared that the item name has higher priority.

Symbol images

The image view will hold the artwork for the found item, such as an album cover, book cover, or an app icon. It may take a few seconds for these images to be loaded, so until then, it's a good idea to show a placeholder image.

Till now we've added images to the Asset Catalog from the bundled resources and used those images. However, there is another way.

➤ Select the Image View. In the **Attributes inspector**, type "square" into the **Image** field. You should get a dropdown with a list of suggestions:



List of image suggestions

You haven't added any images to the project yet! So where did these images come from?

Xcode comes bundled with what are known as Symbol Images. These are vector images which can adapt to different sizes and different contexts depending on what's required. For example, while the images listed are all black and white, you can actually set a color of your preference to each image if you wanted. Is that nifty, or what?

Apple has a handy SF Symbols app — which you can download from the design resources page at developer.apple.com — which allows you to browse all the available symbol images and search for the exact one that would suit your requirements. Once you find the right image, you can simply use it's name in the Interface Builder as we did above to set that image to be displayed in your app.

➤ Select the **square** image — the first one shown in the image above — from the dropdown.

You should now have a blue square displaying as your image:



The cell now uses a symbol image

Wait a minute! Blue? We don't want blue!

Easy enough to fix, actually.

➤ Select a nice grey color from the **Attributes Inspector**'s **View - Tint** dropdown – something like **System Gray Color** which displays fine in both Light and Dark modes.

Of course, if you prefer, you can set a different color too – totally your call. But do test the color out in both Light and Dark modes to make sure that it displays fine in all appearance modes.

What's that? You think the gray stroke is too wide? No problem!

➤ Select **Thin** (or **Ultra Light**) from the **Symbol Configuration - Weight** dropdown in the **Attributes Inspector**.

The cell design should now look like this:



The cell design with placeholder symbol image

Looking good, right? Again, don't forget to test for Light appearance if you're designing for Dark or vice versa.

Setting colors

There's one more change to make – the text color for the Artist Name label. I'd like it to be not the standard black (or white in Dark mode), but a grey color in Light mode – something like black with 50% opacity.

But that won't look good against the black background in Dark mode. Try it and see.

What do we do?

We could, of course, use our (new) old friend System Gray Color since we know that it displays fine in any appearance. But what if we wanted our own custom colors for each appearance?

There's another way that you briefly learnt about in the last app. Yes, color assets!

➤ Open the Asset Catalog, **Assets.xcassets**, and click the + button at the bottom of the Xcode window and select **Color Set**.

This adds a new named color asset to the asset catalog.

➤ Name the color **ArtistName**.

Notice that the asset has two color values – Any Appearance and Dark Appearance. The Any Appearance color value would be used for both Light appearance and for devices where there is no appearance support.

If you wanted to differentiate colors even further and have a special color for Any Appearance and a separate color for Light Appearance, then you can use the Appearance dropdown in the Attributes Inspector to select "Any, Light, Dark" to get three options for your color value.

We are fine with just the two default options we got.

➤ Select **Any Appearance** and change the **Input Method** dropdown (under the **Color** section) in the **Attributes Inspector** to **8-bit (0-255)**.

This gives you the color inputs that you're used to from the previous apps where you specify the red, green, and blue values as an integer in the 0-255 range. If you prefer using the Color Panel, you can also tap the **Show Color Panel** button below the inputs to select your color directly via the Color Panel.

➤ Set the color values to **red=0**, **green=0**, **blue=0**, **opacity=50** to get the **black with 50% opacity** color that we wanted.

➤ Next, open **SearchResultCell.xib**, select the **Artist Name** label, and open the **Label - Color** dropdown. There's a section in the dropdown called **Named Colors** and it should have the **ArtistName** asset that you added just now. Select it.

The Artist Name label now has the color asset that you set up. Switch between the Light and Dark appearances and make sure that the label displays correctly for all appearances.

You'll notice that under Dark appearance, the Artist Name still displays as white text.

> **Exercise:** We didn't set up a color for the Dark appearance, so how did the Artist Name get to white text under Dark appearance?

Answer: The ArtistName color asset had a default value set for both Any Appearance and Dark Appearance. That default value was white. That's why we still get white text under Dark appearance.

So, let's change the color for Dark Appearance.

➤ Select the asset catalog, select the ArtistName color, and then select the Dark Appearance option. Set the color values to **red=255**, **green=255**, **blue=255**, **opacity=50** to set the color to **white with 50% opacity**.

➤ Switch back to **SearchResultCell.xib** and check how the Artist Name label displays under all appearance options.

That looks more like it, right?

That concludes the design for this cell. Now you have to tell the app to use this nib.

Register nib file for use in code

➤ In **SearchViewController.swift**, add these lines to the end of `viewDidLoad()`:

```
let cellNib = UINib(nibName: "SearchResultCell", bundle: nil)
tableView.register(cellNib, forCellReuseIdentifier:
"SearchResultCell")
```

The `UINib` class is used to load nibs. Here, you tell it to load the nib you just created — note that you don't specify the .xib file extension. Then you ask the table view to register this nib for the reuse identifier "SearchResultCell".

From now on, when you call `dequeueReusableCell(withIdentifier:)` for the identifier "SearchResultCell", `UITableView` will automatically make a new cell from the nib — or reuse an existing cell if one is available, of course. And that's all you need to do.

➤ In `tableView(_:cellForRowAt:)` change this bit of code:

```
let cellIdentifier = "SearchResultCell"

var cell: UITableViewCell! = tableView.dequeueReusableCell(
  withIdentifier: cellIdentifier)
if cell == nil {
  cell = UITableViewCell(
    style: .subtitle, reuseIdentifier: cellIdentifier)
}
```

So that the final method looks like this:

```
func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cellIdentifier = "SearchResultCell"

  let cell = tableView.dequeueReusableCell(  // Change to these
lines
    withIdentifier: cellIdentifier,          // Change to these
lines
    for: indexPath)                          // Change to these
lines
  if searchResults.count == 0 {
    . . .
  } else {
    . . .
  }
  return cell
}
```

You were able to replace a chunk of code with just one statement. Now, it's almost exactly like using prototype cells, except that you have to create your own nib object and you need to register it with the table view beforehand.

> **Note:** The call to `dequeueReusableCell(withIdentifier:)` now takes a second parameter, `for:`, that takes an `IndexPath` value. This variant of the dequeue method lets the table view be a bit smarter, but it only works when you have registered a nib with the table view — or when you use a prototype cell.

➤ Run the app and do a (fake) search. Yikes, the app crashes.

> **Exercise:** Any ideas why?

Answer: Because you made your own custom cell design, you cannot use the `textLabel` and `detailTextLabel` properties of `UITableViewCell`.

Every table view cell — even a custom cell that you load from a nib — has a few labels and an image view of its own, but you should only employ these when you're using one of the standard cell styles: `.default`, `.subtitle`, etc. If you use them on custom cells, then these built-in labels get in the way of your own labels.

In this case, you shouldn't use `textLabel` and `detailTextLabel` to put text into the cell — you need to make your own properties for your labels.

Where do you put these properties? In a new class, of course. You're going to make a new class named `SearchResultCell` which extends `UITableViewCell` and has properties — and logic — for displaying the search results in this app.

Add a custom UITableViewCell subclass

➤ Add a new file to the project using the **Cocoa Touch Class** template. Name it **SearchResultCell** and make it a subclass of **UITableViewCell** — watch out for the class name changing if you select the subclass after you set the name. "Also create XIB file" should be **unchecked** as you already have one.

This creates the Swift file to accompany the nib file you created earlier.

➤ Open **SearchResultCell.xib** and select the Table View Cell — make sure you select the actual Table View Cell object, not its Content View.


➤ In the **Identity inspector**, change its class from "UITableViewCell" to **SearchResultCell**.

You do this to tell the nib that the top-level view object it contains is no longer a `UITableViewCell` but your own `SearchResultCell` subclass. From now on, whenever you call `dequeueReusableCell()`, the table view will return an object of type `SearchResultCell`.

➤ Add the following outlet properties to **SearchResultCell.swift**:

```
@IBOutlet weak var nameLabel: UILabel!
@IBOutlet weak var artistNameLabel: UILabel!
@IBOutlet weak var artworkImageView: UIImageView!
```

➤ Hook these outlets up to the respective labels and image view in the nib. It is easiest to do this from the Connections inspector for SearchResultCell:



Connect the labels and image view to Search Result Cell

You can also open the Assistant editor and Control-drag from the labels and image view to their respective outlet definitions. If you've used nib files before you might be tempted to connect the outlets to File's Owner but that won't work in this case; they must be connected to the table view cell.

Now that this is all set up, you can tell the `SearchViewController` to use these new `SearchResultCell` objects.

Use custom table view cell in app

➤ In **SearchViewController.swift**, change `cellForRowAt` to:


```
func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  let cellIdentifier = "SearchResultCell"
  let cell = tableView.dequeueReusableCell(
    withIdentifier: cellIdentifier,
```

```
      for: indexPath) as! SearchResultCell                    //
  Change this
    if searchResults.count == 0 {
      cell.nameLabel.text = "(Nothing found)"                 //
  Change this
      cell.artistNameLabel.text = ""                          //
  Change this
    } else {
      let searchResult = searchResults[indexPath.row]
      cell.nameLabel.text = searchResult.name                 //
  Change this
      cell.artistNameLabel.text = searchResult.artistName     //
  Change this
    }
    return cell
  }
```

Notice the first changed line. Previously this returned a `UITableViewCell` object, but now that you've changed the class name in the nib, you're guaranteed to always receive a `SearchResultCell` — you still need to cast it with `as!`, though.

Given that cell, you can put the name and artist name from the search result into the proper labels. You're now using the cell's `nameLabel` and `artistNameLabel` outlets instead of `textLabel` and `detailTextLabel`. You also no longer need to write `!` to unwrap because the outlets are implicitly unwrapped optionals.

➤ Run the app and it should look something like this:



Much better!

Use a constant for table cell identifier

Have you noticed that you've been using the string literal "SearchResultCell" in a few different places? It's generally better to create a single constant for such occasions.

Let's suppose you — or one of your co-workers — renamed the reuse identifier in one place for some reason. Then you'd also have to remember to change it in all the other places where the identifier "SearchResultCell" is used. It's better to limit those changes to one single spot by using a symbolic name instead.

➤ Add the following to **SearchViewController.swift**, somewhere within the class definition:

```
struct TableView {
  struct CellIdentifiers {
    static let searchResultCell = "SearchResultCell"
  }
}
```

This defines a new struct, `TableView`, containing a secondary struct named `CellIdentifiers` which contains a constant named `searchResultCell` with the value "SearchResultCell".

Should you want to change this value, then you only have to do it here and any code that uses `TableView.CellIdentifiers.searchResultCell` will be automatically updated.

There is another reason for using a symbolic name rather than the actual value: it gives extra meaning. Just seeing the text "SearchResultCell" says less about its intended purpose than the symbol `TableView.CellIdentifiers.searchResultCell`.

> **Note:** Putting symbolic constants as `static let` members inside a `struct` — or a series of structs — is a common trick in Swift. A static value can be used without an instance so you don't need to instantiate `TableView.CellIdentifiers` before you can use it — like you would need to do with a class.
>
> It's allowed in Swift to place a struct *inside* a class, which permits different classes to all have their own `TableView.CellIdentifier` structs. This wouldn't work if you placed the struct outside the class — then you'd have multiple structs with the same name in the global namespace, which is not allowed.


➤ In **SearchViewController.swift**, search for and replace the string "SearchResultCell" with `TableView.CellIdentifiers.searchResultCell`.

You'd have to do this in `viewDidLoad()` and in `tableView(_:cellForRowAt:)` — in the latter, you would have to remove the local constant and replace that instead with the new value.

➤ Run the app to make sure everything still works.

A new “No results” cell

Remember our friend Justin Bieber? Searching for him now results in this:



The Nothing Found label now looks like this

That’s not very pretty — not to mention slightly off. It would be nicer if you gave this its own look. That’s not too hard: you can simply make another nib for it.

➤ Add another nib file to the project. Again this will be an **Empty** nib. Name it **NothingFoundCell.xib**.

➤ Drag a new **Table View Cell** on to the canvas. Set its **Width** to **375**, its **Height** to **80** and give it the reuse identifier **NothingFoundCell**.

➤ Drag a **Label** into the cell and give it the text **Nothing Found**. Set the text color to the **ArtistName** color asset and the font to **System 15**.

➤ Use **Editor ▸ Size to Fit Content** to make the label fit the text exactly — you may have to deselect and select the label again to enable the menu option.

➤ Choose **Horizontally in Container** and **Vertically in Container** from the Auto Layout **Align** popup.

The cell should now look like this:



The Nothing Found cell

One more thing to fix. Remember that in `willSelectRowAt` you return `nil` if there are no search results to prevent the row from being selected? Well, if you are persistent enough you can still make the row appear gray as if it were selected. For some reason, UIKit draws the selected background if you press down on the cell for long enough, even though this doesn’t count as a real selection. To prevent this, you have to tell the cell not to use a selection color.

➤ Select the cell itself. In the **Attributes inspector**, set **Selection** to **None**. Now tapping or holding down on the Nothing Found row will no longer show any sort of selection.

You don't have to make a `UITableViewCell` subclass for this cell because there is no text to change or properties to set. All you need to do is register this nib with the table view.

➤ Add a new reuse identifier to the struct in **SearchViewController.swift**:

```
struct TableView {
    struct CellIdentifiers {
      static let searchResultCell = "SearchResultCell"
      static let nothingFoundCell = "NothingFoundCell"    // New
    }
}
```

➤ Add these lines to `viewDidLoad()`, below the other code registering the nib:

```
cellNib = UINib(nibName:
TableView.CellIdentifiers.nothingFoundCell, bundle: nil)
tableView.register(
  cellNib,
  forCellReuseIdentifier:
TableView.CellIdentifiers.nothingFoundCell)
```

This also requires you to change `let cellNib` two lines up to `var` because you're re-using the `cellNib` local variable.


➤ And finally, change `tableView(_:cellForRowAt:)` to:

```
func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  if searchResults.count == 0 {
    return tableView.dequeueReusableCell(
      withIdentifier:
TableView.CellIdentifiers.nothingFoundCell,
      for: indexPath)
  } else {
    let cell = tableView.dequeueReusableCell(withIdentifier:
      TableView.CellIdentifiers.searchResultCell,
      for: indexPath) as! SearchResultCell

    let searchResult = searchResults[indexPath.row]
    cell.nameLabel.text = searchResult.name
    cell.artistNameLabel.text = searchResult.artistName
    return cell
  }
}
```

The logic here has been restructured a little. You only make a `SearchResultCell` if there are actually any results. If the array is empty, you'll simply dequeue the cell for the `nothingFoundCell` identifier and return it since there is nothing to configure for that cell.

➤ Run the app. The search results for Justin Bieber now look like this:




The new Nothing Found cell in action

Also try it out on larger screen devices. The label should always be centered in the cell. Sweet. It has been a while since your last commit, so this seems like a good time to secure your work.

Source Control Changes

But before you commit your changes, take a look at **SearchViewController.swift** in your editor view. You might notice some blue lines along the gutter like this:



Source control change indicator in editor view

Whatever could those blue lines mean?

Those blue lines appear in projects which have source control enabled and they indicate the changes made by the developer since the last commit.

But it goes beyond that, if you work with other developers and somebody else made a change to the file you are working on and committed their change to Git, Xcode will even show these pending changes so that you are aware of changes made by somebody else that might impact the work you're doing. Very handy!

➤ Commit the changes to the repository. I used the message "Use custom cells for search results."

Change the look of the app

The app currently looks a little bland. Let's cheer it up a little by giving it more vibrant colors.

To start with, let's change the search bar color and the tint color used throughout the app. And since we want to support Light and Dark appearances, let's set these colors via color assets.

To start with, we'll set just a single color for both appearances and then once we know how that color looks, we can change to suit a particular appearance, if we need to.

➤ Open the Asset Catalog and select the **AccentColor** which is added to it by default. As you learnt with the previous app, this color can be used to specify the global tint color for your whole app.

The AccentColor currently has no color value set. You can tell by looking at the **Color - Content** setting in the **Attributes Inspector** because it is set to "None".

➤ Change **Color - Content** to **sRGB**, and the panel below will get new controls. Set **Input Method** to **8-bit (0-255)** and then set the color to **red=10**, **green=80**, **blue=80**.

This sets the global tint to a dark green.

➤ Click the + button at the bottom of the window and select **Color Set** to create a new color set. Name it **SearchBar**.

➤ Change the **Appearances** dropdown for the new color set in the **Attributes Inspector** to **None**. This will change your available color choices to one.

➤ Set the color (as you did earlier) to **red=180**, **green=240**, **blue=210**, which is a lighter shade of green.

➤ Switch to the storyboard, select the **Search Bar** and set its **Bar Tint** to the **SearchBar** color asset.

That's all you need to do change the colors.

But does these new colors work for all appearances

➤ Run the app and notice the difference:




The new theme in action

The new color looks fine for Light Appearance but it's a bit too bright for Dark mode and the status bar text is hard to read. Let's change that.

➤ Go to the **Asset Catalog**, select the **SearchBar** color asset, and change the **Appearances** (in the Attributes Inspector) to **Any, Dark**. Now you get two color instances to work with.

➤ Set the color for **Dark Appearance** to **red=10**, **green=120**, **blue=100**.

➤ Run the app again and check for both appearance modes.



The updated theme in action

That looks much better, doesn't it?

You can't see the change you made to AccentColor much except in the search bar's cursor, but it will become more obvious later on. Then you can decide if you want to change that to fit the Dark appearance or not.

Change the row selection color

Currently, tapping a row highlights it in gray. This doesn't go so well with the new color theme. So, you'll give the row selection the same color tint.

As you learnt with *MyLocations*, that's very easy to do because all table view cells have a `selectedBackgroundView` property. The view from that property is placed on top of the cell's background, but below the other content, when the cell is selected.

➤ Add the following code to `awakeFromNib()` in **SearchResultCell.swift**:

```
override func awakeFromNib() {
  super.awakeFromNib()
  // New code below
  let selectedView = UIView(frame: CGRect.zero)
  selectedView.backgroundColor = UIColor(named:
```

```
  "SearchBar")?.withAlphaComponent(0.5)
    selectedBackgroundView = selectedView
  }
```

The `awakeFromNib()` method is called after the cell object has been loaded from the nib but before the cell is added to the table view. You can use this method to do additional work to prepare the object for use. That's perfect for creating the view with the selection color.

Why don't you do that in an init method, such as `init?(coder)`? To be fair, in this case you could. But it's worth noting that `awakeFromNib()` is called some time after `init?(coder)` and also after the objects from the nib have been connected to their outlets.

For example, in `init?(coder)` the `nameLabel` and `artistNameLabel` outlets will still be `nil` but in `awakeFromNib()` they will be properly hooked up to their `UILabel` objects. So, if you wanted to do something with those outlets in code, you'd need to do that in `awakeFromNib()`, not in `init?(coder)`.

That's why `awakeFromNib()` is the ideal place for this kind of thing — it's similar to how you use `viewDidLoad()` in a view controller.

Don't forget to first call `super.awakeFromNib()` — it is required. If you forget, then the superclass `UITableViewCell` — or any of the other superclasses — may not get a chance to initialize themselves.

> **Tip:** It's always a good idea to call `super.methodName(…)` in methods that you're overriding — such as `viewDidLoad()`, `viewWillAppear()`, `awakeFromNib()`, and so on — unless the documentation says otherwise.


The code itself should hold no surprises except for the creation of the color. As you can see, you can initialize color assets by simply using their name from the asset catalog. How handy is that?

Now, you can simply set up the whole color scheme that you want to use for your app as color assets, set their values for any appearance you want to support and then be able to simply instantiate any of those colors by using the name you assigned to the color. No more guessing at what a color might be based on RGB values!

Also, as you can see from the code, you can modify the originally defined color by adjusting the transparency using `withAlphaComponent`. Here, you've made the color semi-transparent so that it isn't as prominent as the search bar color.

You know why you have the question mark before the call to `withAlphaComponent`, right? Because the named color might not exist, or you might have made a mistake spelling the name correctly, and so the color is not guaranteed to be a valid value. If the system can't find the color based on the name, it returns a `nil` value.

When you run the app, do a search and tap a row, it should look like this:




The new selection color in action

Add app icons

While you're at it, you might as well give the app an icon.


➤ Open the asset catalog (**Assets.xcassets**) and select the **AppIcon** group.

➤ Drag the images from the **Icon** folder from the Resources folder into the matching slots.



All the icons in the asset catalog

➤ Run the app and notice that it now has a nice new icon:



The app icon

Show keyboard on app launch

One final user interface tweak I'd like to make is that the keyboard should be immediately visible when you start the app so the user can start typing right away.

➤ Add the following line to `viewDidLoad()` in **SearchViewController.swift**:


```
searchBar.becomeFirstResponder()
```

As you are aware from the *Checklists* app, `becomeFirstResponder()` will give `searchBar` the "focus" and show the keyboard. Anything you type will end up in the search bar.

➤ Try it out and commit your changes. You styled the search bar and added app icons.

Tag commits


If you look through the various commits you've made so far, you'll notice a bunch of strange numbers, such as "7cc930f":



The commits listed in the history window have weird numbers

Those are internal numbers — known as the *hash* — that Git uses to uniquely identify commits. Such numbers aren't very memorable, or useful, for us humans, so Git also allows you to "tag" a certain commit with a more friendly label.

➤ Tagging a commit in Xcode is as simple a selecting the commit in the Source Control navigator view, right-clicking to get the context menu and selecting the **Tag** option.



Tagging a commit in Xcode

➤ Enter "v0.1" as the **Tag**, and an optional message describing what this particular tag encompasses. Then click **Create** to create the tag.

You can see the new tag in the Source Control navigator view:



The new tag in Xcode

Xcode works quite well with Git, but you might want more power to do complex Git operations. If you do, you'll probably need to learn how to use the Terminal or get a GUI tool such as SourceTree (sourcetreeapp.com), which is available for free.

The debugger

Xcode has a built-in debugger. Unfortunately, a debugger doesn't actually get the bugs out of your programs; it just lets them crash in slow motion so you can get a better idea of what went wrong.

The debugger lets you dig through the evidence after the damage has been done — like a CSI unit member or a detective —, in order to find the scoundrel who did it. Thanks to the debugger, you don't have to stumble in the dark with no idea what just happened. Instead, you can use it to quickly pinpoint what went wrong and where. Once you know those two things, figuring out *why* it went wrong becomes a lot easier.


Index out of range bug

Let's introduce a bug into the app so that it crashes — knowing what to do when your app crashes is very important.

➤ Change **SearchViewController.swift**'s `numberOfRowsInSection` method to:

```
func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  if !hasSearched {
    . . .
  } else if searchResults.count == 0 {
    . . .
  } else {
    return searchResults.count + 1  // This line changes
  }
}
```

➤ Now run the app and search for something. The app crashes and the Xcode window changes to something like this:



The Xcode debugger appears when the app crashes

The crash is: **Thread 1: Fatal error: Index out of range**. Sounds nasty!

According to the error message, the index that was used to access some array is larger than the number of items inside the array. In other words, the index is "out of range". That is a common error with arrays and you're likely to make this mistake more than once in your programming career.

Now that you know what went wrong, the big question is: *where* did it go wrong? You may have many calls to `array[index]` in your app, and you don't want to have to dig through the entire code to find the culprit.


Thankfully, you have the debugger to help you out. In the source code editor it already points out the offending line as you can see in the screenshot above — apparently its line 99.

Important: This line isn't necessarily the *cause* of the crash — after all, you didn't change anything in this method — but it is where the crash happens. From here you can trace backwards to the cause.

The array is `searchResults` and the index is given by `indexPath.row`. It would be great to get some insight into the row number in the index path – there are several ways to do this.

The one we'll look at here is to use the debugger's command line interface, like a hacker whiz kid from the movies :]

➤ In the Xcode Console, after the **(lldb)** prompt, type **p indexPath.row** and press enter:



Printing the value of indexPath.row

The output should be something like:

```
(Int) $R0 = 3
```

This means the value of `indexPath.row` is 3 and the type is `Int` — you can ignore the `$R0` bit.

Let's also find out how many items are in the array.

➤ Type **p searchResults** and press enter. If you use the auto complete functionality, do note that both `searchResult` — without the "s" at the end — and `searchResults` are choices. Be sure to select the correct one.:



Printing the searchResults array

The output shows an array with three items.

You can now reason about the problem: the table view is asking for a cell for the fourth row — i.e. the one at index 3 — but apparently there are only three rows in the data model — rows 0 through 2.

The table view knows how many rows there are from the value that is returned from `numberOfRowsInSection`, so maybe that method is returning the wrong number of rows? That is indeed the cause, of course, as you intentionally introduced the bug in that method.

I hope this illustrates how you should deal with crashes: first find out where the crash happens and what the actual error is, then reason your way backwards until you find the cause.

Storyboard outlet bug

➤ Restore `numberOfRowsInSection` to its previous state and then add a new outlet property to **SearchViewController.swift**:

```
@IBOutlet weak var searchBar2: UISearchBar!
```

➤ Open the storyboard and **Control-drag** from Search View Controller to the Search Bar. Select **searchBar2** from the popup.

Now the search bar is also connected to this new `searchBar2` outlet — it's perfectly fine for an object to be connected to more than one outlet at a time.

➤ Delete the `searchBar2` outlet property from **SearchViewController.swift** in the source code, not the storyboard.

This is a dirty trick on my part to create another crash. The storyboard contains a connection to a property that no longer exists. If you think this a convoluted example, then wait until you make this mistake in one of your own apps. It happens more often than you may think!

➤ Run the app and it immediately crashes. The crash is "Thread 1: "[<StoreSearch.SearchViewController 0x7fc7d690a6e0> setValue:forUndefinedKey:]: this class is not key value coding-compliant for the key searchBar2."".

Scrolling up the Xcode Console output in the Debug pane you should come across:

```
2021-08-07 14:24:08.534401-0400 StoreSearch[78283:13469540] ***
Terminating app due to uncaught exception
'NSUnknownKeyException', reason:
'[<StoreSearch.SearchViewController 0x7f8147d09520>
setValue:forUndefinedKey:]: this class is not key value coding-
compliant for the key searchBar2.'
*** First throw call stack:
  . . .
```

The first part of this message is very important: it tells you that the app was terminated because of an "NSUnknownKeyException". On some platforms, exceptions are a commonly used error handling mechanism, but on iOS this is always a fatal error and the app is forced to halt.

The bit that should pique your interest is this:

```
this class is not key value coding-compliant for the key
searchBar2
```


Hmm, that is a bit cryptic. It does mention `searchBar2` but what does "key value-coding compliant" mean? I've seen this error enough times to know what is wrong, but if you're new to this game, a message like that isn't very enlightening.

So let's see where Xcode thinks the crash happened:



Crash in AppDelegate

That also isn't very useful. Xcode says the app crashed happened in `AppDelegate` but we know that isn't the root cause. Xcode goes through the *call stack* until it finds a method that it has source code for and that's the one it shows. The call stack is the list of methods that have been called most recently. You can see it on the left of the Debugger window.



The call stack

The method at the top, `__pthread_kill`, was the last method that was called — it's actually a function, not a method. It got called from `pthread_kill`, which was called from `abort`, which was called from `abort_message`, and so on, all the way back to the `main` function, which is the entry point of the app and the very first function that was called when the app started.

A lot of the methods and functions that are listed in this call stack are from system libraries, which is why they are grayed out. If you click on one, you'll get a bunch of unintelligible assembly code. The non-gray methods are the ones with Swift source code, like the one for `AppDelegate` on item 24.


Clearly, this approach is not getting you anywhere. However, there is another thing you can try — set an **Exception Breakpoint**.

A **breakpoint** is a special marker in your code that will pause app execution and launch the debugger.

When your app hits a breakpoint, the app will pause at that exact spot. Then you can use the debugger to step line-by-line through your code in order to run it in slow motion. That can be a handy tool if you really cannot figure out why something crashes.


You're not going to step through code in this book, but you can read more about it in the Debugging section of Apple's developer support site: developer.apple.com/support/debugging. Or, you can check the **Debug code** topic under Xcode's **Help ▸ Xcode Help** menu option — if the help window is blank except for a few links, click on **Show topics** to see the list of topics. You are going to set a special breakpoint that is triggered whenever a fatal exception occurs. This will halt the program just as it is about to crash, which should give you more insight into what is going on.

➤ Switch to the **Breakpoint navigator** and click the + button at the bottom to add an **Exception Breakpoint**:




Adding an Exception Breakpoint

This will add a new breakpoint:



After adding the Exception Breakpoint

➤ Run the app again. It will still crash, but now Xcode shows a lot more info:



Xcode now has more info about the exception

There are many more methods in the call stack now. Let's see if we can find some clues as to what is going on.

What catches my attention is the call to something called `[UINib instantiateWithOwner:options:]`. That's a pretty good hint that this error occurs when loading a nib file, or the storyboard in this case.

Using these hints and clues, and the somewhat cryptic error message that you got without the Exception Breakpoint, you can usually figure out what is making your app crash.

In this case, we've established that the app crashes when it's loading the storyboard, and the error message mentioned "searchBar2". Put two and two together and you've got your answer.A quick peek in the source code confirms that the `searchBar2` outlet no longer exists in the view controller but the storyboard still refers to it.

➤ Open the storyboard and in the **Connections inspector** disconnect Search View Controller from **searchBar2** to fix the crash. That's another bug squashed!

> **Note:** Enabling the Exception Breakpoint means that you no longer get a useful error message in the Console if the app crashes — the breakpoint stops the app just before the exception happens. If sometime later during development your app crashes on another bug, you may want to disable this breakpoint to actually see the error message. You can do that from the Breakpoint navigator by simply selecting the breakpoint and clicking on the dark blue arrow. If the arrow goes from dark blue to a pale blue, it is disabled.

To summarize:

- If your app crashes while running in Xcode, the Xcode debugger will often show you an error message and where in the code the crash happened.
- If Xcode thinks the crash happened in a system library — not very useful! — add an Exception Breakpoint to get more info.
- If the app crashes but there is no error message in the Console, disable any Exception Breakpoints you may have and make the app crash again. Alternatively, click the **Continue program execution** button from the debugger toolbar a few times. That will also show the error message… eventually.
- An EXC_BAD_ACCESS error usually means something went wrong with your memory management. An object may have been "released" one time too many or not "retained" enough. With Swift these problems are mostly a thing of the past because the compiler will usually make sure to do the right thing. However, it's still possible to mess up if you're talking to Objective-C code or low-level APIs.


- EXC_BREAKPOINT is not an error. The app has stopped on a breakpoint, the blue arrow points at the line where the app is paused. You set breakpoints to pause your app at specific places in the code, so you can examine the state of the app inside the debugger. The "Continue program execution" button resumes the app.

  It is fairly common for this to happen because you accidentally clicked on the gutter of the source code editor and set a breakpoint when you didn't mean to.

This should help you get to the bottom of most of your crashes!

The build log

If you're wondering what Xcode actually does when it builds your app, then take a peek at the **Report navigator**. It's the last tab in the navigator pane.



The Report navigator keeps track of your builds and debug sessions so you can look back at what happened. It even remembers the debug output of previous runs of the app.

Make sure **All Messages** – at the top of the log window – is selected. To get more information about a particular log item, select the item and click the little detail icon that appears on the right. The line will expand and you'll see exactly which commands Xcode executed and what the result was.

Should you run into some weird compilation problem, then this is the place for troubleshooting. Besides, it's interesting to see what Xcode is up to from time to time.

★ ★ ★

You can find the project files for this chapter under **33-Custom-table-cells** in the Source Code folder.

34 Chapter 34: Networking

By Fahim Farook

Now that the preliminaries are out of the way, you can finally get to the good stuff: adding networking to the app so that you can download actual data from the iTunes Store!

The iTunes Store sells a lot of products: songs, e-books, movies, software, TV episodes... you name it. You can sign up as an affiliate and earn a commission on each sale that happens because you recommended a product — it can be even your own apps!

To make it easier for affiliates to find products, Apple made available a web service that queries the iTunes store. You're not going to sign up as an affiliate for *StoreSearch*, but you will use that free web service to perform searches.


In this chapter you will learn the following:

- **Query the iTunes web service:** An introduction to web services and the specifics about querying Apple's iTunes Store web service.
- **Send an HTTP request:** How to create a proper URL for querying a web service and how to send a request to the server.
- **Parse JSON:** How to make sense of the JSON information sent back from the server and convert that to objects with properties that can be used in your app.
- **Sort the search results:** Explore different ways to sort the search results alphabetically so as to write the most concise and compact code.

Query the iTunes web service

So what is a *web service*? Your app — also known as the "client" — will send a message over the network to the iTunes store — the "server" — using the HTTP protocol.

Because the iPhone can be connected to different types of networks — Wi-Fi or a cellular network such as LTE, 3G, or GPRS — the app has to "speak" a variety of networking protocols to communicate with other computers on the Internet.



The HTTP requests fly over the network

Fortunately you don't have to worry about any of that as the iPhone firmware will take care of this complicated process. All you need to know is that you're using HTTP.

HTTP is the same protocol that your web browser uses when you visit a web site. In fact, you can play with the iTunes web service using a web browser. That's a great way to figure out how this web service works.

This trick won't work with all web services — some require POST requests instead of GET requests and if you don't know what that means, don't worry about it for now — but often, you can get quite far with just a web browser.

Open your favorite web browser — I'm using Safari — and go to the following URL:

```
http://itunes.apple.com/search?term=metallica
```

The browser will download a file. If you open the file in a text editor, it should contain something like this:

```
{
 "resultCount":50,
 "results": [
{"wrapperType":"track", "kind":"song", "artistId":3996865,
"collectionId":579372950, "trackId":579373079,
```

```
"artistName":"Metallica", "collectionName":"Metallica",
"trackName":"Enter Sandman",
"collectionCensoredName":"Metallica", "trackCensoredName":"Enter
Sandman", "artistViewUrl":"https://itunes.apple.com/us/artist/
metallica/id3996865?uo=4", "collectionViewUrl":"https://
itunes.apple.com/us/album/enter-sandman/id579372950?
i=579373079&uo=4", "trackViewUrl":"https://itunes.apple.com/us/
album/enter-sandman/id579372950?i=579373079&uo=4",
"previewUrl":"http://a38.phobos.apple.com/us/r30/Music7/v4/bd/
fd/e4/bdfde4e4-5407-9bb0-e632-edbf079bed21/
mzaf_907706799096684396.plus.aac.p.m4a", "artworkUrl30":"http://
is1.mzstatic.com/image/thumb/Music/v4/0b/9c/
d2/0b9cd2e7-6e76-8912-0357-14780cc2616a/source/30x30bb.jpg",
"artworkUrl60":"http://is1.mzstatic.com/image/thumb/Music/v4/0b/
9c/d2/0b9cd2e7-6e76-8912-0357-14780cc2616a/source/60x60bb.jpg",
"artworkUrl100":"http://is1.mzstatic.com/image/thumb/Music/
v4/0b/9c/d2/0b9cd2e7-6e76-8912-0357-14780cc2616a/source/
100x100bb.jpg", "collectionPrice":9.99, "trackPrice":1.29,
"releaseDate":"1991-07-29T07:00:00Z",
"collectionExplicitness":"notExplicit",
"trackExplicitness":"notExplicit", "discCount":1,
"discNumber":1, "trackCount":12, "trackNumber":1,
"trackTimeMillis":331560, "country":"USA", "currency":"USD",
"primaryGenreName":"Metal", "isStreamable":true},
. . .
```

Those are the search results that the iTunes web service gives you. The data is in a format named JSON, which stands for **J**ava**S**cript **O**bject **N**otation.

JSON

JSON is commonly used to send structured data back-and-forth between servers and clients, i.e. apps. Another data format that you may have heard of is XML, but that's being fast replaced by JSON.

There are a variety of tools that you can use to make the JSON output more readable for mere humans. I have a Quick Look plug-in installed that renders JSON files in a colorful view (www.sagtau.com/quicklookjson.html).

You do need to save the output from the server to a file with a **.json** extension first, and then open it from Finder by selecting the file and then pressing the space bar:



A more readable version of the output from the web service

That makes a lot more sense.

> **Note:** You can find extensions for Safari (and most other browsers) that can prettify JSON directly inside the browser. github.com/rfletcher/safari-json-formatter is a good one.
>
> There are also dedicated tools on the Mac App Store, for example Visual JSON, that let you directly perform the request on the server and show the output in a structured and readable format.
>
> A great online tool is codebeautify.org/jsonviewer.

Browse through the JSON text for a bit. You'll see that the server gave back a list of items, some of which are songs; others are audiobooks, or music videos.

Each item has a bunch of data associated with it, such as an artist name — "Metallica", which is what you searched for —, a track name, a genre, a price, a release date, and so on.

You'll store some of these fields in the `SearchResult` class so you can display them on the screen.

The results you get from the iTunes store might be different from mine. By default, the search returns at most 50 items and since the store has quite a bit more than fifty entries that match "Metallica", each time you do the search you may get back a different set of 50 results.

Also notice that some of these fields, such as `artistViewUrl` and `artworkUrl100` and `previewUrl` are links/URLs. Go ahead and copy-paste these URLs in your browser and see what happens.

The `artistViewUrl` will open an iTunes Preview page for the artist, the `artworkUrl100` loads a thumbnail image, and the `previewUrl` opens a 30-second audio preview.

This is how the server tells you about additional resources. The images and so on are not embedded directly into the search results, but you're given a URL that allows you to download each item separately. Try some of the other URLs from the JSON data and see what they do!

The HTTP request

Back to the original HTTP request. You made the web browser go to the following URL:

```
http://itunes.apple.com/search?term=the search term
```

You can add other parameters as well to make the search more specific. For example:

```
http://itunes.apple.com/search?term=metallica&entity=song
```

Now the results won't contain any music videos or podcasts, only songs.

If the search term has a space in it you should replace it with a + sign, as in:

```
http://itunes.apple.com/search?term=pokemon+go&entity=software
```

This searches for all apps that have something to do with Pokemon Go — you may have heard of some of them.

The fields in the JSON results for this particular query are slightly different than before. There is no `previewUrl` but there are several screenshot URLs per entry. Different kinds of products — songs, movies, software — return different types of data.

That's all there is to it. You construct a URL to itunes.apple.com with the search parameters and then use that URL to make an HTTP request. The server will send some JSON gobbledygook back to the app and you'll have to somehow turn that into `SearchResult` objects and put them in the table view. Let's get on it!

Synchronous networking = bad

Before we begin though, there is a good way to do networking in your apps and a bad way.

The bad way is to perform the HTTP requests on your app's **main thread** — it is simple to program, but it will block the user interface and make your app unresponsive while the networking is taking place. Because it blocks the rest of the app, this is called synchronous networking.

Unfortunately, many programmers insist on doing networking the wrong way in their apps, which makes for apps that are slow and prone to crashing.

I will begin by demonstrating the easy-but-bad way, just to show you how *not* to do this. It's important that you realize the consequences of synchronous networking, so you will avoid it like the plague (or COVID-19) in your own apps.

After I have convinced you of the evilness of this approach, I will show you how to do it the right way — it only requires a small modification to the code, but may require a big change in how you think about these problems.

Asynchronous networking — the right kind, with an "a" — makes your apps much more responsive, but also brings with it additional complexity that you need to deal with.

Send an HTTP(S) request

In order to query the iTunes Store web service, the very first thing you must do is send an HTTP request to the iTunes server. This involves several steps such as creating a URL with the correct search parameters, sending the request to the server, getting a response back etc.

You'll take these step-by-step.

Create the URL for the request

➤ Add a new method to **SearchViewController.swift**:

```
// MARK: - Helper Methods
func iTunesURL(searchText: String) -> URL {
  let urlString = String(
    format: "https://itunes.apple.com/search?term=%@",
    searchText)
  let url = URL(string: urlString)
  return url!
}
```

This first builds a URL string by placing the search text behind the "term=" parameter, and then turns this string into a `URL` object.

Because `URL(string:)` is a failable initializer, it returns an optional. You force unwrap that using `url!` to return an actual `URL` object.

HTTP vs. HTTPS

Previously you used `http://` but here you're using `https://`. The difference is that HTTPS is the secure, encrypted version of HTTP. It protects your users from eavesdropping. The underlying protocol is the same, but any bytes that you're sending or receiving are encrypted before they go out on the network.

As of iOS 9, Apple recommends that apps should always use HTTPS. In fact, even if you specify an unprotected `http://` URL, iOS will still try to connect using HTTPS. If the server isn't configured to use HTTPS, then the network connection will fail.

You can ask to be exempted from this behavior in your Info.plist file, but that is generally not recommended.

➤ Change `searchBarSearchButtonClicked(_:)` to:

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  if !searchBar.text!.isEmpty {
    searchBar.resignFirstResponder()

    hasSearched = true
    searchResults = []

    let url = iTunesURL(searchText: searchBar.text!)
    print("URL: '\(url)'")

    tableView.reloadData()
  }
}
```

You've removed the code that created fake `SearchResult` items, and instead, call the new `iTunesURL(searchText:)` method. For testing purposes, you log the `URL` object that this method returns.

This logic sits inside an `if` statement so that none of this happens unless the user actually typed text into the search bar — it doesn't make much sense to search the iTunes store for "nothing".

> **Note:** Don't get confused by all the exclamation points in the line,
>
> `if !searchBar.text!.isEmpty`
>
> The first one is the "logical not" operator because you want to go inside the `if` statement only if the text is not empty. The second exclamation point is for force unwrapping the value of `searchBar.text`, which is an optional — it will never actually be `nil`, so it being an optional is a bit silly, but whaddya gonna do?

➤ Run the app and type in some search text that is a single word, for example "metallica", or one of your other favorite metal bands, and press the Search button.


Xcode should now show this in its Debug pane:

```
URL: 'https://itunes.apple.com/search?term=metallica'
```

That looks good.

➤ Now type in a search term with one or more spaces, like "pokemon go", into the search box.

Whoops, the app crashes!



The crash after searching for 'pokemon.go'

Look at the left-hand pane, the **Variables view**, of the Xcode debugger and you'll see that the `url` constant has no value.

The app apparently did not create a valid `URL` object. But why?

A space is not a valid character in a URL. Many other characters aren't valid either — such as the < or > signs — and therefore must be **escaped**. Another term for this is **URL encoding**.

A space, for example, can be encoded as the + sign — you did that earlier when you typed the URL into the web browser — or as the character sequence `%20`.

➤ Fortunately, `String` can do this encoding already. So, you only have to add one extra statement to the app to make this work:

```
func iTunesURL(searchText: String) -> URL {
  let encodedText = searchText.addingPercentEncoding(
      withAllowedCharacters: CharacterSet.urlQueryAllowed)!  //
Add this
  let urlString = String(
    format: "https://itunes.apple.com/search?term=%@",
    encodedText)                                             //
Change this
  let url = URL(string: urlString)
  return url!
}
```

This calls the `addingPercentEncoding(withAllowedCharacters:)` method to create a new string where all the special characters are escaped, and you use that string for the search term.

UTF-8 string encoding

This new string treats the special characters as being "UTF-8 encoded". It's important to know what that means because you'll run into this UTF-8 thing every once in a while when dealing with text.

There are many different ways to encode text. You've probably heard of ASCII and Unicode, the two most common encodings.

UTF-8 is a version of Unicode that is very efficient for storing regular text, but less so for special symbols or non-Western alphabets. Still, it's the most popular way to deal with Unicode text today.

Normally, you don't have to worry about how your strings are encoded. But when sending requests to a web service you need to transmit the text with the proper encoding.

Tip: When in doubt, use UTF-8, it will almost always work.

➤ Run the app and search for "pokemon go" again. This time a valid `URL` object can be created, and it looks like this:

```
URL: 'https://itunes.apple.com/search?term=pokemon%20go'
```

The space has been turned into the character sequence `%20`. The `%` indicates an escaped character and 20 is the UTF-8 value for a space. Also try searching for terms with other special characters, such as # and ∗ or even Emoji, and see what happens.

Perform the search request

Now that you have a valid `URL` object, you can do some actual networking!

➤ Add a new method to **SearchViewController.swift**:

```
func performStoreRequest(with url: URL) -> String? {
  do {
    return try String(contentsOf: url, encoding: .utf8)
  } catch {
    print("Download Error: \(error.localizedDescription)")
    return nil
  }
}
```

The meat of this method is the call to `String(contentsOf:encoding:)` which returns a new string object with the data it receives from the server pointed to by the URL.

Note that you're telling the app to interpret the data as UTF-8 text. Should the server send back the text in a different encoding, then it will look like a garbled mess to your app. It's important that the sending and receiving sides agree on the encoding they are using!

Because things can go wrong — for example, the network may be down and the server cannot be reached — you enclose this in a `do-try-catch` block. If there is a problem, the code jumps to the `catch` branch and the `error` variable will contain more details about the error. If this happens, you print out a user-understandable form of the error and return `nil` to signal that the request failed.

➤ Add the following lines to `searchBarSearchButtonClicked(_:)`, after the `print()` line:

```
if let jsonString = performStoreRequest(with: url) {
  print("Received JSON string '\(jsonString)'")
}
```

This invokes `performStoreRequest(with:)` with the `URL` object as a parameter and returns the JSON data that is received from the server. If everything goes according to plan, this method returns a new string containing the JSON data that you're after. Let's try it out!

➤ Run the app and search for your favorite band. After a second or so, a whole bunch of data will be dumped to the Xcode Console:

```
URL: 'http://itunes.apple.com/search?term=metallica'

Received JSON string '


{
 "resultCount":50,
 "results": [
{"wrapperType":"track", "kind":"song", "artistId":3996865,
"collectionId":579372950, "trackId":579373079,
"artistName":"Metallica", "collectionName":"Metallica",
"trackName":"Enter Sandman",
"collectionCensoredName":"Metallica", "trackCensoredName":"Enter
Sandman",
. . . and so on . . .
```

Congratulations, your app has successfully talked to a web service!

This prints the same stuff that you saw in the web browser earlier. Right now it's all contained in a single `String` object, which isn't really useful for our purposes, but you'll convert it to a more useful format in a minute.

Of course, it's possible that you received an error. In that case, the output should be something like this:

```
URL: 'https://itunes.apple.com/search?term=Metallica'
2020-08-20 11:44:52.963727-0400 StoreSearch[5676:12463647]
Connection 2: received failure notification
2020-08-20 11:44:52.963818-0400 StoreSearch[5676:12463647]
Connection 2: failed to connect 1:50, reason -1
2020-08-20 11:44:52.963896-0400 StoreSearch[5676:12463647]
Connection 2: encountered error(1:50)
2020-08-20 11:44:52.965094-0400 StoreSearch[5676:12462585] Task
<1E233D0F-44B8-4F3D-BE8C-CFCB8AA07615>.<0> HTTP load failed, 0/0
bytes (error code: -1009 [1:50])
2020-08-20 11:44:52.965515-0400 StoreSearch[5676:12463648]
NSURLConnection finished with error - code -1009
Download Error: The file “search” couldn’t be opened.
```

You'll add better error handling to the app later, but if you get such an error at this point, then make sure your computer — or your iPhone in case you're running the app on a device and not in the Simulator — is connected to the Internet. Also try the URL directly in your web browser and see if that works.

Parse JSON

Now that you have managed to download a chunk of JSON data from the server, what do you do with it?

JSON is a *structured* data format. It typically consists of arrays and dictionaries that contain other arrays and dictionaries, as well as regular data such as strings and numbers.

An overview of the JSON data

The JSON from the iTunes store roughly looks like this:

```
{
  "resultCount": 50,
  "results": [ . . . a bunch of other stuff . . . ]
}
```


The { } brackets surround a dictionary. This particular dictionary has two keys: `resultCount` and `results`. The first one, `resultCount`, has a numeric value. This is the number of items that matched your search query. By default the limit is a maximum of 50 items, but as you will see later, you can increase this upper limit.

The results key contains an array, which is indicated by the [ ] brackets. Inside that array are more dictionaries, each of which describes a single product from the store. You can tell these things are dictionaries because they have the { } brackets again.

Here are two of these items from the array:

```
{
  "wrapperType": "track",
  "kind": "song",
  "artistId": 3996865,
  "artistName": "Metallica",
  "trackName": "Enter Sandman",
  . . . and so on . . .
},
{
  "wrapperType": "track",
  "kind": "song",
  "artistId": 3996865,
  "artistName": "Metallica",
  "trackName": "Nothing Else Matters",
  . . . and so on . . .
},
```

Each product is represented by a dictionary made up of several keys. The values of the `kind` and `wrapperType` keys determine what sort of product this is: a song, a music video, an audiobook, and so on. The other keys describe the artist and the song itself.



The structure of the JSON data

To summarize, the JSON data represents a dictionary and inside that dictionary is an array of more dictionaries. Each of the dictionaries from the array represents one search result. Currently, all of this sits in a `String`, which isn't very handy, but using a **JSON parser** you can turn this data into Swift `Dictionary` and `Array` objects.

★ ★ ★

JSON or XML?

JSON is not the only structured data format out there. XML, which stands for E**X**tensible **M**arkup **L**anguage, is a slightly more formal standard. Both formats serve the same purpose, but they look a bit different. If the iTunes store returned its results as XML, the output would look more like this:

```
<?xml version="1.0" encoding="utf-8"?>
<iTunesSearch>
  <resultCount>5</resultCount>
  <results>
    <song>
      <artistName>Metallica</artistName>
      <trackName>Enter Sandman</trackName>
    </song>
    <song>
      <artistName>Metallica</artistName>
      <trackName>Nothing Else Matters</trackName>
    </song>
    . . . and so on . . .
  </results>
</iTunesSearch>
```

These days, most developers prefer JSON because it's simpler than XML and easier to parse. But it's certainly possible that if you want your app to talk to a particular web service, you might be expected to deal with XML data.

★ ★ ★

Prepare to parse JSON data

In the past, if you wanted to parse JSON, it used to be necessary to include a third-party framework into your apps, or to manually walk through the data structure using the built-in iOS JSON parser. But as of Swift 4, there's a new way to do things — your old pal `Codable`.

Remember how you used a `PropertyListDecoder` to decode plist data that supported the `Codable` protocol for reading — and saving — data in *Checklists*? Well, property lists aren't the only format supported by `Codable` out of the box — JSON is supported too!

All you need to do in order to allow your app to read JSON data directly into the relevant data structures is to set them up to conform to `Codable`!

"Now hold on there", I hear you saying. "How does `Codable` know how an arbitrary data structure from the Internet is set up in order to correctly extract the right bits of data?" Ah, it's all in how you set your data structures up. You'll understand as you proceed to parse the data you received from the iTunes server.

The trick to using `Codable` to parse JSON data is to set up your classes — or structs — to reflect the structure of the data that you'll parse. As you noticed above, there are two parts to the JSON response received from the iTunes server:

1. The response wrapper which contains the number of results and an array of results.

2. The array itself which is made up of individual search result items.

We need to model both of the above in order to parse the JSON data correctly. We've already made some headway in terms of modeling the search results by way of the `SearchResult` object, but we need to do some modifications in order to get the object ready for JSON parsing.

But first, let's add a new data model for the results wrapper.

➤ Open **SearchResult.swift** and replace its contents with the following:

```
class ResultArray: Codable {
    var resultCount = 0
    var results = [SearchResult]()
}

class SearchResult: Codable {
  var artistName: String? = ""
  var trackName: String? = ""

  var name: String {
    return trackName ?? ""
  }
}
```

There are a few changes here:

1. The `ResultArray` class models the response wrapper by containing a results count and an array of `SearchResult` objects. Note that this class supports the `Codable` protocol.

   If you are wondering why this class is within the same file as `SearchResult`, it is simply for the sake of expediency. This class is not used anywhere else except as a temporary holder during the JSON parsing process. So I put it in the same file as `SearchResult`, which is the actual class you'll be using. But if you prefer, you can put this class in a separate Swift file by itself — it doesn't make any difference to the app functionality.

2. The `SearchResult` class now supports the `Codable` protocol too.

3. It also has a new optional property named `trackName` and the `artistName` property has been changed to an optional one — the optional properties are to make `Codable`'s work easier since `Codable` expects non-optional values to be always present in the JSON data. Unfortunately, the response from the iTunes server might not always have these properties, and you have to allow for that.

4. The existing property for `name` has been converted to a computed property which returns the value of the `trackName` property, or an empty string if `trackName` is `nil`.

The reason for changes #3 and #4 might not be obvious immediately. Take a look at the response data you received from the server. Did you notice the "kind" key?

The search results from iTunes can be for multiple types of items — songs, videos, movies, tv shows, books etc. That key indicates the type of item the search result is for. And depending on the item type, you might want to vary how you display an item name. For example, you might not always want to use the "trackName" key as the item name — in fact, as we mention above, "trackName" might not even be there in the returned data. The computed `name` property is simply preparation for the future in case you want to display different names depending on the result type.

Also, notice that now all the property names in the class match actual keys in the JSON data — you can parse JSON even without the property names matching the key names, but that's a bit more complicated. So let's take the easy route here. Remember, baby steps …

And that's all you need in order to prepare for JSON parsing. Onwards!

Parse the JSON data

You will be using the `JSONDecoder` class, appropriately enough, to parse JSON data. Only trouble is, `JSONDecoder` needs its input to be a `Data` object. You currently have the JSON response from the server as a `String`.

You can convert the `String` to `Data` pretty easily, but it would be better to get the response from the server as `Data` in the first place — you got the response from the server as `String` initially only to ensure that the response was correct.

➤ Switch to **SearchViewController.swift** and modify `performStoreRequest(with:)` as follows:

```
func performStoreRequest(with url: URL) -> Data? {  // Change to
Data?
  do {
    return try Data(contentsOf:url)                 // Change
this line
  } catch {
    . . .
  }
}
```

You simply change the request method to fetch the response from the server as `Data` instead of a `String` — the method now returns the value as an optional `Data` value instead of an optional `String` value.

➤ Add the following method to **SearchViewController.swift**:

```
func parse(data: Data) -> [SearchResult] {
  do {
    let decoder = JSONDecoder()
    let result = try decoder.decode(
      ResultArray.self, from: data)
    return result.results
  } catch {
    print("JSON Error: \(error)")
    return []
  }
}
```

You use a `JSONDecoder` object to convert the response data from the server to a temporary `ResultArray` object from which you extract the `results` property. Or at least, you *hope* you can convert the data without any issues…

Assumptions cause trouble

When you write apps that talk to other computers on the Internet, one thing to keep in mind is that your conversational partners may not always say the things you expect them to say.

There could be an error on the server and instead of valid JSON data, it may send back some error message. In that case, `JSONDecoder` will not be able to parse the data and the app will return an empty array from `parse(data:)`.

Another thing that could happen is that the owner of the server changes the format of the data they send back. Usually, this is done in a new version of the web service that is accessible via a different URL. Or, they might require you to send along a "version" parameter. But not everyone is careful like that, and by changing what the server does, they may break apps that depend on the data coming back in a specific format.

In the case of the iTunes store web service, the top-level object *should* be a dictionary with two keys — one for the count, the other for the array of results — but you can't control what happens on the server. If for some reason the server programmers decide to put `[ ]` brackets around the JSON data, then the top-level object will no longer be a `Dictionary` but an `Array`. This in turn will cause `JSONDecoder` to fail parsing the data since it is no longer in the expected format.

Being paranoid about these kinds of things and showing an error message in the unlikely event this happens is a lot better than your application suddenly crashing when something changes on a server that is outside of your control.

Just to be sure, you're using the `do-try-catch` block to check that the JSON parsing goes through fine. Should the conversion fail, then the app doesn't burst into flames but simply returns an empty results array.

It's good to add checks like these to the app to make sure you get back what you expect. If you don't own the servers you're talking to, it's best to program defensively.

➤ Modify `searchBarSearchButtonClicked(_:)` as follows:

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  if !searchBar.text!.isEmpty {
    . . .
    print("URL: '\(url)'")
    if let data = performStoreRequest(with: url) {  // Modified
      let results = parse(data: data)               // New line
      print("Got results: \(results)")              // New line
```

```
      }
      tableView.reloadData()
    }
  }
```

You simply change the constant for the result from the call to `performStoreRequest(with:)` from `jsonString` to `data`, call the new `parse(data:)` method, and print the return value.

➤ Run the app and search for something. The Xcode Console now prints the following:

```
URL: 'https://itunes.apple.com/search?term=Metallica'
Got results: [StoreSearch.SearchResult,
StoreSearch.SearchResult, StoreSearch.SearchResult,
StoreSearch.SearchResult, StoreSearch.SearchResult,
StoreSearch.SearchResult, StoreSearch.SearchResult,
StoreSearch.SearchResult, StoreSearch.SearchResult,
StoreSearch.SearchResult, StoreSearch.SearchResult,
StoreSearch.SearchResult,
. . . ]
```

Hmm ... that certainly *looks* like an array of 50 items, but it doesn't really tell you anything much about the actual data — just that the array consists of `SearchResult` objects. That's not much good to you, is it?

Print object contents

➤ Modify the `SearchResult` class in **SearchResult.swift** to conform to the `CustomStringConvertible` protocol:

```
class SearchResult: Codable, CustomStringConvertible {
```

The `CustomStringConvertible` protocol allows an object to have a custom string representation. Or, to put it another way, the protocol allows objects to have a custom string describing the object, or its contents. So, how does the protocol provide this string description? That is done via the protocol's `description` property.

➤ Add the following code to the `SearchResult` class:

```
var description: String {
  return "\nResult - Name: \(name), Artist Name: \(artistName ??
"None")"
}
```

The above is your implementation of the `description` property to conform to the `CustomStringConvertible`. For your `SearchResult` class, the description consists of a line break (`\n`) at the beginning, a string identifying the type of object, and the values of the `name` and `artistName` properties. But since `artistName` is an optional value, you have to account for when it might be `nil` and output "None" when that happens.

Notice the `??` operator in the above code — it's called the *nil-coalescing operator* and you probably remember it from previous chapters. The nil-coalescing operator unwraps the variable to the left of the operator if it has a value, if not, it returns the value to the right of the operator as the default value.

➤ Run the app again and search for something. The Xcode Console should now print something like the following:

```
URL: 'https://itunes.apple.com/search?term=Metallica'
Got results: [
Result - Name: Enter Sandman, Artist Name: Metallica,
Result - Name: Nothing Else Matters, Artist Name: Metallica,
Result - Name: The Unforgiven, Artist Name: Metallica,
. . .
```

Yep, that looks more like it!

Do you now see why you put a line break at the beginning of the object description? That way, when you have multiple items in an array, each item gets displayed in a separate line instead of everything being jumbled together. Try removing the line break and see how the output looks.

You have converted a bunch of JSON that didn't make a lot of sense into actual objects that you can use.

Error handling

Let's add an alert to handle potential errors. It's inevitable that something goes wrong somewhere and it's best to be prepared.

➤ Add the following method to **SearchViewController.swift**:

```
func showNetworkError() {
  let alert = UIAlertController(
    title: "Whoops...",
    message: "There was an error accessing the iTunes Store." +
    " Please try again.",
    preferredStyle: .alert)
```

```
    let action = UIAlertAction(
      title: "OK", style: .default, handler: nil)
    alert.addAction(action)
    present(alert, animated: true, completion: nil)
  }
```

Nothing you haven't seen before; it simply presents an alert controller with an error message.

> **Note:** The `message` variable is split into two separate strings and concatenated, or added together, using the plus (+) operator just so that the string would display nicely for this book. You can feel free to type out the whole string as a single string instead.

➤ Add the following line to `performStoreRequest(with:)` just before the `return nil`:

```
showNetworkError()
```


Simply put, if something goes wrong with the request to the iTunes store, you call `showNetworkError()` to show an alert box.

If you did everything correctly up to this point, then the web service should always have worked. Still it's a good idea to test a few error situations, just to make sure the error handling is working for those unlucky users with bad network connections.

➤ Try this: In `iTunesURL(searchText:)` method, temporarily change the "itunes.apple.com" part of the URL to "NOMOREitunes.apple.com".

You should now get an error alert when you try a search because no such server exists at that address. This simulates the iTunes server being down. Don't forget to change the URL back when you're done testing.

Tip: To simulate no network connection you can pull the network cable and/or disable Wi-Fi on your Mac, or run the app on your device in Airplane Mode.



The app shows an alert when there is a network error

It should be obvious that when you're doing networking, things can — and will! — go wrong, often in unexpected ways. So, it's always good to be prepared for surprises.

Work with the JSON results

So far you've managed to send a request to the iTunes web service and you parsed the JSON data into an array of `SearchResult` objects. However, we are not quite done.

The iTunes Store sells different kinds of products — songs, e-books, software, movies, and so on — and each of these has its own structure in the JSON data. A software product will have screenshots but a movie will have a video preview. The app will have to handle these different kinds of data.

You're not going to support everything the iTunes store has to offer, only these items:

- Songs, music videos, movies, TV shows, podcasts
- Audio books
- Software (apps)
- E-books

The reason I have split them up like this is because that's how the iTunes store does it. Songs and music videos, for example, share the same set of fields, but audiobooks and software have different data structures. The JSON data makes this distinction using the `kind` field.

Let's modify our data model to load the value for the above key.

➤ Add the following property to `SearchResult` (**SearchResult.swift**):

```
var kind: String? = ""
```

You might think that the "kind" property would always be there in the iTunes data and so it need not be an optional. I thought so too, but unfortunately, iTunes proved me wrong :] So we go with an optional value there...

➤ Also modify the `return` line for `description` to:

```
return "\nResult - Kind: \(kind ?? "None"), Name: \(name),
Artist Name: \(artistName ?? "None")"
```

That makes sense given that `kind` is optional, right?

➤ Run the app and do a search. Look at the Xcode output.

When I did this, Xcode showed three different types of products, with the majority of the results being songs. What you see may vary, depending on what you search for.

```
URL: 'https://itunes.apple.com/search?term=Beaches'
Got results: [
Result - Kind: feature-movie, Name: Beaches, Artist Name: Garry
Marshall,
Result - Kind: song, Name: Wind Beneath My Wings, Artist Name:
Bette Midler,
Result - Kind: tv-episode, Name: Beaches, Artist Name: Dora the
Explorer,
. . .
```

Now, let's add some new properties to the `SearchResult` object.

Always check the documentation

But first, if you were wondering how I knew how to interpret the data from the iTunes web service, or even how to set up the URLs to use the service in the first place, then you should realize there is no way you can be expected to use a web service if there is no documentation.

Fortunately, for the iTunes store web service, there is some good documentation here:

affiliate.itunes.apple.com/resources/documentation/itunes-store-web-service-search-api

Just reading the docs is often not enough though. You have to play with the web service a bit to know what you can and cannot do.

There are some things that the *StoreSearch* app needs to do with the search results that were not clear from reading the documentation. So, first read the docs and then play with it. That goes for any API, really, whether it's something from the iOS SDK or a web service.

Load more properties

The current `SearchResult` class only has a few properties. As you've seen, the iTunes store returns a lot more information than that, so you'll need to add a few new properties.

➤ Add the following properties to **SearchResult.swift**:

```
var trackPrice: Double? = 0.0
var currency = ""
var artworkUrl60 = ""
var artworkUrl100 = ""
var trackViewUrl: String? = ""
var primaryGenreName = ""
```

You're not including *everything* that the iTunes store returns, only the fields that are relevant to this app. Also, note that you've named the properties to match the keys in the JSON data exactly and that only some have been marked as optional.

Note: The optionality of the properties was based on my own results. It is possible that with the above code, you still find that the app barfs all over the place with an error like this:

```
URL: 'https://itunes.apple.com/search?term=Macky'
JSON Error: keyNotFound(CodingKeys(stringValue: "trackViewUrl",
intValue: nil), Swift.DecodingError.Context(codingPath:
[CodingKeys(stringValue: "results", intValue: nil),
_JSONKey(stringValue: "Index 1", intValue: 1)],
debugDescription: "No value associated with key
CodingKeys(stringValue: \"trackViewUrl\", intValue: nil)
(\"trackViewUrl\").", underlyingError: nil))
```

If this happens to you, look at the error message to figure out the property in `SearchResult` which is missing and then mark it as optional — problem solved!

`SearchResult` stores the item's price and the currency — US dollar, Euro, British Pounds, etc. It also stores two artwork URLs, one for a 60×60 pixel image and the other for a 100×100 pixel image, a link to the product's page on the iTunes store, and the genre of the item.

Provided the class supports `Codable`, with just the simple addition of new properties — as long at they are named the same as the JSON keys and have the right optionality — you are now able to load these new values into your class.

But what if you don't want to use the not-quite-user-friendly names from the JSON data such as artworkUrl60 or artworkUrl100 but instead want to use more descriptive names such as artworkSmall and artworkLarge?

Never fear, `Codable` has support for that too :]

But before we get to that, you should run your app once to make sure that the above code changes didn't break anything. So, run your app, make a search, and verify that you still get output in the Xcode Console indicating that the search was successful.

All working fine? Great! Let's move on to naming the `SearchResults` properties to be as you want them and not as the JSON data sets them ...

Support better property names

➤ Replace the following lines of code in **SearchResult.swift**:

```
var artworkUrl60 = ""
var artworkUrl100 = ""
var trackViewUrl: String? = ""
var primaryGenreName = ""
```

With this:

```
var imageSmall = ""
var imageLarge = ""
var storeURL: String? = ""
var genre = ""

enum CodingKeys: String, CodingKey {
  case imageSmall = "artworkUrl60"
  case imageLarge = "artworkUrl100"
  case storeURL = "trackViewUrl"
  case genre = "primaryGenreName"
  case kind, artistName, trackName
  case trackPrice, currency
}
```

As you'll notice, you've changed the property names to be more descriptive, but what does the `enum` do?

As you've seen previously, an `enum` (or enumeration), is a way to have a list of values and names for those values. Here, you use the `CodingKeys` enumeration to let the `Codable` protocol know how you want the `SearchResult` properties matched to the JSON data.

Do note that if you do use the `CodingKeys` enumeration, it has to provide a `case` for all your properties in the class — the ones which map to a JSON key with the same name are the last two cases in the `enum`, you'll notice that they don't have a value specified.

That's all there is to it :] Run your app again (and maybe change the `description` property to return one of the new values to test they display correctly) and verify that the code still works with the new properties.

Use the results

With these latest changes, `searchBarSearchButtonClicked(_:)` retrieves an array of `SearchResult` objects populated with useful information, but you're not doing anything with that array yet.

➤ Switch to **SearchViewController.swift** and in `searchBarSearchButtonClicked(_:)`, replace the following lines:


```
let results = parse(data: data)
print("Got results: \(results)"))
```

With:

```
searchResults = parse(data: data)
```

Instead of placing the results in a local variable and printing them out, you now place the returned array into the `searchResults` instance variable so that the table view can show the actual search result objects.

➤ Run the app and search for your favorite musician. After a second or so, you should see a whole bunch of results appear in the table. Cool!



The results from the search now show up in the table

Differing data structures

Remember how I said that some items, such as audiobooks have different data structures? Let's talk about that a bit more in detail...

The biggest differences currently between the other item types and audiobooks is that audiobooks do not have certain JSON keys that are present for other items. Here's a breakdown:

1. **kind:** This value is not present at all.
2. **trackName:** Instead of "trackName", you get "collectionName".
3. **trackviewUrl:** Instead of this value, you have "collectionViewUrl" — which provides the iTunes link to the item.
4. **trackPrice:** Instead of "trackPrice", you get "collectionPrice".

Interestingly enough, you'll notice that in `SearchResult` these are all properties that we had marked as optional. You grok now why we had to mark them optional, right? If your search results included an audiobook item, those properties would not have been there and so `Codable` would have had a fit :]

Additionally, there are a few other JSON differences for a couple of item types:

1. Software and e-book items do not have "trackPrice" key, instead they have a "price" key.
2. E-books don't have a "primaryGenreName" key — they have an array of genres.

So how can you fix things so that the `JSONDecoder` can correctly decode the JSON data from the iTunes Store server no matter the type of item? How do you handle the situations where the same property — for example, "trackPrice" — can be present as a different property — like "collectionPrice" or "price" — depending on the type of item?

Remember how you added a computed variable called `name` which returns the `trackName`? This is where that comes into play ... If you add another variable to store `collectionName` — the name of the item when it is an audiobook — then you can return the correct value from `name` depending on the case. You can do something similar for the store URL and price as well.

Let's make the necessary changes.

➤ Remove the `storeURL` property from `SearchResult` — you'll add two separate optional properties for the audiobook and non-audiobook types. Also remove the `storeURL` case from `CodingKeys`.

➤ Remove the `genre` property from `SearchResult` — you'll add two separate optional properties for the e-book and non-e-book types. Also remove the `genre` case from `CodingKeys`.

➤ Add new optional properties for the variant keys present in the special items mentioned above:

```
var trackViewUrl: String?
var collectionName: String?
var collectionViewUrl: String?
var collectionPrice: Double?
var itemPrice: Double?
var itemGenre: String?
var bookGenre: [String]?
```

➤ Replace the `name` computed property with the following:

```
var name: String {
  return trackName ?? collectionName ?? ""
}
```

The change is simple enough, except for the *chaining* of the nil-coalescing operator. You check to see if `trackName` is `nil` — if not, you return the unwrapped value of `trackName`. If `trackName` is `nil`, you move on to `collectionName` and do the same check. If both values are `nil`, you return an empty string.

➤ Add the following three new computed properties:

```
var storeURL: String {
  return trackViewUrl ?? collectionViewUrl ?? ""
}

var price: Double {
  return trackPrice ?? collectionPrice ?? itemPrice ?? 0.0
}

var genre: String {
  if let genre = itemGenre {
    return genre
  } else if let genres = bookGenre {
    return genres.joined(separator: ", ")
  }
  return ""
}
```

The first two computed properties work similar to how the `name` computed property works. So nothing new there. The `genre` property simply returns the genre for items which are not e-books. For e-books, the method combines all the genre values in the array separated by commas and then returns the combined string.

All that remains is to add all the new properties to the `CodingKeys` enumeration — if you don't, some of the values might not be populated correctly during JSON decoding. Once you're done, `CodingKeys` should look like this:

```
enum CodingKeys: String, CodingKey {
  case imageSmall = "artworkUrl60"
  case imageLarge = "artworkUrl100"
  case itemGenre = "primaryGenreName"
  case bookGenre = "genres"
  case itemPrice = "price"
  case kind, artistName, currency
  case trackName, trackPrice, trackViewUrl
  case collectionName, collectionViewUrl, collectionPrice
}
```

➤ Run the app again, and search for something like "Stephen King" to be sure to get some results which include audiobooks for the master of horror! In case you wonder why that specific search term, we are looking for audiobooks specifically because that is one of the item types with variations in the data structures...

Show the product type

The search results may include podcasts, songs, or other related products. It would be useful to make the table view display what type of product it is showing.

➤ Still in **SearchResult.swift**, add the following computed properties:

```
var type: String {
  return kind ?? "audiobook"
}

var artist: String {
    return artistName ?? ""
}
```


Remember that `kind` could be `nil` if the item type is an audiobook and that we've marked `artistName` as an optional. You hedge against that with these new computed properties.

➤ Open **SearchViewController.swift** and in `tableView(_:cellForRowAt:)`, change the line that sets `cell.artistNameLabel` to the following:

```
if searchResult.artist.isEmpty {
  cell.artistNameLabel.text = "Unknown"
} else {
  cell.artistNameLabel.text = String(
    format: "%@ (%@)",
    searchResult.artist,
    searchResult.type)
}
```

The first change is that you now check that the `SearchResult`'s `artist` is not empty. When testing the app I noticed that sometimes a search result did not include an artist name. In that case you make the cell say "Unknown".

You also add the value of the new `type` property to the artist name label, which should tell the user what kind of product they're looking at:



They're not books...

There is one problem with this. The value of `kind` comes straight from the server and it is more of an internal name than something you'd want to show directly to the user.

What if you want it to say "Movie" instead, or maybe you want to translate the app to another language — something you'll do later for *StoreSearch*. It's better to convert this internal identifier, "feature-movie", into the text that you want to show to the user, "Movie".

➤ Replace the `type` computed property in **SearchResult.swift** with this one:

```
var type: String {
  let kind = self.kind ?? "audiobook"
  switch kind {
  case "album": return "Album"
  case "audiobook": return "Audio Book"
  case "book": return "Book"
  case "ebook": return "E-Book"
  case "feature-movie": return "Movie"
  case "music-video": return "Music Video"
  case "podcast": return "Podcast"
  case "software": return "App"
  case "song": return "Song"
  case "tv-episode": return "TV Episode"
  default: break
  }
  return "Unknown"
}
```

These are the types of products that this app understands.

It's possible that I missed one or that the iTunes Store adds a new product type at some point. If that happens, the `switch` jumps to the `default:` case and you'll simply return a string saying "Unknown" — and hopefully help identify and fix the unknown type in an update of the app.

Default and break


Switch statements often have a `default:` case at the end that just says `break`.

In Swift, a `switch` must be exhaustive, meaning that it must have a `case` for all possible values of the thing that you're looking at.

Here you're looking at `kind`. Swift needs to know what to do when `kind` is not any of the known values. That's why you're required to include the `default:` case, as a catchall for any other possible values of `kind`.

> By the way: unlike in other languages, the `case` statements in Swift do not need to say `break` at the end. They do not automatically "fall through" from one case to the other as they do in Objective-C.

Now the item type should display not as a value from the web service, but instead, as the value you set for each item type:



The product type is a bit more human-friendly

➤ Run the app and search for software, audio books or e-books to see that the parsing code works. It can take a few tries before you find some because of the enormous quantity of products on the store.

Later on, you'll add a control that lets you pick the type of products that you want to search for, which makes it a bit easier to find just e-books or audiobooks.

Sort the search results

It'd be nice to sort the search results alphabetically. That's actually quite easy. A Swift `Array` already has a method to sort itself. All you have to do is tell it what to sort on.

➤ In **SearchViewController.swift**, in `searchBarSearchButtonClicked(_:)`, right after the call to `parse(data:)` add the following:


```
searchResults.sort { result1, result2 in
  return result1.name.localizedStandardCompare(result2.name)
== .orderedAscending
}
```

After the results array is fetched, you call `sort` on the `searchResults` array with a trailing closure that determines the sorting rules. This is identical to what you did in *Checklists* to sort the to-do lists.

In order to sort the contents of the `searchResults` array, the closure will compare the `SearchResult` objects with each other and return `true` if `result1` comes before `result2`. The closure is called repeatedly on different pairs of `SearchResult` objects until the array is completely sorted.

The comparison of the two objects uses `localizedStandardCompare()` to compare the names of the `SearchResult` objects. Because you used `.orderedAscending`, the closure returns `true` only if `result1.name` comes before `result2.name` — in other words, the array gets sorted from A to Z.

➤ Run the app and verify that the search results are sorted alphabetically.



The search results are sorted by name

Sorting was pretty easy to add, but there is an even easier way to write this.

Improve the sorting code

➤ Change the sorting code you just added to:

```
searchResults.sort { $0.name.localizedStandardCompare($1.name)
== .orderedAscending }
```

Now, inside the closure you no longer refer to the two `SearchResult` objects by name but as the special `$0` and `$1` variables. Using this shorthand instead of full parameter names is common in Swift closures. There is also no longer a `return` statement.

➤ Verify that this works.

Believe it or not, you can do even better. Swift has a very cool feature called **operator overloading**. It allows you to take the standard operators such as + or ∗ and apply them to your own objects. You can even create completely new operator symbols.

It's not a good idea to go overboard with this feature and make operators do something completely unexpected — don't overload / to do multiplications, eh? — but it comes in very handy for sorting.

➤ Open **SearchResult.swift** and add the following code, outside of the class:

```
func < (lhs: SearchResult, rhs: SearchResult) -> Bool {
  return lhs.name.localizedStandardCompare(rhs.name)
== .orderedAscending
}
```

This should look familiar! You're creating a function named < that contains the same code as the closure from earlier. This time, the two `SearchResult` objects are called `lhs` and `rhs`, for left-hand side and right-hand side, respectively.

You have now overloaded the less-than operator so that it takes two `SearchResult` objects and returns `true` if the first one should come before the second, and `false` otherwise. Like so:

```
searchResultA.name = "Waltz for Debby"
searchResultB.name = "Autumn Leaves"

searchResultA < searchResultB  // false
searchResultB < searchResultA  // true
```

➤ Back in **SearchViewController.swift**, change the sorting code to:

```
searchResults.sort { $0 < $1 }
```

That's pretty sweet. Using the < operator makes it very clear that you're sorting the items from the array in ascending order.

But wait, you can write it even shorter:

```
searchResults.sort(by: <)
```

Wow, it doesn't get much simpler than that! This line literally says, "Sort this array in ascending order". Of course, this only works because you added your own `func <` to overload the less-than operator so it takes two `SearchResult` objects and compares them.

➤ Run the app again and make sure everything is still sorted.

> **Exercise:** See if you can make the app sort by the artist name instead.

> **Exercise:** Try to sort in descending order, from Z to A. Tip: use the > operator.

Excellent! You made the app talk to a web service and you were able to convert the data that was received into your own data model object.

The app may not support every product that's shown on the iTunes store, but I hope it illustrates the principle of how you can take data that comes in slightly different forms and convert it to objects that are more convenient to use in your own apps.

Feel free to dig through the web service API documentation to add the remaining items that the iTunes store sells: https://affiliate.itunes.apple.com/resources/documentation/itunes-store-web-service-search-api/

➤ Commit your changes with a message such as "Add fetching data from web service using synchronous network request".

You can find the project files for this chapter under **34-Networking** in the Source Code folder.

Chapter 35: Asynchronous Networking

By Fahim Farook

You've got your app doing network searches and it's working well. The synchronous network calls aren't so bad, are they?

Yes they are, and I'll show you why! Did you notice that whenever you performed a search, the app became unresponsive? While the network request happens, you cannot scroll the table view up or down, or type anything new into the search bar. The app is completely frozen for a few seconds.

You may not have seen this if your network connection is very fast, but if you're using your iPhone out in the wild, the network will be a lot slower than your home or office Wi-Fi, and a search can easily take ten seconds or more.

To most users, an app that does not respond is an app that has crashed. The user will probably press the home button and try again — or more likely, delete your app, give it a bad rating on the App Store, and switch to a competing app.

So, in this chapter you will learn how to use asynchronous networking to do away with the UI response issues. You'll do the following:

- **Extreme synchronous networking:** Learn how synchronous networking can affect the performance of your app by dialing up the synchronous networking to the maximum.
- **The activity indicator:** Add an activity indicator to show when a search is going on so that the user knows something is happening.
- **Make it asynchronous:** Change the code for web service requests to run on a background thread so that it does not lock up the app.

Extreme synchronous networking

Still not convinced of the evils of synchronous networking? Let's slow down the network connection to pretend the app is running on an iPhone that someone may be using on a bus or in a train, not in the ideal conditions of a fast home or office network.

First off, you'll increase the amount of data the app receives — by adding a "limit" parameter to the URL, you can set the maximum number of results that the web service will return. The default value is 50, the maximum is 200.

➤ Open **SearchViewController.swift** and in `iTunesURL(searchText:)`, change the line with the web service URL to the following:

```
let urlString = String(format:
  "https://itunes.apple.com/search?term=%@&limit=200",
  encodedText)
```

You added `&limit=200` to the URL. Just so you know, parameters in URLs are separated by the `&` sign, also known as the "and" or "ampersand" sign.


➤ If you run the app now, the search should be quite a bit slower.

The network link conditioner

Still too fast for you to see any app response issues? Then use the **Network Link Conditioner**. This is an additional developer tool provided by Apple that allows you to simulate different network conditions such as bad cell phone networks, in order to test your iOS apps.


But first, before you can use it, you probably have to install the Network Link Conditioner since that is not something that is installed by default either as part of macOS or as part of your Xcode installation.

➤ Select **Open Developer Tool ▸ More Developer Tools...** from the Xcode menu.



The More Developer Tools menu option

This should open the More Downloads for Apple Developers (https://developer.apple.com/download/more/) web page in your default browser — you might be asked to login to the Apple Developer portal first since this is a resource which is only available to registered Apple developers.




The Downloads for Apple Developers page

➤ If you opened the site via the Xcode menu, then it should open as shown in the screenshot, pre-set to search for "for Xcode". You should get a list of different downloads including ones for "Additional Tools". Select the most recent download for Additional Tools based on Release Date, download it, open the DMG file, switch to the **Hardware** folder on the DMG, and then double-click **Network Link Conditioner.prefPane** to install it.

> **Note:** If you already have the Network Link Conditioner installed, you'll get an error about the Network Link Conditioner being installed with macOS and that it can't be replaced.
>
> If you do see this error, go to your System Preferences, right click on the existing Network Link Conditioner and select to remove the preference pane option. You should be able to install the new version after that without any issues.

The Network Link Conditioner is now available to you to use as a System Preferences panel option.

➤ If you want to find it later, open **System Preferences** on your Mac and locate **Network Link Conditioner** — it should be in the last section of items, at the very bottom.




The Network Link Conditioner preference pane

Let's simulate a really slow connection.

➤ Click on **Manage Profiles** and create a new profile by clicking the plus button on the bottom left. Add the following settings:

- Name: **Very Slow Connection**
- Downlink Bandwidth: **48** Kbps
- Downlink Packets Dropped: **0** %
- Downlink Delay: **5000** ms, i.e. 1 second



Adding the profile for a very slow connection

Press **OK** to add this profile and return to the main screen. Make sure this new profile is selected and flick the switch to ON to start the Network Link Conditioner.

➤ Now run the app and search for something. The Network Link Conditioner tool will delay the HTTP request by 5 seconds in order to simulate a slow connection, and then downloads the data very slowly.

> **Tip:** If the download still appears very fast, then try searching for some term you haven't used before; the system may be caching the results from a previous search.

> **Note:** While the Network Link Conditioner has worked reliably for previous iOS versions, my results with the latest iOS from the betas up to GM has been very spotty. It would sometimes work flawlessly, and sometimes it would not work at all. I don't know whether this is due to changes in the Network Link Conditioner or changes to the iOS simulator itself or both.

> But if you do experience these issues, know that this is just issues with the Network Link Conditioner itself. Just turning the Network Link Conditioner off should restore normal functionality.

Device conditions

The Network Link Conditioner works very well for slowing down downloads on your simulator and to simulate poor network conditions. But it doesn't work for actual devices. Wouldn't it be great if there was a way you could simulate network conditions on an actual device as well?

Actually, there is a way.

➤ Get your iPhone, iPad or iPod touch device and connect it to your Mac.

➤ Select **Window ▸ Devices and Simulators** from the Xcode menu.


➤ Select the **Devices** tab and select your phone from the available list of device.

➤ Scroll down to **Device Conditions** section at the bottom of the screen.

➤ Under **Condition** select **Network Link**.

➤ Select the network profile you want to use from the **Profile** dropdown.

➤ Click the **Start** button.



Setting network link conditions for device

You can also enable the Network Link Conditioner from your device itself. Go to **Settings ▸ Developer ▸ Network Link Conditioner**.

> **Note:** If you do not see the **Developer** option in the iOS Settings app, you might need to connect your iPhone to your computer via a USB cable, and launch the Xcode **Devices and Simulators** window so that your device is recognized by Xcode as a developer device.

Now you can create poor network conditions either on simulator or device!

Using these tools to test whether your app can deal with real-world network conditions is a must! Not every user has the luxury of broadband...


The activity indicator

Did you notice how the app totally doesn't respond during a search operation? It feels like something is wrong. Did the app crash or is it still doing something? It's impossible to tell and very confusing to your users when this happens.

Even worse, if your program is unresponsive for too long, iOS may actually force kill it, in which case it really does crash. You don't want that to happen!

"Ah," you say, "let's show some type of animation to let the user know that the app is communicating with a server. Then at least they will know that the app is busy."

You've used a spinning activity indicator before in *MyLocations* to show the user that the app was busy. Let's create a new table view cell that you'll show while the app is querying the iTunes store. It will look like this:



The app shows that it is busy

The activity indicator table view cell

➤ Create a new, empty nib file. Call it **LoadingCell.xib**.


➤ Drag a new **Table View Cell** on to the canvas. Set its width to **375** points and its height to **80** points.

➤ Set the reuse identifier of the cell to **LoadingCell** and set the **Selection** attribute to **None**.

➤ Drag a new **Label** into the cell. Set the title to **Loading...** and change the font to **System 15**. Set the label's text color to the **ArtistName** color asset.

➤ Drag a new **Activity Indicator View** into the cell and put it next to the label. Make sure its **Style** is set to **Medium** and give it a **Tag** of 100.

The design should look like this:



The design of the LoadingCell nib

To make this cell work properly on larger screens, you'll add constraints that keep the label and the activity spinner centered in the cell. The easiest way to do this is to place these two items inside a container view and center that.

➤ Select both the Label and the Activity Indicator View — hold down ⌘ to select multiple items. From the Xcode menu bar, choose **Editor ▸ Embed In ▸ Stack View**. This puts a white view behind the selected views.

This puts both views in a specialized container view known as stack view which can be used to display multiple views either horizontally as a row or vertically as a column. You'll learn more about stack views later on.

➤ With the stack view selected, click the **Align** button and put checkmarks in front of **Horizontally in Container** and **Vertically in Container** to make new constraints.

Cool, you now have a cell that automatically adjusts itself to any size screen.

Use the activity indicator cell

To make this special table view cell appear, you'll follow the same steps as for the "Nothing Found" cell.

➤ Add the following line to the `TableView.CellIdentifiers` structure in **SearchViewController.swift**:

```
  static let loadingCell = "LoadingCell"
```

➤ And register the nib in `viewDidLoad()`:

```
cellNib = UINib(
  nibName: TableView.CellIdentifiers.loadingCell,
  bundle: nil)
tableView.register(
  cellNib,
  forCellReuseIdentifier: TableView.CellIdentifiers.loadingCell)
```

You now have to come up with some way to let the table view's data source know that the app is currently in a state of downloading data from the server. The simplest way to do that is to add another boolean flag. If this variable is `true`, then the app is downloading stuff and the new Loading... cell should be shown; if the variable is `false`, you show the regular contents of the table view.

➤ Add a new instance variable:

```
var isLoading = false
```

➤ Change `tableView(_:numberOfRowsInSection:)` to:

```
func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  if isLoading {
    return 1
  } else if !hasSearched {
    . . .
  } else if . . .
```

The `if isLoading` condition returns 1, because you need a row in order to show a cell.

➤ Update `tableView(_:cellForRowAt:)` as follows:

```
func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  // New code
  if isLoading {
    let cell = tableView.dequeueReusableCell(
      withIdentifier: TableView.CellIdentifiers.loadingCell,
      for: indexPath)

    let spinner = cell.viewWithTag(100) as!
UIActivityIndicatorView
    spinner.startAnimating()
```

```
      return cell
    } else
    // End of new code
    if searchResults.count == 0 {
      . . .
```

You added an `if` condition to return an instance of the new Loading... cell. It also looks up the `UIActivityIndicatorView` by its tag and then tells the spinner to start animating. The rest of the method stays the same.

➤ Change `tableView(_:willSelectRowAt:)` to:

```
func tableView(
  _ tableView: UITableView,
  willSelectRowAt indexPath: IndexPath
) -> IndexPath? {
  if searchResults.count == 0 || isLoading {    // Changed
    return nil
  } else {
    return indexPath
  }
}
```

You added `|| isLoading` to the `if` statement. Just like you don't want users to select the "Nothing Found" cell, you also don't want them to select the "Loading..." cell, so you return `nil` in both cases.

There's only one thing remaining: you should set `isLoading` to `true` before you make the HTTP request to the iTunes server, and also reload the table view to make the Loading... cell appear.

➤ Change `searchBarSearchButtonClicked(_:)` to:

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  if !searchBar.text!.isEmpty {
    searchBar.resignFirstResponder()
    // New code
    isLoading = true
    tableView.reloadData()
    // End of new code
    . . .
    isLoading = false                    // New code
    tableView.reloadData()
  }
}
```

Before you do the networking request, you set `isLoading` to `true` and reload the table to show the activity indicator.

After the request completes and you have the search results, you set `isLoading` back to `false` and reload the table again to show the `SearchResult` objects.

Makes sense, right? Let's fire up the app and see this in action!

Test the new loading cell

➤ Run the app and perform a search. While search is taking place the Loading… cell with the spinning activity indicator should appear…

…or should it?!

The sad truth is that there is no spinner to be seen. And in the unlikely event that it does show up for you, it won't be spinning — try it with Network Link Conditioner enabled.

➤ To show you why, first change `searchBarSearchButtonClicked(_:)` as follows:

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  if !searchBar.text!.isEmpty {
    searchBar.resignFirstResponder()
    isLoading = true
    tableView.reloadData()
    /*
       . . . the networking code (commented out) . . .
     */
  }
}
```

Note that you don't have to remove anything from the code — simply comment out everything after the first call to `tableView.reloadData()`.

➤ Run the app and do a search. Now the activity spinner does show up!

So at least you know that part of the code is working fine. But with the networking code enabled, the app is not only totally unresponsive to any input from the user, it also doesn't want to redraw its screen. What's going on here?

The main thread

The CPU (**C**entral **P**rocessing **U**nit) in the oldest iPhone and iPad models had one core, which meant it can only do one thing at a time. Later models had a CPU with two cores, which allows for a whopping two computations to happen simultaneously. The latest Apple mobile CPUs have six cores.


With limited cores available, how can modern computers have many more applications and other processes — I count 287 active processes on my Mac right now — running at the same time?

To get around the hardware limitation of having only a few CPU cores, most computers, including the iPhone and iPad, use **preemptive multitasking** and **multithreading** to give the illusion that they can do many things at once.

Multitasking is something that happens between different apps. Each app is said to have its own **process** and each process is given a small portion of each second of CPU time to perform its jobs. Then it is temporarily halted, or *pre-empted*, and control is given to the next process.


Each process contains one or more **threads**. I just mentioned that each process is given a bit of CPU time to do its work. The process splits up that time among its threads. Each thread typically performs its own work and is as independent as possible from the other threads within that process.

An app can have multiple threads and the CPU switches between them:



If you go into the Xcode debugger and pause the app, the debugger will show you which threads are currently active and what they were doing before you stopped them.

For the StoreSearch app, there were apparently nine threads at the time the following screenshot was taken:



Most of these threads are managed by iOS itself and you don't have to worry about them. Also, you may see less or more than nine threads. However, there is one thread that requires special care: the **main thread**. In the image above, that is **Thread 1**.

The main thread is the app's initial thread and from there all the other threads are spawned. The main thread is responsible for handling user interface events and also for drawing the UI. Most of your app's activities take place on the main thread. Whenever the user taps a button in your app, it is the main thread that performs your action method.

Because it's so important, you should be careful not to hold up, or "block", the main thread. If your action method takes more than a fraction of a second to run, then doing all these computations on the main thread is not a good idea because that would lock up your main thread.

The app becomes unresponsive because the main thread cannot handle any UI events while you're keeping it busy doing something else — and if the operation takes too long, the app may even be killed by the system.

In *StoreSearch*, you're doing a lengthy network operation on the main thread. It could potentially take many seconds, maybe even minutes, to complete.

After you set the `isLoading` flag to `true`, you tell the `tableView` to reload its data so that the user can see the spinning animation. But that never comes to pass. Telling the table view to reload schedules a "redraw" event, but the main thread gets no chance to handle that event as you immediately start the networking operation, keeping the main thread busy for a long time.

This is why the current synchronous approach to doing networking is bad: **Never block the main thread**. It's one of the cardinal sins of iOS programming!

Make it asynchronous

To prevent blocking the main thread, any operation that might take a while to complete should be **asynchronous**. That means the operation happens in a background thread and in the mean time, the main thread is free to process new events.


That is not to say you should create your own thread. If you've programmed on other platforms before, you may not think twice about creating new threads, but on iOS that is often not the best solution.

You see, threads are tricky. Not threads per se, but doing things in parallel. I won't go into too much detail here, but generally, you want to avoid the situation where two threads are modifying the same piece of data at the same time. That can lead to very surprising — but not very pleasant — results.

Rather than making your own threads, iOS has several more convenient ways to start background processes. For this app you'll be using **queues** and **G**rand **C**entral **D**ispatch, or GCD. GCD greatly simplifies tasks that require parallel programming. You've already briefly played with GCD in *MyLocations*, but now you'll put it to even better use.

In short, GCD has a number of queues with different priorities. To perform a job in the background, you put the job in a closure and then pass that closure to a queue and forget about it. It's as simple as that.

GCD will get the closures — or "blocks" as it calls them — from the queues one-by-one and perform their code in the background. Exactly how it does that is not important, you're only guaranteed it happens on a background thread somewhere. Queues are not exactly the same as threads, but they use threads to do their job.



Queues have a list of closures to perform on a background thread

Put the web request in a background thread

To make the web service requests asynchronous, you're going to put the networking part from `searchBarSearchButtonClicked(_:)` into a closure and then place that closure on a medium priority queue.

➤ Change `searchBarSearchButtonClicked(_:)` as follows:

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  if !searchBar.text!.isEmpty {
    . . .
    searchResults = []
    // Replace all code after this with new code below
    // 1
    let queue = DispatchQueue.global()
    let url = self.iTunesURL(searchText: searchBar.text!)
    // 2
    queue.async {

      if let data = self.performStoreRequest(with: url) {
        self.searchResults = self.parse(data: data)
        self.searchResults.sort(by: <)
        // 3
        print("DONE!")
        return
      }
    }
  }
}
```

Here is the new stuff:

1. This gets a reference to the queue. You're using a "global" queue, which is a queue provided by the system. You can also create your own queues, but using a standard queue is fine for this app. You also get the URL for your search here, outside the closure.

2. Once you have the queue, you can dispatch a closure on it — everything between `queue.async {` and the closing `}` is the closure. Whatever code in the closure will be put on the queue and be executed asynchronously in the background. After scheduling this closure, the main thread is immediately free to continue. It is no longer blocked.

3. Inside the closure, I have removed the code that reloads the table view after the search is done, as well as the error handling code. For now, this has been replaced by `print()` statements. There is a good reason for this and we'll get to it in a second. First let's try the app again.

➤ Run the app and do a search. The "Loading..." cell should be visible, complete with animating spinner! After a short while you should see the "DONE!" message appear in the Console.

Of course, the Loading... cell sticks around forever because you still haven't told it to go away.

Put UI updates on the main thread

The reason I removed all the user interface code from the closure — and moved getting the search URL outside the closure — is that UIKit has a rule that UI code should *always* be performed on the main thread. This is important!

Accessing the same data from multiple threads can create all sorts of misery, so the designers of UIKit decided that changing the UI from other threads would not be allowed. That means you cannot reload the table view from within this closure, because it runs on a queue that is on a background thread, not the main thread.

As it happens, there is also a "main queue" that is associated with the main thread. If you need to do anything on the main thread from a background queue, you can simply create a new closure and schedule the main thread actions on the main queue.

➤ Replace the line in `searchBarSearchButtonClicked(_:)` that says `print("DONE!")` with:

```
DispatchQueue.main.async {
  self.isLoading = false
  self.tableView.reloadData()
}
```

With `DispatchQueue.main.async` you can schedule a new closure on the main queue. This new closure sets `isLoading` back to `false` and reloads the table view. Note that `self` is required because this code sits inside a closure.

➤ Try it out. With these changes in place, your networking code no longer occupies the main thread and the app suddenly feels a lot more responsive!

★ ★ ★

All kinds of queues

When working with GCD queues you will often see this pattern:

```
let queue = DispatchQueue.global()
queue.async {
  // code that needs to run in the background

  DispatchQueue.main.async {
    // update the user interface
  }
}
```

Basically, while you do your work in a background thread, you still have to switch over to the main thread to do any user interface updates. That's just the way it is.

There is also `queue.sync`, without the "a", which takes the next closure from the queue and performs it in the background, but makes you wait until that closure is done. That can be useful in some cases but most of the time you'll want to use `queue.async`. No one likes to wait!


★ ★ ★

The main thread checker

I mentioned previously that you should not run UI code on a background thread. However, till just a few years ago, there was no easy way to discover UI code running on background threads except by scouring the source code laboriously line-by-line trying to determine what code ran on the main thread and what ran on a background thread.


Then Apple introduced a new diagnostic setting called the Main Thread Checker which would warn you if you had any UI code running on a background thread. This setting is supposed to be enabled by default, but if it is not, you can enable it quite easily — I would suggest that you have it enabled at all times if possible since it can be quite invaluable.

➤ Click on the scheme dropdown in the Xcode toolbar and select Edit Scheme...



Edit scheme

➤ Select **Run** in the left panel, switch to the **Diagnostics** tab, and make sure **Main Thread Checker** is checked under Runtime API Checking.



Main Thread Checker setting

➤ Now, move the following line from outside the closure in `searchBarSearchButtonClicked(_:)`:

```
let url = self.iTunesURL(searchText: searchBar.text!)
```


to be inside the closure like this:

```
queue.async {
    let url = self.iTunesURL(searchText: searchBar.text!)
    ...
}
```

➤ Run *StoreSearch* and do a search for an item, you should see something like the following in the Xcode Console:


```
Main Thread Checker: UI API called on a background thread: -
[UISearchBar text]
PID: 92439, TID: 13807148, Thread name: (none), Queue name:
com.apple.root.default-qos, QoS: 0
Backtrace:
4   StoreSearch                         0x000000010785e823
$s11StoreSearch0B14ViewControllerC09searchBarB13ButtonClickedyyS
o08UISearchF0CFyycfU_ + 291
5   StoreSearch                         0x000000010785eec8
$sIeg_IeyB_TR + 40
6   libdispatch.dylib                   0x0000000107a39034
_dispatch_call_block_and_release + 12
. . .
```

You might also notice that Xcode's activity view now has a purple icon and that there's a purple icon on the right corner of the jump bar, where errors are normally displayed.



Purple icons indicating Main Thread Checker issues

If you click on the icon in the activity view, you will be taken to the **Runtime** tab of the **Issue navigator**, where you can click on a listed issue to be taken to the offending line in your source code:



Issue navigator

And you finally see what the issue is — you access the data from a UI control, the Search Bar, in a background thread. It might be better to do this in the main thread. Since we created this issue to illustrate the background thread checker, the fix is simple, just move the line of code back to where it was originally :]

Commit your code

➤ I think with this important improvement, the app deserves a new version number. So commit the changes and create a tag for **v0.2**. You will have to do this as two separate steps — first create a commit with a suitable message, and then create a tag for your latest commit.

You can find the project files for this chapter under **35-Asynchronous-networking** in the Source Code folder.

Chapter 36: URLSession

By Fahim Farook

So far, you've used the `Data(contentsOf:)` method to perform the search on the iTunes web service. That is great for simple apps, but I want to show you another way to do networking that is more powerful.

iOS itself comes with a number of different classes for doing networking, from low-level sockets stuff that is only interesting to really hardcore network programmers, to convenient classes such as `URLSession`.

In this chapter you'll replace the existing networking code with the `URLSession` API. That is the API the pros use for building real apps, but don't worry, it's not more difficult than what you've done before — just more powerful.

You'll cover the following items in this chapter:

- **Branch it:** Creating Git branches for major code changes.
- **Put URLSession into action:** Use the `URLSession` class for asynchronous networking instead of downloading the contents of a URL directly.
- **Cancel operations:** Canceling a running network request when a second network request is initiated.
- **Search different categories:** Allow the user to select a specific iTunes Store category to search in instead of returning items from all categories.
- **Download the artwork:** Download the images for search result items and display them as part of the search result listing.
- **Merge the branch:** Merge your changes from your working Git branch back to your main branch.


Branch it

Whenever you make a big change to the code — such as replacing all the networking stuff with `URLSession` — there is a possibility that you'll mess things up. I certainly do often enough! That's why it's smart to create a Git **branch** first.

The Git repository contains a history of all the app's code, but it can also contain this history along different paths.

You just finished the first version of the networking code and it works pretty well. Now you're going to completely replace that with a — hopefully — better solution. In doing so, you may want to commit your progress at several points along the way.

What if it turns out that switching to `URLSession` wasn't such a good idea after all? Then you'd have to restore the source code to a previous commit from before you started making those changes. In order to avoid this potential mess, you can make a branch instead.




Branches in action

Every time you're about to add a new feature to your code or have a bug to fix, it's a good idea to make a new branch and work on that. When you're done and are satisfied that everything works as it should, merge your changes back into the main branch. Different people use different branching strategies but this is the general principle.


So far you have been committing your changes to the "main" branch. Now you're going to make a new branch, let's call it "urlsession", and commit your changes to that. When you're done with this new feature you will merge everything back into the main branch.

You can find the branches for your repository in the **Source Control navigator**:




The Source Control branch list

➤ Right-click on the branch name (**main**) to get a context-menu with possible actions and select **New Branch from "main"...**:



The branch context-menu

➤ You will get a dialog asking for the new branch name. Enter **urlsession** as the new name and click **Create**.



Creating a new branch

When Xcode is done, you'll see that a new "urlsession" branch has been added and that it is now the current one.

This new branch contains the exact same source code and history as the main branch, or whichever branch you used as the parent for the new branch. But from here on out the two paths will diverge — any changes you make happen on the "urlsession" branch only.

Put URLSession into action

Good, now that you're in a new branch, it's safe to experiment with these new APIs.

➤ First, remove `performStoreRequest(with:)` from **SearchViewController.swift**. Yup, that's right, you won't be needing that method anymore.

Don't be afraid to remove old code. Some developers only comment out the old code but leave it in the project, just in case they may need it again some day. You don't have to worry about that because you're using source control. Should you really need it, you can always find the old code in the Git history. Besides, if the experiment should fail, you can simply throw away this branch and switch back to the "original" one.

Anyway, on to `URLSession`. This is a closure-based API, meaning that instead of making a delegate, you pass it a closure containing the code that should be performed once the response from the server has been received. `URLSession` calls this closure the *completion handler*.

➤ Change `searchBarSearchButtonClicked(_:)` as follows:

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  if !searchBar.text!.isEmpty {
    . . .
    searchResults = []
    // Replace all code after this with new code below
    // 1
    let url = iTunesURL(searchText: searchBar.text!)
    // 2
    let session = URLSession.shared
    // 3
    let dataTask = session.dataTask(with: url) {data, response,
error in
      // 4
      if let error = error {
        print("Failure! \(error.localizedDescription)")
      } else {
        print("Success! \(response!)")
      }
    }
    // 5
    dataTask.resume()
  }
}
```

This is what the code does:

1. Create the `URL` object using the search text, just like before.
2. Get a shared `URLSession` instance, which uses the default configuration with respect to caching, cookies, and other web stuff.

   If you want to use a different configuration — for example, to restrict networking to when Wi-Fi is available but not when there is only cellular access — then you have to create your own `URLSessionConfiguration` and `URLSession` objects. But for this app, the default one will be fine.
3. Create a data task. Data tasks are for fetching the contents of a given URL. The code from the completion handler will be invoked when the data task has received a response from the server.
4. Inside the closure, you're given three parameters: `data`, `response`, and `error`. These are all optionals so they can be `nil` and have to be unwrapped before you can use them.

   If there was a problem, error contains an `Error` object describing what went wrong. This happens when the server cannot be reached or the network is down or there is some other hardware failure.

If `error` is `nil`, the communication with the server succeeded; `response` holds the server's response code and headers, and `data` contains the actual data fetched from the server, in this case a blob of JSON.

For now, you simply use `print()` to show success or failure.

5. Finally, once you have created the data task, you need to call `resume()` to start it. This sends the request to the server on a background thread. So, the app is immediately free to continue — `URLSession` is as asynchronous as they come.

With these changes made, you can run the app and see what `URLSession` makes of it.

➤ Run the app and search for something. After a second or two you should see a Console message saying "Success!" followed by a dump of the HTTP response headers.

Excellent!

★ ★ ★

A brief review of closures

You've seen closures a few times now. They are a really powerful feature of Swift and you can expect to be using them all the time when you're working with Swift code. So, it's good to have at least a basic understanding of how they work.

A closure is simply a piece of source code that you can pass around just like any other type of object. The difference between a closure and regular code is that the code from the closure is not executed right away. Instead, it is stored in a "closure object" and can be executed at a later point, even more than once.

That's exactly what `URLSession` does: it holds on to the "completion handler" closure and only performs it when a response is received from the web server or when a network error occurs.

While we used a trailing closure above, the same code could also be written like this:

```
let dataTask = session.dataTask(with: url, completionHandler: {
   data, response, error in
   . . . source code . . .
})
```

The thing behind `completionHandler` inside the `{ }` brackets is the closure. The form of a closure is always:

```
{ parameters in
  your source code
}
```

or without parameters:

```
{
  your source code
}
```

Just like a method or function, a closure can accept parameters. They are separated from the source code by the "`in`" keyword. In `URLSession`'s completion handler the parameters are `data`, `response`, and `error`.

Thanks to Swift's type inference, you don't need to specify the data types of the parameters. However, you could write them out in full if you wanted to:

```
let dataTask = session.dataTask(with: url, completionHandler: {
  (data: Data?, response: URLResponse?, error: Error?) in
  . . .
})
```

Tip: For a parameter without the type annotation, you can Option-click in Xcode to find out what its type is. This trick works for any symbol in your code.

If you don't use a particular parameter in your closure code you can substitute it with _, the *wildcard* symbol:

```
let dataTask = session.dataTask(with: url, completionHandler: {
   data, _, error in
  . . .
})
```

If a closure is really simple, you can leave out the parameter list altogether and use `$0`, `$1`, and so on as the parameter names.

```
let dataTask = session.dataTask(with: url, completionHandler: {
   print("My parameters are \($0), \($1), \($2)")
})
```

You wouldn't do that with `URLSession`'s completion handler, though. It's much easier if you know the parameters are called `data`, `response`, and `error` than remembering what `$0`, `$1`, and `$2` stand for.

As you've seen all the closure code in this book, if a closure is the last parameter of a method, you can use *trailing* syntax to simplify the code a little:

```
let dataTask = session.dataTask(with: url) {
  data, response, error in
  . . .
}
```

Now the closure appears after the closing parenthesis, not inside. Many people, myself included, find this more natural to read.

Closures are useful for other things too, such as initializing objects and lazy loading:

```
lazy var dateFormatter: DateFormatter = {
  let formatter = DateFormatter()
  formatter.dateStyle = .medium
  formatter.timeStyle = .short
  return formatter
}()
```

The code to create and initialize the `DateFormatter` object sits inside a closure. The `()` at the end causes the closure to be *evaluated* and the returned object is put inside the `dataFormatter` variable. This is a common trick for placing complex initialization code right next to the variable declaration.

It's no coincidence that closures look a lot like functions. In Swift, closures, methods, and functions are really all the same thing. For example, you can supply the name of a method or function when a closure is expected, as long as the parameters match:

```
let dataTask = session.dataTask(with: url, completionHandler:
myHandler)
. . .

func myHandler(data: Data?, response: URLResponse?, error:
Error?) {
  . . .
}
```

The above somewhat negates one of the prime benefits of closures — keeping all the code in the same place — but there are situations where this is quite useful when the method acts as a "mini" delegate.

One final thing to be aware of with closures is that they *capture* any variables used inside the closure, including `self`. This can create ownership cycles, often leading to memory leaks. To avoid this, you can supply a *capture list*:

```
let dataTask = session.dataTask(with: url) {
  [weak self] data, response, error in
  . . .
}
```

Whenever you access a property or call a method, you're implicitly using `self`. Inside a closure, however, Swift requires that you always write `self.` in front of the method or property name. This makes it clear that `self` is being captured by the closure:

```
let dataTask = session.dataTask(with: url) { data, response,
error in
  self.callSomeMethod()     // self is required
}
```

`SearchViewController` doesn't have to worry about `URLSession` capturing `self` because the data task is only short-lived, while the view controller sticks around for as long as the app itself. This ownership cycle is quite harmless. As you add more functionality to *StoreSearch* you *will* have to use `[weak self]` with `URLSession` or the app might crash and burn!

Note: Swift also has the concept of "no escape" closures. We won't go into that here, except to mention that no-escape closures don't capture `self`, so you don't have to write "`self.`" everywhere. Nice, but you can only use such closures under very specific circumstances!

★ ★ ★

Handle status codes

After a successful request, the app prints the HTTP response from the server. The response object might look something like this:

```
<NSHTTPURLResponse: 0x600002dab5e0> { URL: https://
itunes.apple.com/search?term=Jack&limit=200 } { Status Code:
200, Headers {
    "Cache-Control" =     (
        "max-age=86371"
```

```
    );
    "Content-Disposition" =     (
        "attachment; filename=1.txt"
    );
    "Content-Encoding" =     (
        gzip
    );
    "Content-Length" =     (
        88447
    );
    "Content-Type" =     (
        "text/javascript; charset=utf-8"
    );
    Date =     (
        "Fri, 13 Aug 2021 22:38:09 GMT"
    );
    . . .
} }
```

If you've done any web development before, this should look familiar. These "HTTP headers" are always the first part of the response from a web server that precedes the actual data you're receiving. The headers give additional information about the communication that just happened.

What you're especially interested in is the *status code*. The HTTP protocol has defined a number of status codes that tell clients whether the request was successful or not. No doubt you're familiar with 404, web page not found.

The status code you want to see is 200 OK, which indicates success — Wikipedia has the complete list of codes, wikipedia.org/wiki/List_of_HTTP_status_codes.

To make the error handling of the app a bit more robust, let's check to make sure the HTTP response code really is 200. If not, something has gone wrong and we can't assume that the received data contains the JSON we're after.

➤ Change the contents of the `completionHandler` to:

```
if let error = error {
  print("Failure! \(error.localizedDescription)")
} else if let httpResponse = response as? HTTPURLResponse,
  httpResponse.statusCode == 200 {
  print("Success! \(data!)")
} else {
  print("Failure! \(response!)")
}
```

The `response` parameter has the data type `URLResponse`, but that doesn't have a property for the status code. Because you're using the HTTP protocol, what you've really received is an `HTTPURLResponse` object, a subclass of `URLResponse`. So, first you cast it to the proper type, and then look at its `statusCode` property — you'll consider the job a success only if the status code is 200.

Notice the use of the comma inside the `if let` statement to combine these checks into a single line. You could also have written it with a second `if`, but I find that harder to read:

```
} else if let httpResponse = response as? HTTPURLResponse {
  if httpResponse.statusCode == 200 {
    print("Success! \(data!)")
  }
```

Whenever you need to unwrap an optional and also check the value of that optional, using `if let …, …` is the nicest way to do that.

➤ Run the app and search for something. You should now see something like:

```
Success! 295831 bytes
```

Since your received data is in the form of a `Data` object, unlike text, its content can't be printed out. So, you just get the length of the data instead.

It's always a good idea to actually test your error handling code. So, let's first fake an error and get that out of the way.

➤ In `iTunesURL(searchText:)`, change the URL string to:

```
"https://itunes.apple.com/searchLOL?term=%@&limit=200"
```

Here, I've changed the endpoint from `search` to `searchLOL`. It doesn't really matter what you type there, as long as it's something that cannot possibly exist on the iTunes server.

➤ Run the app again. Now a search should respond with something like this:

```
<NSHTTPURLResponse: 0x60000217cf00> { URL: https://
itunes.apple.com/searchLOL?term=Jack&limit=200 } { Status Code:
404, Headers {
    "Cache-Control" =     (
        "private, max-age=285"
    );
    . . .
} }
```

As you can see, the status code is now 404 — there is no searchLOL page — and the app correctly considers this a failure. That's a good thing too, because if you were to convert the value of `data` to text, `data` now contains the following:

```
<!DOCTYPE HTML PUBLIC "-//IETF//DTD HTML 2.0//EN">
<html><head>
<title>404 Not Found</title>
</head><body>
<h1>Not Found</h1>
<p>The requested URL /searchLOL was not found on this server.</
p>
</body></html>
```

That is definitely not JSON but HTML. If you tried to convert that into JSON objects, you'd fail horribly.

Great, so the error handling works! Let's parse received JSON data.

Parse the data

➤ First, put `iTunesURL(searchText:)` back to the way it was — use ⌘+Z to undo.

➤ In the `completionHandler`, replace the `print("Success! \(data)")` line with:

```
if let data = data {
  self.searchResults = self.parse(data: data)
  self.searchResults.sort(by: <)
  DispatchQueue.main.async {
    self.isLoading = false
    self.tableView.reloadData()
  }
  return
}
```

This unwraps the optional object from the `data` parameter and then calls `parse(data:)` to turn the dictionary's contents into `SearchResult` objects, just like you did before. Finally, you sort the results and put everything into the table view. This should look very familiar.

It's important to realize that the completion handler closure won't be performed on the main thread. Because `URLSession` does all the networking asynchronously, it will also call the completion handler on a background thread.

Parsing the JSON and sorting the list of search results could potentially take a while — not seconds but possibly long enough to be noticeable. You don't want to block the main thread while that is happening, so it's preferable that this happens in the background too.

But when the time comes to update the UI, you need to switch back to the main thread — them's the rules. That's why you wrap the reloading of the table view in a `DispatchQueue.main.async` closure.

If you forget to do this, your app may still appear to work. That's the insidious thing about working with multiple threads. However, it may also crash in all kinds of mysterious ways. So remember, UI stuff should always happen on the main thread. Write it on a Post-It note and stick it to your screen!

➤ Run the app. The search should work again. You have successfully replaced the old networking code with `URLSession`!

> **Tip:** If you want to determine via code whether a particular piece of code is being run on the main thread or not, add the following code snippet:
>
> ```
> print("On main thread? " + (Thread.current.isMainThread ?
> "Yes" : "No"))
> ```
>
> Go ahead, paste this at the top of the `completionHandler` closure and see what it says.
>
> Of course, the official framework documentation should be your first stop. Usually when a method takes a closure, the docs mention whether it is performed on the main thread or not. But if you're not sure, or just can't find it in the docs, add the above `print()` and be enlightened.

Handle errors

➤ At the very end of the completion handler closure, below the `if` statements, add the following:

```
DispatchQueue.main.async {
  self.hasSearched = false
  self.isLoading = false
  self.tableView.reloadData()
  self.showNetworkError()
}
```

The code execution reaches here only if something went wrong. You call `showNetworkError()` to let the user know about the problem.

Note that you do `tableView.reloadData()` here too, because the contents of the table view need to be refreshed to get rid of the Loading… indicator. And of course, all this happens on the main thread.

> **Exercise:** Why doesn't the error alert show up on success? After all, the above piece of code sits at the bottom of the closure, so doesn't it always get executed?

Answer: Upon successfully loading the data, the `return` statement exits the closure after the search results get displayed in the table view. So in that case, execution never reaches the bottom of the closure.

➤ Fake an error situation to test that the error handling code really works.

Testing errors is not a luxury! The last thing you want is for your app to crash when a networking error occurs because of faulty error handling code. I've worked on codebases where it was obvious the previous developer never bothered to verify that the app was able to recover from errors — that's probably why they were the *previous* developer.

Things will go wrong in the wild and your app better be prepared to deal with it. As the MythBusters say, "failure is always an option".

Does the error handling code work? Great! Time to add some new networking features to the app.

➤ This is a good time to commit your changes. Remember, this commit only happens on the "urlsession" branch, not on the main branch.

Cancel operations

What happens when a search takes a long time and the user starts a second search while the first one is still going? The app doesn't disable the search bar, so it's possible for the user to do this. When dealing with networking — or any asynchronous process, really — you have to think these kinds of situations through.

There is no way to predict what happens, but it will most likely be a strange experience for the user. They might see the results from their first search, which they are no longer expecting, only for that to be replaced by the results of the second search a few seconds later. Confusing!

But there is no guarantee the first search completes before the second, so the results from search #2 may arrive first and then get overwritten by the results from search #1, which is definitely not what the user wanted to see either.

Because you're no longer blocking the main thread, the UI always accepts user input, and you cannot assume the user will sit still and wait until the request is done.

You can usually fix this in one of two ways:

1. Disable all controls. The user cannot tap anything while the operation is taking place. This does not mean you're blocking the main thread; you're just making sure the user cannot mess up the order of things.
2. Cancel the on-going request when the user initiates a new request.

For this app, you're going to pick the second solution because it makes for a nicer user experience. Every time the user performs a new search, you cancel the previous request. `URLSession` makes this easy: data tasks have a `cancel()` method.

When you created the data task, you were given a `URLSessionDataTask` object, and you placed this into a local constant named `dataTask`. Cancelling the task, however, needs to happen the *next* time `searchBarSearchButtonClicked(_:)` is called.

Storing the `URLSessionDataTask` object into a local variable isn't good enough anymore; you need to keep that reference beyond the scope of the method. In other words, you have to store it in an instance variable.

➤ Add the following instance variable to **SearchViewController.swift**:

```
var dataTask: URLSessionDataTask?
```

This is an optional because you won't have a data task until the user performs a search.

➤ In `searchBarSearchButtonClicked(_:)`, remove `let` from the line that creates the new data task object:

```
dataTask = session.dataTask(with: url) {data, response, error in
```

You've removed the `let` keyword because `dataTask` should no longer be a local; it now refers to the instance variable.

➤ At the end of the method, add a question mark to the line that starts the task:

```
dataTask?.resume()
```

Because `dataTask` is an optional, you have to unwrap the optional somehow before you can use it. Here you're using optional chaining.

➤ Finally, near the top of the method before you set `isLoading` to `true`, add:

```
dataTask?.cancel()
```

If there is an active data task, this cancels it, making sure that no old searches can ever get in the way of the new search.

Thanks to the optional chaining, if no search has been done yet and `dataTask` is still `nil`, this simply ignores the call to `cancel()`. You could also unwrap the optional with `if let`, but using the question mark is shorter and just as safe.

Exercise: Why can't you write `dataTask!.cancel()` to unwrap the optional?

Answer: If an optional is `nil`, using `!` will crash the app. You're only supposed to use `!` to unwrap an optional when you're sure it won't be `nil`. But the very first time the user types something into the search bar, `dataTask` will still be `nil` and using `!` is not a good idea.

➤ Test the app with and without this call to `dataTask.cancel()` to experience the difference.

Use the Network Link Conditioner preferences pane to delay each query by a few seconds so it's easier to get two requests running at the same time.

Hmm... you may notice something odd. When the data task gets cancelled, you get the network error popup.

As it turns out, when a data task gets cancelled, its completion handler is still invoked but with an `Error` object that has error code -999. That's what caused the error alert to pop up.

You'll have to make the error handler a little smarter to ignore code -999. After all, the user cancelling the previous search is no cause for panic.

➤ In the `completionHandler`, change the `if let error` section to:

```
if let error = error as NSError?, error.code == -999 {
  return  // Search was cancelled
} else if let httpResponse = . . .
```


This simply ends the closure when there is an error with code -999. The rest of the closure gets skipped.

➤ If you're satisfied it works, commit the changes to the repository.

> **Note:** Maybe you don't think it's worth making a commit when you've only changed a few lines, but many small commits are often better than a few big ones. Each time you fix a bug or add a new feature, it is a good time to commit.

Search different categories

The iTunes store has a vast collection of products and each search returns at most 200 items. It can be hard to find what you're looking for by name alone. So, you'll add a control to the screen that lets users pick the category they want to search in. It will look like this:



Searching in the Software category

This type of control is called a **segmented control** and is used to pick one option out of a set of choices.

Add the segmented control

➤ Open the storyboard. Drag a new **Toolbar** into the view and put it below the Search Bar. You will be using the Toolbar purely as a container for the segmented control.


Make sure the Toolbar doesn't get added inside the Table View. It may be easiest to drag it from the Objects Library directly into the Document Outline and drop it below the Search Bar. Then change its Y-position to 51.

➤ The Toolbar comes with an item in it. Select the item and delete it. If you find this hard to do on the canvas, select the item via the Document Outline and then delete it.

➤ With the Toolbar selected, open the **Add New Constraints menu** and pin its **top**, **left**, and **right**.

➤ Drag a new **Segmented Control** from the Objects Library on to the Toolbar.

The design should now look like this:




The Segmented Control sits in a Toolbar below the Search Bar

➤ Select the Segmented Control — you might need to use the Document Outline again since the Segmented Control gets embedded in a Bar Button Item when you place it in the Toolbar — and in the **Attributes inspector**, set the number of segments to 4.

➤ Change the title of the first segment to **All**. Then select the second segment via the **Segment** dropdown and set its title to **Music**. The title for the third segment should be **Software** and the fourth segment is **E-books**.

> **Note:** You can also change the segment title by double-clicking inside the segment.

The scene should look like this now:



The finished Segmented Control


Next, you'll add a new outlet and action method for the Segmented Control. This is a good opportunity to practice using the Assistant editor.

Use the assistant editor

➤ Press **Control+Option+⌘+Enter** to open the Assistant editor and then Control-drag from the Segmented Control into the view controller source code to add the new outlet:

```
@IBOutlet weak var segmentedControl: UISegmentedControl!
```

To add the action method you can also use the Assistant editor. Control-drag from the Segmented Control into the source code again, but this time choose the following:



Adding an action method for the segmented control


- Connection: **Action**
- Name: **segmentChanged**
- Type: **UISegmentedControl**
- Event: Value Changed
- Arguments: Sender

➤ Press **Connect** to add the action method. Then, add a `print()` statement to the new method:

```
@IBAction func segmentChanged(_ sender: UISegmentedControl) {
  print("Segment changed: \(sender.selectedSegmentIndex)")
}
```

Type ⌘+**Enter** to close the Assistant editor. These are very handy keyboard shortcuts to remember.

➤ Run the app to make sure everything still works. Tapping a segment should log a number — the index of that segment — to the Console.



The segmented control in action

Use the segmented control

If you do a search now, you'll notice that the first row of the table view is partially obscured again. Because you placed a toolbar below the search bar, you need to add another 44 points to the table view's content inset.

➤ Change that line in `viewDidLoad()` to:

```
tableView.contentInset = UIEdgeInsets(top: 91, left: 0, . . .
```

You will be using the segmented control in two ways. First of all, it determines what sort of products the app will search for. Second, if you have already performed a search and you tap on one of the other segment buttons, the app will search again for the new product category.

That means a search can now be triggered by two different events: tapping the Search button on the keyboard and selecting an item in the Segmented Control.

➤ Rename the `searchBarSearchButtonClicked(_:)` method to `performSearch()` and remove the `searchBar` parameter.

You're doing this to put the search logic into a separate method that can be invoked from more than one place. Removing `searchBar` as the parameter of this method is no problem because there is also an `@IBOutlet` property with that name and any references to `searchBar` in `performSearch()` will simply use that property.

➤ Now add a new version of `searchBarSearchButtonClicked(_:)` to the source code:

```
func searchBarSearchButtonClicked(_ searchBar: UISearchBar) {
  performSearch()
}
```

➤ Also replace the `segmentChanged(_:)` action method with:

```
@IBAction func segmentChanged(_ sender: UISegmentedControl) {
  performSearch()
}
```

➤ Run the app and verify that searching still works. When you tap on the different segments, the search should be performed again as well.

> **Note:** The second time you search for the same thing, the app may return results very quickly. The networking layer is now returning a *cached* response so it doesn't have to download the whole thing again, which is usually a performance gain on mobile devices. However, there is an API to turn off this caching behavior if that makes sense for your app.

There is one thing left to be done — you have to tell the app to use the category based on the selected segment for the search. You've already seen that you can get the index of the selected segment with the `selectedSegmentIndex` property. This returns an `Int` value (0, 1, 2, or 3).

➤ Change the `iTunesURL(searchText:)` method so that it accepts this `Int` as a parameter and then builds up the request URL accordingly:

```
func iTunesURL(searchText: String, category: Int) -> URL {
  let kind: String
  switch category {
    case 1: kind = "musicTrack"
    case 2: kind = "software"
    case 3: kind = "ebook"
    default: kind = ""
  }
  let encodedText = searchText.addingPercentEncoding(
      withAllowedCharacters: CharacterSet.urlQueryAllowed)!
  let urlString = "https://itunes.apple.com/search?" +
    "term=\(encodedText)&limit=200&entity=\(kind)"

  let url = URL(string: urlString)
  return url!
}
```

This first turns the category index from a number into a string, `kind`. Note that the category index is passed to the method as a new parameter.

Then it puts this string behind the `&entity=` parameter in the URL. For the "All" category, the entity value is empty, but for the other categories it is "musicTrack", "software", and "ebook", respectively. Also note that instead of calling `String(format:)`, you now construct the URL string using string interpolation.


➤ In `performSearch()`, change the line that gets the URL to the following:

```
let url = iTunesURL(
  searchText: searchBar.text!,
  category: segmentedControl.selectedSegmentIndex)
```

And that should do it!

> **Note:** You could have used `segmentedControl.selectedSegmentIndex` directly inside `iTunesURL` instead of passing the category index as a parameter. Using the parameter is the better design, though. It makes it possible to reuse the same method with a different type of control, should you decide that a Segmented Control isn't really the right component for this app. It is always a good idea to make methods as independent from each other as possible.

➤ Run the app and search for "stephen king". In the All category that gives results for anything from songs to movies to podcasts to audio books. But if all you wanted were to get to his books, you can now use the E-Books category to finally find some of his novels.



You can now limit the search to just e-books

This finalizes the UI design of the main screen. This is as good a point as any to replace the empty launch screen from the template.

Set the launch screen

➤ Remove the **LaunchScreen.storyboard** file from the project.

➤ In the **Project Settings** screen, under **App Icons and Launch Images**, change **Launch Screen File** to **Main**.

Now when the app starts, it uses the initial view controller from the storyboard as the launch image.

➤ Commit the changes and get ready for some more networking!

Download the artwork

The JSON search results contain a number of URLs to images and you put two of those — `imageSmall` and `imageLarge` — into the `SearchResult` object. Now you are going to download these images over the Internet and display them in the table view cells. Downloading images, just like using a web service, is simply a matter of doing an HTTP request to a server that is connected to the Internet. An example of such a URL is:

https://is2-ssl.mzstatic.com/image/thumb/Music/v4/de/e7/a7/dee7a7df-02f9-1333-0272-f44c45263f82/source/100x100bb.jpg

Click that link and it will open the picture in a new web browser window. The server where this picture is stored is not itunes.apple.com but is2-ssl.mzstatic.com, but that doesn't matter at all to the app. As long as it has a valid URL, the app will just go fetch the file at that location, no matter where it is and what kind of file it is.

There are various ways that you can download files from the Internet. You're going to use `URLSession` and write a handy `UIImageView` extension to make this really convenient. Of course, you'll be downloading these images asynchronously!

SearchResultCell refactoring

First, you will move the logic for configuring the contents of the table view cells into the `SearchResultCell` class. That's a better place for it. Logic related to an object should live inside that object as much as possible, not somewhere else.

Many developers have a tendency to stuff everything into their view controllers, but if you can move some of the logic into other objects, that makes for a much cleaner program.

➤ Add the following method to **SearchResultCell.swift**:

```
// MARK: - Helper Methods
func configure(for result: SearchResult) {
  nameLabel.text = result.name

  if result.artist.isEmpty {
    artistNameLabel.text = "Unknown"
  } else {
    artistNameLabel.text = String(format: "%@ (%@)",
result.artist, result.type)
  }
}
```

This is basically the same code as in `tableView(_:cellForRowAt:)`.

➤ Now, change `tableView(_:cellForRowAt:)` as follows:

```
func tableView(_ tableView: UITableView,
    cellForRowAt indexPath: IndexPath) -> UITableViewCell {
  if isLoading {
    . . .
  } else if searchResults.count == 0 {
    . . .
  } else {
    . . .
    let searchResult = searchResults[indexPath.row]
    // Replace all code after this with new code below
    cell.configure(for: searchResult)
    return cell
  }
}
```

This small refactoring of moving some code from one class, `SearchViewController`, into another, `SearchResultCell`, was necessary to make the next bit work right.

In hindsight, it makes more sense to do this sort of thing in `SearchResultCell` anyway, but until now it did not really matter. Don't be afraid to refactor your code! Remember, if you screw up, you can always go back to your last Git commit.

➤ Run the app to make sure everything still works fine.

UIImageView extension for downloading images

OK, here comes the cool part. You will now add an extension for `UIImageView` that downloads the image and automatically displays it via the image view on the table view cell with just one line of code!

As you know, an extension can be used to extend the functionality of an existing class without having to subclass it. This works even for classes from system frameworks.

`UIImageView` doesn't have built-in support for downloading images, but this is a very common thing to do in apps. It's great that you can simply plug in your own extension and from then on every `UIImageView` in your app has this new ability.

➤ Add a new file to the project using the **Swift File** template, and name it **UIImageView+DownloadImage.swift**.

➤ Replace the contents of the new file with the following:

```
import UIKit

extension UIImageView {
  func loadImage(url: URL) -> URLSessionDownloadTask {
    let session = URLSession.shared
    // 1
    let downloadTask = session.downloadTask(with: url) {
      [weak self] url, _, error in
      // 2
      if error == nil, let url = url,
        let data = try? Data(contentsOf: url),   // 3
        let image = UIImage(data: data) {
        // 4
        DispatchQueue.main.async {
          if let weakSelf = self {
            weakSelf.image = image
          }
        }
      }
    }
    // 5
    downloadTask.resume()
    return downloadTask
  }
}
```

This should look very similar to what you did before with `URLSession`, but there are some differences:

1. After obtaining a reference to the shared `URLSession`, you create a download task. This is similar to a data task, but it saves the downloaded file to a temporary location on disk instead of keeping it in memory.

2. Inside the completion handler for the download task, you're given a URL where you can find the downloaded file — this URL points to a local file rather than an internet address. Of course, you must also check that `error` is `nil` before you continue.

3. With this local URL you can load the file into a `Data` object and then create an image from that. It's possible that constructing the `UIImage` fails, for example, when what you downloaded was not a valid image but a 404 page or something else unexpected. As you can tell, when dealing with networking code, you need to check for errors every step of the way!

4. Once you have the image, you can put it into the `UIImageView`'s `image` property. Because this is UI code you need to do this on the main thread.

   Here's the tricky thing: it is theoretically possible that the `UIImageView` no longer exists by the time the image arrives from the server. After all, it may take a few seconds and the user might have navigated away to a different part of the app by then.

   That won't happen in this part of the app because the image view is part of a table view cell and they get recycled but not thrown away. But later on you'll use this same code to load an image on a screen that may be closed while the image file is still downloading. In that case, you don't want to set the image if the `UIImageView` is not visible anymore.

   That's why the capture list for this closure includes `[weak self]`, where `self` now refers to the `UIImageView`. Inside the `DispatchQueue.main.async` you need to check whether "self" still exists; if not, then there is no more `UIImageView` to set the image on.

5. After creating the download task, you call `resume()` to start it, and then return the `URLSessionDownloadTask` object to the caller. Why return it? That gives the app the opportunity to call `cancel()` on the download task if necessary. You'll see how that works in a minute.

And that's all you need to do. From now on you can call `loadImage(url:)` on any `UIImageView` object in your project. Cool, huh?

> **Note:** Swift lets you combine multiple `if let` statements into a single line, like you did above:
>
> ```
> if error == nil, let url = …, let data = …, let image = … {
> ```
>
> There are three optionals being unwrapped here: 1) `url`, 2) the result from `Data(contentsOf:)`, and 3) the result from `UIImage(data:)`.
>
> You can write this as three separate `if let` statements, and one for `if error == nil`, but I find that having everything inside a single `if` statement is easier to read than many nested `if` statements spread over several lines.

Use the image downloader extension

➤ Switch to **SearchResultCell.swift** and add a new instance variable, `downloadTask`, to hold a reference to the image downloader:

```
var downloadTask: URLSessionDownloadTask?
```


➤ Now, add the following lines to the end of `configure(for:)`:

```
artworkImageView.image = UIImage(systemName: "square")
if let smallURL = URL(string: result.imageSmall) {
  downloadTask = artworkImageView.loadImage(url: smallURL)
}
```

This tells the `UIImageView` to load the image from `imageSmall` and to place it in the cell's image view. While the real artwork is downloading, the image view displays a placeholder image — the same symbol image as the one one from the nib for this cell.

> **Note:** You can load an image from the asset catalog by using `UIImage(named:)` while you can load a symbol image using `UIImage(systemName:)` – note that the parameter name is different for each type of use.

➤ Run the app and enjoy your colorful images!



The app now downloads the album artwork

App transport security

While your image downloading experience worked great here, sometimes when dealing with image downloads, or accessing any web URL for that matter, you might see something like the following in the Xcode Console, along with a ton of error messages like the following for failed download tasks:

```
The resource could not be loaded because the App Transport
Security policy requires the use of a secure connection.
```

While you could previously download images over HTTP, you can no longer do so. Instead, you always need to use HTTPS.

If for some reason you do need to access files over HTTP in your app, you can add a key to the app's Info.plist to bypass this App Transport Security feature, allowing you to use plain `http://` URLs.

➤ Open the **Info** tab and add a new row. Choose **App Transport Security Settings** from the list of keys.

➤ Make sure the Type is a Dictionary.

➤ Add a new row inside that dictionary and choose **Allow Arbitrary Loads** from the list. Set it to YES.



Overriding App Transport Security


That's all you need to do to access HTTP links. However, you're only supposed to bypass App Transport Security if there is absolutely no way you can make the app work over HTTPS. If you're making an app that talks to a server you control, then the best thing to do is to enable HTTPS on the server, not disable HTTPS in the app.

The Info setting is only intended for when you need to communicate with other people's servers that do not support HTTPS. Obviously, in that case, the app should not send sensitive data to those servers! Unprotected HTTP should only be used for downloading publicly accessible data, such as images.

When you set the *Allow Arbitrary Loads* key to YES, the app can use *any* URL that starts with http://, regardless of the domain. To allow HTTP on specific domains only, set to *Allow Arbitrary Loads* to NO and add a new row under the *App Transport Security Settings* dictionary and select **Exception Domains** from the list of keys.

The value for the new *Exception Domains* key is a dictionary. Under that dictionary, you can add a new dictionary for each domain.

For example, the iTunes web service appears to host all its preview images on the website mzstatic.com. You could configure the Info setting as follows:



Now the app only allows http:// requests from mzstatic.com and any of its subdomains, but requires https:// URLs for any other domains.

Note that Apple has indicated that this ability to bypass App Transport Security (ATS) will be removed at some time in the future. So do not rely on the ATS-bypass being something which would always be available.

Cancel previous image downloads

These images already look pretty sweet, but you're not quite done yet. Remember that table view cells can be reused, so it's theoretically possible that you're scrolling through the table and some cell is about to be reused while its previous image is still downloading.

You no longer need that image, so you should really cancel the pending download. Table view cells have a special method named `prepareForReuse()` that is ideal for this.

➤ Add the following method to **SearchResultCell.swift**:

```
override func prepareForReuse() {
  super.prepareForReuse()
  downloadTask?.cancel()
  downloadTask = nil
}
```

You simply cancel any image download that is still in progress.

> **Exercise:** Put a `print()` in the `prepareForReuse()` method and see if you can trigger it.

On a decent Wi-Fi connection, loading the images is very fast. You almost cannot see it happen, even if you scroll quickly. It also helps that the image files are small — only 60 by 60 pixels — and that the iTunes servers are fast.

That is key to having a snappy app: don't download more data than you need.

★ ★ ★

Caching

Depending on what you searched for, you may have noticed that many of the images were the same. For example, you might get many identical album covers in the search results. `URLSession` is smart enough not to download identical images — or at least images with identical URLs — twice. That principle is called *caching* and it's very important on mobile devices.

Mobile developers are always trying to optimize their apps to do as little as possible. If you can download something once and then use it over and over, that's a lot more efficient than re-downloading it all the time.

Images aren't the only things that you can cache. You can also cache the results of big computations, for example. Or views, as you have been doing in the previous apps, probably without even realizing it. When you use the principle of lazy loading, you delay the creation of an object until you need it and then you cache it for the next time.

Cached data does not stick around forever. When your app gets a memory warning, it's a good idea to remove any cached data that you don't need right away. That means you will have to reload that data when you need it again later, but that's the price you have to pay. For `URLSession` this is completely automatic, so that takes another burden off your shoulders.

Some caches are in-memory — the cached data only stays in the computer's working memory. But it is also possible to cache the data to the disk. Your app even has a special directory for it, Library/Caches.

The caching policy used by *StoreSearch* is very simple — it uses the default settings. But you can configure `URLSession` to be much more advanced. Look into the documentation for `URLCache` and `URLSessionConfiguration` to learn more.

★ ★ ★

Merge the branch

This concludes the section on talking to the web service and downloading images. Later on, you'll tweak the web service requests a bit more to include the user's language and country, but for now, you're done with this feature. I hope you got a good glimpse of what is possible with web services and how easy it is to build this functionality into your apps using `URLSession`.

➤ Commit these latest changes to the repository.


Merge the branch using Xcode

Now that you've completed a feature, you can merge this temporary branch back into the main branch.

➤ Switch to the **Source Control navigator**, select the **main** branch under branches, and right-click to get the context menu of actions.


➤ Select **Checkout…** to switch your active branch back to the main branch.

➤ Next, right-click on the **urlsession** branch to get the context menu again and select **Merge "urlsession" into "main"…**:



Merging your changes back to the main branch

➤ You'll get a confirmation dialog. Click **Merge** if you want to continue.



The confirmation dialog before merging changes

Now that the main branch is up-to-date with the networking changes, if you wanted to, you could remove the "urlsession" branch. Or, you could keep it and do more work on it later.

Merge the branch from the command line

The source control features in Xcode used to be a bit rough around the edges. So, it was possible that certain commands, especially merging changes, might not work correctly. If Xcode didn't want to cooperate when you tried to merge changes, here is how you'd do it from the command line.

➤ First close Xcode. You don't want to do any of this while Xcode still has the project open. That's just asking for trouble.

➤ Open a Terminal, `cd` to the *StoreSearch* folder, and type the following commands:

```
git stash
```

This moves any unsaved files out of the way — no, it doesn't have anything to do with facial hair :] This saves any uncommitted changes so you can later restore them, if need be.

```
git checkout main
```

This switches the current branch back to the main branch.

```
git merge urlsession
```

This merges the changes from the "urlsession" branch back into the main branch. If you get an error message at this point, then simply do `git stash` again and repeat the `git merge` command.

By the way, you don't really need to keep those stashed files around, so if you want to remove them from your repository, you can do `git stash drop`. If you stashed twice, you also need to drop twice.

➤ Open the project again in Xcode. Now you're back at the main branch and it also has the latest networking changes.

➤ Build and run to see if everything still works.

Git is a pretty awesome tool, but it takes a while to get familiar with it. Xcode's Git support has improved a lot over the years, but for more complex things you might still need to use the command line — it's well worth learning!


> **Note:** Even though `URLSession` is pretty easy to use and quite capable, many developers prefer to use third-party networking libraries that are often even more convenient and powerful.
>
> One of the most popular native Swift libraries at this point is Alamofire (github.com/Alamofire/Alamofire).
>
> I suggest you check out some of these libraries and see how you like them. Networking is such an important feature of mobile apps that it's worth being familiar with the different possible approaches to send data up and down the 'net.

You can find the project files for this chapter under **36-URLSession** in the Source Code folder.

Chapter 37: The Detail Pop-up

By Fahim Farook

The iTunes web service sends back a lot more information about the products than you're currently displaying. Let's add a "details" screen to the app that pops up when the user taps a row in the table:



The app shows a pop-up when you tap a search result

The table and search bar are still visible in the background, but they have been darkened.

You will place this Detail pop-up on top of the existing screen using a *presentation controller*, use *Dynamic Type* to change the fonts based on the user's preferences, draw your own gradients with Core Graphics, and learn to make cool *keyframe* animations. Fun times ahead!

This chapter will cover the following:

- **The new view controller:** Create the bare minimum necessary for the new Detail pop-up and add the code to show/hide the pop-up.
- **Add the rest of the controls:** Complete the design for the Detail pop-up.
- **Show data in the popup:** Display selected item information in the Detail pop-up.

The new view controller

A new screen means a new view controller, so let's start with that.

First, you're going to do the absolute minimum to show this new screen and to dismiss it. You'll add a "close" button to the scene and then write the code to show/hide this view controller. Once that works, you will put in the rest of the controls.

The basic view controller

➤ Add a new **Cocoa Touch Class** file to the project. Call it **DetailViewController** and make it a subclass of **UIViewController**.

➤ Open the storyboard and drag a new **View Controller** on to the canvas. Change its **Class** to **DetailViewController** — via the **Identity inspector** tab.

➤ For ease of reference, change the new scene's name from **Detail View Controller** to **Detail** by clicking on the yellow circle for the view controller on the Document Outline and clicking again to be able to edit the name.



Editing the scene name to give it a simpler name

➤ Similarly, rename the previously added **Search View Controller** scene to **Search**.

➤ Set the **Background** color of the Detail scene's view to the **ArtistName** color asset. That makes it easier to see what is going on in the next steps. If you recall, this color asset is 50% black in Light mode and 50% white in dark mode.

➤ Drag a new **View** into the scene. Using the **Size inspector**, make it **280** points wide and **280** high. Add Auto Layout constraints for **width=280** and **height=280** to ensure that the view stays at this size.

➤ Center the view in the scene by setting up horizontal and vertical centering Auto Layout constraints.


➤ Open the Asset Catalog and add a new **Color Set** via the + button at the bottom and name it **DetailBG**.

➤ Set the **Any Appearance** color to **white, 95% opaque** via the Color Panel and the Dark Appearance to **black, 95% opaque**.

> **Note:** It's easiest to use the Color Palettes tab of the color panel to select the white and black colors but if you want to enter RGB values, remember that white is red=255, green=255, blue=255 and black is red=0, green=0, blue=0.

➤ Back in the storyboard, for the new view, in the **Attributes inspector**, change the **Background** color to the newly created **DetailBG** color asset. This makes it appear slightly translucent, just like navigation bars.

➤ With this new view still selected, go to the **Identity inspector**. For **Document - Label** — the field with the hint text of "Xcode Specific Label" — type **Pop-up View**. You can use this field to give your views names, so they are easier to distinguish in the Document Outline in Interface Builder. Now, instead of having multiple items called "View", this particular view will display as "Pop-up View" in the Document Outline.



Giving the view a description for use in Xcode

➤ Drag a **Button** into the scene and place it somewhere on the Pop-up View. In the **Attributes** inspector, change **Image** to **xmark.circle.fill** — this is another Symbol Image from Apple's SF Symbols set.


➤ Remove the button's text and place it in the top-right corner of the Pop-up View by adding new Auto Layout constraints for **top = 8** and **right = 8**

➤ If the button's **Type** now says **Custom**, change it back to **System**.

➤ The image should be the dark green you set as the AccentColor. If it isn't, switch to the **File inspector** and change the **Interface Builder Document - Global Tint** to **AccentColor**. Now the button image should show the dark green you selected earlier.

➤ Set the Xcode Specific Label for the Button to **Close Button**. Remember that this only changes the title displayed in the Interface Builder; the user will never see that text.

The design should look something like this (for Dark Appearance):



The initial Detail scene

> **Note:** Xcode currently gives a warning that this new scene is unreachable. This warning will disappear after you make a segue to it, which you'll do in a second.

Show and hide the scene

Let's write the code to show and hide this new screen.

➤ In **DetailViewController.swift**, add the following action method:

```
// MARK: - Actions
@IBAction func close() {
  dismiss(animated: true, completion: nil)
}
```

➤ Connect this action method to the **X** button's Touch Up Inside event in Interface Builder — as before, **Control-drag** from the button to the view controller and pick from **Sent Events**.

➤ Control-drag from the yellow circle at the top of the Search scene to the Detail scene to make a **Present Modally** segue. Give it the identifier **ShowDetail**.

Because the table view doesn't use prototype cells, you have to put the segue on the view controller itself. That means you need to trigger the segue manually when the user taps a row.


➤ Open **SearchViewController.swift** and change `didSelectRowAt` to the following:

```
func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  tableView.deselectRow(at: indexPath, animated: true)
  // Add the following line
  performSegue(withIdentifier: "ShowDetail", sender: indexPath)
}
```

You're sending along the index-path of the selected row as the `sender` parameter. This will come in handy later when you're putting the `SearchResult` object into the Detail pop-up.

Let's see how well this works.

➤ Run the app, do a search, and tap on a search result.



The Detail screen presented modally

The results aren't too bad. But you'll notice that the main results view is now inset a little and that the modal view looks a little strange under the Light appearance because you can't clearly see the edges of the modal view and so it looks as if the background does not reach all the way to the top. It looks more like an accident rather than an intentional presentation style.

For the Dark appearance, the intention is more clear because the white background stands out clearly – especially the rounded corners of the modal view – against the darker background.

There are two possible solutions that immediately spring to mind:

1. Change the background color for the Light appearance so that the modal view is more evident.

   This is the easier option since you'll simply be changing a color value to make the contrast against the background better. But do remember that we are using this particular color asset, ArtistName, elsewhere as well. Of course, we could simply create a new color asset to get around that – so still not a big issue.

2. Change the presentation style of the modal view to make it full screen.

   Modal views can have several different presentation styles. The one you see, where the parent view is slightly inset and the modal view has a card-style appearance, is the default style that you get, at least on an iPhone, when you don't set a specific modal presentation style.

Modal presentation style

With the latest iOS versions, you get multiple styles to present a view modally. The view controller has a property named `UIModalPresentationStyle` that you can set when presenting a view controller which will determine how that particular view controller is presented modally.

While the modal presentation style property has been there since iOS 3.2, the number of available modal presentation styles keeps going up and is now at a whopping 11. We are not going to cover all of the available styles but we'll go over some of the more important/useful ones.

1. `pageSheet` - This is the style that you saw in action when you presented the Detail view in your app. This shows a card-style appearance on iPhone and iPad.
2. `formSheet` - This displays just like `pageSheet` on iPhone but on iPad it displays the detail view centered on the screen instead of showing it card-style.
3. `fullScreen` - This style displays the detail view full screen, covering up the contents of the presenting parent view. Note that this style does not show the underlying parent view's contents if you made your detail/child view have a transparent/semi-transparent background.
4. `overFullScreen` - As the name implies, this again displays the detail view as a full screen view but this time, it shows the underlying view content if the detail view has a transparent/semi-transparent background.
5. `custom` - This style allows you to create your own custom presentation controller and decide how you present the detail view via your custom code.
6. `blurOverFullScreen` - You might see this style listed in the documentation and since it seems to imply that the underlying content is blurred – which it does – that this is a cool effect to have in your app. Unfortunately, this is a style is only available for tvOS – bummer!

There are a few more modal presentation styles but the above cover the most important For our purposes, if we wanted to go full screen, then the one we'd want to use would be `overFullScreen`.


> **Exercise:** How would you set the modal presentation style so that the Detail view is presented with the `overFullScreen` modal presentation style.

Answer: The best place to do this would be via `prepare(for:sender:)` in `SearchViewController` since `SearchViewController` is the presenting view. You simply have to add the following code to **SearchViewController.swift**:

```
override func prepare(for segue: UIStoryboardSegue, sender:
Any?) {
  if segue.identifier == "ShowDetail" {
    segue.destination.modalPresentationStyle = .overFullScreen
  }
}
```

Try it and see. In fact, try out some of the other modal presentation styles as well to see how each one looks and performs. Once you are done, don't forget to remove this code. But setting the presentation style via code is not the only way to go. You can also set the presentation style via storyboard.

➤ Open the storyboard and select the segue from Search to Detail. Switch to the **Attributes inspector** and check out the Presentation dropdown:



The presentation styles in Interface Builder

You can simply set the presentation style to be used by a segue right there. As usual, there's more than one way to do things in iOS :]

One thing to be aware of, while the `overFullScreen` style looks nice, it has one drawback over the `pageSheet` style we got by default – you can't dismiss the modal view except by tapping the close button you added. But with the card-style modal, you can dismiss the modal also by swiping down from the top.

Personally, I prefer the card-style modal. So we'll stick with that.


"But what about the modal view not looking quite right in Light mode?" I hear you asking. Well, we could play around with the colors a bit and get that right.

➤ The semi-transparent white looks good against the darker edges of the background. So, instead of using the color asset which switches colors for each type of appearance, you can simply set the background for the Detail view to **white 50%** by selecting a custom color instead of a color asset.

But that makes the *white 95%* container view look off because now in Light mode, it's white-on-white.

➤ Since we're using a color asset for the Pop-up View and the only issue is the color for Light appearance, simply change the **DetailBG** color for **Any Appearance** (in the asset catalog) to **red=197**, **green=197**, **blue=197**, **opacity=95%**.

Run the app and test under both Light and Dark appearances:



The updated Detail modal


That looks much better, right?

➤ Also verify that both swiping down from the pop-up and the close button work to dismiss the pop-up.

Add the rest of the controls

Let's finish the design of the Detail screen. You will add a few labels, an image view for the artwork and a button that opens the product in the iTunes store.

The finished Detail view will look like this:



The Detail screen with the rest of the controls

In the early days of iOS, to create a view like the above, you would have put in the controls positioned each control manually and then corrected everything as needed.

Then you got Auto Layout and you could specify how far away from the edge of the screen (and from each other) each control had to be. It made things easier, but you still had to set up a lot of constraints.

But then Apple introduced Stack Views.

Using Stack Views

If you look at the above design for the Detail view, you will notice that it is basically a grid. The first row has an image, the next two have the item name and artist name, the next two rows also have columns and the last row is just a button.

The `UIStackView` control is meant for just such layouts. It is a control which, unlike views, is has no drawing component – it's purely a layout component. So, it is lighter on system resources since iOS does not have to draw all the stack views on screen.

This means that using multiple nested stack views to create a complicated grid layout does not impact the system as much as if you'd used nested views to do the same job.

➤ Drag a **Vertical Stack View** on to the pop-up view and pin it to the pop-up view with Auto Layout constraints where **left=16**, **top=16**, **right=16**, and **bottom=16**.

> **Note:** Depending on how you placed the stack view, it is possible that your right constraint might end up pinning the stack view to the close button instead of the pop-up view. Check the Size inspector to make sure that this is not the case and if it is, change the right constraint so that the stack view has 8 points of trailing space to its superview.

➤ In the Attributes inspector, change the stack view's **Alignment** to **Fill** and **Distribution** to **Equal Spacing** – this makes all contents of the stack view fill all the available space horizontally — because this is a vertical stack view — and equally distribute the spacing between each row.

➤ Drag a new **Horizontal Stack View** on to the existing stack view – check the Document Outline to make sure that the horizontal stack view is a child of the previous vertical stack view. This will be the main container for the Type and Genre values since you need a 2 x 2 grid. Name this view **Grid** in the Document Outline.

➤ Change the **Spacing** for the Horizontal Stack View to **8**.

➤ Drag a new **Vertical Stack View** on to the new Grid stack view you just added. Change this one's **Spacing** to **8** as well. This will be the first column in the grid.

We won't add the second column in the grid just yet – I want to show you a different way to do that in a bit :]

➤ Next drag an **Image View** and put it into the main stack view so that it sits above the horizontal stack view. It's probably easiest to drop the Image View on to the Document Outline to make sure that you get the positioning correct.

➤ Pin the Image View using Auto Layout constrains so that **width=100**, **height=100**. (The image might get red markers indicating that there are Auto Layout issues. Don't worry about it for now - we'll be fixing this soon.)

➤ Drag two **Label** controls below the Image View you just added and above the Horizontal Stack View. Tip: Remember that you can duplicate items by Alt/Option+dragging an existing item. This works in both the scene view and in the Document Outline.

➤ Change the **Title** of the first label to **Name** and set its font to **System Bold 20**. Set **Autoshrink** to **Minimum Font Scale** so the font can become smaller if necessary to fit as much text as possible.

➤ Set the **Title** of the second label to **Artist Name**.

➤ Option+drag the **Artist Name** label from the Document Outline into the Vertical Stack View inside the Grid stack view. This adds a label inside the Vertical Stack View.

➤ Repeat the above step to add another **Label** to the Vertical Stack View inside the Grid stack view.

➤ Now Option+drag the whole Vertical Stack View inside the Grid stack view below itself to create a second Vertical Stack View which already has two labels inside.

Yes, you can duplicate a container view including all its children this way! This way, you can build a complex layout much faster by creating one container view and then duplicating it.

➤ Change the **Title** of the two labels in the first Vertical Stack View to **Type:** and **Genre:**.


➤ Change the **Title** of the two labels in the second Vertical Stack View to **Kind Value** and **Genre Value**.

➤ Set the **Color** for the **Type:** and **Genre:** labels to the **ArtistName** asset color.

➤ Finally, drag a **Button** on to the Vertical Stack View where the Button is the last item in the stack – below the two Horizontal Stack Views.

➤ Change the Button's **Style** to **Default**, **Title** to **$9.99** and set the title font to **System Bold 20**.

Your Pop-up View should now look like this:



All of the controls in place

There are some issues:

1. The image is not 100 x 100 but instead stretches from side-to-side.
2. The Kind Value and Genre Value are too far away from their respective labels.
3. The $9.99 button isn't right-aligned.

All the issues are alignment issues of some kind. Each stack view has an alignment setting but we set the main vertical stack view's alignment to Fill when we first created it. Any of the other alignment settings would put some controls in the right position but others would be out of place. Fill is the optimal one to use because it fills the whole area and allows us to position individual items as we want.

> **Exercise:** Can you think of how to fix the alignment issues?

Answer: We simply embed the views that need a different alignment in another stack view and change the alignment on the new stack view.

Confused?

Let's try it out.

➤ Select the **Image View** and click on the **Embed In** button at the bottom of the Interface Builder — it's next to the Auto Layout buttons — and select **Stack View**.

You could also do the same thing by selecting **Editor ▸ Embed In ▸ Stack View** from the Xcode menu.

➤ Select the new stack view and set its **Alignment** to **Center**. Now the image view is centered and shows the correct size.

➤ Select the $9.99 button and embed it in another stack view and this time set the new stack view's **Alignment** to Trailing.

That just leaves the spacing for the Kind Value and Genre Value labels.


It might be helpful to know what the underlying issue here is — when you have multiple items in a stack view and the stack view has its Alignment set to Fill, Auto Layout has to decide how to distribute the controls for each row (or column) so as to fill the entire width (or height). Auto Layout takes the Content Hugging Priority — which is a setting you can see for each control under the Size inspector — for the control into account to figure out the size for the control.

The Content Hugging Priority indicates how reluctant a control is to expand from its default size. The higher the priority, more unlikely a control is to expand from the default size and take up more space than it needs.

➤ Select the **Type:** label and set its **Content Hugging Priority - Horizontal** to **252** in the **Size inspector**.

➤ Do the same for the **Genre:** label — you don't need this as the layout stands now, but it's better to be safe.

Your layout now looks like this:



All of the controls now align

That looks much more like it!


Add the outlets

These new controls are pretty useless without outlet properties, so add the following lines to **DetailViewController.swift**:

```
@IBOutlet weak var popupView: UIView!
@IBOutlet weak var artworkImageView: UIImageView!
@IBOutlet weak var nameLabel: UILabel!
@IBOutlet weak var artistNameLabel: UILabel!
@IBOutlet weak var kindLabel: UILabel!
@IBOutlet weak var genreLabel: UILabel!
@IBOutlet weak var priceButton: UIButton!
```

➤ Connect the outlets to the views in the storyboard. Control-drag from Detail View Controller to each of the views and pick the corresponding outlet. The Type: and Genre: labels and the X button do not get an outlet.

➤ Run the app to see if everything still works.



The new controls in the Detail pop-up

Everything appears to work ... until you try to close the pop-up using the Close button. That doesn't work any longer.

> **Exercise:** Do you have any idea why this might be?

Answer: This is because the Close button is now being covered by the main stack view – the vertical one. While stack views aren't visual components which are drawn on screen, they do handle touch input. This is because each control on screen passes on touch events to its child controls and if the stack view did not handle touches, anything contained by it — such as our $9.99 button — would not react to touch events either.

The fix is simple, move the Close button further up the view hierarchy so that it sits above the stack view. You can do this easily via the Document Outline.

Once you do that, test again to make sure that you can now use the Close button again.

Change the AccentColor

The dark green color looks fine for Light mode, but in Dark mode it just blends in too much with the background. Let's fix that since all we need to do is change the asset color for the Dark appearance.

➤ Select the **AccentColor** in the **Asset Catalog**.

Till now, you've had a single color for the AccentColor since we haven't seen it in action much. But now that the AccentColor is visible on the Detail screen, it's evident that there should be a lighter version in play for Dark mode.

➤ Select the color asset from the central screen – where it says Universal under the color – and in the **Attributes inspector** change **Appearances** to **Any, Dark**.

➤ Now select the **Dark Appearance** variant of the color and change it to **red=60**, **green=130**, **blue=130**.

➤ Save your changes and run the app again to make sure that everything works correctly.

Stretchable images


The $9.99 button would look good with a background image.

When you put a background image on a button in Interface Builder, it always has to fit the button exactly. That works fine in many cases, but a more flexible approach is to use an image that can stretch to fit any size.

And if you say here, "Hey, why don't we use a Symbol Image?", then that's actually a good idea. If you want, you can try that and see how that works out. For some situations, that could be the right solution. But I want to tell you about another option – *stretchable images*.

When an image view is wider than the image, it will automatically stretch the image to fit. In the case of a button, however, you don't want to stretch the ends (or "caps") of the button, only the middle part.

That's what a stretchable image lets you do.




The caps are not stretched but the inner part of the image is

For *Bull's Eye* you used `resizableImage(withCapInsets:)` to cut the images for the slider track into stretchable parts. You can also do this in the asset catalog without having to write any code.

➤ Open the Asset Catalog and add the **PriceButton@2x.png** and **PriceButton@3x.png** images from the **Images** folder from this app's resources. There are other images in that folder but don't add them yet – you'll get to them later.


➤ Select the **PriceButton** image set.



The PriceButton image


If you take a look at the 2x image info, you will see that it is only 22 points wide. That means it has a 10-point cap on the left, a 10-point cap on the right, and a 2-point body that will be stretched out.

Select **Editor ▸ Show Slicing** from the Xcode menu.




The Start Slicing button

Now all you have to do is click **Start Slicing** on each of the two images, followed by the **Slice Horizontally** button:



The Slice Horizontally button

You should end up with something like this for each of the button sizes:



After slicing


Each image is cut into three parts: the caps on the end and an area in the middle that is the stretchable part. Now when you use this image with a button or a `UIImageView`, it will automatically stretch itself to whatever size it needs to be.

Important: Do the above for *both* the 2x image and the 3x image.

➤ Go back to the storyboard. For the $9.99 button, change **Background** to **PriceButton**.

If you see the image repeating, make sure that the button is only 24 points high, the same as the image height.

➤ Run the app and check out that button. Here's a close-up of what it looks like:



The price button with the stretchable background image

The main reason you're using a stretchable image here is that the text on the button may vary in size depending on the price of the item. So, you don't know in advance how big the button needs to be. If your app has a lot of custom buttons, it's worth making their images stretchable. That way you won't have to re-do the images whenever you're tweaking the sizes of the buttons.

The button could still look a little better, though — a black frame around green text doesn't particularly please the eye in Light mode. And in Dark mode, the border completely disappears!

What if we could set the AccentColor for the image, then it would look right for all appearances.

The tint color

The color of the button text comes from the global tint color. `UIImage` makes it very easy to make images appear in the same tint color.

➤ In the asset catalog, select the **PriceButton** again and go to the **Attribute inspector**. Change **Render As** to **Template Image**.

When you set the "template" rendering mode on an image, UIKit removes the original colors from the image and paints the whole thing in the tint color.

That's all you need to do, really, since the global tint color is already set to AccentColor. The background image will be automatically tinted to that color the next time you run the app.

But, there's another tiny issue – the background image is way too close to the price text in the button. Is there perhaps a way to add some space before and after the text?

➤ Select the price button in the storyboard, switch to the **Size inspector** and set **Button - Content Inset** values to **left=10** and **right=10**.

That looks much better, doesn't it?

Rounded corner views

There is one more thing to tweak. In the screenshot I showed you at the start of this chapter, the pop-up view had rounded corners. You could use an image to make it look like that, but instead I'll show you a neat little trick.


`UIViews` do their drawing using what's known as a `CALayer` object. The CA prefix stands for **C**ore **A**nimation, which is the awesome framework that makes animations so easy on the iPhone. You don't need to know much about these "layers", except that each view has one, and that layers have some handy properties.

➤ Add the following line to `viewDidLoad()` in **DetailViewController.swift**:

```
popupView.layer.cornerRadius = 10
```

You ask the Pop-up View for its layer and then set the corner radius of that layer to 10 points. And that's all you need to do!

➤ Run the app. You have your rounded corners:



The pop-up now has rounded corners

Tap gesture recognizer

You have two ways to close the pop-up – the close button and swiping down from the top of the pop-up view. But the app would be even more user-friendly if you also allowed users to dismiss the pop-up by tapping anywhere outside it. The ideal tool for this job is a **gesture recognizer**.

➤ Add a new extension to **DetailViewController.swift**:

```
extension DetailViewController: UIGestureRecognizerDelegate {
  func gestureRecognizer(
    _ gestureRecognizer: UIGestureRecognizer,
    shouldReceive touch: UITouch
  ) -> Bool {
    return (touch.view === self.view)
  }
}
```

You only want to close the Detail screen when the user taps outside the pop-up, i.e. on the background. Any other taps should be ignored. That's what this delegate method is for. It only returns `true` when the touch was on the background view — it will return `false` if the touch was inside the Pop-up View.

Note that you're using the identity operator === to compare `touch.view` with `self.view`. You want to know whether both variables refer to the same object. This is different from using the == equality operator. That would check whether both variables refer to objects that are considered equal, even if they aren't the same object.

Using == here would have worked too, but only because `UIView` treats == and === the same. But not all objects do, so be careful!

➤ Add the following lines to `viewDidLoad()`:

```
let gestureRecognizer = UITapGestureRecognizer(
  target: self,
  action: #selector(close))
gestureRecognizer.cancelsTouchesInView = false
gestureRecognizer.delegate = self
view.addGestureRecognizer(gestureRecognizer)
```

This creates a new gesture recognizer that listens to taps anywhere in this view controller and calls the `close()` method in response.

➤ Try it out. You can now dismiss the pop-up by tapping anywhere outside the pop-up area. That's a common thing that users expect to be able to do, and it was easy enough to add to the app!

Show data in the pop-up

Now that the app can show this pop-up after a tap on a search result, you should put the name, genre and price from the selected product in the pop-up.

> **Exercise:** Try to do this by yourself. It's not very different from what you've done in the previous apps!

There is more than one way to pull this off, but I like to do it by passing the `SearchResult` object to the `DetailViewController`.

Display selected item information in pop-up

➤ Add a property to **DetailViewController.swift** to store the passed in object reference:

```
var searchResult: SearchResult!
```

As usual, this is an implicitly-unwrapped optional because you won't know what its value will be until the segue is performed. It is `nil` in the mean time.

➤ Also add a new method, `updateUI()`:

```
// MARK: - Helper Methods
func updateUI() {
  nameLabel.text = searchResult.name

  if searchResult.artist.isEmpty {
    artistNameLabel.text = "Unknown"
  } else {
    artistNameLabel.text = searchResult.artist
  }

  kindLabel.text = searchResult.type
  genreLabel.text = searchResult.genre
}
```

That looks very similar to what you did in `SearchResultCell`. The logic for setting the text on the labels has its own method, `updateUI()`, because that is cleaner than stuffing everything into `viewDidLoad()`.

➤ Add a call to the new method to the end of `viewDidLoad()`:

```
override func viewDidLoad() {
  . . .
  if searchResult != nil {
    updateUI()
  }
}
```

The `if != nil` check is a defensive measure, just in case the developer forgot to fill in `searchResult` on the segue.

> **Note:** You can also write the above check as `if let _ = searchResult` to unwrap the optional — because you're not actually using the unwrapped value for anything, you use the _ wildcard symbol.


The Detail pop-up is launched with a segue triggered from `SearchViewController`'s `tableView(_:didSelectRowAt:)`. You'll have to add a `prepare(for:sender:)` method to configure the `DetailViewController` when the segue happens.

➤ Add this method to **SearchViewController.swift**:

```
// MARK: - Navigation
override func prepare(for segue: UIStoryboardSegue, sender:
Any?) {
 if segue.identifier == "ShowDetail" {
   let detailViewController = segue.destination as!
DetailViewController
   let indexPath = sender as! IndexPath
   let searchResult = searchResults[indexPath.row]
   detailViewController.searchResult = searchResult
 }
}
```

This should hold no big surprises for you. When `didSelectRowAt` starts the segue, it sends along the index-path of the selected row. That lets you find the `SearchResult` object and pass it on to `DetailViewController`.

➤ Try it out. All right, now you're getting somewhere!



The pop-up with filled-in data

Show the price

You still need to show the price for the item and the correct currency.

➤ Add the following code to the end of `updateUI()` in **DetailViewController.swift**:

```
// Show price
let formatter = NumberFormatter()
formatter.numberStyle = .currency
formatter.currencyCode = searchResult.currency

let priceText: String
```

```
if searchResult.price == 0 {
  priceText = "Free"
} else if let text = formatter.string(
          from: searchResult.price as NSNumber) {
  priceText = text
} else {
  priceText = ""
}

priceButton.setTitle(priceText, for: .normal)
```

You've used `DateFormatter` previously to turn a `Date` object into human-readable text. Here you use `NumberFormatter` to do the same thing for numbers.

Previously, you've turned numbers into text using string interpolation `\(…)` and `String(format:)` with the `%f` or `%d` format specifier. However, in this case you're not dealing with regular numbers but with money in a certain currency.

There are different rules for displaying various currencies, especially if you take the user's language and country settings into consideration. You could program all of these rules yourself — which is a lot of effort — or, choose to ignore them. Fortunately, you don't have to make that tradeoff because you have `NumberFormatter` to do all the heavy lifting for you.

You simply tell the `NumberFormatter` that you want to display a currency value and what the currency code is. That currency code comes from the web service and is something like "USD" or "EUR". `NumberFormatter` will insert the proper symbol, such as $ or € or ¥, and format the monetary amount according to the user's regional settings.

There's one caveat: if you're not feeding `NumberFormatter` an actual number, it cannot do the conversion. That's why `string(from:)` returns an optional that you need to unwrap.

➤ Run the app and see if you can find some good deals :].

Navigate to the product page on iTunes

Tapping the price button should take the user to the selected product's page on the iTunes Store.

➤ Add the following method to **DetailViewController.swift**:

```
@IBAction func openInStore() {
  if let url = URL(string: searchResult.storeURL) {
    UIApplication.shared.open(url, options: [:],
```

```
    completionHandler: nil)
    }
  }
```

➤ Connect the `openInStore` action to the button's Touch Up Inside event in the storyboard.

That's all you have to do. The web service returns a URL for the product page. You simply tell the `UIApplication` object to open this URL. iOS will now figure out what sort of URL it is and launch the proper app in response — iTunes Store, App Store, or Mobile Safari. On the Simulator you'll probably receive an error message that the URL could not be opened — try it on a device instead.

> **Note:** You haven't used `UIApplication` before, but every app has a `UIApplication` object and it handles application-wide functionality. You won't directly use `UIApplication` a lot, except for special features such as opening URLs. Instead, most of the time you deal with `UIApplication` through your `AppDelegate` class, which — as you can guess from its name — is the delegate for `UIApplication`.

Load artwork

For the Detail pop-up, you need to display a slightly larger, more detailed image than the one from the table view cell. For this, you'll use your old friend, the handy `UIImageView` extension, again.

➤ First add a new instance variable to **DetailViewController.swift**. This is necessary to cancel the download task:

```
var downloadTask: URLSessionDownloadTask?
```

➤ Then add the following line to `updateUI()`:

```
// Get image
if let largeURL = URL(string: searchResult.imageLarge) {
  downloadTask = artworkImageView.loadImage(url: largeURL)
}
```

This is the same thing you did in `SearchResultCell`, except that you use the other artwork URL — 100×100 pixels — and no placeholder image.


It's a good idea to cancel the image download if the user closes the pop-up before the image has been downloaded completely.

➤ To do that, add a `deinit` method:

```
deinit {
  print("deinit \(self)")
  downloadTask?.cancel()
}
```

Remember that `deinit` is called whenever the object instance is deallocated and its memory is reclaimed. That happens after the user closes the `DetailViewController` and the animation to remove it from the screen has completed. If the download task is not done by then, you cancel it.

➤ Try it out!



The pop-up now shows the artwork image

Did you see the `print()` from `deinit` after closing the pop-up? It's always a good idea to log a message when you're first trying out a new `deinit` method, to see if it really works. If you don't see that `print()`, it means `deinit` is never called, and you may have an ownership cycle somewhere keeping your object alive longer than intended. This is why you used `[weak self]` in the closure from the `UIImageView` extension, to break any such ownership cycles.

➤ This is a good time to commit the changes.

You can find the project files for this chapter under **37-Detail-popup** in the Source Code folder.

Chapter 38: Polish the Pop-up

By Fahim Farook

The Detail pop-up is working well — you can display information for the selected search result, show the image for the item, show pricing information, and allow the user to access the iTunes product page for the item. You are done with the Detail pop-up and can move on to the next item, right?

Well, not quite ... There are still a few things you can do to make the Detail pop-up more polished and user friendly.


This chapter will cover the following:

- **Dynamic type:** Add support for dynamic type so that your text can display at a size specified by the user.
- **Gradients in the background:** Add a gradient background to make the Detail pop-up background look more polished.
- **Animation!:** Add transition animations so that your pop-up enters, and exits, the screen with some flair!

Dynamic Type

The iOS Settings app has an accessibility option — under **Accessibility ▸ Display & Text Size ▸ Larger Text** — that allows users to choose larger or smaller text. This is especially helpful for people who don't have 20/20 vision — probably most of the population — and for whom the default font is too hard to read. Nobody likes squinting at their device!

You can find this setting both in your device and in the Simulator:




The Larger Text accessibility settings

Apps have to opt-in to use this **Dynamic Type** feature. Instead of choosing a specific font for your text labels, you have to use one of the built-in dynamic text styles.

Configure for Dynamic Type

To provide a better user experience for all users, whether their eyesight is good or bad, you'll change the Detail pop-up to use Dynamic Type for its labels.

➤ Open the storyboard and go to the **Detail** scene. Change the **Font** setting for the **Name** label to the **Headline** text style:



Changing the font to the dynamic Headline style

You can't pick a font size when selecting text styles — the font size depends on the user and the Larger Text setting they use on their device.

➤ Under **Dynamic Type**, check the **Automatically Adjusts Font** checkbox. This ensures that the label's text size will automatically change when the system text size changes without you having to detect the text size change in your code and reload the view to display the label at the new text size.

➤ Set the **Lines** attribute to 0. This allows the Name label to fit more than one line of text.

Of course, if you don't know beforehand how large the label's font will be, you also won't know how large the label itself will end up being, especially if it sometimes may have more than one line of text. Generally, you would have used Auto Layout to set up constraints between the display elements in the pop-up view to handle the changes in layout as the font size changes because Auto Layout and Dynamic Type go hand-in-hand.

However, since you used stack views to set up your layout, most of the spacing and layout issues are automatically handled for you by Stack View and you don't need to go through setting up, testing, and changing your Auto Layout constraints.

➤ Select the **Artist Name** label and set its **Font** to the **Subhead** text style.

➤ Set the **Font** of the other four labels to the **Caption 1** text style. You can do this in a single go if you multiple-select these labels by holding down the ⌘ key.

➤ Check **Automatically Adjusts Font** for all five of the above labels. Again, you can hold down ⌘ to select multiple items — in this particular instance, doing so from the Document Outline is probably the easiest.

Test Dynamic Type

➤ Close the app and open the Settings app. Go to **Accessibility ▸ Display & Text Size ▸ Larger Text**. Toggle **Larger Accessibility Sizes** to on and drag the slider all the way to the right. That gives you the maximum font size — it's huge!


Now go back to StoreSearch and open a new pop-up. The text will be a lot bigger!

For fun, change the font of the Name label to Body. Bazinga, that's some big text!

When you're done playing, put the Name label font back to Headline, and turn off the Larger Text setting — the slider goes in the middle.

Dynamic Type is an important feature to add to your apps. This was only a short introduction, but I hope the principle is clear: instead of a font with a fixed size, you use one of the available Text Styles: Body, Headline, Caption, and so on.

➤ Run the app, change the font size via Settings and see how the pop-up displays at different text sizes:



The pop-up at different text sizes

Well, the word-wrapping seems to work, but at higher text size things get a little squished together and then at the highest text sizes, things go really wrong.


> **Exercise:** How do you think you can fix this layout?

Answer: You set up the pop-up view originally to be 280 x 280 points. It's this size constraint which is forcing the content to get squished together. If you remove the size constraints — either for height or both width *and* height — the content should display much better.

Changing the pop-up view

When you use Auto Layout, the height of a UI element can be determined by the Auto Layout constraints of its child elements.

For example, take the following image which shows all the constraints for the pop-up view we used to have before using stack views:



The height of the pop-up view is determined by the constraints

As you can see, if all the items within the pop-up view had correct Auto Layout constraints set up, then you know the size and position of each of those items. And if you know that, you can add up the sizes and positions of the relevant child items to get the height of the parent, in this case, the pop-up view.

"But we didn't use Auto Layout for the pop-up view!" I hear you say. But we did. Or rather, under the hood, the stack views we added use Auto Layout to position their contents. And if you recall, you did set up Auto Layout constraints of 16 points all around between the topmost stack view and the pop-up view.

So the above principle still applies – iOS can still calculate the height of the pop-up view based on its child views and so we do not really need a height constraint on the pop-up view.

➤ Select **Pop-up View** in the storyboard, go to the **Size inspector** and delete the 280 point height constraint. Now the pop-up view can expand (or contract) as its contents dictates.

But hang on, what would happen if the content was so long/large that the pop-up view's height was larger than the height of the device screen? Then, the view would extend beyond the screen bounds – like this:



The pop-up view is too tall for the screen

That's not a very nice look at all! What if you added top and bottom constraints to limit how much the pop-up view can grow? Also, while you're at it, why don't you also let the pop-up grow horizontally by removing the 280 point width constraint and instead, set up left and right right constraints?

➤ Select **Pop-up View** in the storyboard and remove the 280 point width constraint in the **Size inspector**.

➤ Pin the pop-up view to its parent view so that **left=32**, **top>=16**, **right=32** and **bottom>=16**.

> **Exercise:** Why did you set up the constraints as "greater than or equal to" rather than simply "equal to" for top and bottom?

Answer: Because if you'd set up the constraints as equal to then the pop-up view would be exactly 16 points away from the top and bottom edge of the screen all the time. It wouldn't grow or shrink to fit the content but instead, will always be this huge view covering the rest of the screen.

➤ Run the app and try out your changes at the largest font size.



The pop-up now shows all the content

That at least shows all the content on screen and so that should count as an improvement, right?

Tweaks

You'll notice that the price button looks rather puny amongst all the other items. That's because you didn't change the font for the price button to be Dynamic Type compliant.

It's easy – you follow the same steps as before and change the font to one of the pre-defined styles instead of an actual font. But do note that the price button would also be competing for the available screen space at that point.

Additionally, the price button uses a stretchable image as its background and that button currently only scales horizontally. If you set the price button title to dynamically size, it would change the height of the price button and result in weird drawing issues. You can fix this by changing the stretchable image configuration to stretch the image both horizontally and vertically. I leave this to you as an exercise :]

Did you also note that the Close button has gotten huge. Why do you think that is?

Remember that the Close button uses a Symbol Image, which are scalable and configurable symbols and not images. They scale according to font size settings. One quick fix you can make is to specify how you want the symbol to scale.

➤ Select the **Close button** in the story board and in the Attributes inspector change **Symbol Scale** to **Small**.

The above change will drop the Close button from 25 x 25 to around 18 x 18 at normal size but at really gigantic Dynamic Type settings, it would not be as huge as you have it above.

You now have an automatically resizing Detail pop-up that uses Dynamic Type for its labels!

Feel free to play around with the various settings and see how one change impacts the overall layout of the pop-up view. You'll learn more by experimenting than you would by me telling you to do stuff. So experiment and see how you can make things better for smaller screen devices vs. larger screen devices.

➤ This is a good time to commit the changes.

> **Exercise:** Set up the cells from the table view for Dynamic Type. There's a catch: when the user returns from changing the text size settings, the app should refresh the screen without needing an app restart. You can do this by reloading the table view when the app receives a `UIContentSizeCategoryDidChange` notification — see the previous app for a refresher on how to handle notifications.
>
> Also check out the property `adjustsFontForContentSizeCategory` on `UILabel`. If you set this to `true`, then the app will automatically update the label whenever the font size changes. Good luck! Check the forums at forums.raywenderlich.com for solutions from other readers.

Gradients in the background

As you can see in the previous screenshots, the table view in the background is dimmed by the view of the `DetailViewController`, which is semi-transparent. That allows the pop-up to stand out more.

It works well, but a plain overlay is a bit dull. Let's turn it into a circular gradient instead.

You could use Photoshop to draw such a gradient and place an image view behind the pop-up, but why use an image when you can also draw using Core Graphics? Additionally, an image would increase the size of your app and might also create some issues when you need to support larger screen sizes. Not to mention the fact that you'd have to do two image variants to support both Light and Dark appearances.

To pull this off, you will create your own `UIView` subclass.

The GradientView class

➤ Add a new **Swift File** to the project. Name it **GradientView**.

This will be a very simple view. It simply draws a circular gradient that goes from opaque in the corners to mostly transparent in the center.

➤ Replace the contents of **GradientView.swift** with:

```
import UIKit

class GradientView: UIView {
  override init(frame: CGRect) {
    super.init(frame: frame)
    backgroundColor = UIColor.clear
  }

  required init?(coder aDecoder: NSCoder) {
    super.init(coder: aDecoder)
    backgroundColor = UIColor.clear
  }

  override func draw(_ rect: CGRect) {
    // 1
    let traits = UITraitCollection.current
    let color: CGFloat = traits.userInterfaceStyle == .light ?
0.314 : 1
    // 2
    let components: [CGFloat] = [
      color, color, color, 0.2,
      color, color, color, 0.4,
      color, color, color, 0.6,
      color, color, color, 1
    ]
    let locations: [CGFloat] = [ 0, 0.5, 0.75, 1 ]
    // 3
    let colorSpace = CGColorSpaceCreateDeviceRGB()
    let gradient = CGGradient(
      colorSpace: colorSpace,
      colorComponents: components,
```

```
        locations: locations,
        count: 4)
      // 4
      let x = bounds.midX
      let y = bounds.midY
      let centerPoint = CGPoint(x: x, y: y)
      let radius = max(x, y)
      // 5
      let context = UIGraphicsGetCurrentContext()
      context?.drawRadialGradient(
        gradient!,
        startCenter: centerPoint,
        startRadius: 0,
        endCenter: centerPoint,
        endRadius: radius,
        options: .drawsAfterEndLocation)
    }
  }
```

In the `init(frame:)` and `init?(coder:)` methods you simply set the background color to fully transparent — the "clear" color. Then in `draw()` you draw the gradient on top of that transparent background, so that it blends with whatever is below.

The drawing code uses the Core Graphics framework. It may look a little scary but this is what it does:

1. First, you determine the color to use based on the current appearance. The `UITraitCollection` object allows you to access the current iOS traits such as screen size, appearance etc. If the appearance is Light, you go with a color value which will result in a dark grey gradient and if the appearance is Dark, you with a color value which will give you a white gradient.

2. Next, you create two arrays that define how the gradient will be drawn. A gradient is drawn by using a set of colors and stops/locations. You start at the first location with the first color and draw till you get to the second location and then switch to the second color and draw till you get to the third location etc.

   The first array, `components`, gives you the colors to be used in the gradient and the second array, `locations`, gives you the points along the gradient path where you want the color changes to occur.

   The drawing will start at the center of the screen because you're drawing a circular gradient. Note that all values in these two arrays go from 0 to 1 where the colors — which can go from 0 to 255 — are represented as the actual color value divided by 255.

3. With those color stops you can create the gradient. This gives you a new `CGGradient` object.

4. Now that you have the gradient object, you have to figure out how big you need to draw it. The `midX` and `midY` properties return the center point of a rectangle. That rectangle is given by `bounds`, a `CGRect` object that describes the dimensions of the view.

   If I can avoid it, I prefer not to hard-code any dimensions such as "375 by 667 points". By using `bounds`, you can use this view anywhere you want to, no matter how big a space it should fill. You can use it without problems on any screen size from the smallest iPhone to the biggest iPad.

   The `centerPoint` constant contains the coordinates for the center point of the view and `radius` contains the larger of the `x` and `y` values; `max()` is a handy function that you can use to determine which of two values is the biggest.

5. With all those preliminaries done, you can finally draw the thing. Core Graphics drawing always takes places in what's known as a *graphics context*. We're not going to worry about exactly what that is, just know that you need to obtain a reference to the current context and then you can do your drawing.

   And finally, the `drawRadialGradient()` function draws the gradient according to your specifications.

Generally speaking, it isn't optimal to create new objects inside your `draw()` method, such as gradients, especially if `draw()` is called often. In such cases it is better to create the objects the first time you need them and to reuse the same instance over and over — lazy loading for the win!

However, you don't really have to do that here because this `draw()` method will be called just once — when the `DetailViewController` gets loaded — so you can get away with being less than optimal.

> **Note:** By the way, you'll only be using `init(frame:)` to create the `GradientView` instance. The other init method, `init?(coder:)`, is never used in this app. However, `UIView` demands that all subclasses implement `init?(coder:)` — that's why it is marked as `required` — and if you remove this method, Xcode will complain with an error.

Use GradientView

Putting this new `GradientView` class to work is pretty easy. You'll add it to your `DetailViewController`. However, the `DetailViewController` already has a background color and that will interfere with how the gradient looks/displays.


We could simply change the current background color to transparent in the storyboard but instead, we'll do that in code as well.

➤ Open **DetailViewController.swift** and add the following code to the end of `viewDidLoad`:

```
// Gradient view
view.backgroundColor = UIColor.clear
let dimmingView = GradientView(frame: CGRect.zero)
dimmingView.frame = view.bounds
view.insertSubview(dimmingView, at: 0)
```

The first line sets the `DetailViewController` background to be clear. Then you create a new instance of `GradientView`, set its size to match that of `DetailViewController`, and finally add the new gradient view to the `DetailViewController` view hierarchy.

➤ Run the app and see what happens.



The background behind the pop-up now has a gradient

Nice! That looks a lot smarter.

Animation!

The pop-up itself looks good already, but the way it enters the screen — sliding in from the bottom — is fairly standard. Let's jazz things up a bit!

You've used Core Animation and UIView animations before. This time you'll use a **keyframe animation** to make the pop-up bounce into view.

To animate the transition between two screens, you use an animation controller object. The purpose of this object is to animate a screen while it's being presented or dismissed, nothing more.

Now let's add some liveliness to this pop-up!

The animation controller class

➤ Add a new **Swift File** to the project, named **BounceAnimationController**.

➤ Replace the contents of the new file with:

```
import UIKit

class BounceAnimationController: NSObject,
UIViewControllerAnimatedTransitioning {
  func transitionDuration(
    using transitionContext:
UIViewControllerContextTransitioning?
  ) -> TimeInterval {
    return 0.4
  }

  func animateTransition(
    using transitionContext:
UIViewControllerContextTransitioning
  ) {
    if let toViewController = transitionContext.viewController(
      forKey: UITransitionContextViewControllerKey.to),
      let toView = transitionContext.view(
        forKey: UITransitionContextViewKey.to) {
      let containerView = transitionContext.containerView
      toView.frame = transitionContext.finalFrame(
        for: toViewController)
      containerView.addSubview(toView)
      toView.transform = CGAffineTransform(scaleX: 0.7, y: 0.7)

      UIView.animateKeyframes(
        withDuration: transitionDuration(
          using: transitionContext),
```

```
          delay: 0,
          options: .calculationModeCubic,
          animations: {
            UIView.addKeyframe(
              withRelativeStartTime: 0.0,
              relativeDuration: 0.334) {
                toView.transform = CGAffineTransform(
                  scaleX: 1.2, y: 1.2)
            }
            UIView.addKeyframe(
              withRelativeStartTime: 0.334,
              relativeDuration: 0.333) {
                toView.transform = CGAffineTransform(
                  scaleX: 0.9, y: 0.9)
            }
            UIView.addKeyframe(
              withRelativeStartTime: 0.666,
              relativeDuration: 0.333) {
                toView.transform = CGAffineTransform(
                  scaleX: 1.0, y: 1.0)
            }
          }, completion: { finished in
            transitionContext.completeTransition(finished)
          })
      }
    }
  }
```

To become an animation controller, the object needs to extend `NSObject` and also implement the `UIViewControllerAnimatedTransitioning` protocol — quite a mouthful! The important methods from this protocol are:

- `transitionDuration(using:)` – This determines how long the animation is. You're making the pop-in animation last for only 0.4 seconds, but that's long enough. Animations are fun, but they shouldn't keep the user waiting.
- `animateTransition(using:)` – This performs the actual animation.

To find out what to animate, you look at the `transitionContext` parameter. This gives you a reference to a new view controller and lets you know how big it should be.

The actual animation starts at the line `UIView.animateKeyframes(…)`. This works like all UIView-based animations: you set the initial state before the animation block, and UIKit will automatically animate any properties that get changed inside the closure. The difference from before is that a keyframe animation lets you animate the view in several distinct stages.

The property you're animating is the `transform`. If you've ever taken any matrix math you'll be pleased — or terrified! — to hear that this is an affine transformation matrix. It allows you to do all sorts of funky stuff with the view, such as rotating it or shearing it. But the most common use of the transform is for scaling.

The animation consists of several **keyframes**. It will smoothly proceed from one keyframe to the next over a certain amount of time. Because you're animating the view's scale, the different `toView.transform` values represent how much bigger or smaller the view will be over time.

The animation starts with the view scaled down to 70% (scale 0.7). The next keyframe inflates it to 120% of its normal size. After that, it will scale the view down a bit again but not as much as before — only 90% of its original size. The final keyframe ends up with a scale of 1.0, which restores the view to an undistorted shape.

By quickly changing the view size from small to big to small to normal, you create a bounce effect.

You also specify the duration between the successive keyframes. In this case, each transition from one keyframe to the next takes 1/3rd of the total animation time. These times are not in seconds but in fractions of the animation's total duration, which is 0.4 seconds.

Do tinker with the animation code. I'm sure you can make it even more spectacular!

Use the new animation controller

To use this animation in your app, you have to tell the app to use the new animation controller when presenting the Detail pop-up.

➤ In **DetailViewController.swift**, add the following extension to the end of the file:

```
extension DetailViewController:
UIViewControllerTransitioningDelegate {
  func animationController(
    forPresented presented: UIViewController,
    presenting: UIViewController,
    source: UIViewController
  ) -> UIViewControllerAnimatedTransitioning? {
    return BounceAnimationController()
  }
}
```

The methods from this delegate protocol tell UIKit what objects it should use to perform the transition to the Detail View Controller. It will now use your new `BounceAnimationController` class for the presentation animation instead of whatever it uses by default.

➤ Also add the following init method to `DetailViewController`:

```
required init?(coder aDecoder: NSCoder) {
  super.init(coder: aDecoder)
  transitioningDelegate = self
}
```

Recall that `init?(coder)` is invoked to load the view controller from the storyboard. Here you set the transitioning delegate so that the method you just implemented is called when an animation controller is needed.

And that's all you need to do.

➤ Run the app and get ready for some bouncing action!

The pop-up looks a lot spiffier with the bounce animation, but the animation upon dismissal of the pop-up is very plain.

Animate the pop-up exit

After tapping the Close button, the pop-up slides off the screen, like modal screens always do. Let's make this a bit more exciting and make it slide up instead of down. For that you need another animation controller.

➤ Add a new **Swift File** to the project, named **SlideOutAnimationController**.

➤ Replace the new file's contents with:

```
import UIKit

class SlideOutAnimationController: NSObject,
UIViewControllerAnimatedTransitioning {
  func transitionDuration(
    using transitionContext:
UIViewControllerContextTransitioning?
  ) -> TimeInterval {
    return 0.3
  }

  func animateTransition(
    using transitionContext:
UIViewControllerContextTransitioning
```

```
    ) {
      if let fromView = transitionContext.view(
        forKey: UITransitionContextViewKey.from) {
        let containerView = transitionContext.containerView
        let time = transitionDuration(using: transitionContext)
        UIView.animate(
          withDuration: time,
          animations: {
          fromView.center.y -= containerView.bounds.size.height
          fromView.transform = CGAffineTransform(
            scaleX: 0.5, y: 0.5)
          }, completion: { finished in
          transitionContext.completeTransition(finished)
          }
        )
      }
    }
  }
```

This is pretty much the same as the other animation controller, except that the animation itself is different. Inside the animation block you subtract the height of the screen from the view's center position while simultaneously zooming it out to 50% of its original size, making the Detail screen fly up-up-and-away.

➤ In **DetailViewController.swift**, add the following method to the `UIViewControllerTransitioningDelegate` extension:

```
  func animationController(
    forDismissed dismissed: UIViewController
  ) -> UIViewControllerAnimatedTransitioning? {
    return SlideOutAnimationController()
  }
```

This simply overrides the animation controller that is used when a view controller is dismissed.

➤ Run the app and try it out. That looks pretty sweet if you ask me!

➤ If you're happy with the way the animations look, then commit your changes.


Exercise: Create some exciting new animations. I'm sure you can improve on mine. Hint: use the `transform` matrix to add some rotation to the mix.

You can find the project files for this chapter under **38-Polish-the-popup** in the Source Code folder.

Chapter 39: Landscape

By Fahim Farook

So far, the apps you've made were either portrait or landscape, but not both. Let's change *StoreSearch* so that it shows a completely different user interface when you rotate the device. When you're done, the app will look like this:



The app looks completely different in landscape orientation

The landscape screen shows just the artwork for the search results. Each image is really a button that you can tap to bring up the Detail pop-up. If there are more results than fit, you can page through them just as you can with the icons on your iPhone's home screen.

You'll cover the following in this chapter:

- **The landscape view controller:** Create a basic landscape view controller to make sure that the functionality works.
- **Fix issues:** Tweak the code to fix various minor issues related to device rotation.
- **Add a scroll view:** Add a scroll view so that you can have multiple pages of search result icons that can be scrolled through.

- **Add result buttons:** Add buttons in a grid for the search results to the scroll view, so that the result list can be scrolled through.
- **Paging:** Configure scrolling through results page-by-page rather than as a single scrolling list.
- **Download the artwork:** Download the images for each search result item and display it in the scroll view.

The landscape view controller

Let's begin by creating a very simple view controller that shows just a text label.


The storyboard

➤ Add a new file to the project using the **Cocoa Touch Class** template. Name it **LandscapeViewController** and make it a subclass of **UIViewController**.

➤ In Interface Builder, with **Main** storyboard open, drag a new **View Controller** on to the canvas.

➤ In the Document Outline, click on the yellow circle for the view controller and change it's name to **Landscape**.

➤ In the Identity inspector, change the **Class** to **LandscapeViewController**. Also type this into the **Storyboard ID** field.



Giving the view controller an ID

There will be no segue to this view controller. Instead, you'll instantiate this view controller programmatically when you detect a device rotation. For that, it needs to have an ID so you can uniquely identify this particular view controller in the storyboard.


➤ Use the **Orientation** button on the toolbar at the bottom of Interface Builder to switch to landscape mode.

This flips *all* the scenes in the storyboard to landscape, but that is OK — it doesn't change what happens when you run the app. Putting Interface Builder in landscape mode is just a design aid that makes it easier to lay out your UI. What actually happens when you run the app depends on the orientation the user holds the device in. The trick is to use Auto Layout constraints to make sure that the view controllers properly resize to landscape or portrait at runtime.

➤ Drag a new **Label** into the scene and give it some text. You're just using this label to verify that the new view controller shows up in the correct orientation.

➤ Use the **Align** Auto Layout menu to center the label horizontally and vertically.

Your design should look something like this:



Initial design for the Landscape scene

Show the landscape view on device rotation

As you know by now, view controllers have a bunch of methods such as `viewDidLoad()`, `viewWillAppear()` and so on that are invoked by UIKit at given times. There is also a method that is invoked when the device is rotated. You can override this method to show (and hide) the new `LandscapeViewController`.

➤ Add the following method to **SearchViewController.swift**:

```
override func willTransition(
  to newCollection: UITraitCollection,
  with coordinator: UIViewControllerTransitionCoordinator
```

```
  ) {
    super.willTransition(to: newCollection, with: coordinator)

    switch newCollection.verticalSizeClass {
    case .compact:
      showLandscape(with: coordinator)
    case .regular, .unspecified:
      hideLandscape(with: coordinator)
    @unknown default:
      break
    }
  }
```

This method isn't just invoked on device rotations, but any time the *trait collection* for the view controller changes. You've seen trait collections used before in the previous chapter to detect the current appearance. But let's learn a bit more about it.

So what is a trait collection? It is, um, a collection of *traits*, where a trait can be:


- The horizontal size class
- The vertical size class
- The display scale — is this a Retina screen or not?
- The user interface idiom — is this an iPhone or iPad?
- The preferred Dynamic Type font size
- The appearance — is it Light or Dark?
- And a few other things

Whenever one or more of these traits change, for whatever reason, UIKit calls `willTransition(to:with:)` to give the view controller a chance to adapt to the new traits.

What we are interested in here are the *size classes*. This feature allows you to design a user interface that is independent of the device's actual dimensions or orientation. With size classes, you can create a single storyboard that works across all devices, from iPhone to iPad — a "universal storyboard".

So how exactly do these size classes work? Well, there's two of them, a horizontal one and a vertical one, and each can have two values: *compact* or *regular*.

The combination of these four things creates the following possibilities:



Horizontal and vertical size classes

When an iPhone app is in portrait orientation, the horizontal size class is *compact* and the vertical size class is *regular*.

Upon a rotation to landscape, the vertical size class changes to *compact*.

What you may not have expected is that the horizontal size class doesn't change and stays *compact* in both portrait and landscape orientations — except on a growing list of iPhone models such as the Plus, Xr, Max etc. that is.

In landscape, the horizontal size class on these non-consistent iPhones is *regular*. That's because the larger dimensions of these devices can fit a split screen in landscape mode, like the iPad — something you'll see later on.

What this boils down to is, to detect an iPhone rotation you just have to look at how the vertical size class changed. That's exactly what the `switch` statement does:

```
switch newCollection.verticalSizeClass {
case .compact:
  showLandscape(with: coordinator)
case .regular, .unspecified:
  hideLandscape(with: coordinator)
@unknown default:
  break
}
```

If the new vertical size class is `.compact` the device got flipped to landscape and you show the `LandscapeViewController`. But if the new size class is `.regular`, the app is back in portrait and you hide the landscape view again.

The reason the second `case` statement also checks `.unspecified` is because `switch` statements must always be exhaustive and have cases for all possible values. `.unspecified` shouldn't happen, but just in case it does, you also hide the landscape view. This is another example of defensive programming.

And the third `case` for `@unknown default` is another example of defensive programming. While the current `case` statements cover all the possible values, it's possible that in future there might be additional values for vertical sizes. So you guard for that. Try commenting out the code and you'll see that Xcode prompts you to add this particular safeguard.

Just to keep things readable, the actual showing and hiding happens in methods of their own. You will add these next.

In the early years of iOS, it was tricky to put more than one view controller on the same screen. The motto used to be: one screen, one view controller. However, when devices with larger screens became available, that became inconvenient — you often want one area of the screen to be controlled by one view controller and a second area by a separate view controller. So now, view controllers are allowed to be part of other view controllers if you follow a few rules.

This is called *view controller containment*. These APIs are not limited to just the iPad; you can take advantage of them on the iPhone as well. These days a view controller is no longer expected to manage a screenful of content, but manages a "self-contained presentation unit", whatever that may be for your app.

You're going to use view controller containment for the `LandscapeViewController`.

It would be eminently possible to make a modal segue to this scene and present it with your own custom animations. But you've already done that and it's more fun to play with something new. Besides, it's useful to learn about containment and child view controllers.

➤ Add an instance variable to **SearchViewController.swift**:

```
var landscapeVC: LandscapeViewController?
```

This is an optional because there will only be an active `LandscapeViewController` instance if the phone is in landscape orientation. In portrait orientation this will be `nil`.

➤ Add the following helper method:

```
func showLandscape(with coordinator:
UIViewControllerTransitionCoordinator) {
  // 1
  guard landscapeVC == nil else { return }
  // 2
  landscapeVC = storyboard!.instantiateViewController(
    withIdentifier: "LandscapeViewController") as?
LandscapeViewController
  if let controller = landscapeVC {
    // 3
    controller.view.frame = view.bounds
    // 4
    view.addSubview(controller.view)
    addChild(controller)
    controller.didMove(toParent: self)
  }
}
```

In previous apps you called `present(animated:completion:)` or made a segue to show a new modal screen. Here, however, you add the new `LandscapeViewController` as a *child* view controller of `SearchViewController`.

Here's how it works, step-by-step:

1. It should never happen that the app instantiates a second landscape view when you're already looking at one. The `guard` statement codifies this requirement. If it should happen that `landscapeVC` is not `nil`, then you're already showing the landscape view and you simply `return` right away.

2. Find the scene with the ID "LandscapeViewController" in the storyboard and instantiate it. Because you don't have a segue, you need to instantiate the view controller manually. This is why you set the Storyboard ID in the Identity inspector.

   The `landscapeVC` instance variable is an optional, so you need to unwrap it before you can continue.

3. Set the size and position of the new view controller. This makes the landscape view just as big as the `SearchViewController`, covering the entire screen.

   The `frame` is the rectangle that describes the view's position and size in terms of its superview. To move a view to its final position and size you usually set its `frame`. The `bounds` is also a rectangle but seen from inside the view.

   Because `SearchViewController`'s view is the superview here, the `frame` of the landscape view must be made equal to the `SearchViewController`'s `bounds`.

4. These are the minimum required steps to add the contents of one view controller to another, in this order:

   a. Add the landscape controller's view as a subview. This places it on top of the table view, search bar and segmented control.

   b. Tell the `SearchViewController` that the `LandscapeViewController` is now managing that part of the screen, using `addChild()`. If you forget this step, then the new view controller may not always work correctly.

   c. Tell the new view controller that it now has a parent view controller with `didMove(toParent:)`.

   In this new arrangement, `SearchViewController` is the "parent" view controller, and `LandscapeViewController` is the "child". In other words, the Landscape screen is embedded inside the `SearchViewController`.


> **Note:** Even though it will appear on top of everything else, the Landscape screen is not presented modally. It is "contained" in its parent view controller, and therefore owned and managed by the parent — it isn't independent like a modal screen. This is an important distinction.
>
> View controller containment is also used for navigation and tab bar controllers where the `UINavigationController` and `UITabBarController` "wrap around" their child view controllers.
>
> Usually, when you want to show a view controller that takes over the whole screen, you'd use a modal segue. But when you want just a portion of the screen to be managed by its own view controller, you'd make it a child view controller.
>
> One of the reasons you're not using a modal segue for the Landscape screen in this app, even though it is a full-screen view controller, is that the Detail pop-up already is modally presented and this could potentially cause conflicts. Besides, I wanted to show you a fun alternative to modal segues.

➤ To get the app to compile, add an empty implementation of the "hide" method:

```
func hideLandscape(with coordinator:
UIViewControllerTransitionCoordinator) {
}
```

By the way, the transition coordinator parameter is needed for doing animations, which you'll add soon.

➤ Try it out! Run the app, do a search and rotate your iPhone or the Simulator to landscape — don't forget to test out for both Light and Dark appearances.



The Simulator after flipping to landscape

Remember: to rotate the Simulator, press ⌘ and the left (or right) arrow keys. Or, you can use the rotate simulator button on the toolbar above the simulator. It's possible that the Simulator won't flip over right away — it can be buggy like that. If that happens, press ⌘+**arrow key** a few more times.

This is not doing any animation just yet. As always, first get it to work right, and *then* make it look pretty.

If you don't do a search first before rotating to landscape, the keyboard may remain visible. You'll fix that shortly. In the mean time you can press ⌘+**K** (on the Simulator only) to hide the keyboard manually.

Switch back to the portrait view

Switching back to portrait doesn't work yet, but that's easily fixed.

➤ Replace the *method stub*, which is basically a method name with no implementation code, that you added earlier with the following implementation to hide the landscape view controller:

```
func hideLandscape(with coordinator:
UIViewControllerTransitionCoordinator) {
  if let controller = landscapeVC {
    controller.willMove(toParent: nil)
    controller.view.removeFromSuperview()
    controller.removeFromParent()
    landscapeVC = nil
  }
}
```

This is essentially the reverse of what you did to embed the landscape view controller.

First, you call `willMove(toParent:)` to tell the view controller that it is leaving the view controller hierarchy and it no longer has a parent. Then, you remove its view from the screen, and finally, `removeFromParent()` truly disposes of the view controller.

You also set the instance variable to `nil` in order to remove the last strong reference to the `LandscapeViewController` object now that you're done with it.

➤ Run the app. Switching back to portrait should remove the black landscape view.

> **Note:** If you press **⌘-right** (or **⌘-left**) twice, the Simulator first rotates to landscape and then to portrait, but the `LandscapeViewController` does not disappear. Why is that?
>
> It's might not be immediately evident, but what you're looking at now is *not* portrait but portrait upside down. This orientation is not recognized by the app — see the Device Orientation setting under Deployment Info in the project settings — and therefore the app keeps thinking it's in landscape.
>
> Press **⌘-right** (or **⌘-left**) twice again and you're back in regular portrait.

Animate the transition to landscape

The transition to the landscape view is a bit abrupt. I don't want to go overboard with animations here as the screen is already doing a rotating animation. A simple crossfade will be sufficient.

➤ Change the `showLandscape(with:)` method in **SearchViewController.swift** as follows:

```
func showLandscape(with coordinator:
UIViewControllerTransitionCoordinator) {
  . . .
  if let controller = landscapeVC {
    controller.view.frame = view.bounds
    controller.view.alpha = 0           // New line

    view.addSubview(controller.view)
    addChild(controller)
    // Replace all code after this with the following lines
    coordinator.animate(
```

```
        alongsideTransition: { _ in
          controller.view.alpha = 1
        }, completion: { _ in
          controller.didMove(toParent: self)
        })
    }
  }
```

You're still doing the same things as before, except now, the landscape view starts out completely transparent — `alpha` = 0 — and slowly fades in while the rotation takes place until it's fully visible — `alpha` = 1.

Now you see why the `UIViewControllerTransitionCoordinator` object is needed — so your animation can be performed alongside the rest of the transition from the old traits to the new. This ensures the animations run as smoothly as possible.

The call to `animate(alongsideTransition:completion:)` takes two closures: the first is for the animation itself, the second is a "completion handler" that gets called after the animation finishes. The completion handler gives you a chance to delay the call to `didMove(toParent:)` until the animation is over.

Both closures are given a "transition coordinator context" parameter (the same context that animation controllers get) but you don't use it here and so, you use the _ wildcard to ignore it.

Animate the transition from landscape

➤ Make similar changes to `hideLandscape(with:)`:

```
  func hideLandscape(with coordinator:
  UIViewControllerTransitionCoordinator) {
    if let controller = landscapeVC {
      controller.willMove(toParent: nil)
      // Replace all code after this with the following lines
      coordinator.animate(
        alongsideTransition: { _ in
          controller.view.alpha = 0
        }, completion: { _ in
          controller.view.removeFromSuperview()
          controller.removeFromParent()
          self.landscapeVC = nil
        })
    }
  }
```

This time you fade out the view. You don't remove the view and the controller until the animation is completely done.

➤ Try it out. The transition between the portrait and landscape views should be a lot smoother now.

Tip: To see the transition animation in slow motion, select **Debug ▸ Slow Animations** from the Simulator menu.


> **Note:** The order of operations for removing a child view controller is exactly the reverse of adding a child view controller, except for the calls to `willMove` and `didMove(toParent:)`.
>
> The rules for view controller containment say that when adding a child view controller, the last step is to call `didMove(toParent:)`. UIKit does not know when to call this method, as that needs to happen after any of your animations. You are responsible for sending the "did move to parent" message to the child view controller once the animation completes.
>
> There is also a `willMove(toParent:)` but that gets called on your behalf by `addChild()` already, so you're not supposed to do that yourself.
>
> The rules are opposite when removing the child controller. First you should call `willMove(toParent: nil)` to let the child view controller know that it's about to be removed from its parent. The child view controller shouldn't actually be removed until the animation completes, at which point you call `removeFromParent()`. That method will then take care of sending the "did move to parent" message.
>
> You can find these rules in the API documentation for `UIViewController`.

Fix issues

There are two more small tweaks that you need to make.

Hide the keyboard

Maybe you already noticed that when rotating the app while the keyboard is showing, the keyboard doesn't go away.



The keyboard is still showing in landscape mode

> **Exercise:** See if you can fix this yourself.

Answer: You've done something similar already after the user taps the Search button. The code is exactly the same here.

➤ Add the following line to `showLandscape(with:)`:

```
func showLandscape(with coordinator:
UIViewControllerTransitionCoordinator) {
    . . .
    coordinator.animate(alongsideTransition: { _ in
      controller.view.alpha = 1
      self.searchBar.resignFirstResponder()    // Add this line
    }, completion: { _ in
      . . .
    })
  }
}
```

Now the keyboard disappears as soon as you rotate the device. I found it looks best if you call `resignFirstResponder()` inside the animate-alongside-transition closure. After all, hiding the keyboard also happens with an animation.

Hide the Detail pop-up

Speaking of things that stay visible, what happens when you tap a row in the table view and then rotate to landscape? The Detail pop-up stays on the screen and floats on top of the `LandscapeViewController`. I find that a little strange. It would be better if the app dismissed the pop-up before rotating.

> **Exercise:** See if you can fix that one.

The Detail pop-up is presented modally via a segue, so you can call `dismiss(animated:completion:)` to dismiss it, just like you do in the `close()` action method.

There's a complication though: you should only dismiss the Detail screen when it is actually visible. For that, you can look at the `presentedViewController` property. This returns a reference to the current modal view controller, if any. If `presentedViewController` is `nil` there isn't anything to dismiss.

➤ Add the following code to the end of the `animate(alongsideTransition:)` closure in `showLandscape(with:)`:

```
if self.presentedViewController != nil {
  self.dismiss(animated: true, completion: nil)
}
```

➤ Run the app and tap on a search result, then rotate to landscape. The pop-up should now fly off the screen. When you return to portrait, the pop-up is nowhere to be seen.

Tweak the animation

The Detail pop-up flying up and out the screen looks a little weird in combination with the rotation animation. There's too much happening on the screen at once for my taste. Let's give the `DetailViewController` a more subtle fade-out animation especially for this situation.

When you tap the X button to dismiss the pop-up, you'll still make it fly out of the screen. But when it is automatically dismissed upon rotation, the pop-up will fade out with the rest of the table view instead.

You'll give `DetailViewController` a property that that specifies how it will animate the pop-up's dismissal. You can use an `enum` for this.

➤ Add the following to **DetailViewController.swift**, *inside* the class:

```
enum AnimationStyle {
  case slide
  case fade
}

var dismissStyle = AnimationStyle.fade
```

This defines a new `enum` named `AnimationStyle`. An enum, or enumeration, is simply a list of possible values. The `AnimationStyle` enum has two values, `slide` and `fade`. Those are the animations the Detail pop-up can perform when dismissed.

The `dismissStyle` variable determines which animation is chosen. This variable is of type `AnimationStyle`, so it can only contain one of the values from that enum. By default it is `.fade`, the animation that will be used when rotating to landscape.

> **Note:** The full name of the enum is `DetailViewController.AnimationStyle` because it sits inside the `DetailViewController` class.
>
> It's a good idea to keep the things that are closely related to a particular class, such as this enum, inside the definition for that class. That puts them inside the class's *namespace*.
>
> Doing this allows you to also add a completely different `AnimationStyle` enum to one of the other view controllers, without running into naming conflicts.

➤ In the `close()` method, set the animation style to `.slide`, so that it keeps using the animation you're already familiar with:

```
@IBAction func close() {
  dismissStyle = .slide                    // Add this line
  dismiss(animated: true, completion: nil)
}
```

➤ Add a new **Swift File** to the project, named **FadeOutAnimationController**. This will handle the animation for the `.fade` style.

➤ Replace the source code of this new file with:

```
import UIKit

class FadeOutAnimationController: NSObject,
  UIViewControllerAnimatedTransitioning {
```

```
  func transitionDuration(
    using transitionContext:
UIViewControllerContextTransitioning?
  ) -> TimeInterval {
    return 0.4
  }

  func animateTransition(
    using transitionContext:
UIViewControllerContextTransitioning
  ) {
    if let fromView = transitionContext.view(
      forKey: UITransitionContextViewKey.from) {
      let time = transitionDuration(using: transitionContext)
      UIView.animate(
        withDuration: time,
        animations: {
          fromView.alpha = 0
        }, completion: { finished in
          transitionContext.completeTransition(finished)
        }
      )
    }
  }
}
```

This is mostly the same as the other animation controllers. The actual animation simply sets the view's `alpha` value to 0 in order to fade it out.

➤ Switch to **DetailViewController.swift** and in the extension for the transitioning delegate, change the method that returns the animation controller for dismissing the pop-up to the following:

```
func animationController(
  forDismissed dismissed: UIViewController
) -> UIViewControllerAnimatedTransitioning? {
  switch dismissStyle {
  case .slide:
    return SlideOutAnimationController()
  case .fade:
    return FadeOutAnimationController()
  }
}
```

Instead of always returning a new `SlideOutAnimationController` instance, it now looks at the value from `dismissStyle`. If it is `.fade`, then it returns an instance of the new `FadeOutAnimationController` object.

➤ Run the app, bring up the Detail pop-up and rotate to landscape. The pop-up should now fade out while the landscape view fades in — enable slow animations to clearly see what is going on.

And that does it. If you want to create more animations that can be used on dismissal, you only have to add a new value to the `AnimationStyle` enum and check for it in the `animationController(forDismissed:)` method. And build a new animation controller, of course.

That concludes the first version of the landscape screen. It doesn't do much yet, but it's already well integrated with the rest of the app. That's worthy of a commit, methinks.

Add a scroll view

If an app has more content to show than can fit on the screen, you can use a *scroll view*, which allows the user to, as the name implies, scroll through the content horizontally and/or vertically.

You've already been working with scroll views all this time without knowing it: the `UITableView` object extends from `UIScrollView`.

In this section, you'll use a scroll view of your own, in combination with a *paging control*, to show the artwork for all the search results, even if there are more images than can fit on the screen at once.

Add the scrollview to the storyboard


➤ Open the storyboard and delete the label from the Landscape scene.

➤ Now, drag a **Scroll View** into the scene and set it to completely cover the screen — 667 x 375 if you're using the iPhone SE (2nd generation) layout.

➤ Drag a new **Page Control** object into the scene — make sure you pick Page Control and *not* Page View Controller.

This gives you a small view with three white dots. Place it bottom center. The exact location doesn't matter because you'll move it to the right position later.


Important: Do not place the Page Control *inside* the Scroll View. They should be at the same level in the view hierarchy:



The Page Control should be a "sibling" of the Scroll View, not a child

If you did drop your Page Control inside the Scroll View instead of on top, then you can rearrange it in the Document Outline.

That's it for the design of the Landscape scene. The rest you will do in code.



The final design of the Landscape scene - Dark appearance

Disable Auto Layout for a view controller

The other view controllers you've created all employed Auto Layout to resize them to the dimensions of the user's screen, but here, you're going to take a different approach. Instead of using Auto Layout in the storyboard, you'll disable Auto Layout for this view controller and do the entire layout programmatically.

You do need to hook up the controls to outlets, of course.

➤ Add these outlets to **LandscapeViewController.swift**, and connect them in Interface Builder:

```
@IBOutlet weak var scrollView: UIScrollView!
@IBOutlet weak var pageControl: UIPageControl!
```

Next up you'll disable Auto Layout for this view controller. The storyboard has a "Use Auto Layout" checkbox but you cannot use that. It would turn off Auto Layout for all the view controllers, not just this one.

➤ Replace **LandscapeViewController.swift**'s `viewDidLoad()` with:

```
override func viewDidLoad() {
  super.viewDidLoad()
  // Remove constraints from main view
  view.removeConstraints(view.constraints)
  view.translatesAutoresizingMaskIntoConstraints = true
  // Remove constraints for page control
  pageControl.removeConstraints(pageControl.constraints)
  pageControl.translatesAutoresizingMaskIntoConstraints = true
  // Remove constraints for scroll view
  scrollView.removeConstraints(scrollView.constraints)
  scrollView.translatesAutoresizingMaskIntoConstraints = true
}
```

Remember how, if you don't add constraints of your own, Interface Builder will give the views automatic constraints? Well, those automatic constraints get in the way if you're going to do your own layout. That's why you need to remove these unwanted constraints from all the visible views in the view controller first.

You also do `translatesAutoresizingMaskIntoConstraints = true`. This allows you to position and size your views manually by changing their `frame` property.

When Auto Layout is enabled, you're not really supposed to change the `frame` yourself — you can only indirectly move views into position by creating constraints. Modifying the `frame` by hand can cause conflicts with the existing constraints and bring all sorts of trouble — you don't want to make Auto Layout angry, you wouldn't like it when it's angry.

For this view controller, it's much more convenient to manipulate the `frame` property directly than it is making constraints — especially when you're placing the buttons for the search results — which is why you're disabling Auto Layout.

> **Note:** Auto Layout doesn't really get disabled, but with the "translates autoresizing mask" option set to true, UIKit will convert your manual layout code into the proper constraints behind the scenes. That's also why you removed the automatic constraints because they will conflict with the new ones, possibly causing your app to crash.

Custom scroll view layout

Now that Auto Layout is out of the way, you can do your own layout. That happens in the `viewWillLayoutSubviews()` method.

➤ Add this new method:

```
override func viewWillLayoutSubviews() {
  super.viewWillLayoutSubviews()
  let safeFrame = view.safeAreaLayoutGuide.layoutFrame
  scrollView.frame = safeFrame
  pageControl.frame = CGRect(
    x: safeFrame.origin.x,
    y: safeFrame.size.height - pageControl.frame.size.height,
    width: safeFrame.size.width,
    height: pageControl.frame.size.height)
}
```

The `viewWillLayoutSubviews()` method is called by UIKit as part of the layout phase of your view controller when it first appears on screen. It's the ideal place for changing the `frames` of your views by hand.

The scroll view should always be as large as the entire screen, so you would think that you should make its `frame` equal to the main view's `bounds`. This used to be the case till Apple introduced the iPhone X. But things change ...

With the iPhone X, you had to make sure that your content did not appear where the iPhone X's notch was, or where the scroll bar appeared at the bottom of the screen. So, Apple introduced the *safe area* concept — iOS would tell you what parts of a view were safe to have content on and each view would have several properties which defined the safe area for that view.

We make use of the `safeAreaLayoutGuide` property of the main view to get its `layoutFrame` — the safe area for the view in its own coordinate system — and then use that to set up the scroll view and the page control.

The page control is located at the bottom of the screen, and spans the entire width of the safe area. If this calculation doesn't make any sense to you, then try to sketch what happens on a piece of paper. It's what I usually do when writing my own layout code.

> **Note:** If you're confused about how the layout looks/works, easy way to get a better understanding is to set the background color of the scroll view and the page control to two distinctive colors like yellow and red and then run the app.

You will now see each control's actual content area in different colors against the black background and show you how each view is laid out.

You will find that this is a good technique to use in debugging any view positioning/sizing related issue.

➤ Run the app and flip to landscape. Nothing much happens yet: the screen has the page control at the bottom (the dots) but it's otherwise blank.

Add a background to the view

Let's make the view a little less plain by adding a background to it.

➤ Open the Asset Catalog and add the **LandscapeBackground@2x.png** and **LandscapeBackground@3x.png** images from the **Images** folder from this app's resources.

There are also **LandscapeBackground-dark@2x.png** and **LandscapeBackground-dark@3x.png** images in that folder – be sure that you don't add those. You'll be using them soon enough.

➤ Select the new **LandscapeBackground** image and in the **Attributes inspector**, change **Appearances** to **Any, Dark**.

This allows you to have a dark variant of the same image for when the app is showing the Dark appearance. Now you see where the other two images go, right?

Note: If you had not changed your Xcode settings since slicing the images previously, you might not see any chances after changing the Appearance above and still see the slicing interface. If so, just select **Editor ▸ Show Overview** from the Xcode menu to go back to the normal image view.

➤ Drag the **LandscapeBackground-dark@2x.png** and **LandscapeBackground-dark@3x.png** images into the 2x and 3x slots for Dark Appearance.

Now you have an image which works in either appearance. Cool!

➤ Add the following line to `viewDidLoad()` in **LandscapeViewController.swift**:

```
view.backgroundColor = UIColor(patternImage: UIImage(named:
"LandscapeBackground")!)
```

This puts an image as the main view's background. An image? But you're setting the `backgroundColor` property, which is a `UIColor`, not a `UIImage`! Yup, that's true, but `UIColor` has a cool trick that lets you use a tile-able image as a color.

If you look at the **LandscapeBackground** image in the asset catalog, you'll see that it is a small square. When you set this image as a pattern image for the background, the image repeats to cover the entire area. Tile-able images can be used anywhere where you can use a `UIColor`.

You might be tempted to set the background for the scroll view instead of the main view and for most iOS devices, that would work just as well. In fact, it would work better in the case of the scroll view because when you scroll the view, the background would animate.

However, on an iPhone X, if you set the image as the background for the scroll view, you'll notice that it doesn't cover the whole screen. This is again due to that pesky safe area.

Try it for yourself and see the difference.

And if you have the bright idea of setting the background of the main view *and* the background of the scroll view to the same image in the hopes of having a seamless background that scrolls, all I can say is to try that too and see what happens. :]

Set the Scroll View content size

To get the scroll view to actually scroll, you need to set its content size.

➤ Add the following line to `viewDidLoad()`:

```
scrollView.contentSize = CGSize(width: 1000, height: 1000)
```

It is very important to set the `contentSize` property when dealing with scroll views. This tells the scroll view how big the content area for the scroll view is — a scroll view's inside (the content area), can be bigger than its actual bounds. If the content area is bigger than the scroll view's bounds, that's when the scroll view allows you to scroll.

People often forget this step and then they wonder why their scroll view doesn't scroll. Unfortunately, you cannot set `contentSize` from Interface Builder, so it must be done from code.

➤ Run the app and try some scrolling — also, don't forget to test both Light and Dark appearances.


You might not notice too much of a difference since the background is static, but if you pay close attention, you'll notice that the horizontal and vertical scroll bars do move as you scroll around.

If the dots at the bottom also move while scrolling, then you've placed the page control inside the scroll view. Open the storyboard and in the Document Outline drag the Page Control below the Scroll View.

The page control itself doesn't do anything yet. Before you can make that work, you first have to add some content to the scroll view.

Add result buttons

The idea is to show the search results in a grid:



Each of these results is really a button. Before you can place these buttons on the screen, you need to calculate how many will fit on the screen at once. Easier said than done, because different iPhone models have different screen sizes.

Time for some math! Let's assume the app runs on a 4-inch device. In that case, the scroll view is 568 points wide by 320 points tall. It can fit 3 rows of 6 columns if you put each search result in a rectangle of 94 by 88 points. That comes to 3×6 = 18 search results on the screen at once. A search may return up to 200 results. Obviously, there is not enough room for everything and you will have to spread out the results over several pages.

One page contains 18 buttons. For the maximum number of results you will need 200 / 18 = 11.1111 pages, which rounds up to 12 pages. That last page will only be filled partially.

The 4.7-inch iPhone models have room for 7 columns plus some leftover vertical space, and the 5.5-inch iPhone Plus models can fit an extra row. Also there's the iPhone X, Xs, and 11 Pro which can handle 4 rows and 9 columns. Not to mention the iPhone 11, Xr, Xs Max, and 11 Pro Max which can fit 4 rows by 8 columns.

That's a lot of different possibilities!

You need to add the logic to `LandscapeViewController` so it can calculate how big the scroll view's `contentSize` has to be. It will also need to add a `UIButton` object for each search result.

Once you have that working, you can display the artwork via that `UIButton`.

Of course, this means the app first needs to pass the array of search results to `LandscapeViewController` so it can use them for its calculations.

Pass the search results to the landscape view

➤ Let's add a property for this to **LandscapeViewController.swift**:

```
var searchResults = [SearchResult]()
```

Initially, this will be an empty array. `SearchViewController` replaces it with the real array upon rotation to landscape.

➤ Assign the array to the new property in **SearchViewController.swift**:

```
func showLandscape(with coordinator:
UIViewControllerTransitionCoordinator) {
  . . .
  if let controller = landscapeVC {
    controller.searchResults = searchResults  // add this line
    . . .
```

You have to be sure to set `searchResults` before you access the `view` property from the `LandscapeViewController`, because that will trigger the view to be loaded and call `viewDidLoad()`.

The view controller will read from the `searchResults` array in `viewDidLoad()` to build up the contents of its scroll view. But if you access `controller.view` before setting `searchResults`, this property will still be `nil` and no buttons will be created. The order in which you do things matters here!

➤ Switch back to **LandscapeViewController.swift**. Remove the line that sets `scrollView.contentSize` from `viewDidLoad()`. That was just for testing.

Now let's go make those buttons.

Initial configuration

➤ Add a new instance variable:

```
private var firstTime = true
```

The purpose for this variable will become clear in a moment.

★ ★ ★

Private parts

You declared the `firstTime` instance variable as `private`. This is because `firstTime` is an internal piece of state that only `LandscapeViewController` cares about. It should not be visible to other objects.

You don't want the other objects in your app to know about the existence of `firstTime`, or worse, actually try to use this variable. Strange things are bound to happen if some other view controller changes the value of `firstTime` when `LandscapeViewController` isn't expecting the change.

We haven't talked much about the distinction between *interface* and *implementation* yet, but what an object shows to the outside is different from what it has on the inside. That's done on purpose because its internals — the implementation details — should not be of interest to anyone else, and are often even dangerous to expose since messing around with internal settings can crash the app.

It is considered good programming practice to hide as much as possible inside the object and only show a few things on the outside. To make certain variables and methods invisible from outside of your own class, you declare them to be `private`. That removes them from the object's public interface.

★ ★ ★

Exercise: Find other variables and methods in the app that can be made `private`.

➤ Add the following lines to the end of `viewWillLayoutSubviews()`:

```
if firstTime {
  firstTime = false
  tileButtons(searchResults)
}
```

This calls a new method, `tileButtons(_:)`, that performs the necessary math and places the buttons on the screen in neat rows and columns. This needs to happen just once, when the `LandscapeViewController` is added to the screen.

You may think that `viewDidLoad()` would be a good place for this, but at the point in the view controller's lifecycle when `viewDidLoad()` is called, the view is not on the screen yet and has not been added into the view hierarchy. At this time, it doesn't know how large the view should be. Only after `viewDidLoad()` is done does the view get resized to fit the actual screen.

So you can't use `viewDidLoad()` for this. The only safe place to perform calculations based on the final size of the view — that is, any calculations that use the view's `frame` or `bounds` — is in `viewWillLayoutSubviews()`.

A warning: `viewWillLayoutSubviews()` may be invoked more than once! For example, it's also called when the landscape view gets removed from the screen. You use the `firstTime` variable to make sure you only place the buttons once.

Calculate the tile grid

We could calculate custom button sizes based on the view size to get an optimum layout. And that's exactly what we used to do previously.

However, given the number of different iPhone devices and the fact that more are being added, that approach is probably going to end up in a lot of additional code with each new iOS iteration.

To make things simpler, we are going to calculate a standard grid based on the view size.

➤ Add the new `tileButtons(_:)` method. It's a bit long, so we'll take it piece-by-piece.

```
// MARK: - Private Methods
private func tileButtons(_ searchResults: [SearchResult]) {
  let itemWidth: CGFloat = 94
  let itemHeight: CGFloat = 88
  var columnsPerPage = 0
```

```
    var rowsPerPage = 0
    var marginX: CGFloat = 0
    var marginY: CGFloat = 0
    let viewWidth = scrollView.bounds.size.width
    let viewHeight = scrollView.bounds.size.height
    // 1
    columnsPerPage = Int(viewWidth / itemWidth)
    rowsPerPage = Int(viewHeight / itemHeight)
    // 2
    marginX = (viewWidth - (CGFloat(columnsPerPage) * itemWidth))
  * 0.5
    marginY = (viewHeight - (CGFloat(rowsPerPage) * itemHeight)) *
  0.5

    // TODO: more to come here
  }
```

The method must decide how many rows and columns of 94 x 88 button can be placed on the view based on the view width and height. So here's the important parts:

1. You calculate the number of columns needed by dividing the view width by the button width and the number of rows needed by dividing the view height by the button height.

   Note that `viewWidth` and `itemWidth` are `CGFloat` values and the result of the division would be a `CGFloat` value as well. But `columnsPerPage` is an `Int` value. So you have to cast the result of the division to an `Int` in order to assign the value to `columnsPerPage`.

2. You calculate how much space is left over horizontally by finding the difference between the view width and the width of all the columns, and then divide the result by 2 — which is the same as multiplying by 0.5 — to get the padding on the left and right. Similarly, you calculate the padding on the top and bottom as well.


From now on, you'll keep adding more code to the end of `tileButtons()` (where the `TODO` comment is) till the method is complete.

➤ Add the following lines to `tileButtons()`:

```
  // Button size
  let buttonWidth: CGFloat = 82
  let buttonHeight: CGFloat = 82
  let paddingHorz = (itemWidth - buttonWidth) / 2
  let paddingVert = (itemHeight - buttonHeight) / 2
```

You've already specified that each search result gets a grid square of 94 by 88 points, but that doesn't mean you need to make the buttons that big as well.

The image you'll put on the buttons is 60×60 pixels, so that leaves quite a gap around the image. After playing with the design a bit, I decided that the buttons will be 82×82 points (`buttonWidth` and `buttonHeight`), leaving a small amount of padding between each button and its neighbors (`paddingHorz` and `paddingVert`).



The dimensions of the buttons in the 5x3 grid

Add buttons

Now you can loop through the array of search results and make a new button for each `SearchResult` object.

➤ Add the following lines to `tileButtons()`:

```
// Add the buttons
var row = 0
var column = 0
var x = marginX
for (index, result) in searchResults.enumerated() {
  // 1
  let button = UIButton(type: .system)
  button.backgroundColor = UIColor.white
  button.setTitle("\(index)", for: .normal)
  // 2
  button.frame = CGRect(
    x: x + paddingHorz,
    y: marginY + CGFloat(row) * itemHeight + paddingVert,
    width: buttonWidth,
    height: buttonHeight)
  // 3
  scrollView.addSubview(button)
  // 4
```

```
    row += 1
    if row == rowsPerPage {
      row = 0; x += itemWidth; column += 1
      if column == columnsPerPage {
        column = 0; x += marginX * 2
      }
    }
  }
```

Here is how this works:

1. Create the `UIButton` object. For debugging purposes, you give each button a title with the array index. If there are 200 results in the search, you also should end up with 200 buttons. Setting the index on the button will help to verify this.

2. When you make a button by hand, you always have to set its `frame`. Using the measurements you figured out earlier, you determine the position and size of the button. Notice that `CGRect`'s properties are all `CGFloat` but `row` is an `Int`. You need to convert `row` to a `CGFloat` before you can use it in the calculation.

3. You add the new button object to the `UIScrollView` as a subview. After the first 18 or so buttons (depending on the screen size), this places any subsequent buttons out of the visible range of the scroll view, but that's the whole point. As long as you set the scroll view's `contentSize` accordingly, the user can scroll to view these other buttons.

4. You use the `x` and `row` variables to position the buttons, going from top to bottom (by increasing `row`). When you've reached the bottom (`row` equals `rowsPerPage`), you go up again to row 0 and skip to the next column (by increasing the `column` variable).

   When the `column` reaches the end of the screen (equals `columnsPerPage`), you reset it to 0 and add any leftover space to `x` (twice the X-margin).

   Note that in Swift you can put multiple statements on a single line by separating them with a semicolon. I did that to save some space, you can have those statements on separate lines, if you so prefer.

If this sounds like gobbledygook to you, I suggest you play around a bit with these calculations to gain insight into how they work. It's not rocket science, but it does require some mental gymnastics. Tip: Sketching the process on paper can help!

Note: By the way, did you notice what happened in the `for in` loop?

```
for (index, result) in searchResults.enumerated() {
```

This `for...in` loop steps through the `SearchResult` objects from the array, but with a twist. By calling the array's `enumerated()` method, you get a *tuple* containing not only the next `SearchResult` object but also its index in the array.

A tuple is nothing more than a temporary list with two or more items in it. Here, the tuple is `(index, result)`. This is a neat trick to loop through an array and get both the objects and their indices.

➤ Finally, add the last part of this very long method:

```
// Set scroll view content size
let buttonsPerPage = columnsPerPage * rowsPerPage
let numPages = 1 + (searchResults.count - 1) / buttonsPerPage
scrollView.contentSize = CGSize(
      width: CGFloat(numPages) * viewWidth,
      height: scrollView.bounds.size.height)

print("Number of pages: \(numPages)")
```

At the end of the method you calculate the `contentSize` for the scroll view based on how many buttons fit on a page and the number of `SearchResult` objects.

You want the user to be able to "page" through these results — you'll enable this feature shortly — rather than simply scroll. So, you should always make the content width a multiple of the scroll width (568, 667, 736, or 812 points). You can then determine how many pages you need with a simple formula.

Note: Dividing an integer value by an integer always results in an integer. If `buttonsPerPage` is 18 (3 rows × 6 columns) and there are fewer than 18 search results, `searchResults.count / buttonsPerPage` is 0.

It's important to realize that `numPages` will never have a fractional value because all the variables involved in the calculation are `Int`s, which makes `numPages` an `Int` too.

That's why the formula is `1 + (searchResults.count - 1) / buttonsPerPage`.

If there are 18 results, exactly enough to fill a single page, `numPages = 1 + 17/18 = 1 + 0 = 1`. But if there are 19 results, the 19th result needs to go on the second page, and `numPages = 1 + 18/18 = 1 + 1 = 2`. Plug in some other values to verify this formula is correct.

I also threw in a `print()` for good measure, so you can verify that you really end up with the right number of pages.

> **Note:** Xcode currently gives a warning "Immutable value 'result' was never used; consider replacing with '_' or removing it". That warning will go away once you use the `result` variable in the next section.

➤ Run the app, do a search, and rotate to landscape. You should now see a whole bunch of buttons neatly laid out in a grid.

Scroll all the way to the right and you'll notice that the last button is titled 199. That is 200 buttons indeed — you started counting at 0, remember?.

Just to make sure that this logic works properly, you should test a few different scenarios. What happens when there are fewer results than 18 — the amount that fit on a single page on an iPhone SE? What happens when there are exactly 18 search results? How about 19, one more than can go on a single page?

The easiest way to test these situations is to change the `&limit` parameter in the search URL.

> **Exercise:** Try these situations for yourself and see what happens.

➤ Also test when there are no search results. The landscape view should now be empty. You'll add a "Nothing Found" label to this screen too, in a bit.

Paging

So far, the Page Control at the bottom of the screen has always shown three dots. And there wasn't much paging to be done on the scroll view either.

In case you're wondering what *paging* means: if the user has moved the scroll view a certain amount, it should snap to a new page.

With paging enabled, you can quickly flick through the contents of a scroll view, without having to drag it all the way. You're no doubt familiar with this effect because it is what the iPhone uses in its springboard. Many other apps use the effect too, for example, the Weather app uses paging to flip between the cards for different cities.

Enable scroll view paging

➤ Go to **Landscape** scene in the storyboard and check the **Scrolling - Paging Enabled** option for the scroll view in the Attributes inspector.

There, that was easy! Now run the app and the scroll view will let you page rather than scroll. That's cool, but you also need to do something with the page control at the bottom of the screen.

Configure the page control

➤ Switch to **LandscapeViewController.swift** and add this line to `viewDidLoad()`:

```
pageControl.numberOfPages = 0
```

This effectively hides the page control, which is what you want to do when there are no search results.

➤ Add the following lines to the end of `tileButtons()`:

```
pageControl.numberOfPages = numPages
pageControl.currentPage = 0
```

This sets the number of dots that the page control displays to the number of pages that you calculated. The active dot — the white one — needs to be synchronized with the active page in the scroll view. Currently, it never changes unless you tap in the page control and even then it has no effect on the scroll view.

To get this to work, you'll have to make the page control talk to the scroll view, and vice versa. The view controller must become the delegate of the scroll view so it will be notified when the user is flicking through the pages.

Connect the scroll view and page control

➤ Add this new extension to the end of **LandscapeViewController.swift**:

```
extension LandscapeViewController: UIScrollViewDelegate {
  func scrollViewDidScroll(_ scrollView: UIScrollView) {
    let width = scrollView.bounds.size.width
    let page = Int((scrollView.contentOffset.x + width / 2) /
width)
    pageControl.currentPage = page
  }
}
```

This is a `UIScrollViewDelegate` method. You figure out what the index of the current page is by looking at the `contentOffset` property of the scroll view. This property determines how far the scroll view has been scrolled and is updated while you're dragging the scroll view.

Unfortunately, the scroll view doesn't simply tell us, "The user has flipped to page X". So, you have to calculate this yourself. If the content offset gets beyond halfway on the page (`width/2`), the scroll view will move to the next page. In that case, you update the `pageControl`'s active page number.

You also need to know when the user taps on the Page Control so you can update the scroll view. There is no delegate for this, but you can use a regular `@IBAction` method for it.

➤ Add the action method:

```
// MARK: - Actions
@IBAction func pageChanged(_ sender: UIPageControl) {
  scrollView.contentOffset = CGPoint(
    x: scrollView.bounds.size.width *
CGFloat(sender.currentPage),
    y: 0)
}
```

This works the other way around: when the user taps in the Page Control, its `currentPage` property gets updated. You use that to calculate a new `contentOffset` for the scroll view.

➤ In the storyboard, for the **Landscape** scene, **Control-drag** from the Scroll View to the view controller and select **delegate**.

➤ Also **Control-drag** from the Page Control to the view controller and select **pageChanged:** under Sent Events.

➤ Try it out, the page control and the scroll view should now be in sync.


The transition from one page to another after tapping in the page control is still a little abrupt, though. An animation would help here.

Exercise: See if you can animate what happens in `pageChanged(_:)`.

You can simply wrap the code from the action method in an animation block:

```
@IBAction func pageChanged(_ sender: UIPageControl) {
  UIView.animate(
    withDuration: 0.3,
    delay: 0,
    options: [.curveEaseInOut],
    animations: {
      self.scrollView.contentOffset = CGPoint(
        x: self.scrollView.bounds.size.width *
CGFloat(sender.currentPage),
        y: 0)
    },
    completion: nil)
}
```

You're using a version of the `UIView` animation method that allows you to specify options because the "Ease In, Ease Out" timing (`.curveEaseInOut`) looks good here.



We've got paging!

➤ This is a good time to commit.

Download the artwork

First, let's give the buttons a nicer look.

Set button background

➤ Open the Asset Catalog and add the **LandscapeButton@2x.png** and **LandscapeButton@3x.png** images from the **Images** folder from this app's resources. As before, do not add the **-dark** variant of the image yet.

➤ Select the new **LandscapeButton** image and in the **Attributes inspector**, change **Appearances** to **Any, Dark**.

➤ Drag the **LandscapeButton-dark@2x.png** and **LandscapeButton-dark@3x.png** images into the 2x and 3x slots for Dark Appearance.


That sets up the images we'll use. Now, you can use them via code.

➤ Replace the button creation code in `tileButtons()` (in **LandscapeViewController.swift**) with:

```
let button = UIButton(type: .custom)
button.setBackgroundImage(UIImage(named: "LandscapeButton"),
for: .normal)
```

Instead of a regular button, you now make a `.custom` one, and you give it a background image instead of a white background and a title.

If you run the app, it will look like this for each Appearance:



The buttons now have a custom background image

Display button images

Now you have to download the artwork images, if they haven't already been downloaded and cached by the table view, and put them on the buttons.

Problem: You're dealing with `UIButtons` here, not `UIImageViews`, so you cannot simply use that handy extension from earlier. Fortunately, the code is very similar!

➤ Add a new method to **LandscapeViewController.swift**:

```
private func downloadImage(
  for searchResult: SearchResult,
  andPlaceOn button: UIButton
) {
  if let url = URL(string: searchResult.imageSmall) {
    let task = URLSession.shared.downloadTask(with: url) {
      [weak button] url, _, error in
      if error == nil, let url = url,
        let data = try? Data(contentsOf: url),
        let image = UIImage(data: data) {
```

```
          DispatchQueue.main.async {
            if let button = button {
              button.setImage(image, for: .normal)
            }
          }
        }
      }
      task.resume()
    }
  }
```

This looks very much like what you did in the `UIImageView` extension.

First you get a `URL` instance with the link to the 60×60-pixel artwork, and then you create a download task. Inside the completion handler you put the downloaded file into a `UIImage`, and if all that succeeds, use `DispatchQueue.main.async` to place the image on the button.

➤ Add the following line to `tileButtons()` to call this new method, right after where you create the button:

```
downloadImage(for: result, andPlaceOn: button)
```

And that should do it. Run the app and you'll get some cool-looking buttons:



Showing the artwork on the buttons

Note: The Xcode warning about `result` is gone, but now it gives the same message for the `index` variable. Xcode doesn't like it if you declare variables but don't use them. You'll use `index` again later in this app but in the mean time, you can replace it by the _ wildcard symbol to stop Xcode from complaining.

Clean up

It's always a good idea to clean up after yourself, in life as well as in programming :] Imagine this: what would happen if the app is still downloading images and the user flips back to portrait mode?

At that point, the `LandscapeViewController` is deallocated but the image downloads keep going. That is exactly the sort of situation that can crash your app if not handled properly.

To avoid ownership cycles, you capture the button with a `weak` reference. When `LandscapeViewController` is deallocated, so are the buttons. So, the completion handler's captured `button` reference automatically becomes `nil`. The `if let` inside the `DispatchQueue.main.async` block will now safely skip `button.setImage(for)`. No harm done. That's why you wrote `[weak button]`.

However, to conserve resources, the app should really stop downloading these images because they are not needed. Otherwise, it's just wasting bandwidth and battery life, and users don't take too kindly to apps that do this.

➤ Add a new property to **LandscapeViewController.swift**:

```
private var downloads = [URLSessionDownloadTask]()
```

This array will keep track of all the active `URLSessionDownloadTask` objects.

➤ Add the following line to the end of `downloadImage(for:andPlaceOn:)`, right after where you resume the download task:

```
downloads.append(task)
```

➤ And finally, add a `deinit` method to cancel any operations that are still on the way:

```
deinit {
  print("deinit \(self)")
  for task in downloads {
    task.cancel()
  }
}
```

This will stop the download for any button whose image was still pending or in transit. Good job, partner!

➤ Commit your changes.

Exercise: Despite what the iTunes web service promises, not all of the artwork is truly 60×60 pixels. Some of it is bigger, some are not even square, and so, it might not always fit nicely in the button. Your challenge is to use the image sizing code from *MyLocations* to always resize the image to 60×60 points before you put it on the button. Note that we're talking points here, not pixels — on Retina devices, the image should actually end up being 120×120 or even 180×180 pixels in size.

Note: In this section you learned how to create a grid-like view using a `UIScrollView`. iOS comes with a versatile class, `UICollectionView`, that lets you do the same thing — and much more! — without having to resort to the sort of math you did in `tileButtons()`. To learn more about `UICollectionView`, check out the website `https://www.raywenderlich.com/library?q=collectionview&sort_order=relevance`

You can find the project files for this chapter under **39-Landscape** in the Source Code folder.

Chapter 40: Refactoring

By Fahim Farook

Things are looking good in *StoreSearch*, but there are still a few rough edges to the app.

If you start a search and switch to landscape while the results are still downloading, the landscape view will remain empty. You can reproduce this situation by artificially slowing down your network connection using the Network Link Conditioner tool.

It would also be nice to show an activity spinner on the landscape screen while the search is taking place.

You will polish off some of these rough edges in this chapter and cover the following:

- **Refactor the search:** Refactor the code to put the search logic into its own class so that you have centralized access to the search state and results.
- **Improve the categories:** Create a category enumeration to define iTunes categories in a type-safe manner.
- **Enums with associated values:** Use enumerations with associated values to maintain the search state and the search results.
- **Spin me right round:** Add an activity indicator to the landscape view. Also add a network activity indicator to the app.
- **Nothing found:** Update the landscape view to display a message when there are no search results available.
- **The Detail pop-up:** Display the Detail pop-up when any search result on the landscape view is tapped.

Refactor the search

So how can `LandscapeViewController` tell what state the search is in? Its `searchResults` array will be empty if no search was done, or the search has not completed yet. Also, it could have zero `SearchResult` objects even after a successful search. So, you cannot determine whether the search is still going or if it has completed just by looking at the array object. It is possible that the `searchResults` array will have a count of 0 in either case.

You need a way to determine whether a search is still going on. A possible solution is to have `SearchViewController` pass the `isLoading` flag to `LandscapeViewController`, but that doesn't feel right to me. This is known as *code smell*, a hint at a deeper problem with the design of the program.

Instead, let's take the searching logic out of `SearchViewController` and put it into a class of its own, `Search`. Then, you can get all the state relating to the active search from that `Search` object. Time for some refactoring!

The Search class

➤ If you want, create a new branch for this in Git.

This is a pretty comprehensive change to the code and there is always a risk that it won't work as you hoped. By making the changes in a new branch, you can commit your changes without messing up the main branch. Plus, you can revert back to the main branch if the changes don't work out. Making new branches in Git is quick and easy, so it's good to get into the habit.

➤ Create a new file using the **Swift File** template. Name it **Search**.

➤ Change the contents of **Search.swift** to:

```
import Foundation

class Search {
  var searchResults: [SearchResult] = []
  var hasSearched = false
  var isLoading = false

  private var dataTask: URLSessionDataTask?

  func performSearch(for text: String, category: Int) {
    print("Searching...")
  }
}
```

You've given this class three internal properties, one private property, and a method. This stuff should look familiar because it comes straight from `SearchViewController`.

You'll be removing code from that class and putting it into this new `Search` class.

The `performSearch(for:category:)` method doesn't do much yet but that's OK. First I want you to make `SearchViewController` work with this new `Search` object and when it compiles without errors, you will move all the logic over. Baby steps!

Move code over

Let's make the changes to **SearchViewController.swift**. Xcode will probably give a bunch of errors and warnings while you're making these changes, but it will all work out in the end.

➤ In **SearchViewController.swift**, remove the declarations for the following properties:

```
var searchResults: [SearchResult] = []
var hasSearched = false
var isLoading = false
var dataTask: URLSessionDataTask?
```

And replace them with this one:

```
private let search = Search()
```

The new `Search` object not only describes the state and results of the search, it will also encapsulate all the logic for talking to the iTunes web service. You can now remove a lot of code from the view controller.

➤ Move the following methods over to **Search.swift**:

- `iTunesURL(searchText:category:)`
- `parse(data:)`

➤ Make these methods `private`. They are only important to `Search` itself, not to any other classes from the app, so it's good to "hide" them.

➤ Back in **SearchViewController.swift**, replace the `performSearch()` method with the following (Tip: set aside the old code in a temporary file because you'll need it again later).

```
func performSearch() {
  search.performSearch(
    for: searchBar.text!,
    category: segmentedControl.selectedSegmentIndex)

  tableView.reloadData()
  searchBar.resignFirstResponder()
}
```

This simply makes the `Search` object do all the work. Of course, you still reload the table view — to show the activity spinner — and hide the keyboard.

There are a few places in the code that still use the old `searchResults` array even though that no longer exists. You should change them to use the `searchResults` property from the `Search` object instead. Likewise for `hasSearched` and `isLoading`.

➤ For example, change `tableView(_:numberOfRowsInSection:)` to:

```
func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  if search.isLoading {
    return 1  // Loading...
  } else if !search.hasSearched {
    return 0  // Not searched yet
  } else if search.searchResults.count == 0 {
    return 1  // Nothing Found
  } else {
    return search.searchResults.count
  }
}
```

Similar to the above, find the other places in code where the relevant properties have moved and make the necessary changes. If you aren't sure of where to make the changes, look for Xcode errors — for this step, once you make all the changes correctly, the code will compile again without any errors.

➤ In `showLandscape(with:)`, change the line that sets the `searchResults` property on the new view controller from:

```
controller.searchResults = search.searchResults
```

To:

```
controller.search = search
```

This line will give an error after you make the change, but you'll fix that next.

The `LandscapeViewController` still has a property for a `searchResults` array so you have to change that to use the `Search` object as well.

➤ In **LandscapeViewController.swift**, remove the `searchResults` instance variable and replace it with:

```
var search: Search!
```

➤ In `viewWillLayoutSubviews()`, change the call to `tileButtons()` into:

```
tileButtons(search.searchResults)
```

OK, that's the first round of changes. Build the app to make sure there are no compiler errors.

Add the search logic back in

The app itself doesn't do much anymore because you removed all the searching logic. So let's put that back in.

➤ In **Search.swift**, replace `performSearch(for:category:)` with the following (you can use that temporary file from earlier, but be careful to make the proper changes):

```
func performSearch(for text: String, category: Int) {
  if !text.isEmpty {
    dataTask?.cancel()

    isLoading = true
    hasSearched = true
    searchResults = []

    let url = iTunesURL(searchText: text, category: category)

    let session = URLSession.shared
    dataTask = session.dataTask(with: url) {
      data, response, error in
      // Was the search cancelled?
      if let error = error as NSError?, error.code == -999 {
        return
      }
```

```
        if let httpResponse = response as? HTTPURLResponse,
          httpResponse.statusCode == 200, let data = data {
          self.searchResults = self.parse(data: data)
          self.searchResults.sort(by: <)

          print("Success!")
          self.isLoading = false
          return
        }

        print("Failure! \(response!)")
        self.hasSearched = false
        self.isLoading = false
      }
      dataTask?.resume()
    }
  }
```

This is basically the same logic as before, except all the user interface code has been removed. The purpose of `Search` is just to perform a search, it should not do any UI stuff. That's the job of the view controller.

➤ Run the app and search for something. When the search finishes, the Console shows a "Success!" message but the table view does not reload and the spinner keeps spinning for eternity.

The `Search` object currently has no way to tell the `SearchViewController` that it is done. You could solve this by making `SearchViewController` a delegate of the `Search` object, but for situations like these, closures are much more convenient.

The SearchComplete closure

Let's create your own closure!

➤ Add the following line to **Search.swift**, above the `class` line:

```
typealias SearchComplete = (Bool) -> Void
```

The `typealias` declaration allows you to create a more convenient name for a data type, in order to save some keystrokes and to make the code more readable.

Here, you declare a type for your own closure, named `SearchComplete`. This is a closure that returns no value (it is `Void`) and takes one parameter, a `Bool`. If you think this syntax is weird, then I'm right there with you, but that's the way it is.

From now on, you can use the name `SearchComplete` to refer to a closure that takes a `Bool` parameter and returns no value.

Closure types

Whenever you see a –> in a type definition, the type is intended for a closure, function, or method.

Swift treats these three things as mostly interchangeable. Closures, functions, and methods are all blocks of source code that possibly take parameters and return a value. The difference is that a function is really just a closure with a name, and a method is a function that lives inside an object.

Some examples of closure types:

`() -> ()` is a closure that takes no parameters and returns no value.

`Void -> Void` is the same as the previous example – `Void` and `()` mean the same thing.

`(Int) -> Bool` is a closure that takes one parameter, an `Int`, and returns a `Bool`.

`Int -> Bool` is the same as the above. If there is only one parameter, you can leave out the parentheses.

`(Int, String) -> Bool` is a closure taking two parameters, an `Int` and a `String`, and returning a `Bool`.

`(Int, String) -> Bool?` as above, but now returns an optional `Bool` value.

`(Int) -> (Int) -> Int` is a closure that returns another closure that returns an `Int`. Freaky! Swift treats closures like any other type of object, so you can also pass them as parameters and return them from functions.

➤ Make the following changes to `performSearch(for:category:)`:

```
func performSearch(
  for text: String,
  category: Int,
  completion: @escaping SearchComplete) {      // new
  if !text.isEmpty {
    . . .
    dataTask = session.dataTask(with: url) {
      data, response, error in
      var success = false                                 // new
      . . .
      if let httpResponse = response as? . . . {
        . . .
        self.isLoading = false
        success = true                      // instead of return
      }
```

```
        if !success {                                          // new
          self.hasSearched = false
          self.isLoading = false
        }                                                      // new
        // New code block - add the next three lines
        DispatchQueue.main.async {
          completion(success)
        }
      }
      dataTask?.resume()
    }
  }
```

You've added a third parameter named `completion` that is of type `SearchComplete`. Whoever calls `performSearch(for:category:completion:)` can now supply their own closure, and the method will execute the code that is inside that closure when the search completes.

> **Note:** The `@escaping` annotation is necessary for closures that are not used immediately. It tells Swift that this closure may need to capture variables such as `self` and keep them around for a little while until the closure can finally be executed, in this case, when the search is done.

Instead of returning early from the closure upon success, you now set the `success` variable to `true` replacing the `return` statement. The value of `success` is used for the `Bool` parameter of the `completion` closure, as you can see inside the call to `DispatchQueue.main.async` at the bottom.

To perform the code from the closure, you simply call it as you'd call any function or method: `closureName(parameters)`. You call `completion(true)` upon success and `completion(false)` upon failure. This is done so that the `SearchViewController` can reload its table view or, in the case of an error, show an alert view.

➤ In **SearchViewController.swift**, replace `performSearch()` with:

```
  func performSearch() {
    search.performSearch(
      for: searchBar.text!,
      category: segmentedControl.selectedSegmentIndex) { success
  in
        if !success {
          self.showNetworkError()
        }
        self.tableView.reloadData()
      }
```

```
    tableView.reloadData()
    searchBar.resignFirstResponder()
  }
```

You now pass a closure – as a trailing closure – to `performSearch(for:category:completion:)`. The code in this closure gets called after the search completes, with the `success` parameter being either `true` or `false`. A lot simpler than making a delegate, right? The closure is always called on the main thread, so it's safe to use UI code here.

➤ Run the app. You should be able to search again.

That's the first part of this refactoring complete. You've extracted the relevant code for searching out of the `SearchViewController` and placed it into its own object, `Search`. The view controller now only does view-related things, which is exactly how it is supposed to work.

➤ You've made quite a few extensive changes, so it's a good idea to commit.

Improve the categories

The idea behind Swift's strong typing is that the data type of a variable should be as descriptive as possible. Right now, the category to search for is represented by a number, 0 to 3, but is that the best way to describe a category to your program?

If you see the number 3, does that mean "e-book" to you? It could be anything... And what if you use 4 or 99 or -1, what would that mean? These are all valid values for an `Int` but not for a category. The only reason the category is currently an `Int` is because `segmentedControl.selectedSegmentIndex` is an `Int`.

Represent the category as an enum

There are only four possible search categories, so this sounds like a job for an enum!

➤ Add the following to **Search.swift**, *inside* the `class` brackets:

```
  enum Category: Int {
    case all = 0
    case music = 1
    case software = 2
    case ebooks = 3
  }
```

This creates a new enumeration type named `Category` with four possible values. Each of these has a numeric value associated with it, called the **raw** value.

Contrast this with the `AnimationStyle` enum you made before:

```
enum AnimationStyle {
  case slide
  case fade
}
```

That enum does not associate numbers with its values — it doesn't say `: Int` behind the enum name. For `AnimationStyle` it doesn't matter that `slide` is really number 0 and `fade` is number 1, or whatever the values might be. All you care about is that a variable of type `AnimationStyle` can either be `.slide` or `.fade`, a numeric value is not important.

For the `Category` enum, however, you want to connect its four values to the four possible indices of the Segmented Control. If segment 3 is selected, you want this to correspond to `.ebooks`. That's why the items from the `Category` enum have associated numbers.

Use the Category enum

➤ Change the method signature of `performSearch(for:category:completion:)` to use this new type:

```
func performSearch(
  for text: String,
  category: Category,
  completion: @escaping SearchComplete) {
```

The `category` parameter is no longer an `Int`. It is not possible to pass it the value 4 or 99 or -1 anymore. It must always be one of the values from the `Category` enum. This reduces a potential source of bugs and it has made the program more expressive. Whenever you have a limited list of possible values that can be turned into an enum, it's worth doing!

➤ Also change `iTunesURL(searchText:category:)` because that also assumed `category` would be an `Int`:

```
private func iTunesURL(searchText: String, category: Category)
-> URL {
  let kind: String
  switch category {
  case .all: kind = ""
```

```
    case .music: kind = "musicTrack"
    case .software: kind = "software"
    case .ebooks: kind = "ebook"
    }

    let encodedText = . . .
```

The `switch` now looks at the various cases from the `Category` enum instead of the numbers 0 to 3. Note that the `default` case is no longer needed because the `category` parameter cannot have any other values.

This code works, but to be honest I'm not entirely happy with it. I've said before that any logic that is related to an object should be an integral part of that object. In other words, an object should do as much as it can itself.

Converting the category into a "kind" string that goes into the iTunes URL is a good example. That sounds like something the `Category` enum itself could do.

Swift enums can have their own methods and properties. So, let's take advantage of that and improve the code even more.

➤ Add the `type` property to the `Category` enum:

```
enum Category: Int {
  case all = 0
  case music = 1
  case software = 2
  case ebooks = 3

  var type: String {
    switch self {
    case .all: return ""
    case .music: return "musicTrack"
    case .software: return "software"
    case .ebooks: return "ebook"
    }
  }
}
```

Swift enums cannot have instance variables, only computed properties. `type` has the exact same `switch` statement that you just saw, except that it switches on `self`, the current value of the enumeration object.

➤ In `iTunesURL(searchText:category:)` you can now simply write:

```
private func iTunesURL(searchText: String, category: Category)
-> URL {
  let kind = category.type
  let encodedText = . . .
```

That's a lot cleaner. Everything that has to do with categories now lives inside its own enum, `Category`.

Convert an Int to Category

You still need to tell `SearchViewController` about this, because it needs to convert the selected segment index into a proper `Category` value.

➤ In **SearchViewController.swift**, change the first part of `performSearch()` to:

```
func performSearch() {
  if let category = Search.Category(
    rawValue: segmentedControl.selectedSegmentIndex) {   // New
line
    search.performSearch(
      for: searchBar.text!,
      category: category) { success in                   //
Change to category
        . . .
    }
    . . .
  }                                                      // New
line
}
```

To convert the `Int` value from `selectedSegmentIndex` to an item from the `Category` enum, you use the built-in `init(rawValue:)` method. This may fail — for example, when you pass in a number that isn't covered by one of `Category`'s cases, i.e. anything that is outside the range 0 to 3. That's why `init(rawValue:)` returns an optional that needs to be unwrapped with `if let` before you can use it.

> **Note:** Because you placed the `Category` enum inside the `Search` class, its full name is `Search.Category`. In other words, `Category` lives inside the `Search` *namespace*. It makes sense to bundle up these two things because they are so closely related.

➤ Build and run to see if the different categories still work.

Enums with associated values

Enums are pretty useful for restricting something to a limited range of possibilities, like what you did with the search categories. But they are even more powerful than you might have expected, as you'll find out...

Like all objects, the `Search` object has a certain amount of *state*. For `Search`, this is determined by its `isLoading`, `hasSearched`, and `searchResults` variables.

These three variables describe four possible states:

State	hasSearched	isLoading	searchResults
No search has been performed yet (this is also the state after an error)	false	false	Empty array
The search is in progress	true	true	Empty array
No results were found	true	false	Empty array
There are search results	true	false	Contains at least one `SearchResult` object

The `Search` object is in only one of these states at a time, and when it changes from one state to another, there is a corresponding change in the app's UI. For example, upon a change from "searching" to "have results", the app hides the activity spinner and loads the results into the table view.

The problem is that this state is scattered across three different variables. It's tricky to see what the current state is just by looking at these variables.

Consolidate search state

You can improve upon things by giving `Search` an explicit `state` variable. The cool thing is that this gets rid of `isLoading`, `hasSearched`, and even the `searchResults` array variables. Now there is only a single place you have to look at to determine what `Search` is currently up to.

➤ In **Search.swift**, remove the following instance variables:

```
var searchResults: [SearchResult] = []
var hasSearched = false
var isLoading = false
```

➤ In their place, add the following enum, which goes inside the class again:

```
enum State {
  case notSearchedYet
  case loading
  case noResults
  case results([SearchResult])
}
```

This enumeration has a case for each of the four states listed above. It does not need raw values, so the cases don't have numbers — do note that the state `.notSearchedYet` is also used for when there is an error.

The `.results` case is special: it has an *associated value* — an array of `SearchResult` objects.

This array is only important when the search is successful. In all the other cases, there are no search results and the array is empty — see the state table above. By making it an associated value, you'll only have access to this array when `Search` is in the `.results` state. In the other states, the array simply does not exist.

Use the new state enum

Let's see how this works.

➤ First add a new instance variable:

```
private(set) var state: State = .notSearchedYet
```

This keeps track of `Search`'s current state. Its initial value is `.notSearchedYet` — obviously no search has happened yet when the `Search` object is first constructed.

This variable is `private`, but only half so. It's not unreasonable for other objects to want to ask `Search` what its current state is. In fact, the app won't work unless you allow this.

But you don't want those other objects to be able to *change* the value of `state`; they are only allowed to read the state value. With `private(set)` you tell Swift that reading is OK for other objects, but assigning (or setting) new values to this variable may only happen inside the `Search` class.

➤ Change `performSearch(for:category:completion:)` to use this new variable:

```
func performSearch(
  for text: String,
  category: Category,
```

```
    completion: @escaping SearchComplete
  ) {
    if !text.isEmpty {
      dataTask?.cancel()
      // Remove the next 3 lines and replace with the following
      state = .loading
      . . .
      dataTask = session.dataTask(with: url) {
        data, response, error in

        var newState = State.notSearchedYet           // add this
        . . .
        if let httpResponse = response . . . {
          // Replace all code within this if block with following
          var searchResults = self.parse(data: data)
          if searchResults.isEmpty {
            newState = .noResults
          } else {
            searchResults.sort(by: <)
            newState = .results(searchResults)
          }
          success = true
        }
        // Remove "if !success" block
        DispatchQueue.main.async {
          self.state = newState                       // add this
          completion(success)
        }
      }
      dataTask?.resume()
    }
  }
```

Instead of the old variables `isLoading`, `hasSearched`, and `searchResults`, this code now only changes `state`.

Note: You don't update `state` directly, but instead, use a new local variable `newState`. Then at the end, in the `DispatchQueue.main.async` block, you transfer the value of `newState` to `self.state`. The reason for doing this the long way round is that `state` must only be changed by the main thread, or it can lead to a nasty and unpredictable bug known as a *race condition*.

When you have multiple threads trying to use the same variable at the same time, the app may do unexpected things and crash. In our app, the main thread will try to use `search.state` to display the activity spinner in the table view — and that can happen at the same time as `URLSession`'s completion handler, which runs in a background thread. We have to make sure these two threads don't get in each other's way!

Here's how the new logic works:

There is a lot that can go wrong between performing the network request and parsing the JSON. By setting `newState` to `.notSearchedYet` (which doubles as the error state) and `success` to `false` at the start of the completion handler, you assume the worst — always a good idea when doing network programming — unless there is evidence otherwise.

That evidence comes when the app is able to successfully parse the JSON and create an array of `SearchResult` objects. If the array is empty, `newState` becomes `.noResults`.

The interesting part is when the array is *not* empty. After sorting it like before, you do `newState = .results(searchResults)`. This gives `newState` the value `.results` and also associates the array of `SearchResult` objects with it. You no longer need a separate instance variable to keep track of the array; the array object is intrinsically attached to the value of `newState`.

Finally, you copy the value of `newState` into `self.state`. As I mentioned, this needs to happen on the main thread to prevent race conditions.

Update other classes to use the state enum

That completes the changes in **Search.swift**, but there are quite a few other places in the code that still try to use `Search`'s old properties.

➤ In **SearchViewController.swift**, replace `tableView(_:numberOfRowsInSection:)` with:

```
func tableView(
  _ tableView: UITableView,
  numberOfRowsInSection section: Int
) -> Int {
  switch search.state {
  case .notSearchedYet:
    return 0
  case .loading:
    return 1
  case .noResults:
    return 1
  case .results(let list):
    return list.count
  }
}
```

This is pretty straightforward — instead of trying to make sense out of the separate `isLoading`, `hasSearched`, and `searchResults` variables, this simply looks at the value from `search.state`. The `switch` statement is ideal for situations like this.

The `.results` case requires a bit more explanation. Because `.results` has an array of `SearchResult` objects associated with it, you can *bind* this array to a temporary variable, `list`, and then use that variable inside the case to read how many items are in the array. That's how you make use of the associated value. This pattern, using a `switch` statement to look at `state`, is going to become very common in your code.

➤ Replace `tableView(_:cellForRowAt:)` with:

```
func tableView(
  _ tableView: UITableView,
  cellForRowAt indexPath: IndexPath
) -> UITableViewCell {
  switch search.state {
  case .notSearchedYet:
    fatalError("Should never get here")

  case .loading:
    let cell = tableView.dequeueReusableCell(
      withIdentifier: TableView.CellIdentifiers.loadingCell,
      for: indexPath)

    let spinner = cell.viewWithTag(100) as!
UIActivityIndicatorView
    spinner.startAnimating()
    return cell

  case .noResults:
    return tableView.dequeueReusableCell(
      withIdentifier:
TableView.CellIdentifiers.nothingFoundCell,
      for: indexPath)

  case .results(let list):
    let cell = tableView.dequeueReusableCell(
      withIdentifier:
TableView.CellIdentifiers.searchResultCell,
      for: indexPath) as! SearchResultCell

    let searchResult = list[indexPath.row]
    cell.configure(for: searchResult)
    return cell
  }
}
```

The same thing happens here. The various `if` statements have been replaced by a `switch` and `case` statements for the four possibilities.

Note that `numberOfRowsInSection` returns 0 for `.notSearchedYet` and no cells will ever be asked for. But because a switch must always be exhaustive, you also have to include a case for `.notSearchedYet` in `cellForRowAt`. Since it would be a bug if the code ever got there, you can use the built-in `fatalError()` function to help catch such a situation.

➤ Next up is `tableView(_:willSelectRowAt:)`:

```
func tableView(
  _ tableView: UITableView,
  willSelectRowAt indexPath: IndexPath
) -> IndexPath? {
  switch search.state {
  case .notSearchedYet, .loading, .noResults:
    return nil
  case .results:
    return indexPath
  }
}
```

It's only possible to tap on rows when the state is `.results`. So for all the other cases, this method returns `nil`. And for the `.results` case, you don't need to bind the results array because you're not using it for anything here.

➤ And finally, change `prepare(for:sender:)` to:

```
override func prepare(for segue: UIStoryboardSegue, sender:
Any?) {
  if segue.identifier == "ShowDetail" {
    if case .results(let list) = search.state {
      let detailViewController = segue.destination as!
DetailViewController
      let indexPath = sender as! IndexPath
      let searchResult = list[indexPath.row]
      detailViewController.searchResult = searchResult
    }
  }
}
```

Here you only care about the `.results` case, so writing an entire `switch` statement is a bit much. For situations like this, you can use the special `if case` statement to look at a single case.

There is one more change to make in **LandscapeViewController.swift**.

➤ Change the `if firstTime` block in `viewWillLayoutSubviews()` to:

```
if firstTime {
  firstTime = false

  switch search.state {
  case .notSearchedYet, .loading, .noResults:
    break
  case .results(let list):
    tileButtons(list)
  }
}
```

This uses the same pattern as before. If the state is `.results`, it binds the array of `SearchResult` objects to the temporary constant `list` and passes it along to `tileButtons()`. The reason you don't use a `if case` condition here is because you'll be adding additional code to the other cases soon. But, because these cases are currently empty, they must contain a `break` statement.

However, when multiple cases have the same action, you can combine them in a single `case` statement as you see above.

➤ Build and run to see if the app still works — it should!

I think enums with associated values are one of the most exciting features of Swift. Here you used them to simplify the way the `Search` state is expressed. No doubt you'll find many other great uses for them in your own apps!

➤ This is a good time to commit your changes.

Spin me right round

If you rotate to landscape while the search is still taking place, the app really ought to show an animated spinner to let the user know that an action is taking place. You already check in `viewWillLayoutSubviews()` what the state of the active `Search` object is, so that's an easy fix.

Show an activity indicator in landscape mode

➤ In **LandscapeViewController.swift**, add a new method to display an activity indicator:

```
private func showSpinner() {
  let spinner = UIActivityIndicatorView(style: .large)
```


```
    spinner.center = CGPoint(
      x: scrollView.bounds.midX + 0.5,
      y: scrollView.bounds.midY + 0.5)
    spinner.tag = 1000
    view.addSubview(spinner)
    spinner.startAnimating()
  }
```

This creates a new `UIActivityIndicatorView` object, puts it in the center of the screen, and starts animating it. You give the spinner the tag 1000, so you can easily remove it from the screen once the search is done.

➤ In `viewWillLayoutSubviews()` change the `.loading` case in the `switch` statement to call this new method – you'll have to move the `loading` case out of the combined case line too:

```
case .loading:
  showSpinner()
```

➤ Run the app. After starting a search, quickly rotate the phone to landscape. You should now see a spinner:



A spinner indicates a search is still taking place

Note: In the new method you add `0.5` to the spinner's `center` position. This kind of spinner is 37 points wide and high, which is not an even number. If you were to place the center of this view at the exact center of the screen at (284, 160) then it would extend 18.5 points to either end. The top-left corner of that spinner will be at coordinates (265.5, 141.5), making it look all blurry.

It's best to avoid placing objects at fractional coordinates. By adding 0.5 to both the X and Y position, the spinner is placed at (266, 142) and everything looks sharp. Pay attention to this when working with the `center` property and objects that have odd widths or heights.

Hide the landscape spinner when results are found

This is all great, but the spinner doesn't disappear when the actual search results are received. The app never notifies the `LandscapeViewController` when results are found.

There is a variety of ways you can choose to tell the `LandscapeViewController` that the search results have come in, but let's keep it simple.

➤ In **LandscapeViewController.swift**, add these two new methods:

```
// MARK: - Helper Methods
func searchResultsReceived() {
  hideSpinner()

  switch search.state {
  case .notSearchedYet, .loading, .noResults:
    break
  case .results(let list):
    tileButtons(list)
  }
}

// If you care about organization, then the following should go
under the
// Private Methods section
private func hideSpinner() {
  view.viewWithTag(1000)?.removeFromSuperview()
}
```

The private `hideSpinner()` method looks for the view with tag 1000 — the activity spinner — and then tells that view to remove itself from the screen.

You could have kept a reference to the spinner and used that, but for a simple situation such as this you might as well use a tag.

Because no one else has any strong references to the `UIActivityIndicatorView`, this instance will be deallocated. Note that you have to use optional chaining because `viewWithTag()` can potentially return `nil`.

The `searchResultsReceived()` method should be called from somewhere, of course, and that somewhere is the `SearchViewController`.

➤ In **SearchViewController.swift**'s `performSearch()` method, add the following line into the closure, below `self.tableView.reloadData()`:

```
self.landscapeVC?.searchResultsReceived()
```

The sequence of events here is quite interesting. When the search begins there is no `LandscapeViewController` object yet because the only way to start a search is from portrait mode.

But by the time the closure is invoked, the device may have rotated and if that happened `self.landscapeVC` will contain a valid reference.

Upon rotation, you also gave the new `LandscapeViewController` a reference to the active `Search` object. Now you just have to tell it that search results are available so it can create the buttons and fill them up with images.

Of course, if you're still in portrait mode by the time the search completes, then `self.landscapeVC` is `nil` and the call to `searchResultsReceived()` will simply be ignored due to the optional chaining — you could have used `if let` here to unwrap the value of `self.landscapeVC`, but optional chaining has the same effect and is shorter to write.

➤ Try it out. That works pretty well, eh?

> **Exercise:** Verify that network errors are also handled correctly when the app is in landscape orientation. Find a way to create, or fake, a network error and see what happens in landscape mode. Hint: if you don't want to use the Network Link Conditioner, the `sleep(5)` function will put your app to sleep for 5 seconds. Put that in the completion handler to give yourself some time to flip the device around.

Nothing found

You're not done yet. If there are no matches found, you should also tell the user about this if they're in landscape mode.

➤ First, add the following method to **LandscapeViewController.swift**:

```
private func showNothingFoundLabel() {
  let label = UILabel(frame: CGRect.zero)
  label.text = "Nothing Found"
```

```
    label.textColor = UIColor.label
    label.backgroundColor = UIColor.clear

    label.sizeToFit()

    var rect = label.frame
    rect.size.width = ceil(rect.size.width / 2) * 2    // make
  even
    rect.size.height = ceil(rect.size.height / 2) * 2  // make
  even
    label.frame = rect

    label.center = CGPoint(
      x: scrollView.bounds.midX,
      y: scrollView.bounds.midY)
    view.addSubview(label)
  }
```

You first create a `UILabel` object and give it text and a color — note that the color is the system `label` color so that the text would display correctly in either appearance. The `backgroundColor` property is set to `UIColor.clear` to make the label transparent.

The call to `sizeToFit()` tells the label to resize itself to the optimal size. You could have given the label a frame that was big enough to begin with, but I find this just as easy. This also helps when you're translating the app to a different language, in which case you may not know beforehand how large the label needs to be.

The only trouble is that you want to center the label in the view and as you saw before, that gets tricky when the width or height are odd — something you don't necessarily know in advance. So here you use a little trick to always force the dimensions of the label to be even numbers:

```
width = ceil(width/2) * 2
```


If you divide a number such as 11 by 2 you get 5.5. The `ceil()` function rounds up 5.5 to make 6, and then you multiply by 2 to get a final value of 12. This formula always gives you the next even number if the original is odd. You only need to do this because these values have type `CGFloat`. If they were integers, you wouldn't have to worry about fractional parts.

> **Note:** Because you're not using a hardcoded number such as 480 or 568 but `scrollView.bounds` to determine the width of the screen, the code to center the label works correctly on all screen sizes.

➤ Inside the `switch` statement in `viewWillLayoutSubviews()`, call the new method from the case for `.noResults`:

```
case .noResults:
  showNothingFoundLabel()
```

➤ Run the app and search for something ridiculous (**ewdasuq3sadf843** will do). When the search is done, flip to landscape.



Yup, nothing found here either

It doesn't work properly yet if you flip to landscape while the search is taking place. Of course, you also need to put some logic in `searchResultsReceived()`.

➤ Change the `switch` statement in that method to:

```
switch search.state {
case .notSearchedYet, .loading:
  break
case .noResults:
  showNothingFoundLabel()
case .results(let list):
  tileButtons(list)
}
```

Now you should have all your bases covered.

The Detail pop-up

The landscape view is that much more functional after all the refactoring and changes. But there's still one more thing left to do. The landscape search results are not buttons for nothing. The app should show the Detail pop-up when you tap an item.

This is fairly easy to achieve. When adding the buttons you can give them a *target-action* — a method to call when the Touch Up Inside event is received. Just like in Interface Builder, except now you hook up the event to the action method programmatically.

Show the Detail pop-up

➤ First, still in **LandscapeViewController.swift** add the method to be called when a button is tapped:

```
@objc private func buttonPressed(_ sender: UIButton) {
  performSegue(withIdentifier: "ShowDetail", sender: sender)
}
```

Even though this is an action method, you didn't declare it as `@IBAction`. That is only necessary when you want to connect the method to something in Interface Builder. Here you make the connection via code, so you can skip the `@IBAction` annotation.

Also note that the method has the `@objc` attribute — as you learnt previously with *MyLocations*, you need to tag any method that is identified via a `#selector` with the `@objc` attribute. So, that would seem to indicate that you'll be calling this new method using a `#selector`, right?

Pressing the button simply triggers a segue, and you'll get to the segue part in a moment. But first, you should hook up the buttons to the above method.

➤ Add the following two lines to the button creation code in `tileButtons()`:

```
button.tag = 2000 + index
button.addTarget(
  self,
  action: #selector(buttonPressed),
  for: .touchUpInside)
```

First you give the button a tag, so you know to which index in the `.results` array this button corresponds. That's needed in order to pass the correct `SearchResult` object to the Detail pop-up.

Also, if you replaced the `index` variable in the `for` loop earlier with a wildcard because of the Xcode compiler warning, this would be the time to revert that change.

Tip: You added 2000 to the index because tag 0 is used on all views by default, so asking for a view with tag 0 might actually return a view that you didn't expect. To avoid this kind of confusion, you simply start counting from 2000.

You also tell the button it should call the `buttonPressed()` method when it gets tapped.


➤ Next, add the `prepare(for:sender:)` method to handle the segue:

```
// MARK: - Navigation
override func prepare(for segue: UIStoryboardSegue, sender:
Any?) {
  if segue.identifier == "ShowDetail" {
    if case .results(let list) = search.state {
      let detailViewController = segue.destination as!
DetailViewController
      let searchResult = list[(sender as! UIButton).tag - 2000]
      detailViewController.searchResult = searchResult
    }
  }
}
```

This is almost identical to `prepare(for:sender:)` from `SearchViewController`, except now you don't get the index of the `SearchResult` object from an index-path, but from the button's tag minus 2000.


Of course, none of this will work unless you actually have a segue in the storyboard.

➤ Go to the Landscape scene in the storyboard and Control-drag from the yellow circle at the top to the Detail View Controller. Make it a **Present Modally** segue with the identifier set to **ShowDetail**. The storyboard should look like this now:



The storyboard after connecting the Landscape view to the Detail pop-up

➤ Run the app and check it out. It probably looks like this:



The pop-up in landscape mode is too wide

Fix the detail pop-up

Hmm … that's not quite what you were expecting, was it?

> **Exercise:** Do you know what went wrong?

Answer: When you removed the width constraint on the pop-up in order to support really large fonts after adding Dynamic Type support, you were only dealing with portrait mode. In portrait mode, generally, the even at its widest, the pop-up would look fine. But not in landscape mode …


There are several ways to fix this:

1. Add the width constraint back so that the pop-up always displays at a reasonable size whether in portrait or landscape mode.
2. Set up separate constraints for landscape mode for the pop-up so that it isn't so wide.

While option #1 is easier, option #2 will make the app function better for each device orientation. So let's go with option #2.


You could, of course, add outlets for the relevant constraints and change them depending on the device orientation. But that's something that you're already familiar with. Let's learn a different way that teaches you how to set up constraints based on traits :]

➤ Open the storyboard, select **Pop-up View**, go to the **Size inspector**, select the **Align Leading to:** constraint to the Safe Area and double click it to get the constraint editor:



The constraint editor

➤ Click the + (plus) button next to **Constant** to be able to add a custom Constant value based on a few factors available from the new popup which opens:




The variation options

You can add variations based on the size classes you already learnt about when you set up the landscape view. The new dialog is pre-configured for the currently selected device and orientation that you selected via the IB toolbar.

So, you would be adding a new variation for an iPhone SE in landscape mode at this point if you went with the default values.

➤ Click **Add Variation**.

You should now get a new value under Constant for the specific size class variation you requested:



The new variation value

➤ Enter **150** as the new value – notice how the leading constraint changes on the canvas for your pop-up view.

➤ Similarly set up a new variation value of **150** for the trailing constraint too.

Your pop-up view looks much more compact in Interface Builder now. But what about other size classes?

➤ Use the Interface Builder toolbar to switch your preview to a larger device like the **iPhone 11 Pro Max**.

You'll notice that the pop-up view is again too wide. This is because the iPhone 11 Pro Max (and similar devices) have a Regular size class for the height when in landscape mode.

➤ Add two new variations — one for leading and another for trailing — for this size class too. Feel free to adjust the spacing as you see fit if you think a value of 150 is not enough.

Now, your detail pop-up looks much better in landscape:



The final pop-up in landscape mode

Hide the pop-up on rotation

Cool! But what happens when you rotate back to portrait with a Detail pop-up showing? Unfortunately, it sticks around. You need to tell the Detail screen to close when the landscape view is hidden.

➤ In **SearchViewController.swift**, in `hideLandscape(with:)`, add the following lines to the `animate(alongsideTransition:)` animation closure:

```
if self.presentedViewController != nil {
  self.dismiss(animated: true, completion: nil)
}
```

In the Console output you should see that the `DetailViewController` is properly deallocated when you rotate back to portrait.

➤ If you're happy with the way the code works, then let's commit it. If you also made a branch, then merge it back into the main branch.

You can find the project files for this chapter under **40-Refactoring** in the Source Code folder.

Chapter 41: Internationalization

By Fahim Farook

So far, the apps you've made in this book have all been in English. No doubt the United States is the single biggest market for apps, followed closely by Asia. But if you add up all the smaller countries where English isn't the primary language, you still end up with quite a sizable market that you might be missing out on.

Fortunately, iOS makes it very easy to add support for other languages to your apps, a process known as *internationalization*. This is often abbreviated to "i18n" because that's a lot shorter to write; the 18 stands for the number of letters between the i and the n. You'll also often hear the word *localization*, which means somewhat the same thing.


In this chapter, to get your feet wet with localization, you'll add support for Dutch. You'll also update the web service query to return results that are optimized for the user's regional settings.

You'll cover the following items:

- **Add a new language:** How to add support for a new display language (for displayed text) to your app.
- **Localize on-screen text:** How to localize text values used in code.
- **InfoPlist.strings:** Localize Info.plist file settings such as the app name.
- **Regional Settings:** Modify the web query to send the device language and region to get localized search results.

Add a new language

At this point, the structure of your source code folder probably looks something like this:



The files in the source code folder

There is a subfolder named **Base.lproj** that contains at least the storyboard, **Main.storyboard**. The Base.lproj folder is for files that can be localized. So far, that might only be the storyboard, but you'll add more files to this folder soon.


When you add support for another language, a new **XX.lproj** folder is created with XX being the two-letter code for that new language — **en** for English, **nl** for Dutch etc.

Localize a nib file

Let's begin by localizing a simple file, the **NothingFoundCell.xib**. Often nib files contain text that needs to be translated. You can simply make a new copy of the existing nib file for a specific language and put it in the right .lproj folder. When the iPhone is using that language, it will automatically load the translated nib.

➤ Select **NothingFoundCell.xib** in the Project navigator. Switch to the **File inspector** pane on the right.


Because the NothingFoundCell.xib file isn't in any XX.lproj folders, it does not have any localizations yet.



The NothingFoundCell has no localizations

➤ Click the **Localize...** button in the Localization section.


Xcode asks for confirmation because this involves moving the file to a new folder:



Xcode asks whether it's OK to move the file


➤ Choose **English** (*not* Base) and click **Localize** to continue.

Look in Finder and you will see there is a new **en.lproj** — for English — folder and NothingFoundCell.xib has been moved to that folder:



Xcode moved NothingFoundCell.xib to the en.lproj folder

The **File inspector** for **NothingFoundCell.xib** now lists English as one of the localizations.




The Localization section now contains an entry for English

Add support for a new language

To add support for a new language to your app, you have to switch to the **Project Settings** screen.


➤ Click on **StoreSearch** at the top of the Project navigator to open the settings page. From the central sidebar, choose **StoreSearch** under **PROJECT** (*not* under TARGETS).

If the central sidebar isn't visible, click the small icon at the top of the sidebar area to open it.



The Project Settings


➤ In the **Info** tab, under the **Localizations** section, press the + button:



Adding a new language

➤ From the pop-up menu choose **Dutch (nl)**.


Xcode now asks which resources you want to localize. Uncheck everything except for **NothingFoundCell.xib** and click **Finish**.



Choosing the files to localize

If you look in Finder again you'll notice that a new subfolder has been added, **nl.lproj**, and that it contains another copy of NothingFoundCell.xib.

That means there are now two nib files for `NothingFoundCell`. You can also see this in the Project navigator:



NothingFoundCell.xib has two localizations

Edit a language specific nib

Let's edit the Dutch version of this nib.

➤ Click on **NothingFoundCell.xib (Dutch)** to open it in Interface Builder.

➤ Change the label text to **Niets gevonden**.



That's how you say it in Dutch

It is perfectly all right to resize or move around items in a translated nib. You could make the whole nib look completely different if you wanted to — but that's probably a bad idea. Some languages, such as German, have very long words and in those cases you may have to tweak label sizes and fonts to get everything to fit.

If you run the app now, nothing will have changed. You have to switch the Simulator to use the Dutch language first. However, before you do that, you really should remove the app from the simulator, clean the project, and do a fresh build.


The reason for this is that the nibs were previously not localized. If you were to switch the simulator's language now, the app might still use the old, non-localized versions of the nibs, or it might not. It's better to be safe than tear your hair out wondering what went wrong, right?

> **Note:** For this reason, it's a good idea to already put all your nib files and storyboards in the **en.lproj** folder — or in **Base.lproj**, which we'll discuss shortly — when you create them. Even if you don't intend to internationalize your app any time soon, you don't want your users to run into the same problem later on. It's not nice to ask your users to uninstall the app — and lose their data — in order to be able to switch languages.

Switch device language

➤ Remove the app from the Simulator. Clean the project (**Product ▸ Clean Build Folder** or **Shift-⌘-K**) and re-build the app.


➤ Open the **Settings** app in the Simulator and go to **General ▸ Language & Region ▸ iPhone Language**. From the list pick **Nederlands (Dutch)**.



Switching languages in the Simulator

The Simulator will take a moment to switch between languages. This terminates the app if it was still running.

➤ Search for some nonsense text and the app will now respond in Dutch:



I'd be surprised if that did turn up a match

Pretty cool, just by placing some files in the **en.lproj** and **nl.lproj** folders, you have internationalized the app! You're going to keep the Simulator in Dutch for a while because the other nibs need translating too.

> **Note:** If the app crashes for you at this point, then the following might help. Quit Xcode. Reset the Simulator and then quit it. In Finder, go to your **Library** folder, **Developer/Xcode** and throw away the entire **DerivedData** folder. Empty your trashcan. Then open the *StoreSearch* project again and give it another try. Also, don't forget to switch the Simulator back to **Nederlands**.

Base internationalization

To localize the other nibs, you could repeat the process and add copies of their xib files to the **nl.lproj** folder. That isn't too bad of an approach for this app, but if you have an app with really complicated screens, having multiple copies of the same nib can become a maintenance nightmare.

Whenever you need to change something on a particular screen, you need to update all of those nibs for each language. There's a risk that you might overlook one or more nib files and they'll be out-of-sync. That's just asking for bugs — in languages that you probably don't speak!


To prevent this from happening, you can use *base internationalization*. With this feature enabled, you don't copy the entire nib, but only the text strings. This is what the **Base.lproj** folder is for.

Let's translate the other nibs.

➤ Select **LoadingCell.xib** in the Project navigator. In the **File inspector** press the **Localize...** button. This time use **Base** as the language.

Verify with Finder that LoadingCell.xib got moved into the **Base.lproj** folder.

➤ The Localization section in the **File inspector** for **LoadingCell.xib** now contains three options: Base (with a checkmark), English, and Dutch. Put a checkmark in front of **Dutch**:




Adding a Dutch localization

In Finder you can see that **nl.proj** doesn't get a copy of the nib, but a new file does get added: **LoadingCell.strings**.

➤ Click the disclosure triangle in front of **LoadingCell.xib** to expand it in the Project navigator and select the **LoadingCell.strings (Dutch)** file.

You should see something like the following:



The Dutch localization is a strings file

There is still only one nib, the one from the Base localization. The Dutch translation consists of a "strings" file with just the text from the labels, buttons, and other controls.

This particular strings file contains:

```
/* Class = "UILabel"; text = "Loading..."; ObjectID = "x7v-YC-
QRj"; */
"x7v-YC-QRj.text" = "Loading...";
```

The first line is a comment, just like in Swift. The second line says that the **text** property of the object with ID "x7v-YC-QRj" contains the text **Loading…**


The ID is an internal identifier that Xcode uses to keep track of the objects in your nibs; your own nib probably has a different ID than mine. You can see this ID in the Identity inspector for the label.

➤ Change the text from **Loading…** to **Zoeken…**

Tip: You can use the Assistant editor in Interface Builder to get a preview of your localized nib. Switch to **LoadingCell.xib (Base)** and open the Assistant editor. The tab bar at the top has a two linked circles icon on the right. Click on it to show a menu and choose **Preview** from the menu.

> **Note:** If you don't see the preview in the secondary pane, then try saving the nib file. If that doesn't work, then try quitting Xcode and restarting.

➤ In the bottom-right corner it says English. Click this to switch to a Dutch preview.



The Assistant editor shows a preview of the translation

➤ Do a **Product ▸ Clean Build Folder** (to be safe) and run the app again.

➤ Repeat the steps to add a Dutch localization for **Main.storyboard**. It already has a Base localization so you simply have to put a check in front of **Dutch** in the File inspector.

For the Search View Controller screen, two things need to change: the placeholder text in the Search Bar and the labels on the Segmented Control.


➤ In **Main.strings (Dutch)** change the placeholder text to **Naam van artiest, nummer, album**.

```
"68e-CH-NSs.placeholder" = "Naam van artiest, nummer, album";
```

The segment labels will become: **Alles**, **Muziek**, **Software**, and **E-boeken**.

```
"Sjk-fv-Pca.segmentTitles[0]" = "Alles";
"Sjk-fv-Pca.segmentTitles[1]" = "Muziek";
"Sjk-fv-Pca.segmentTitles[2]" = "Software";
"Sjk-fv-Pca.segmentTitles[3]" = "E-boeken";
```

Of course, your object IDs are going to be different - so don't rely on the IDs to find the right values in the file.



The localized SearchViewController

➤ For the Detail pop-up, you only need to change the **Type:** label to say **Soort:**


```
"DCQ-US-EVg.text" = "Soort:";
```

You don't need to change these:

```
"ZYp-Zw-Fg6.text" = "Genre:";
"yz2-Gh-kzt.text" = "Kind Value";
"Ph9-wm-1LS.text" = "Artist Name";
"JVj-dj-Iz8.text" = "Name";
"7sM-UJ-kWH.text" = "Genre Value";
"xOH-GC-bHs.normalTitle" = "$9.99";
```

These labels can remain the same because you will replace them with values from the `SearchResult` object anyway. Also, "Genre" is the same in both languages.

> **Note:** If you wanted to, you could even remove the text that doesn't need localization from the strings file. If a localized version for a specific resource is missing for the user's language, iOS will fall back to the one from the Base localization.



The pop-up in Dutch


Thanks to Auto Layout, the labels automatically resize to fit the translated text. A common issue with localization is that English words tend to be shorter than words in other languages, so you have to make sure your labels are big enough to accommodate any language. With Auto Layout that is a piece of cake.

The Landscape View Controller doesn't have any text to translate.

➤ There is no need to give **SearchResultCell.xib** a Dutch localization — there is no on-screen text in the nib itself — but do give it a Base localization. This prepares the app for the future, should you need to localize this nib at some point.

When you're done, there shouldn't be any **xib** files outside the **.lproj** folders. That's it for the nibs and the storyboard. Not so bad, was it? I'd say all these changes are commit-worthy.

Tip: You can also test localizations by changing the settings for the active scheme. Click on **StoreSearch** in the active scheme selector in the Xcode toolbar — next to the Simulator name — and choose **Edit Scheme**.



In the **Options** tab you can change the **App Language** and **App Region** settings. That's a bit quicker than restarting the Simulator.

Localize on-screen text

Even though the nibs and storyboard have been translated, not all of the text is. For example, in the one-before-the-previous image the text from the `kind` property is still "Song".

While in this case you could probably get away with it — everyone in the world probably knows what the word "Song" means — not all of the text from the `type` property will be understood by non-English speaking users.

Localize text used in code

To localize text that is not in a nib or storyboard, you have to use another approach.

➤ In **SearchResult.swift**, make sure the Foundation framework is imported:

```
import Foundation
```

➤ Then replace the `type` property with:

```
var type: String {
  let kind = self.kind ?? "audiobook"
  switch kind {
  case "album":
    return NSLocalizedString(
      "Album",
      comment: "Localized kind: Album")
  case "audiobook":
    return NSLocalizedString(
      "Audio Book",
      comment: "Localized kind: Audio Book")
  case "book":
    return NSLocalizedString(
      "Book",
      comment: "Localized kind: Book")
  case "ebook":
    return NSLocalizedString(
      "E-Book",
      comment: "Localized kind: E-Book")
  case "feature-movie":
    return NSLocalizedString(
      "Movie",
      comment: "Localized kind: Feature Movie")
  case "music-video":
    return NSLocalizedString(
      "Music Video",
      comment: "Localized kind: Music Video")
  case "podcast":
    return NSLocalizedString(
      "Podcast",
      comment: "Localized kind: Podcast")
  case "software":
    return NSLocalizedString(
      "App",
      comment: "Localized kind: Software")
  case "song":
    return NSLocalizedString(
      "Song",
      comment: "Localized kind: Song")
  case "tv-episode":
    return NSLocalizedString(
```

```
        "TV Episode",
        comment: "Localized kind: TV Episode")
    default:
      return kind
    }
  }
```

Tip: Rather than typing in the above, you can use Xcode's powerful Regular Expression Replace feature to make those changes in just a few seconds.

Go to the **Find navigator** — the tab with the magnifying glass icon, on the left sidebar — and change its mode from Find to **Replace > Regular Expression**.

In the search box type: **return "(.+)"** and press **return** to search.

In the replacement box type:

return NSLocalizedString("$1", comment: "Localized kind: $1")

This looks for any lines that match the pattern *return "something"*. Whatever that *something* is will be put in the $1 placeholder of the replacement text.

Make sure only the relevant search results from **SearchResult.swift** are selected — you don't want to make this change to all of the search results! Click **Replace** to finish.

Thanks to Scott Gardner for the tip!

The structure of `type` is still the same as before, but instead of doing:

```
return "Album"
```

It now does:

```
return NSLocalizedString("Album", comment: "Localized kind:
Album")
```

Slightly more complicated, but also a lot more flexible.

`NSLocalizedString()` takes two parameters: the text to return, `"Album"`, and a comment, `"Localized kind: Album"`.

Here is the cool thing: if your app includes a file named **Localizable.strings** for the user's language, then `NSLocalizedString()` will look up the text ("Album") and return the translation as specified in Localizable.strings.

If no translation for that text is present, or there is no Localizable.strings file, then `NSLocalizedString()` simply returns the text as-is.

➤ Run the app again. The "Type:" field in the pop-up — or "Soort:" in Dutch — should still show the same text values as before because you haven't translated anything yet.

First, you need to create an empty Localizable.strings file.

➤ Right-click on the **StoreSearch** folder in the Project navigator, select **New File...**, select the **Strings File** template under **iOS - Resource** and tap **Next**. Save the file as **Localizable.strings**.

➤ Select **Localizable.strings**, in the File inspector (on the right) click **Localize...**, select **English** from the dropdown, and click **Localize**.

This creates an empty English **Localizable.strings** file. You need to use a command line tool named **genstrings** to populate the file with text strings from your source files. This requires a trip to the Terminal.

Generate localizable text strings

➤ Open a Terminal, `cd` to the folder that contains the *StoreSearch* project. You want to go into the folder that contains the actual source files. On my system that is:

```
cd ~/Desktop/StoreSearch/StoreSearch
```

Then, type the following command:

```
genstrings *.swift -o en.lproj
```

This looks at all your source files (***.swift**) and writes the text strings from those source files to the **Localizable.strings** file in the **en.lproj** folder.

If you open the Localizable.strings file now, this is what it should contain:

```
/* Localized kind: Album */
"Album" = "Album";

/* Localized kind: Software */
"App" = "App";

/* Localized kind: Audio Book */
"Audio Book" = "Audio Book";

/* Localized kind: Book */
```

```
"Book" = "Book";

/* Localized kind: E-Book */
"E-Book" = "E-Book";

/* Localized kind: Feature Movie */
"Movie" = "Movie";

/* Localized kind: Music Video */
"Music Video" = "Music Video";

/* Localized kind: Podcast */
"Podcast" = "Podcast";

/* Localized kind: Song */
"Song" = "Song";

/* Localized kind: TV Episode */
"TV Episode" = "TV Episode";
```

The things between the `/*` and `*/` symbols are the comments you specified as the second parameter of `NSLocalizedString()`.

They give the translator some context about where the string is supposed to be used in the app.


Tip: It's a good idea to make these comments as detailed as you can. In the words of fellow raywenderlich.com author Scott Gardner:

"The comment to the translator should be as detailed as necessary to not only state the words to be transcribed, but also the perspective, intention, gender frame of reference, etc. Many languages have different words based on these considerations. I translated an app into Chinese Simplified once and it took multiple passes to get it right because my original comments were not detailed enough."

➤ Change the "Song" line to:

```
"Song" = "SUPER HIT!";
```

➤ Now run the app again and search for music. For any search result that is a song, it will now say "SUPER HIT!" instead of "Song".



Where it used to say Song it now says SUPER HIT!

Of course, changing the text in the English localization doesn't make much sense. Reverse the change to Song and then we'll do it properly.

➤ In the **File inspector**, add a Dutch localization for this file. This creates a copy of Localizable.strings in the **nl.lproj** folder.

➤ Change the translations in the Dutch version of **Localizable.strings** to:

```
"Album" = "Album";
"App" = "App";
"Audio Book" = "Audioboek";
"Book" = "Boek";
"E-Book" = "E-Boek";
"Movie" = "Film";
"Music Video" = "Videoclip";
"Podcast" = "Podcast";
"Song" = "Liedje";
"TV Episode" = "TV serie";
```

If you run the app again, the product types will all be in Dutch. Nice!

Always use NSLocalizedString() from the beginning

There are a bunch of other strings in the app that need translation as well. You can search for anything that begins with " but it would have been a lot easier if you had used `NSLocalizedString()` from the start. Then all you would've had to do was run the **genstrings** tool and you'd get all the strings.

Now you have to comb through the source code and add `NSLocalizedString()` to all the text strings that will be shown to the user — mea culpa!

You should really get into the habit of always using `NSLocalizedString()` for strings that you want to display to the user, even if you don't care about internationalization right away.

Adding support for other languages is a great way for your apps to become more popular, and going back through your code to add `NSLocalizedString()` is not much fun. It's better to do it right from the start!

Here are the other strings I found that need to be `NSLocalizedString`-ified:

```
// DetailViewController, updateUI()
artistNameLabel.text = "Unknown"
priceText = "Free"

// LandscapeViewController, showNothingFoundLabel()
label.text = "Nothing Found"

// SearchResultCell, configure(for)
artistNameLabel.text = "Unknown"

// SearchViewController, showNetworkError()
title: "Whoops...",
message: "There was an error reading from the iTunes Store.
          Please try again.",
title: "OK"
```

➤ Add `NSLocalizedString()` around these strings. Don't forget to use descriptive comments!

For example, when instantiating the `UIAlertController` in `showNetworkError()`, you could write:

```
let alert = UIAlertController(
  title: NSLocalizedString("Whoops...",
  comment: "Error alert: title"),
  message: NSLocalizedString(
    "There was an error reading from the iTunes Store. Please
try again.",
    comment: "Error alert: message"),
  preferredStyle: .alert)
```

> **Note:** You don't need to use `NSLocalizedString()` with your `print()`'s. Debug output is really intended only for you, the developer, so it's best if it is in English, or whatever happens to be your native language.

➤ Run the **genstrings** tool again. Give it the same arguments as before. It will put a clean file with all the new strings in the **en.lproj** folder.

Unfortunately, there really isn't a good way to make genstrings merge new strings into existing translations. It will overwrite your entire file and throw away any changes that you made. There is a way to make the tool append its output to an existing file, but then you end up with a lot of duplicate strings.

> **Tip:** Always regenerate only the file in en.lproj and then copy over the missing strings to your other Localizable.strings files. You can use a tool such as FileMerge or Kaleidoscope to compare the two files to find the new strings. There are also several third-party tools on the Mac App Store that are a bit friendlier to use than genstrings.

You might also get a warning similar to the following if you weren't consistent in using the same comment for the same word when it appears in multiple places:

```
Warning: Key "Unknown" used with multiple comments "Artist name
label: Unknown" & "Artist name: Unknown"
```

If you check the Localizable.strings file, you'll notice that you don't have two instances of the word "Unknown" (or whatever the word was that generated the error) in the file. But there are two comments for the same word.

You can easily fix this — if you wanted to — by going back and using the same comment for the same word and then running the genstrings tool again.

➤ Add these new translations to the Dutch **Localizable.strings**:

```
"Nothing Found" = "Niets gevonden";

"There was an error reading from the iTunes Store. Please try
again." = "Er ging iets fout bij het communiceren met de iTunes
winkel. Probeer het nog eens.";

"Unknown" = "Onbekend";

"Whoops..." = "Foutje...";
```

It may seem a little odd that such a long string as "There was an error reading from the iTunes Store. Please try again." would be used as the lookup key for a translated string, but there really isn't anything wrong with it.

By the way, the semicolons at the end of each line are not optional. If you forget a semicolon, the Localizable.strings file cannot be compiled and the build will fail.

Some people write code for `NSLocalizedString` like this:

```
let s = NSLocalizedString("ERROR_MESSAGE23",
                  comment: "Error message on screen X")
```

The Localizable.strings file would then look like:

```
/* Error message on screen X */
"ERROR_MESSAGE23" = "Does not compute!";
```

This works, but I find it harder to read. It requires that you always have an English Localizable.strings as well. Note also that the text `"Unknown"` occurred only once in Localizable.strings even though it shows up in two different places in the source code. Each piece of text only needs to be translated once.

Localize dynamically constructed strings

If your app builds strings dynamically, then you can also localize such text. For example, in **SearchResultCell.swift**, `configure(for:)` you do:

```
artistNameLabel.text = String(
  format: "%@ (%@)",
  result.artist,
  result.type)
```

➤ Internationalize this as follows:

```
artistNameLabel.text = String(
  format: NSLocalizedString(
    "%@ (%@)",
    comment: "Format for artist name"),
  result.artist,
  result.type)
```

After running **genstrings** again, this shows up in Localizable.strings as:

```
/* Format for artist name */
"%@ (%@)" = "%1$@ (%2$@)";
```

If you wanted to, you could change the order of these parameters in the translated file. For example:

```
"%@ (%@)" = "%2$@ van %1$@";
```

It will turn the artist name label into something like this:



The "kind" now comes first, the artist name last

In this instance I would advocate the use of a special key rather than the literal string to find the translation. It's thinkable that your app will employ the format string `"%@ (%@)"` in some other place and you may want to translate that completely differently there.

I'd call it something like `ARTIST_NAME_LABEL_FORMAT` instead (this goes in the Dutch Localizable.strings):

```
/* Format for artist name label */
"ARTIST_NAME_LABEL_FORMAT" = "%2$@ van %1$@";
```

You also need to add this key to the English version of Localizable.strings:

```
/* Format for artist name label */
"ARTIST_NAME_LABEL_FORMAT" = "%1$@ (%2$@)";
```

Don't forget to change the code as well:

```
artistNameLabel.text = String(
  format: NSLocalizedString(
    "ARTIST_NAME_LABEL_FORMAT",                    // Change this
line
    comment: "Format for artist name"),
  result.artist,
  result.type)
```

Data-driven localization

There is one more thing I'd like to improve. Remember how in **SearchResult.swift** the `type` property is this enormous `switch` statement? That's "smelly" to me. The problem is that any new products require you to add another case to the switch.

For situations like these, it's better to use a *data-driven* approach. Here, that means you place the product types and their human-readable names in a data structure, a dictionary, rather than a code structure.

➤ Add the following dictionary to **SearchResult.swift**, inside the `class` (you may want to copy-paste this from `type` as it's almost identical):

```
private let typeForKind = [
  "album": NSLocalizedString(
    "Album",
    comment: "Localized kind: Album"),
  "audiobook": NSLocalizedString(
    "Audio Book",
    comment: "Localized kind: Audio Book"),
  "book": NSLocalizedString(
    "Book",
    comment: "Localized kind: Book"),
  "ebook": NSLocalizedString(
    "E-Book",
    comment: "Localized kind: E-Book"),
  "feature-movie": NSLocalizedString(
    "Movie",
    comment: "Localized kind: Feature Movie"),
  "music-video": NSLocalizedString(
    "Music Video",
    comment: "Localized kind: Music Video"),
  "podcast": NSLocalizedString(
    "Podcast",
    comment: "Localized kind: Podcast"),
  "software": NSLocalizedString(
    "App",
    comment: "Localized kind: Software"),
  "song": NSLocalizedString(
    "Song",
    comment: "Localized kind: Song"),
  "tv-episode": NSLocalizedString(
    "TV Episode",
    comment: "Localized kind: TV Episode")
]
```

Now the code for `type` becomes really short:

```
var type: String {
  let kind = self.kind ?? "audiobook"
  return typeForKind[kind] ?? kind
}
```

It's nothing more than a simple dictionary lookup.


The `??` is the nil coalescing operator. Remember that dictionary lookups always return an optional, just in case the key you're looking for — `kind` in this case — does not exist in the dictionary. That could happen if the iTunes web service added new product types. If the dictionary gives you `nil`, the `??` operator simply returns the original value of kind.

InfoPlist.strings

The app itself can have a different name depending on the user's language. The name that is displayed on the iPhone's home screen comes from the **Bundle name** setting in the **Info** tab, or if present, the **Bundle display name** setting.

To localize the strings from the Info tab, you need a file named **InfoPlist.strings**.

➤ Add a new file to the project. In the template chooser scroll down to the **Resource** group and choose **Strings File**. Name it **InfoPlist.strings** (the capitalization matters!).



Adding a new Strings file to the project

➤ Select **InfoPlist.strings** and click the **Localize...** button from the File inspector. Choose the **English** localization.

➤ Also add a **Dutch** localization for this file.

➤ Open the Dutch version and add the following line:

```
CFBundleDisplayName = "StoreZoeker";
```

The key for the "Bundle display name" setting is `CFBundleDisplayName`.

Dutch readers, sorry for the silly name. This is the best I could come up with. Feel free to substitute your own.

➤ Run the app and close it so you can see its icon. The Simulator's springboard should now show the translated app name:



Even the app's name is localized!

If you switch the Simulator back to English, the app name is StoreSearch again (and of course, all the other text is back to English as well).

> **Note:** If you were testing for Dutch localizations using the scheme options, then you will not see the app name changed to Dutch in the springboard – the scheme options only affect the app only. In this case, you'd still have to switch your simulator (or device) to Dutch in order to see the name change.

Regional settings

I don't know if you noticed in some of the earlier screenshots, but even though you switched the language to Dutch, the prices of the products still show up in US dollars instead of Euros. That's for two reasons:

1. The language settings are independent of the regional settings. How currencies and numbers are displayed depends on the region settings, not the language.
2. The app does not specify anything about country or language when it sends the requests to the iTunes store, so the web service always returns prices in US dollars.

Fix web request to include language and region

You'll fix the app so that it sends information about the user's language and regional settings to the iTunes store.

➤ In **Search.swift**, change the `iTunesURL(searchText:category:)` method as follows:

```
private func iTunesURL(
  searchText: String,
  category: Category
) -> URL {
  // Add the following 3 lines
  let locale = Locale.autoupdatingCurrent
  let language = locale.identifier
  let countryCode = locale.regionCode ?? "en_US"
  . . .
  // Modify the URL string
  let urlString = "https://itunes.apple.com/search?" +
    "term=\(encodedText)&limit=200&entity=\(kind)" +
    "&lang=\(language)&country=\(countryCode)"

  let url = URL(string: urlString)
  print("URL: \(url!)")            // Add this
  return url!
}
```

The regional settings are also referred to as the user's *locale* and of course there is an object to represent it — `Locale`. You get a reference to the `autoupdatingCurrent` locale.

This locale object is called "autoupdating" because it always reflects the current state of the user's locale settings. In other words, if the user changes their regional information while the app is running, the app will automatically use these new settings the next time it does something with the `Locale` object.

From the `locale` object you get the language and the country code. You then put these two values into the URL using the `&lang=` and `&country=` parameters. Because `locale.regionCode` may be `nil`, we use `?? "US"` as a failsafe.

The `print()` lets you see what exactly the URL will be.

➤ Run the app and do a search. Xcode should output something like the following if you have English set as the language:

```
https://itunes.apple.com/search?
term=bird&limit=200&entity=&lang=en_US&country=US
```

It added "en_US" as the language identifier and just "US" as the country. For products that have descriptions (such as apps) the iTunes web service will return the English version of the description. The prices of all items will have USD as the currency.

> **Note:** It's also possible you got an error message, which happens when the locale identifier returns something nonsensical such as `nl_US`. This is due to the combination of language and region settings on your Mac or the Simulator. If you also change the region (see below), the error should disappear. The iTunes web service does not support all combinations of languages and regions — so an improvement to the app would be to check the value of `language` against a list of allowed languages. I'll leave that as an exercise for you.

Test for region changes

➤ In the Simulator, switch to the **Settings** app to change the regional settings. Go to **General ▸ Language & Region ▸ Region**. Select **Netherlands**.

If the Simulator is still in Dutch, then it is under **Algemeen ▸ Taal en Regio ▸ Regio**. Change it to **Nederland**. If the language is not set to Dutch, then set the language to Dutch now.

➤ Run StoreSearch again and repeat the search.

Xcode now says:

```
https://itunes.apple.com/search?
term=bird&limit=200&entity=&lang=nl_NL&country=NL
```

The language and country are both now set to NL — for the Netherlands. If you tap on a search result you'll see that the price is now in Euros:



The price according to the user's region settings

Of course, you have to thank `NumberFormatter` for this. It now knows the region settings are from the Netherlands, so it uses a comma for the decimal point.

And because the web service now returns `"EUR"` as the currency code, the number formatter puts the Euro symbol in front of the amount. You can get a lot of functionality for free if you know which classes to use!

That's it as far as internationalization goes. It takes only a small bit of effort, but it definitely pays back.

You can put the Simulator back to English now.

➤ It's time to commit because you're going to make some big changes in the next section.

If you've also been tagging the code, you can call this v0.9, as you're rapidly approaching the 1.0 version that is ready for release.

You can find the project files for this chapter under **41-Internationalization** in the Source Code folder.

Chapter 42: The iPad

By Fahim Farook

Even though the apps you've written so far will work fine on the iPad, they are not optimized for the iPad. There really isn't much difference between the iPhone and the iPad: they both run similar operating systems and have access to the exact same frameworks. But the iPad has a much bigger screen and that makes all the difference.Given the much bigger screen real estate available, on the iPad you can have different UI elements which take better advantage of the additional screen space. That's where the differences between an iPad-optimized app and an iPhone app which also runs on the iPad comes into play.

In this chapter you will cover the following:


- **Deployment platforms:** A brief explanation of how to switch from universal mode to supporting a specific platform only.
- **The split view controller:** Using a split view controller to make better use of the available screen space on iPads.
- **Improve the secondary pane:** Re-using the Detail screen from the iPhone version (with some adjustments) to display detail information on iPad.
- **Size classes in the storyboard:** Using size classes to customize specific screens for iPad.
- **Your own popover:** Create a menu popover to be displayed on the iPad.
- **Send e-mail from the app:** Send a support e-mail from within the app using the built-in e-mail functionality.
- **Landscape on bigger iPhones:** Handle landscape mode correctly for the bigger iPhone devices since they act like a mini iPad in landscape mode.

Deployment platforms

All new iOS projects created with Xcode support both the iPhone and iPad platforms by default. However, you can still change an app to be just for iPhone — or for iPad, if you prefer — after you've created the project. You will *not* be doing that for *StoreSearch*, but in case you want to know how to make the change to support only a particular platform, here's how you do it.

➤ Go to the **Project Settings** screen and select the StoreSearch target.


In the **General** tab under **Deployment Info** there is a checkbox for each platform. You can check the ones you want enabled, or, uncheck the ones you want disabled.



How to change device support

> **Note:** While you can also enable Mac support (via Mac Catalyst) so that the same code for your iOS app also powers your macOS app, whether this will work for your particular app or not will depend on the features and third-party libraries that you use.

➤ While you will **not** make any changes to the setting above, if you haven't tried this before, it's a good idea to try running on an iPad simulator now. Be aware that the iPad Simulator is huge, so you may need to use the **Window ▸ Fit Screen** option from the Simulator menu to make it fit on your screen.



StoreSearch in the iPad Simulator

This works fine, but as I said before, simply blowing up the interface to iPad size does not take advantage of all the extra space the bigger screen offers. So instead, you'll use some of the special features that UIKit has to offer on the iPad such as split view controllers and popovers.

The split view controller

On the iPhone, with a few exceptions such as when you embed view controllers inside another, a view controller generally manages the whole screen.

On the iPad, because the display is so much bigger, it is common for view controllers to manage just a section of the screen. Often, you will want to combine different types of content in the same screen.

A good example of this is the split view controller. It has two panes: a smaller pane on the left — the "primary" pane — usually containing a list of items, and a larger right pane — the "secondary" pane — showing more information about the thing you have selected in the primary list. Each pane has its own view controller.

If you've used an iPad before, then you've seen the split view controller in action because it's used in many standard apps such as Mail and Settings.



The split view controller in landscape and portrait orientations

If the iPad is in landscape mode, the split view controller has enough room to show both panes at the same time. However, in portrait mode, only the secondary view controller is visible and the app provides a button that will slide the primary pane into view. Or, you can swipe the screen to reveal/hide it.

In this section, you'll convert the app to use a split view controller. This has some consequences for the organization of the user interface.

Check the iPad orientations

Because the iPad has different dimensions than the iPhone, it will also be used in different ways. Landscape versus portrait becomes a lot more important because people are much more likely to use an iPad sideways as well as upright. Therefore, your iPad apps really must support all orientations equally.

This implies that an iPad app shouldn't make landscape show a completely different UI than portrait. So, what you did with the iPhone version of the app won't fly on the iPad — you can no longer show the `LandscapeViewController` when the user rotates the device. That feature goes out the window.

➤ On the **Info** tab there will be a **Supported interface orientations (iPhone)** item with three items under it, and a **Supported interface orientations (iPad)** item with four items under it.

⌄ Supported interface orientations (iPhone)	Array	(3 items)
Item 0	String	Portr...
Item 1	String	Land...
Item 2	String	Land...
Application supports indirect input events	Boolean	YES
› App Transport Security Settings	Dictionary	(1 item)
› Application Scene Manifest	Dictionary	(2 items)
Bundle OS Type code	String	$(PRODUC
Localization native development region	String	$(DE...
⌄ Supported interface orientations (iPad)	Array	(4 items)
Item 0	String	Portr...
Item 1	String	Portr...
Item 2	String	Land...
Item 3	String	Land...

The supported device orientations in Info tab

The iPad has its own supported orientations. On the iPhone, you usually don't want to enable Upside Down but on the iPad you do. If the settings do not correspond to the above, do make sure to change them to match the screenshot.

Next, run the app on the iPad simulator and verify that the app always rotates so that the search bar is on top, no matter what orientation you put the iPad in.

Now, let's put that split view controller into the app.

Add a split view controller


Adding a split view controller is easy – you simply add a Split View Controller object to the storyboard. The split view is only visible on the iPad; on the iPhone it stays hidden.

➤ Open **Main.storyboard**. If you are still in landscape mode, switch back to portrait mode now.

➤ Drag a new **Split View Controller** on to the canvas.

➤ The Split View Controller comes with several scenes pre-attached. Remove the three extra view controllers, leaving just the Split View Controller.

Here's the final result after I was done:



The storyboard with the new Split View Controller

A split view controller has a relationship segue with two child view controllers, one for the smaller primary pane on the left and one for the bigger secondary pane on the right.

The obvious candidate for the primary pane is the `SearchViewController`, and the `DetailViewController` will go into the secondary pane.

➤ Control-drag from the Split View Controller to the Search scene. Choose **Relationship Segue – primary view controller**.


This puts a new arrow between the split view and the Search screen.

➤ Control-drag from the Split View Controller to the Detail Scene. Choose **Relationship Segue – secondary view controller**.

The split view must become the initial view controller so it gets loaded by the storyboard first.


➤ Pick up the arrow that currently points to the Search scene — tap on the arrow to select it first and then drag — and drag it over to the Split View Controller. You can also check the **Is Initial View Controller** option in the Attributes inspector for the Split View Controller instead of dragging the arrow.

Now, everything is connected:



The primary and secondary panes are connected to the split view

That should be enough to get the app up and running with a split view — albeit with some issues:



The app in a split view controller

It will still take a bit of effort to make everything look good and work well, but this was the first step.

If you play with the app you'll notice that it still uses the logic from the iPhone version, and that doesn't always work so well now that the UI sits in a split view. For example, tapping the price button from the new Detail pane crashes the app...

You'll fix the app over the course of this chapter to make sure it doesn't do anything funny on the iPad!

Fix the primary pane

The primary pane works fine in landscape, but in portrait mode it's not visible. You can make it appear by:

1. Tapping the back button on the navigation bar.
2. Swiping from the left edge of the screen — try it —.

The trouble is, the back button — what's known as the *display mode* button — is confusing when it's named "Back". You want it to say "Search" instead.

The fix is very simple – you just have to give the view controller from the primary pane a title.

➤ In **SearchViewController.swift**, add the following line to `viewDidLoad()`:

```
title = NSLocalizedString("Search", comment: "split view primary
button")
```

Of course, you're using `NSLocalizedString()` because this is text that appears to the user. Hint: the Dutch translation is "Zoeken".

➤ Run the app and now you should have the display mode button title showing up correctly as "Search".

> **Exercise:** On the iPad, rotating to landscape doesn't bring up the special Landscape View Controller anymore. That's good because we don't want to use it in the iPad version of the app, but you haven't changed anything in the code. Can you explain what stops the landscape view from appearing?

Answer: The clue is in `SearchViewController`'s `willTransition()`. This shows the landscape view when the new vertical size class becomes *compact*. But on the iPad both the horizontal and vertical size class are always *regular*, regardless of the device orientation. As a result, nothing happens upon rotation.

Improve the secondary pane

The secondary pane needs some more work — it just doesn't look very good yet. Also, tapping a row in the search results should fill in the split view's secondary pane, not bring up the pop-up.

You're using `DetailViewController` for both purposes — pop-up and secondary pane. So, let's give it a boolean that determines how it should behave. On the iPhone it will be a pop-up; on the iPad it will not.

To pop-up or not to pop-up

➤ Add the following instance variable to **DetailViewController.swift**:


```
var isPopUp = false
```

➤ Replace `viewDidLoad()` with the following:

```
override func viewDidLoad() {
  super.viewDidLoad()
  if isPopUp {
    popupView.layer.cornerRadius = 10
    let gestureRecognizer = UITapGestureRecognizer(
      target: self,
      action: #selector(close))
    gestureRecognizer.cancelsTouchesInView = false
    gestureRecognizer.delegate = self
    view.addGestureRecognizer(gestureRecognizer)
    // Gradient view
    view.backgroundColor = UIColor.clear
    let dimmingView = GradientView(frame: CGRect.zero)
    dimmingView.frame = view.bounds
    view.insertSubview(dimmingView, at: 0)
  } else {
    view.backgroundColor = UIColor(patternImage: UIImage(
      named: "LandscapeBackground")!)
    popupView.isHidden = true
  }
  if searchResult != nil {
    updateUI()
  }
}
```

With the gesture recognizer code inside the `if isPopUp` check, tapping the background has no effect on the iPad. Likewise for the line that sets the background color to `clearColor`.

The `else` branch always hides the pop-up view until a `SearchResult` is selected in the table view. The background gets a pattern image to make things look a little nicer — it's the same image you used with the landscape view on the iPhone.



Making the secondary pane look better

Initially this means the `DetailViewController` doesn't show anything except for the patterned background. So, you need `SearchViewController` to tell the `DetailViewController` that a new `SearchResult` has been selected.

Previously, on an iPhone, `SearchViewController` created a new instance of `DetailViewController` every time you tapped a row, but now, on an iPad, it will need to use the existing instance from the split view's secondary pane instead. But how does the `SearchViewController` know what that instance is?

You will have to give it a reference to the `DetailViewController`. A good place for that would be in `SceneDelegate` where you can set up access to the Split View Controller and its child views.

➤ Add the following properties to **SceneDelegate.swift**, inside the class:

```
// MARK: - Properties
var splitVC: UISplitViewController {
  return window!.rootViewController as! UISplitViewController
}

var searchVC: SearchViewController {
  let nav = splitVC.viewControllers.first as!
UINavigationController
  return nav.viewControllers.first as! SearchViewController
}

var detailVC: DetailViewController {
  let nav = splitVC.viewControllers.last as!
UINavigationController
  return nav.viewControllers.first as! DetailViewController
}
```

These three computed properties refer to the various view controllers in the app:

- `splitVC`: The top-level Split View Controller.
- `searchVC`: The Search screen in the primary pane of the split view.
- `detailVC`: The Detail screen in the secondary pane of the split view.

Note that both the primary pane and secondary pane of the Split View Controller has a built-in navigation controller which embeds each view controller. So you need to get the actual view controller you are interested in from each navigation controller's list of views.

By making properties for these view controllers, you can easily refer to them without having to go digging through the view hierarchy as you did for the previous apps.

➤ Now, add a new property to **SearchViewController.swift** to hold a reference to the `DetailViewController`:

```
weak var splitViewDetail: DetailViewController?
```

Notice that you make this property `weak`. The `SearchViewController` isn't responsible for keeping the `DetailViewController` alive since that's the job of the split view controller. It would work fine without `weak` but specifying it makes the relationship clearer.

The variable is an optional because it will be `nil` when the app runs on an iPhone.

➤ Add the following line to `scene(_:willConnectTo:options:)` in **SceneDelegate.swift**:

```
searchVC.splitViewDetail = detailVC
```

➤ To change what happens when the user taps a search result on the iPad, replace `tableView(_:didSelectRowAt:)` in **SearchViewController.swift** with:

```
func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  searchBar.resignFirstResponder()

  if view.window!.rootViewController!.traitCollection
    .horizontalSizeClass == .compact {
    tableView.deselectRow(at: indexPath, animated: true)
    performSegue(withIdentifier: "ShowDetail",
                 sender: indexPath)
  } else {
    if case .results(let list) = search.state {
      splitViewDetail?.searchResult = list[indexPath.row]
    }
  }
}
```

On the iPhone, this still does the same as before — pop up a new Detail screen — but on the iPad it assigns the `SearchResult` object to the existing `DetailViewController` that lives in the secondary pane.

> **Note:** To determine whether the app is running on an iPhone, you look at the horizontal size class of the window's root view controller, which is the `UISplitViewController`. On the iPhone, the horizontal size class is always *compact* — well, almost always since there are some exceptions, but more about that shortly. On the iPad it is always *regular*.
>
> The reason you're looking at the size class from the root view controller and not `SearchViewController` is that the latter's size class is always horizontally *compact*, even on iPad, because it sits inside the split view's primary pane.

These changes by themselves don't update the contents of the labels in the `DetailViewController`. So, let's make that happen.

The ideal place to update the labels is in a *property observer* on the `searchResult` variable. After all, the user interface needs to be updated right after you put a new `SearchResult` object into this variable.

➤ Change the declaration of `searchResult` in **DetailViewController.swift**:

```
var searchResult: SearchResult! {
  didSet {
    if isViewLoaded {
      updateUI()
    }
  }
}
```

You've seen this pattern a few times before. You provide a `didSet` observer to perform certain functionality when the value of a property changes. After `searchResult` has changed, you call the `updateUI()` method to set the text on the labels.


Notice that you first check whether the controller's view is already loaded. It's possible that `searchResult` is given an object when the `DetailViewController` hasn't loaded its view yet — which is exactly what happens in the iPhone version of the app. In that case, you don't want to call `updateUI()` as there is no user interface yet to update. The `isViewLoaded` check ensures this property observer only gets used when on an iPad.

➤ Add the following line to the bottom of `updateUI()`:

```
popupView.isHidden = false
```

This makes the view visible when on the iPad — recall that in `viewDidLoad()` you hid the pop-up because there was nothing to show yet.

➤ Run the app. Now the secondary pane should show details about the selected search result. Notice that the row in the table stays selected as well.



The secondary pane shows additional info about the selected item

That looks good, but there are a few other small improvements to make.

Remove input focus on iPad

On the iPhone, it made sense to give the search bar the input focus so the keyboard appeared immediately after launching the app. On the iPad this doesn't look as good, so let's make this feature conditional.

➤ In `viewDidLoad()` in **SearchViewController.swift**, enclose the call to `becomeFirstResponder()` in a condition:

```
if UIDevice.current.userInterfaceIdiom != .pad {
  searchBar.becomeFirstResponder()
}
```

To figure out whether the app is running on an iPhone or on an iPad, you look at the current `userInterfaceIdiom`. This is either `.pad` or `.phone` — an iPod touch counts as a phone in this case.

Hide the primary pane in portrait mode

In portrait mode, after you tap a search result, the primary pane stays visible and obscures about half of the secondary pane. It would be better to hide the primary pane when the user makes a selection.

➤ Add the following method to **SearchViewController.swift**:

```
// MARK: - Private Methods
private func hidePrimaryPane() {
  UIView.animate(
    withDuration: 0.25,
    animations: {
      self.splitViewController!.preferredDisplayMode
= .secondaryOnly
    }, completion: { _ in
      self.splitViewController!.preferredDisplayMode
= .automatic
    }
  )
}
```

Every view controller has a built-in `splitViewController` property that is non-`nil` if the view controller is currently inside a `UISplitViewController`.

You can tell the split view to change its display mode to `.secondaryOnly` to hide the primary pane. You do this in an animation block, so the primary pane disappears with a smooth animation.

The trick is to restore the preferred display mode to `.automatic` after the animation completes. Otherwise, the primary pane stays hidden even in landscape!

➤ Add the following lines to `tableView(_:didSelectRowAt:)` in the `else` clause, right after the `if case .results` block:

```
if splitViewController!.displayMode != .oneBesideSecondary {
  hidePrimaryPane()
}
```

The `.oneBesideSecondary` mode only applies in landscape, so this says, "if the split view is not in landscape, hide the primary pane when a row gets tapped."

➤ Try it out. Put the iPad in portrait, do a search, and tap a row. Now the primary pane will slide away when you tap a row in the table.

Congrats! You have successfully repurposed the Detail pop-up to also work as the secondary pane of a split view controller. Whether this is possible in your own apps depends on how different you want the user interfaces of the iPhone and iPad versions to be.

If you're lucky, you may be able to use the same view controllers for both versions of the app, but often, you might find that the iPad user interface for your app is different enough from the iPhone's that you have to make all new view controllers with some duplicated logic.

> **The Apple Developer Forums**
>
> When I first wrote this chapter, how to hide the primary pane was not explained anywhere in the official `UISplitViewController` documentation and I had trouble getting it to work properly.
>
> Desperate, I turned to the Apple Developer Forums and asked my question there. Within a few hours I received a reply from a fellow developer who ran into the same problem and who found a solution — thanks, user "timac"!
>
> So if you're stuck, don't forget to look at the Apple Developer Forums for a solution: devforums.apple.com

This would be a good time to commit your changes since you've made quite a few changes.

Fix the Detail pop-up for iPhone

The Detail view works well in the Split View Controller on iPad now. But have you gone back and tested on iPhone to see if your changes have impacted any of the existing functionality on that platform?

This is something that's always important to test — if you make changes specific for one platform, and your app supports more than one platform, test on the other platforms after the changes.

You'll see a few small problems if you test the app now on iPhone:

1. You see the secondary pane of the Split View Controller when you start the app instead of the Search scene.
2. The Search view now shows a navigation bar.

3. The Detail pop-up now doesn't display properly on the iPhone because `isPopUp` is always false — try it.

4. The landscape view has the wrong layout for the buttons and it also has a navigation bar which takes up screen space.

Let's fix these issues.

Show primary pane on start

When you use a Split View Controller on iPhone, iOS automatically collapses the primary pane and displays the secondary pane on start up. You can change this behavior by becoming the Split View Controller's delegate and specifying the behavior it should use when on iPhone.

➤ Add the following extension to **SceneDelegate.swift**:

```
extension SceneDelegate: UISplitViewControllerDelegate {
  func splitViewController(
    _ svc: UISplitViewController,
    topColumnForCollapsingToProposedTopColumn proposedTopColumn:
UISplitViewController.Column
  ) -> UISplitViewController.Column {
    if UIDevice.current.userInterfaceIdiom == .phone {
      return .primary
    }
    return proposedTopColumn
  }
}
```

You ask the Split View Controller to display the primary pane after the views are collapsed when the current device is an iPhone. For all other devices, you display the pane proposed by the operating system.

➤ Add the following line to the end of `scene(_:willConnectTo:options:)` in **SceneDelegate.swift** to to indicate that `SceneDelegate` will be the Split View Controller's delegate:

```
splitVC.delegate = self
```

That should do it!

Run and test on both iPhone and iPad to make sure that the change works exactly as expected and that it did not break anything else.

Remove the navigation bar on iPhone

We don't want the navigation bar showing up when the app is running on iPhone.

➤ Add the following code to **SearchViewController.swift**:

```
override func viewWillAppear(_ animated: Bool) {
  super.viewWillAppear(animated)
  if UIDevice.current.userInterfaceIdiom == .phone {
    navigationController?.navigationBar.isHidden = true
  }
}
```

That will hide the navigation bar for `SearchViewController` and all its child views when running on an iPhone.

Fix the Detail pop-up

➤ In `prepare(for:sender:)` in **SearchViewController.swift**, add the line:


```
detailViewController.isPopUp = true
```

➤ Do the same thing in **LandscapeViewController.swift**.

➤ Verify that the Detail screen works properly in all situations.

Fix the landscape screen

The landscape screen on iPhone currently looks like this:



The iPhone landscape view has some issues

Note that the extra navigation bar that you saw earlier is now gone. This is due to the fix you made on the Search screen to remove the navigation bar there. So all you need to do is fix the button layout.

> **Exercise:** Do you know what caused the button layout to change after adding a Split View Controller?

Answer: The button layout is calculated based on the size of the `LandscapeViewController` but the size of the Landscape view appears not to be correct at the time the layout calculations are done.

However, since the Landscape view is a fullscreen view, you can simply use the size of the device screen instead of using the Landscape view size.

➤ Replace the following lines in `tileButtons(_:)` in **LandscapeViewController.swift**:

```
let viewWidth = scrollView.bounds.size.width
let viewHeight = scrollView.bounds.size.height
```

With the following:

```
let viewWidth = UIScreen.main.bounds.size.width
let viewHeight = UIScreen.main.bounds.size.height
```

All you've done is to change the view width and height to be set based on the screen width and height.

➤ Run the app now and the Landscape view should be laid out correctly now.


Size classes in the storyboard

Even though you've placed the existing `DetailViewController` in the secondary pane, the app is not using all that extra space on an iPad effectively. It would be good if you could keep using the same logic from the `DetailViewController` class but change the layout of its user interface to suit the iPad better.

If you like suffering, you could do `if UIDevice.current.userInterfaceIdiom == .pad` in `viewDidLoad()` and move all the labels around programmatically ... but there is a better way. This is exactly the sort of thing size classes were invented for!

Recall that there are two possible size classes, *compact* and *regular*, and that you can assign one of these values to the horizontal axis (width) and one to the vertical axis (height).

Here is the diagram again:



Horizontal and vertical size classes

➤ Open **Main.storyboard** and use the IB toolbar to switch to **iPad (9.7″)** – the view controllers are larger now.

We want to make the Detail pop-up bigger when the app runs on the iPad. However, if you make any edits to the storyboard right now, these edits will also affect the design of the app in iPhone mode. Fortunately, as you've seen previously, there is a way to make edits that apply to a specific size class only.

You can tell Interface Builder that you only want to change the layout for the *regular* width size class (**wR**), but leave *compact* width alone (**wC**). Now those edits will only affect the appearance of the app on the iPad.

Uninstall an item for a specific size class

The Detail pane doesn't need a close button on the iPad. It is not a pop-up so there's no reason to dismiss it. Let's remove that button from the storyboard.

➤ Select the **Close Button** on the Detail scene. Go to the Attributes inspector and scroll all the way to the bottom, to the **Installed** option.



The installed checkbox


This option lets you remove a view from a specific size class, while leaving it visible in other size classes.

➤ Click the tiny + button to the left of Installed. This brings up a menu. Choose **Width: Regular**, **Height: Regular** and click on **Add Variation**:



Adding a variation for the regular, regular size class


This adds a new line with a second Installed checkbox:



The option can be changed on a per-size class basis

➤ Uncheck Installed for **wR hR**. Now the Close Button disappears from the scene — if the storboard is in iPad mode, of course.

The Close Button still exists, but it is not installed for this size class. You can still see the button in the Document Outline, but it is grayed out:



The Close Button is still present but grayed out

➤ Use the IB toolbar to switch back to **iPhone SE**.

Notice how the Close Button is back in its original position. You've only removed it from the storyboard design for the iPad. That's the power of size classes!

➤ Run the app and you'll see that the close button really is gone on the iPad:



No more close button in the top-left corner

Change the storyboard layout for a given size class

Of course, the Detail pop-up is also way too wide on the iPad :] You fixed this for iPhone devices using variations for size classes previously. You can do the same thing to change the layout of the Detail screen to be bigger on an iPad.

➤ In the storyboard, switch to the **iPad (9.7")** layout again.

➤ Select the **Pop-up View** and add size based variations for **wR hR** for **left**, and **right** Auto Layout pin constraints so that the spacing around the pop-up is **80** points for this size variation.


You'll notice that you already have variations added previously for these pin values from the iPhone customizations you made previously.

➤ Select the **Image View** in the **Detail** pop-up and in the **Size inspector**, add size based variations for **wR hR** for the width and height of the image to be **180**.

➤ Select the main **Stack View** and set its **Spacing** to be **20** for **wR hR** size class.

➤ Change the pin constraints for the **Stack View** so that there is **32** points spacing all around.

You should end up with something that looks like this:




The Pop-up View after iPad-specific changes

Just to double-check, switch back to **iPhone SE** via the IB toolbar and make sure that the Detail pane is restored to its original dimensions. If not, then you may have changed one of the original constraints instead of making a variation for the iPad's size class.

In the iPad's version of the Detail pane, the text is now tiny compared to the pop-up background. So, let's change the fonts. That works in the same fashion: you add a customization for this size class with the + button, then change the property. You can customize any attribute that has a small + in front of it for different size classes.

➤ Select the **Name** label. In the **Attributes inspector** click the + in front of **Font** to add a new variant. Choose the **System Bold** font, size **28**.



Adding a size class variation for the label's font


Unfortunately, this will break Dynamic Type support for iPad but given that the new default fonts are much bigger, it hopefully won't matter. If it does matter to you, then you would need to set the various font sizes via code based on the device type – iPhone or iPad. But that's a larger topic that we can't cover here.

➤ Add a new variant to change the font of the other labels to **System**, size **20**. You can do this in one go by making a multiple-selection.

➤ Add a variant for the **Grid** Stack View's **Spacing**, setting it to **20**.

Switch back to iPhone SE to make sure all the constraints are still correct there.

➤ Run the app and you should have a much bigger detail view:



The iPad now uses different constraints for the secondary pane

Exercise: The first time the secondary pane shows its contents they appear quite abruptly because you simply set the `isHidden` property of `popupView` to `false`, which causes it to appear instantaneously. See if you can make it show up using a cool animation.

➤ This is probably a good time to try the app on the iPhone again. The changes you've made should be compatible with the iPhone version, but it's smart to make sure.

If you're satisfied everything works as it should, then commit the changes.

Slide over and split-screen on iPad

iOS has a very handy split-screen feature that lets you run two apps side-by-side. It works on pretty much all the 64-bit iPads (with a few caveats). Because you used size classes to build the app's user interface, split-screen support should work flawlessly.

Try it out: run the app on one of the iPad simulators. Swipe up from the bottom of the screen to have your dock appear on screen. Drag an app icon from the dock on to the right (or left) edge of the iPad screen and it should snap on, giving you two apps running side-by-side. You can drag the divider bar to adjust the size occupied by each app. Thanks to size classes, the layout of *StoreSearch* will automatically adapt to the allotted space.

The IB toolbar has a **Layout** button which becomes available when you select any of the iPad modes. You can use this to change how a view controller acts when it is part of such a split screen.

Your own popover

Anyone who has ever used an iPad before is no doubt familiar with popovers, the floating panels that appear when you tap a button in a navigation bar or toolbar. They are a very handy UI element.

A popover is nothing more than a view controller that is presented in a special way. In this section you'll create a popover for a simple menu.

Add the menu items


➤ In the storyboard, first switch back to **iPhone SE** because in iPad mode the view controllers are huge and take up too much space.

➤ Drag a new **Table View Controller** on to the canvas and place it next to the Detail screen.

➤ Change the table view to **Grouped** style and give it **Static Cells**.

➤ Set the table view's **Storyboard ID** to **PopoverView** in the **Identity inspector**.

➤ Add these rows (change the cell style to **Basic**):



The design for the new table view controller

This just puts three items in the table. You will only do something with the first one in this book. Feel free to implement the functionality of the other two by yourself.

Display as popover

To display the view controller in a popover, you need a button which triggers the popover. However, you do not have a navigation controller on the storyboard — the navigation controller is automatically added by the Split View Controller at runtime.

So you'll have to add the button via code.

➤ Add the following code to the end of the `else` block of the `if isPopup` condition in `viewDidLoad` in **DetailViewController.swift**:

```
// Popover action button
navigationItem.rightBarButtonItem =
UIBarButtonItem(barButtonSystemItem: .action, target: self,
action: #selector(showPopover(_:)))
```

You set the right bar button item on the Detail screen's navigation bar to a button where a tap would call a method named `showPopover`. This button won't show up on the iPhone because there, the Detail pop-up doesn't sit in a navigation controller.


➤ Add the new method to **DetailViewController.swift**:

```
@objc func showPopover(_ sender: UIBarButtonItem) {
  guard let popover = storyboard?.instantiateViewController(
    withIdentifier: "PopoverView") else { return }
  popover.modalPresentationStyle = .popover
  if let ppc = popover.popoverPresentationController {
    ppc.barButtonItem = sender
```

```
    }
    present(popover, animated: true, completion: nil)
  }
```

You simply create an instance of the table view controller with the menu using the Storyboard ID you set up earlier, configure its presentation style to be a popover, set the button from which to display the popover and then display it.

If you run the app and press the menu button, the app should look like this:




That menu is a bit too tall

Set the popover size


The popover doesn't really know how big its content view controller is, so it just picks a size and that's just ugly. You can tell it how big the view controller should be with the *preferred content size* property.

➤ In the **Attributes inspector** for the **Table View Controller**, in the **Content Size** boxes type Width: 320, Height: 204.



Changing the preferred width and height of the popover

Now the size of the menu popover looks a lot more appropriate:



The menu popover with a size that fits

When a popover is visible, all other controls on the screen become inactive. The user has to tap outside of the popover to dismiss it before they can use the rest of the screen again — you can make exceptions to this by setting the popover's `passthroughViews` property.

Send e-mail from the app

Now, let's make the "Send Support Email" menu option work. Letting users send an e-mail from within your app is pretty easy.

iOS provides the `MFMailComposeViewController` class that takes care of everything for you. It lets the user type an e-mail and then sends the e-mail using the mail account that is set up on the device.

All you have to do is create an `MFMailComposeViewController` object and present it on the screen.

The question is: who will be responsible for this mail compose controller? It can't be the popover because that view controller will be deallocated once the popover goes away.

Instead, you will let the `DetailViewController` handle the sending of the e-mail, mainly because this is the screen that brings up the popover in the first place. `DetailViewController` is the only object that knows anything about the popover.

The MenuViewController class

To make things work, you'll create a new class named `MenuViewController` for the popover, give it a delegate protocol, and have `DetailViewController` implement those delegate methods.

➤ Add a new file to the project using the **Cocoa Touch Class** template. Name it **MenuViewController**, subclass of **UITableViewController**.

➤ Remove all the data source methods from this file because you don't need those for a table view with static cells. Also remove all the commented out boilerplate code.

➤ In the storyboard, change the **Class** of the popover's table view controller to **MenuViewController**.

➤ Add a new protocol to **MenuViewController.swift** (outside the class):

```
protocol MenuViewControllerDelegate: AnyObject {
  func menuViewControllerSendEmail(_ controller:
MenuViewController)
}
```

➤ Also add a property for this protocol inside the class:

```
weak var delegate: MenuViewControllerDelegate?
```

Like all delegate properties, this is weak because you don't want `MenuViewController` to "own" the object that implements the delegate methods.

➤ Finally, add `tableView(_:didSelectRowAt:)` to handle taps on the rows from the table view:

```
// MARK: - Table View Delegates
override func tableView(
  _ tableView: UITableView,
  didSelectRowAt indexPath: IndexPath
) {
  tableView.deselectRow(at: indexPath, animated: true)
  if indexPath.row == 0 {
    delegate?.menuViewControllerSendEmail(self)
  }
}
```

Set the MenuViewController delegate

Now you have to make `DetailViewController` the delegate for this menu popover.

➤ Switch to **DetailViewController.swift** and add the following extension to the bottom of the source file to conform to the new protocol:

```
extension DetailViewController: MenuViewControllerDelegate {
  func menuViewControllerSendEmail(_: MenuViewController) {
  }
}
```

Currently, the code is just a stub. You'll fill in the implementation code in a bit.

➤ Next, change `showPopover(_:)` as follows:

```
@objc func showPopover(_ sender: UIBarButtonItem) {
  guard let popover = storyboard?.instantiateViewController(
    withIdentifier: "PopoverView") as? MenuViewController    //
Change this
  else { return }
  popover.modalPresentationStyle = .popover
  if let ppc = popover.popoverPresentationController {
    ppc.barButtonItem = sender
  }
  popover.delegate = self                                    //
Add this
  present(popover, animated: true, completion: nil)
}
```

You make two changes:

1. You cast the popover to be of type `MenuViewController`
2. You tell the popover instance, which is of type `MenuController`, who its delegate is.

Run the app and tap Send Support Email. Notice how the popover doesn't disappear yet. You'll have to manually dismiss it before you can show the mail compose sheet.

Show the mail compose view

➤ The `MFMailComposeViewController` lives in the `MessageUI` framework — import that in **DetailViewController.swift**:

```
import MessageUI
```

➤ Then, add the following code to `menuViewControllerSendEmail()` (in the extension at the end):


```
dismiss(animated: true) {
  if MFMailComposeViewController.canSendMail() {
    let controller = MFMailComposeViewController()
    controller.setSubject(
      NSLocalizedString("Support Request", comment: "Email
subject"))
    controller.setToRecipients(["your@email-address-here.com"])
    self.present(controller, animated: true, completion: nil)
  }
}
```

The code first calls `dismiss(animated:)` to hide the popover. This method takes a `completion` closure that until now you've always left `nil`. Here you implement the closure — using trailing syntax — to bring up the `MFMailComposeViewController` after the popover has faded away.

It's not a good idea to present a new view controller while the previous one is still in the process of being dismissed. This is why you wait to show the mail compose sheet until after the popover is done animating.

To use the `MFMailComposeViewController` object, you have to give it the subject of the e-mail and the e-mail address of the recipient. You probably should put your own e-mail address there!

➤ Run the app and pick the Send Support Email menu option. The standard e-mail compose sheet should slide up — if you are on a device. This won't work on the Simulator at all, sorry.



The e-mail interface

> **Note:** If you run the app on a device and don't see the e-mail sheet, you may not have set up any e-mail accounts on your device – so do that first.

The mail compose view delegate

Notice that the Send and Cancel buttons don't actually appear to do anything. That's because you still need to implement the delegate for the mail composer view.

➤ Add a new extension to **DetailViewController.swift**:

```
extension DetailViewController:
MFMailComposeViewControllerDelegate {
  func mailComposeController(
```

```
      _ controller: MFMailComposeViewController,
      didFinishWith result: MFMailComposeResult,
      error: Error?
    ) {
      dismiss(animated: true, completion: nil)
    }
  }
```

The `result` parameter says whether the mail was successfully sent or not. This app doesn't really care about that, but you could show an alert in case of an error if you wanted. Check the documentation for the possible result codes.

➤ In the `menuViewControllerSendEmail()` method, add the following line (after the `controller` is created, of course):

```
controller.mailComposeDelegate = self
```

➤ Now, if you press Cancel or Send, the mail compose sheet gets dismissed.

Landscape on bigger iPhones

The iPhones with bigger screens such as the Plus, Xr, 11, 11 Pro Max are strange beasts. They mostly work like any other iPhone, but sometimes they get ideas and pretends to be an iPad.

➤ Run the app on the **iPhone 8 Plus** Simulator, do a search, and rotate to landscape.

You'll first get an empty secondary pane with the navigation bar. Tap the "Search" button and the app will look something like this:



The landscape view for bigger iPhones is messed up

The app tries to do both: show the split view controller and the special landscape view at the same time. Obviously, that's not going to work.

These devices are so big that they're almost small iPads. The designers at Apple decided that in landscape orientation these phone should behave like an iPad, and therefore show the split view controller.

What's the trick? Size classes, of course! On landscape, for these devices, the horizontal size class is *regular*, not *compact*. But the vertical size class is still compact, just like on the smaller iPhone models.

Show split view correctly for bigger iPhones


To stop the `LandscapeViewController` from showing up, you have to make the rotation logic smarter.

➤ In **SearchViewController.swift**, change `willTransition(to:with:)` to:

```
override func willTransition(
  to newCollection: UITraitCollection,
  with coordinator: UIViewControllerTransitionCoordinator
) {
  super.willTransition(to: newCollection, with: coordinator)
  switch newCollection.verticalSizeClass {
  case .compact:
    if newCollection.horizontalSizeClass == .compact {  // Add
this
      showLandscape(with: coordinator)
    }                                                   // Add
this
  case .regular, .unspecified:
    hideLandscape(with: coordinator)
  @unknown default:
    break
  }
}
```

The method is almost the same as before – you've just added an extra `if` condition to check what the *horizontal size class* is when the vertical size class is `.comapct`. This way, you can identify the bigger iPhones which behave differently.

➤ Try it out. Now the iPhone Plus shows a proper split view:



The app on the iPhone 8 Plus with a split-view

Change split view display mode for iPhone

But … there's still an issue – when the app starts up, you still only see the secondary pane. You have to tap the "Search" button to see the primary pane. That's not a very good design, even if this only affects some iPhones …

The fix is easy – you just need to set a different *display mode* for the split view when it's being used on an iPhone. The display mode defines how a split view displays its child view controllers. With iOS 14, a split view can have a primary pane, a secondary pane *and* a supplementary pane. So there could potentially be three panes in play.

How these panes display on a given platform, or under specific conditions, is determined by the split view's display mode. You can't change the display mode for a split view directly. Instead, you set the `preferredDisplayMode` and the split view tries to display the panels as per your preference, but if it is unable to – for example, due to lack of space – it will display what it thinks is the best layout.


So, in order to fix what happens on bigger iPhones, you need to specify that you want the split view to display one additional column besides the secondary pane. We do this in `SceneDelegate` since then we'll be initializing split view before it gets shown on screen.

➤ Add the following to the end of `scene(_:willConnectTo:options:)` in **SceneDelegate.swift** where you put the other split view related code:

```
if UIDevice.current.userInterfaceIdiom == .phone {
  splitVC.preferredDisplayMode = .oneBesideSecondary
}
```

If you wonder how this will affect only the bigger iPhones and not all iPhones, good thinking :] But remember that `.oneBesideSecondary` is your *preferred* display mode. Doesn't necessarily mean that that's what you'll actually see on the device. If you test it out, you will see that this does not result in two panes on a smaller iPhone screen.

In fact, even on a bigger iPhone screen what you get is not what you asked for. You don't get the primary pane side-by-side with the secondary pane – instead, you get the primary pane overlaying the secondary pane:



The primary pane overlays the secondary on iPhone 8 Plus with a split-view

There's a separate display mode setting if you actually want the primary pane to overlay the secondary pane – `.oneOverlaySecondary` instead of `.oneBesideSecondary` – but iOS decided to use the overlay style instead of the one we requested due to the available space.

This at least works for the intended purpose. So we'll accept it – not that we have much choice :]

Add size class based UI changes for bigger iPhones


Of course, the Detail pane now uses the iPhone-size design, not the iPad design.

That's because the size class for `DetailViewController` is now *regular* width, *compact* height. You didn't make a specific design for that size class, so the app uses the default design.

That's fine for the size of the Detail view, but it does mean the close button is visible again.

➤ Open the storyboard, use the IB toolbar to switch to the **iPhone 8 Plus** mode and switch to landscape mode — this will help you get the size classes right when you add exceptions.

➤ Select the **Close Button** in the Detail scene. In the **Attributes inspector**, add a new row for **Installed** (for Width: Regular, Height: Compact) and uncheck it:



Adding a variation for size class width regular, height compact

➤ Build and run the app and test on a variety of devices or simulators — iPad, smaller iPhone, bigger iPhone etc. —, orientations, and appearances to make sure that everything still looks and works right.

And that's it for the *StoreSearch* app! Congratulations for making it this far, it has been a long road.

➤ Celebrate by committing the final version of the source code and tagging it v1.0!

You can find the project files for this chapter under **42-iPad** in the Source Code folder.

Chapter 43: Distributing the App

By Fahim Farook

What do you do with an app that is finished? Upload it to the App Store, of course! And with a little luck, make some big bucks…

Throughout this book, you've probably been testing the apps on the Simulator and occasionally on your device. That's great, but when the app is nearly done, you may want to let other people beta test it.

In this chapter, you'll learn how to beta test the *StoreSearch* app. After that, I'll also show you how to submit the app to the App Store, which is basically an extension of the same process.

By the way, I'd appreciate it if you don't actually submit the apps from this book. Let's not spam the App Store with dozens of identical *StoreSearch* or *Bull's Eye* apps.

This chapter will cover the following:

- **Join the Apple Developer program:** How to sign up for the paid Apple Developer Program.
- **Beta testing:** How to beta test your app using Apple's TestFlight service.
- **Submit to the App Store:** How to submit your app to Apple for review before being made available on the App Store.

Join the Apple Developer program

Once you're ready to make your creations available on the App Store, it's time to join the paid Apple Developer Program.

To sign up, go to developer.apple.com/programs/ and click the blue **Enroll** button.

On the sign-up page you'll need to enter your Apple ID. Your developer program membership will be tied to your Apple ID. It's OK to use the same Apple ID that you're already using with iTunes and your iPhone, but if you run a business, you might want to create a new Apple ID to keep things separate.

You can enroll as an Individual or as an Organization. There is also an Enterprise Program (https://developer.apple.com/programs/enterprise/), but that's generally for companies who want to distribute apps within their own organization only. If you're still in school, the iOS Developer University Program (https://developer.apple.com/programs/ios/university/) may be worth looking into as well.

You buy the Developer Program membership from the online Apple Store for your particular country. Once your payment is processed, you'll receive an activation code that you use to activate your account.

Signing up is usually pretty quick. In the worst case it may take a few weeks, as Apple will check your credit card details and if they find anything out of the ordinary — such as a misspelled name — your application may run into delays. So make sure to enter your credit card details correctly or you'll be in for an agonizing wait.

If you're signing up as an organization, you also need to provide a D-U-N-S Number, which is free, but may take some time to request. You cannot register as an organization if you have a single-person business such as a sole proprietorship or DBA ("doing business as"). In that case you need to sign up as an Individual. You will have to renew your membership every year, but if you're serious about developing apps, then that $99/year will be worth it.

Beta testing

You will be distributing your app for beta testing via Apple's TestFlight service.

TestFlight

In the early days of iOS development, the only way to send builds to your testers was via what was known as Ad Hoc distribution. You had to register specific devices for Ad Hoc distribution — for which you needed to know the unique ID for the device — and there was a limit of 100 devices per developer account. You could only reset the devices in this list once per year, when you renewed your developer account.

Additionally, you had to go through a complicated manual signing process to sign builds for Ad Hoc distribution and you had to send these builds out to your users and hope that they could figure out how to install the builds on their devices and troubleshoot any installation issues by themselves, or provide you enough information to help them figure out what was going on.

All this changed with the introduction of Apple's TestFlight service.

TestFlight allows you to distribute your beta builds to 10,000 testers and all you need is just their e-mail address!

What's more, the process itself is fairly straightforward since you simply build your app in Xcode and upload to the App Store. The app binary would go through some processing at this point and once the processing is complete, you are able to offer the app for testing to your internal testers immediately.

In addition to the 10,000 external testers, you can also have internal testers from your organization. The internal tester count is limited to 100 people — each of whom can run your app on up to 30 devices — and they have to be part of your Apple Developer team. If you signed up as a single developer, this probably would not work for you since you can't add additional members to your team on the Apple Developer portal. On the other hand, if you signed up as an organization, then you can start testing immediately.

If you want to distribute to external testers — the 10,000 testers I mentioned earlier — you do have to go through an initial review of your app by Apple. This process is usually quite fast and takes about a day. This generally has to be done only once per new beta build — for the very first beta build. After that, you can simply push out new builds without needing to wait for approval from Apple.

To add new users to beta test, you simply invite them using their e-mail address. They will receive an invitation e-mail which they can accept, or reject by simply ignoring the e-mail. If they accept the invitation, they are prompted to install the TestFlight app which will handle installing beta builds and notifying users of updates to beta builds from then on.

You can read more on TestFlight at: https://developer.apple.com/testflight/

Apple Developer portal

While the new TestFlight workflow for beta testing is miles ahead of what you had previously, it still requires you to do a bunch of things on several different Apple sites. You start out on the Apple Developer portal where you need to create an App ID for your new app.


➤ Open your favorite web browser and navigate to your account details page at developer.apple.com/account. You might need to sign in if you are not logged in. Once you are there, click on **Certificates, IDs & Profiles** on the left sidebar.

Tip: If you have trouble using the site and you are not using Safari, try using Safari. Other browsers can throw up weird issues sometimes.

> **Note:** Like any piece of software, the Apple Developer Portal changes every now and then. It's possible that by the time you read this, some of the options are in different places or have different names. The general flow should still be the same, though. And if you really get stuck, online help is usually available.

➤ Click on **Identifiers** in the sidebar — you should get a list of existing app IDs. Press the + button next to the **Identifiers** title on the main section to add an Identifier.


You should be presented with a list of possible identifiers you can create on the Apple Developer portal – there are a *lot*. What you need is to create an App ID.



Select identifier type

➤ Select **App IDs** and then tap **Continue**.

Now you have to decide what type of App ID you want :]



Select App ID type

➤ Select **App** and then tap **Continue**.

You finally get to where you can register a new App ID:




Creating a new App ID

➤ Fill in the **Description** field. This can be anything you want — it's just for your reference on the Provisioning Portal.

➤ The **App ID Prefix** field contains the ID for your team. You cannot modify this value.

➤ Under **Bundle ID**, select **Explicit**. In the **Bundle ID** field you must enter the identifier that you used when you created the Xcode project. For me that is **com.razeware.StoreSearch**.



The Bundle ID must match with the identifier from Xcode

If you want your app to support Push Notifications, iCloud, SiriKit etc. then you can enable those options – and sometimes configure them – here. *StoreSearch* doesn't need any of that, so leave the other fields on the default settings.

➤ Press **Continue** and then **Register** to create the App ID. The portal will now generate the App ID for you and add it to the list.

The full App ID will be something like **U89ECKP4Y4.com.yourname.StoreSearch**. That number in front is your Apple Developer Team ID.


App Store Connect

Next, you need to add your app to App Store Connect.

➤ Navigate to appstoreconnect.apple.com via your browser of choice. Again, try using Safari if you run into any issues with the App Store Connect site on a different browser.

➤ If prompted, log in using the same Apple ID that you used to sign up for your Apple Developer account. But generally, the two sites should be connected and you should be able to switch from one to the other without needing to re-log in.

➤ The first screen you see will look something like the following — if you are not an administrator for the App Store Connect account, you might see fewer options on the screen than in the screenshot.




Initial App Store Connect screen

➤ If you've never been to App Store Connect before, then make sure to first visit the **Agreements, Tax, and Banking** section and fill out the forms. All that stuff has to be in order before your app can be distributed on the App Store.


➤ Select **My Apps** — this is the option you need to manage everything related to your apps. You create new app entries, edit existing ones, and manage your beta testing and app distribution tasks all from there.

The page you are taken to lists your existing apps, if you have any. It also allows you to add new apps to App Store Connect.




The My Apps page on App Store Connect

➤ Click the plus (+) icon on the top left to add a new app and then select **New App** from the menu.



Add a new app on App Store Connect

➤ This should present you with a new dialog for entering the basic information necessary for an app.



New app information on App Store Connect

Select the checkbox for **iOS** (since yours is an iOS app), enter the name of your app, select the primary language from the dropdown and select the Bundle ID from the dropdown.

The Bundle ID would be the app ID you added on the Apple Developer Portal earlier. If you don't see the app ID you added, try refreshing your browser or waiting for a bit in case the information has not updated on the Apple servers. Generally, the information should be reflected almost immediately.

Also, note that you **must** have a bundle ID matching the ID you have in Xcode for your project. Otherwise, the upload from Xcode will fail.

Tip: If you are not sure about what you are supposed to enter for a particular field, you can always click on the question mark icon next to each field to get a hint as to what you should enter.

The last value you have to enter is the **SKU** (or "skew"), which stands for **S**tock-**K**eeping **U**nit. This one confuses people a bit since it can be any unique value *for your company*. Basically, Apple does not care what this value is — it's only used for reporting purposes. It has to be unique for your apps. So, for example, if you use 1001 as the SKU for your first app, you *can't* use 1001 as the SKU for your second app.

➤ Once you've filled in all the information, click **Create** and your new app will be added to App Store Connect — if there are no errors.

If your app name has been used before — by anybody, not just you — for another app, or if your Bundle ID is not unique, or if your SKU has been used before *by you*, you will get an error message at this point. You would have to fix these issues and try again if this happens. Generally, it's the app name which gives you problems — so it's always a good idea to figure out if the name you selected is in use before you try to add a new app to App Store Connect.

That's all you need to do at the App Store Connect end for the time being.


Upload for beta testing

Once you have your app on App Store Connect, you can upload the app for beta testing — and later submission to Apple — quite easily.

➤ Start Xcode, if you're not already running it, and then open the *StoreSearch* project.


➤ In the **Project Settings** screen, in the **Signing & Capabilities** tab, choose the correct **Team**. As you noticed when you created the App ID, the team ID is connected to your App ID.

So make sure that you have the right team selected here, otherwise you will run into issues later when you try to upload the build...



Choosing the team

➤ Change the device in the active scheme selector, on the Xcode toolbar, to **Any iOS Device (arm 64)** under the **Build** section.




Selecting Generic iOS Device

Normally, when you build your app, you build for a specific Simulator or for a connected device because your intention at that point is to run the build on that particular Simulator or device.

But when you build for distribution, you have no idea which particular device a build would run on. So, you have to build using the any iOS device setting in order to ensure that the resulting app would be compiled correctly to run on all supported devices.


➤ Select **Product ▸ Archive** from the Xcode menu.



Create app archive

If the Archive option is disabled, then you probably did not select the Any iOS Device from the active scheme selector as per the previous step. You can only build an archive if you have the Any iOS Device selected.

The app will compile the project and link it. If everything goes smoothly, Xcode should open the Organizer window and and display the new archive which was just created.




The Organizer window

You are now ready to upload the build to the App Store, as the big blue button on the right sidebar testifies.

You can simply click the big blue button, or, you can click the *Validate App* button below it to verify that your app passes all of Apple's initial validations. The validations are run even if you use the *Distribute App* button, but the *Validate App* button is an easy way to check your app locally and verify that it passes muster before you spend the time – and bandwidth – to upload it to the Apple servers.

➤ Click the **Distribute App** button.


You will be asked for the method of distribution:



App distribution method

➤ You would, of course, want to select **App Store Connect** for this one.

Then you need to select the destination:




Destination options

Here, you can opt to upload the binary file directly to the Apple servers or to create an export file that you can upload later. The second option can be useful for situations where you are unable to upload via Xcode for some reason — it happens, more often than you might think.

➤ Select **Upload** and click **Next**.


Next, you need to select some distribution options:



App Store distribution options

Each of the options has some helpful text describing what the option does — so you can basically go with the options that are suitable for you. If you are not sure, there won't be any harm in keeping all of the options checked.


Tapping **Next** will take you to another dialog:



Code signing options

➤ Generally, it's best to go with **Automatically manage signing** unless you know what you are doing. The manual option gives you a lot more flexibility, but you also have to deal with the complexity that comes along with it — with great power comes great complexity. :]


Tap **Next** to proceed and Xcode will work for a while signing your app and getting it ready for upload. When Xcode is ready, it should show you a screen similar to the following:



Ready to upload app

➤ Click **Upload** and Xcode will start uploading the binary for your app to the Apple servers. Depending on the size of your app — and the speed of your network connection — this might take a bit of time.

While the upload is in progress, you'll get a progress indicator and status messages indicating what is going on. If the upload completes successfully, you should get a message similar to the following:



App Store Connect app upload successful


If the upload completes successfully, that's all you have to do at the Xcode end.

Sometimes though, you might get an error.

Some of these errors are basically incomprehensible since they might just be an App Store error code and a cryptic message. If your are unlucky enough to get one of those, you might have to Google for the error code and see if you find somebody else who has figured out the issue. Usually, it turns out to be an Xcode issue or an App Store issue that is resolved by Apple a few days later.

On the other hand, you might get specific error messages such as your app missing the app icon, or an app icon for a specific size that App Store Connect expected. In such cases, fixing the issue by adding the missing assets and then creating another archive — you can't re-use the previous one — and uploading that should resolve the issue.

Sometimes, you might also get warnings, like the following:



App Store Connect error about specific issue

The above indicates that the currently uploaded build is fine as far as passing the general validation goes, but that it's missing an icon. While this is just a warning, as the message indicates, you still cannot use this build for external beta testing or for submitting to the App Store for review. So you'll need to fix the issue and upload a new build.


One thing you have to watch out for when uploading multiple builds for the same app to the Apple servers is the build number …

Build number

Each build you submit to Apple has to be uniquely identifiable. How this is generally done for Xcode projects is by combining the version number and build number for the project to get a unique value.

But where is this version number and build number, you ask? Easy enough.

In Xcode, go to your project root in the Project navigator, select your project target, go to the **General** tab, and then check the **Identity** section.




Xcode version and build numbers

For each new version of your app, you need to increment your version number. For each build you submit for a version, the build number has to change too, but, while you cannot repeat a version number, you can repeat a build number as long as the same build number is not used within a given version.

So, for example, you can have the builds for version 1.0 start from 1 and go up to however many builds as you like. And while you cannot use build number 1 for another build for version 1.0, if you start a new version, say 2.0, then you can start the build numbers for the new version again from 1 and go up incrementally.

So, if you've already uploaded a build to App Store Connect and you have to upload another build — either because of an error or because you made a code change — then you need to remember to change the build number. If you don't, you'd get an error during the upload process.



App Store Connect error about build number


Change the build number in your project settings, create a new archive, upload it and you should be good to go!

Check your upload

You can check on the status of your uploaded build by logging into App Store Connect.

➤ Select **My Apps** from the main dashboard to get a listing of your apps and then select the *StoreSearch* app from there.


➤ You'll be taken to the app detail screen on App Store Connect:



The app details on App Store Connect

This is the screen where you would manage everything to do with a given app. You can edit the app information, add screenshots, change the price information, submit builds for review, and check the status of a build.

➤ Click on the **Activity** tab along the top. This should take you to the latest activity for this particular app.



The activity page on App Store Connect


As the screen shows, you can see the status of your app. If you've just uploaded a build, it will generally show that the app is processing. This can sometimes take a bit of time, though most of the time, the process is pretty quick. Once the processing is complete, you should receive a notification e-mail from Apple indicating that your app had completed processing and is now available for either testing or distribution.

Internal testing

As I mentioned before, there are two test modes for TestFlight — internal and external. Once your app upload completes processing, you can immediately start internal testing.

➤ Log in to App Store Connect and go to your app's detail screen. From there, select **TestFlight** from the list of tabs at the top.

This screen will show any builds which are ready for TestFlight testing:




The build detail page on App Store Connect

As you might notice, your app build has a warning — it's apparently missing compliance information. This is standard for all builds unless you provide the compliance information beforehand. The easiest way to fix this is to click on the blue "Manage" link next to "Missing Compliance". You'll have to answer some questions about whether your app uses any encryption.

If you answer "Yes", then there are a few more steps/questions that you'll have to go through. If the answer is "No", then you get a button which says **Start Internal Testing** and you are ready for internal testing as soon as you click it.


➤ Now, click on the blue #1 next to the app icon — that is a link which would take you to the detail information page for this particular build — build #1.



The build detail page on App Store Connect

The above screen has a place to add testers for this build. So, you might think that is where you add testers for your app. Well ... yes, and no.

To add *internal* testers for your app, you actually have to click on the **App Store Connect Users** link on the left of that screen. That takes you to a new screen from where you can select up to 100 existing users in your team to be added as internal testers:



The App Store Connect Users screen

If you don't have any team members at the moment though, you would need to first go back to your App Store Connect dashboard, select the **Users and Roles** option, add some team members — and optionally, assign them the role of tester — and then come back and add the newly created users as internal testers for your app.


You might think that the + button next to Testers would allow you to add new internal testers ... but no. That's actually for adding previously added internal testers as testers for *this* app. Basically, your internal testers could be testing multiple apps for you at the same time. This is where you manage who is a tester for the currently selected app.

The selected team members will be notified via e-mail that a new build is ready for testing and they will be asked to install the TestFlight iOS app so that they can participate in the testing process. Internal testing, as the name implies, is generally for testing within your team. So Apple does not require your beta build to go through any sort of review before you start testing. But internal testing is also limited to just 100 people at most. If you want to do more extensive beta testing, then you have to opt for external testing.

External testing


External testing allows you to distribute beta builds of your app to 10,000 testers. But before you can start inviting testers, you have to get your beta build approved by Apple. To do that, you have to add at least one external tester to your app first.

➤ Go to the build detail information screen that you accessed earlier – the one from the TestFlight tab that you can access by clicking the link for the build number (a blue #1 in this case):



The build detail page on App Store Connect

In the above screen, if you click the + button next to **Individual Testers**, or click the big blue **Add Testers to Build** button, you'll get a menu with options to add testers in multiple ways. If you select an option and add some e-mail addresses as testers, then you'll be presented with a dialog asking for information about what to test:



Enter test information on App Store Connect

Fill in the information about what you want your users to test and then click **Submit for Review** to start the beta review process.

Now, you wait. :]

Generally, you will hear back from Apple within a day or two. If the Apple review team finds any issues with your app, they will let you know and you would need to fix the issues and submit another build and go through the review process again till you succeed.

If the app passes review, then it will be in "Testing" state for external testing and your external testers will be notified via e-mail that a new build is ready for them to test. This will start off the beta cycle for your app. Congratulations!

At this point, all you have to do is wait for feedback from your beta testers, fix any issues they find or make changes based on beta feedback, release another beta build. You rinse and repeat till you are certain that your app is ready to be submitted to Apple for review in preparation for release.

Submit for review

When your beta testing is complete, you can submit the final build which passed beta testing for App Store review instead of uploading yet another build to App Store Connect. This way, you bypass the potential for accidental introduction of any new bugs when you create a new build.

Since the build was already uploaded to the Apple servers when you uploaded it for beta testing, you simply have to move on to the next stage in the process using the correct build.

At this point, if you only entered the bare minimum information to add an app to App Store Connect, you might need to provide some additional information for the app as well.

➤ Go to your app's screen and then select the **App Store** tab and then the **App Information** option from the left sidebar.

On this screen, make sure that the **Category** values are filled in correctly for your app. You can select any category from the dropdown here but do try to make sure that the categories you select are relevant for your app.

➤ Select the **Pricing and Availability** option from the left sidebar and set a price for your app. If you want your app to be available in only specific App Stores around the world, you'd set that here via the Availability section.

You need to do the above two steps only once for every new app. All the other information changes you make below, might have to be done for every new release.

➤ Next, click on the **Prepare for Submission** link on the left sidebar with a yellow circle next to it. This is where you enter all the relevant information for each version that you submit to the App Store. Here, you'd need to complete at least the following information — you can fill in more values than the listed ones, but these are the mandatory ones:

- You can upload up to ten screenshots and three 30-second preview videos per device. At a minimum, you need to supply screenshots for the 6.5" iPhone, 5.5" iPhone, 12.9" iPad Pro (3rd Gen), and 12.9" iPad Pro (2nd Gen). If you do not provide screenshots or videos for the smaller screen devices, the assets from the larger screen devices will be scaled down for the smaller screens.
- A list of keywords that customers can search for — limited to 100 characters.
- The URL for your support page.

- A description that will be visible on the store.
- The build to submit — this is the build that passed your beta testing. You can click on the plus icon (or use the button in the box) to get a list of uploaded builds and select the correct one from there.
- Copyright information.
- The version number.
- The app rating — this is to identify whether your app contains potentially offensive content. You have to select from a list of items to determine your final content rating.
- Your contact details. Apple will contact you at the provided e-mail address if there are any problems with your submission.
- App Review Information. If your app requires a user login to test its functionality, provide the necessary demo user name and password here. If a demo login is not required, remember to uncheck the **Sign-in required** checkbox. Otherwise, you will get an error when you try to submit the app.
- Notes for the reviewer. These are optional, but it's good to provide some notes if the reviewer needs to do anything special in order to test your app.
- When your app should become available

If your app supports multiple languages, then you can also supply a translated description, screenshots and even an application name. For more info and help, consult the guides available under Resources and Help on the home page.

Make a good first impression

People who are searching or browsing the App Store for cool new apps generally look at things in this order:

1. The name of the app. Does it sound interesting or like it does what they are looking for?
2. The icon. You need to have an attractive icon. If your icon sucks, your app probably does too. Or at least that's what people probably think and then they're gone.
3. The screenshots. You need to have good screenshots that are exciting — make it clear what your app is about. A lot of developers go further than just regular screenshots; they turn these images into small billboards for their app.

4. App preview videos. Create up to three 15 to 30-second videos that show off the best features of your app.
5. If you didn't lose the potential customer in the previous steps, they might finally read your description for more info.
6. The price. If you've convinced the customer they really can't live without your app, then the price usually doesn't matter that much anymore.

So, get your visuals to do most of the selling for you. Even if you can't afford to hire a good graphic designer to do your app's user interface, at least invest in a good icon. It will make a world of difference in sales.

After filling out all the fields, click the **Save** button at the top. When you're ready to submit the app, press **Submit for Review**.

If you missed any information, you will get an error message at the top of the screen indicating the errors. The error message will be accompanied by a link which takes you to the page with the missing (or invalid) information. Also, the fields with missing information will be highlighted in red or have a red circle with an exclamation point next to the title (or both). This will help you identify what information needs to be filled in, or corrected.

Once you fix the issues, save and try submitting again. Sometimes, you have to do this multiple times before you finally succeed :]

Once you successfully submit your app, it enters the App Store approval process. If you're lucky, the app will go through in a couple of days, if you're unlucky it can take several weeks. These days the wait time is fairly short. See http://appreviewtimes.com for an indication of how long you might have to wait.

If you find a major bug in the mean time, you can reject the file you uploaded on App Store Connect and upload a new one, but this will put you back at square one and you'll have to start at the bottom of the app review queue once again.

If after your app gets approved, you want to upload a new version of your app, the steps are largely the same. You change the version in Xcode (and change the build number), add a new version number on App Store Connect, upload the new version to App Store Connect, update the information in the Prepare for Submission screen and re-submit.

Updates take about the same amount of time to get reviewed as new apps, so you'll always have to be patient for a few days.

The end

Awesome, you've done it! You made it all the way through *The UIKit Apprentice*. It's been a long journey but I hope you have learned a lot about iOS programming, and software development in general. I had a lot of fun writing these chapters and I hope you had a lot of fun reading them!
Because this book is packed with tips and information, you may want to go through it again in a few weeks, just to make sure you've picked up on everything!

The world of mobile app development now lies at your fingertips. There is a lot more to be learned about iOS and I encourage you to read the official documentation — it's pretty easy to follow once you understand the basics. And play around with the myriad of APIs that the iOS SDK has to offer.

Most importantly, go write some apps of your own!

Credits for *StoreSearch*: The shopping cart from the app icon is based on a design from the Noun Project (thenounproject.com).

Want to learn more?

There are many great videos and books out there to learn more about iOS development. Here are some suggestions for you to start with:

- The iOS Developer Library has the full API reference, programming guides, and sample code: developer.apple.com/develop/
- Mobile Human Interface Guidelines (the "HIG"): developer.apple.com/design/human-interface-guidelines
- UIKit Documentation: developer.apple.com/documentation/uikit
- View Controller Programming Guide: https://developer.apple.com/library/content/featuredarticles/ViewControllerPGforiPhoneOS/#//apple_ref/doc/uid/TP40007457-CH2-SW1
- The WWDC videos. WWDC is Apple's yearly developer conference and the videos of the presentations can be watched online at developer.apple.com/videos/. They are really worth it!
- The team at raywenderlich.com and I also have several other books for sale, including more advanced tutorials on iOS development and game programming on iOS. If you'd like to check these out, visit our store here: www.raywenderlich.com/books

Stuck?

If you are stuck, ask for help. Sites such as Stack Overflow (stackoverflow.com) and the Apple Developer Forums (forums.developer.apple.com) are great — and let's not forget our own forums (forums.raywenderlich.com).

I often go on Stack Overflow to figure out how to write some code. I usually more-or-less know what I need to do — for example, resize a `UIImage` — and I could spend a few hours figuring out how to do it on my own. However, the chances are someone else already wrote a blog post about it. Stack Overflow has tons of great tips on almost anything you can do with iOS development.

However, please don't post questions like this:

"i am having very small problem i just want to hide load more data option in tableview after finished loading problem is i am having 23 object in json and i am parsing 5 obj on each time at the end i just want to display three object without load more option."

This is an actual question that I copy-pasted from a forum. That guy isn't going to get any help because a) his question is unreadable; b) he isn't really making it easy for others to help him.

Here are some pointers on how to ask effective questions:

- Getting Answers mikeash.com/getting_answers.html
- What Have You Tried? mattgemmell.com/what-have-you-tried/
- How to Ask Questions the Smart Way github.com/selfteaching/How-To-Ask-Questions-The-Smart-Way

And that's a wrap!

I hope you learned a lot through the *UIKit Apprentice*, and that you take what you've learned to go forth and make some great apps of your own.

Above all, *have fun programming*, and let us know about your creations!

— Fahim Farook & Matthijs Hollemans

44 Conclusion

We hope you're excited about the new world of iOS development that lies before you!

By completing this book, you've given yourself the knowledge and tools to create your own iOS applications, or even start working with other developers on a team. It's up to you now to couple your creativity with the things you've learned in this book and create some impressive apps of your own!

If you have any questions or comments about the projects in this book or in your own animations, please stop by our forums at http://forums.raywenderlich.com.

Thank you again for purchasing this book. Your continued support is what makes the books, tutorials, videos and other things we do at raywenderlich.com possible. We truly appreciate it!

— Fahim and Matthijs

The *UIKit Apprentice* team